

The Definitive Guide to Java Swing

Third Edition

JOHN ZUKOWSKI

Apress®

The Definitive Guide to Java Swing, Third Edition

Copyright © 2005 by John Zukowski

All rights reserved. No part of this work may be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or by any information storage or retrieval system, without the prior written permission of the copyright owner and the publisher.

ISBN (pbk): 1-59059-447-9

Printed and bound in the United States of America 9 8 7 6 5 4 3 2 1

Trademarked names may appear in this book. Rather than use a trademark symbol with every occurrence of a trademarked name, we use the names only in an editorial fashion and to the benefit of the trademark owner, with no intention of infringement of the trademark.

Lead Editor: Steve Anglin

Technical Reviewer: Robert Castaneda

Editorial Board: Steve Anglin, Dan Appleman, Ewan Buckingham, Gary Cornell, Tony Davis, Jason Gilmore, Jonathan Hassell, Chris Mills, Dominic Shakeshaft, Jim Sumser

Assistant Publisher: Grace Wong

Project Manager: Beth Christmas

Copy Edit Manager: Nicole LeClerc

Copy Editor: Marilyn Smith

Production Manager: Kari Brooks-Copony

Production Editor: Ellie Fountain

Compositor: Susan Glinert

Proofreaders: Linda Seifert, Liz Welch

Indexer: Michael Brinkman

Artist: Kinetic Publishing Services, LLC

Cover Designer: Kurt Krames

Manufacturing Manager: Tom Debolski

Distributed to the book trade in the United States by Springer-Verlag New York, Inc., 233 Spring Street, 6th Floor, New York, NY 10013, and outside the United States by Springer-Verlag GmbH & Co. KG, Tiergartenstr. 17, 69112 Heidelberg, Germany.

In the United States: phone 1-800-SPRINGER, fax 201-348-4505, e-mail orders@springer-ny.com, or visit <http://www.springer-ny.com>. Outside the United States: fax +49 6221 345229, e-mail orders@springer.de, or visit <http://www.springer.de>.

For information on translations, please contact Apress directly at 2560 Ninth Street, Suite 219, Berkeley, CA 94710. Phone 510-549-5930, fax 510-549-5939, e-mail info@apress.com, or visit <http://www.apress.com>.

The information in this book is distributed on an “as is” basis, without warranty. Although every precaution has been taken in the preparation of this work, neither the author(s) nor Apress shall have any liability to any person or entity with respect to any loss or damage caused or alleged to be caused directly or indirectly by the information contained in this work.

The source code for this book is available to readers at <http://www.apress.com> in the Downloads section.

Contents at a Glance

About the Author	xix
About the Technical Reviewers	xxi
Acknowledgments	xxiii
Introduction	xxv
CHAPTER 1 Swing Overview	1
CHAPTER 2 Event Handling with the Swing Component Set	17
CHAPTER 3 The Model-View-Controller Architecture	59
CHAPTER 4 Core Swing Components	67
CHAPTER 5 Toggle Buttons	115
CHAPTER 6 Swing Menus and Toolbars	151
CHAPTER 7 Borders	211
CHAPTER 8 Root Pane Containers	235
CHAPTER 9 Pop-Ups and Choosers	267
CHAPTER 10 Layout Managers	343
CHAPTER 11 Advanced Swing Containers	377
CHAPTER 12 Bounded Range Components	419
CHAPTER 13 List Model Controls	451
CHAPTER 14 Spinner Model Controls	509
CHAPTER 15 Basic Text Components	521
CHAPTER 16 Advanced Text Capabilities	585
CHAPTER 17 Trees	623
CHAPTER 18 Tables	675
CHAPTER 19 Drag-and-Drop Support	729
CHAPTER 20 The Pluggable Look and Feel Architecture	741
CHAPTER 21 The Undo Framework	783

CHAPTER 22 Accessibility 805

APPENDIX UI Manager Properties 813

INDEX 847

Contents

About the Author	xix
About the Technical Reviewers	xxi
Acknowledgments	xxiii
Introduction	xxv
CHAPTER 1 Swing Overview	1
Getting to Know the Swing Components	2
AWT Component Replacements	3
Non-AWT Upgraded Components	5
Event Handling and Layout Management	10
Undo Framework	11
SwingSet Demonstration	11
Swing Component to Chapter Mapping	12
Summary	15
CHAPTER 2 Event Handling with the Swing Component Set	17
Delegation-Based Event Handling	17
Event Delegation Model	17
Event Listeners As Observers	19
Multithreaded Swing Event Handling	21
Using SwingUtilities for Mouse Button Identification	23
Using Property Change Listeners As Observers	26
Managing Listener Lists	29
Timer Class	34
Swing-Specific Event Handling	37
Action Interface	37
AbstractAction Class	38
KeyStroke Class	41
Using Mnemonics and Accelerators	46

Swing Focus Management	46
Moving the Focus	48
Examining Focus Cycles	50
FocusTraversalPolicy Class	52
KeyboardFocusManager Class	55
Verifying Input During Focus Traversal	56
Summary	57
 CHAPTER 3 The Model-View-Controller Architecture	59
Understanding the Flow of MVC	59
MVC Communication	59
UI Delegates for Swing Components	60
Sharing Data Models	61
Understanding the Predefined Data Models	63
Summary	65
 CHAPTER 4 Core Swing Components	67
JComponent Class	67
Component Pieces	69
JComponent Properties	74
Handling JComponent Events	80
JToolTip Class	84
Creating a JToolTip	84
Creating Customized JToolTip Objects	84
Displaying Positional Tooltip Text	85
Customizing a JToolTip Look and Feel	86
ToolTipManager Class	86
ToolTipManager Properties	87
JLabel Class	88
Creating a JLabel	89
JLabel Properties	89
JLabel Event Handling	91
Customizing a JLabel Look and Feel	92
Interface Icon	92
Creating an Icon	93
Using an Icon	94
ImageIcon Class	94
GrayFilter Class	97

AbstractButton Class	98
AbstractButton Properties	98
Handling AbstractButton Events	102
JButton Class	104
Creating a JButton	104
JButton Properties	105
Handling JButton Events	106
Customizing a JButton Look and Feel	108
JPanel Class	110
Creating a JPanel	110
Using a JPanel	110
Customizing a JPanel Look and Feel	112
Summary	112

CHAPTER 5 **Toggle Buttons** 115

ToggleButtonModel Class	115
ButtonGroup Class	116
JToggleButton Class	119
Creating JToggleButton Components	119
JToggleButton Properties	120
Handling JToggleButton Selection Events	121
Customizing a JToggleButton Look and Feel	124
JCheckBox Class	125
Creating JCheckBox Components	126
JCheckBox Properties	127
Handling JCheckBox Selection Events	130
Customizing a JCheckBox Look and Feel	133
JRadioButton Class	134
Creating JRadioButton Components	135
JRadioButton Properties	136
Grouping JRadioButton Components in a ButtonGroup	136
Handling JRadioButton Selection Events	139
Customizing a JRadioButton Look and Feel	147
Summary	149

CHAPTER 6 **Swing Menus and Toolbars** 151

Working with Menus	152
Menu Class Hierarchy	156
JMenuBar Class	157

SingleSelectionModel Interface	161
JMenuItem Class	162
JMenu Class	168
JSeparator Class	175
JPopupMenu Class	176
JCheckBoxMenuItem Class	184
JRadioButtonMenuItem Class	189
Creating Custom MenuElement Components:	
The MenuElement Interface	195
Working with Pop-Ups: The Popup Class	200
Creating Pop-Up Components	200
A Complete Popup/PopupFactory Usage Example	200
Working with Toolbars: The JToolBar Class	202
Creating JToolBar Components	202
Adding Components to a JToolBar	202
JToolBar Properties	203
Handling JToolBar Events	205
Customizing a JToolBar Look and Feel	205
A Complete JToolBar Usage Example	206
JToolBar.Separator Class	208
Summary	208

■ CHAPTER 7 **Borders** 211

Some Basics on Working with Borders	211
Exploring the Border Interface	212
Introducing BorderFactory	215
Starting with AbstractBorder	216
Examining the Predefined Borders	218
EmptyBorder Class	218
LineBorder Class	219
BevelBorder Class	220
SoftBevelBorder Class	222
EtchedBorder Class	223
MatteBorder Class	224
CompoundBorder Class	226
TitledBorder Class	227
Creating Your Own Borders	232
Summary	234

CHAPTER 8	Root Pane Containers	235
	JRootPane Class	235
	Creating a JRootPane	236
	JRootPane Properties	236
	Customizing a JRootPane Look and Feel	238
	RootPaneContainer Interface	239
	JLayeredPane Class	239
	JFrame Class	242
	Creating a JFrame	243
	JFrame Properties	243
	Adding Components to a JFrame	245
	Handling JFrame Events	245
	Extending JFrame	246
	JWindow Class	247
	Creating a JWindow	247
	JWindow Properties	248
	Handling JWindow Events	248
	Extending JWindow	248
	JDialog Class	248
	Creating a JDialog	248
	JDialog Properties	250
	Handling JDialog Events	250
	Extending JDialog	252
	JApplet Class	252
	Working with a Desktop	252
	JInternalFrame Class	253
	JDesktopPane Class	262
	Summary	266
CHAPTER 9	Pop-Ups and Choosers	267
	JOptionPane Class	267
	Creating a JOptionPane	268
	Displaying a JOptionPane	271
	Automatically Creating a JOptionPane in a Pop-Up Window	274
	JOptionPane Properties	280
	Customizing a JOptionPane Look and Feel	287

ProgressMonitor Class	291
Creating a ProgressMonitor	292
Using a ProgressMonitor	293
ProgressMonitor Properties	296
Customizing a ProgressMonitor Look and Feel	297
ProgressMonitorInputStream Class	297
Creating a ProgressMonitorInputStream	297
Using a ProgressMonitorInputStream	298
ProgressMonitorInputStream Properties	299
JColorChooser Class	300
Creating a JColorChooser	301
Using JColorChooser	302
JColorChooser Properties	307
Customizing a JColorChooser Look and Feel	320
JFileChooser Class	322
Creating a JFileChooser	323
Using JFileChooser	323
JFileChooser Properties	326
Working with File Filters	328
Customizing a JFileChooser Look and Feel	336
Summary	341

■ CHAPTER 10 **Layout Managers** 343

Layout Manager Responsibilities	343
LayoutManager Interface	344
Exploring the LayoutManager Interface	344
Exploring the LayoutManager2 Interface	345
FlowLayout Class	345
BorderLayout Class	347
GridLayout Class	349
GridBagLayout Class	350
GridBagLayout Rows and Columns	353
GridBagConstraints Class	353
CardLayout Class	357
BoxLayout Class	357
Creating a BoxLayout	358
Laying Out Components	359
OverlayLayout Class	365
SizeRequirements Class	370

ScrollPaneLayout Class	370
ViewportLayout Class	371
SpringLayout Class	371
Summary	375

■ CHAPTER 11 **Advanced Swing Containers** 377

Box Class	377
Creating a Box	378
Box Properties	379
Working with Box.Filler	380
Creating Areas That Grow	380
Creating Rigid Areas	382
JSplitPane Class	383
Creating a JSplitPane	384
JSplitPane Properties	385
Listening for JSplitPane Property Changes	390
Customizing a JSplitPane Look and Feel	393
JTabbedPane Class	394
Creating a JTabbedPane	395
Adding and Removing Tabs	397
JTabbedPane Properties	398
Listening for Changing Tab Selection	399
Customizing a JTabbedPane Look and Feel	401
JScrollPane Class	403
Creating a JScrollPane	404
Changing the Viewport View	406
Scrollable Interface	406
JScrollPane Properties	407
Customizing a JScrollPane Look and Feel	410
JViewport Class	412
Creating a JViewport	412
JViewport Properties	412
Customizing a JViewport Look and Feel	417
Summary	417

■ CHAPTER 12 **Bounded Range Components** 419

BoundedRangeModel Interface	419
DefaultBoundedRangeModel Class	420

JScrollBar Class	421
Creating JScrollBar Components	422
Handling Scrolling Events	423
JScrollBar Properties	426
Customizing a JScrollBar Look and Feel	427
JSlider Class	428
Creating JSlider Components	428
Handling JSlider Events	430
JSlider Properties	431
Customizing a JSlider Look and Feel	435
JSlider Client Properties	438
JProgressBar Class	439
Creating JProgressBar Components	439
JProgressBar Properties	440
Handling JProgressBar Events	445
Customizing a JProgressBar Look and Feel	446
JTextField Class and BoundedRangeModel Interface	447
Summary	449

■ CHAPTER 13 List Model Controls

ListModel Interface	451
AbstractListModel Class	452
DefaultListModel Class	453
Listening for ListModel Events with a ListDataListener	454
ComboBoxModel Interface	460
MutableComboBoxModel Interface	460
DefaultComboBoxModel Class	460
JList Class	463
Creating JList Components	463
JList Properties	464
Scrolling JList Components	466
Rendering JList Elements	468
Selecting JList Elements	473
Displaying Multiple Columns	479
Customizing a JList Look and Feel	480
Creating a Dual List Box	481
Adding Element-Level Tooltips to List Items	488

JComboBox Class	490
Creating JComboBox Components	491
JComboBox Properties	491
Rendering JComboBox Elements	493
Selecting JComboBox Elements	493
Editing JComboBox Elements	497
Customizing a JComboBox Look and Feel	503
Sharing the Data Model for a JComboBox and JList	506
Summary	508

CHAPTER 14 Spinner Model Controls 509

JSpinner Class	509
Creating JSpinner Components	510
JSpinner Properties	510
Listening for JSpinner Events with a ChangeListener	511
Customizing a JSpinner Look and Feel	512
SpinnerModel Interface	513
AbstractSpinnerModel Class	513
SpinnerDateModel Class	514
SpinnerListModel Class	515
SpinnerNumberModel Class	516
Custom Models	517
JSpinner Editors	518
JSpinner.DefaultEditor Class	518
JSpinner.DateEditor Class	519
JSpinner.ListEditor Class	519
JSpinner.NumberEditor Class	520
Summary	520

CHAPTER 15 Basic Text Components 521

Overview of the Swing Text Components	521
JTextComponent Class	523
JTextComponent Properties	523
JTextComponent Operations	526
JTextField Class	526
Creating a JTextField	527
Using JLabel Mnemonics	527
JTextField Properties	529

JTextComponent Operations with a JTextField	530
Document Interface	537
DocumentListener and DocumentEvent Interfaces	546
Caret and Highlighter Interfaces	547
CaretListener Interface and CaretEvent Class	550
NavigationFilter Class	552
Keymap Interface	554
JTextComponent.KeyBinding Class	556
Handling JTextField Events	556
Customizing a JTextField Look and Feel	562
JPasswordField Class	563
Creating a JPasswordField	563
JPasswordField Properties	564
Customizing a JPasswordField Look and Feel	565
JFormattedTextField Class	566
Creating a JFormattedTextField	566
JFormattedTextField Properties	567
Customizing a JFormattedTextField Look and Feel	569
JTextArea Class	570
Creating a JTextArea	570
JTextArea Properties	571
Handling JTextArea Events	572
Customizing a JTextArea Look and Feel	572
JEditorPane Class	574
Creating a JEditorPane	575
JEditorPane Properties	575
Handling JEditorPane Events	576
Customizing a JEditorPane Look and Feel	579
JTextPane Class	580
Creating a JTextPane	580
JTextPane Properties	580
Customizing a JTextPane Look and Feel	581
Loading a JTextPane with Content	582
Summary	584
 CHAPTER 16 Advanced Text Capabilities	585
Using Actions with Text Components	585
Listing Actions	586
Using Actions	589
Finding Actions	591

Creating Styled Text	595
StyledDocument Interface and DefaultStyledDocument Class ...	595
AttributeSet Interface	597
MutableAttributeSet Interface	597
SimpleAttributeSet Class	597
StyleConstants Class	601
TabStop and TabSet Classes	603
Style Interface	606
StyleContext Class	606
The Editor Kits	607
Loading HTML Documents	607
Iterating Through HTML Documents	608
JFormattedTextField Formats	612
Dates and Numbers	612
Input Masks	618
DefaultFormatterFactory Class	620
Summary	621

CHAPTER 17 **Trees**

Introducing Trees	623
JTree Class	624
Creating a JTree	624
Scrolling Trees	627
JTree Properties	628
Customizing a JTree Look and Feel	630
TreeCellRenderer Interface	634
DefaultTreeCellRenderer Class	635
DefaultTreeCellRenderer Properties	635
Creating a Custom Renderer	637
Working with Tree Tooltips	641
Editing Tree Nodes	643
CellEditor Interface	644
TreeCellEditor Interface	644
DefaultCellEditor Class	645
DefaultTreeCellEditor Class	647
Creating a Proper ComboBox Editor for a Tree	648
Creating an Editor Just for Leaf Nodes	648
CellEditorListener Interface and ChangeEvent Class	650
Creating a Better Check Box Node Editor	650

Working with the Nodes of the Tree	659
TreeNode Interface	659
MutableTreeNode Interface	660
DefaultMutableTreeNode Class	661
Traversing Trees	664
JTree.DynamicUtilTreeNode Class	666
TreeModel Interface	667
DefaultTreeModel Class	667
TreeModelListener Interface and TreeModelEvent Class	668
TreeSelectionModel Interface	668
DefaultTreeSelectionModel Class	670
TreeSelectionListener Interface and TreeSelectionEvent Class	671
TreePath Class	671
Additional Expansion Events	672
TreeExpansionListener Interface and TreeExpansionEvent Class	672
TreeWillExpandListener Interface and ExpandVetoException Class	673
Summary	674

■ CHAPTER 18 Tables

Introducing Tables	675
JTable Class	677
Creating a JTable	677
Scrolling JTable Components	678
Manually Positioning the JTable View	679
Removing Column Headers	680
JTable Properties	680
Rendering Table Cells	686
Handling JTable Events	689
Customizing a JTable Look and Feel	689
TableModel Interface	690
AbstractTableModel Class	691
DefaultTableModel Class	696
Sorting JTable Elements	700
TableColumnModel Interface	707
DefaultTableColumnModel Class	708
Listening to JTable Events with a TableColumnModelListener ...	709
TableColumn Class	712

JTableHeader Class	715
Creating a JTableHeader	716
JTableHeader Properties	716
Using Tooltips in Table Headers	716
Customizing a JTableHeader Look and Feel	717
Editing Table Cells	718
TableCellEditor Interface and DefaultCellEditor Class	718
Creating a Simple Cell Editor	718
Creating a Complex Cell Editor	722
Printing Tables	724
Summary	728
 ■ CHAPTER 19 Drag-and-Drop Support	729
Built-in Drag-and-Drop Support	729
TransferHandler Class	731
Drag-and-Drop Support for Images	733
Summary	740
 ■ CHAPTER 20 The Pluggable Look and Feel Architecture	741
LookAndFeel Class	741
Listing the Installed Look and Feel Classes	742
Changing the Current Look and Feel	743
Customizing the Current Look and Feel	747
Creating a New Look and Feel	767
Using the WindowsLookAndFeel on a Non-Windows Machine ...	767
Adding UI Delegates	771
Working with Metal Themes	772
MetalTheme Class	772
DefaultMetalTheme and OceanTheme Classes	774
Using an Auxiliary Look and Feel	776
SynthLookAndFeel Class	777
Configuring Synth	777
Default Synth Properties	780
Working with Synth Images	780
Summary	781

CHAPTER 21	The Undo Framework	783
	Working with the Undo Framework	783
	Using the Undo Framework with Swing Text Components	784
	The Command Design Pattern	788
	Undo Framework Components	789
	UndoableEdit Interface	789
	AbstractUndoableEdit Class	791
	CompoundEdit Class	791
	UndoManager Class	792
	UndoableEditListener Interface and UndoableEditEvent Class	794
	UndoableEditSupport Class	794
	A Complete Undoable Program Example	795
	Using an Outside Object to Manage Undo States	800
	StateEditable Interface	800
	StateEdit Class	801
	A Complete StateEditable/StateEdit Example	801
	Summary	804
CHAPTER 22	Accessibility	805
	Accessibility Classes	805
	Accessible Interface	806
	AccessibleContext Class	806
	Creating Accessible Components	807
	Working with the Java Access Bridge	808
	Summary	811
APPENDIX	UI Manager Properties	813
INDEX		847

About the Author



JOHN ZUKOWSKI has been involved with the Java platform since it was just called Java, pushing ten years now. He currently writes a monthly column for Sun's Core Java Technologies Tech Tips (<http://java.sun.com/developer/JDCTechTips/>) and IBM's developerWorks (<http://www-136.ibm.com/developerworks/java/>). He has contributed content to numerous other sites, including jGuru (<http://www.jguru.com>), DevX (<http://www.devx.com/>), Intel (<http://www.intel.com/>), and JavaWorld (<http://www.javaworld.com/>).

He is the author of many other popular titles on Java, including *Java AWT Reference* (O'Reilly and Associates), *Mastering Java 2* (Sybex), *Borland's JBuilder: No Experience Required* (Sybex), *Learn Java with JBuilder 6* (Apress), *Java Collections* (Apress), and *Definitive Guide to Swing for Java 2* (Apress).

About the Technical Reviewers

This book was technically reviewed by Daren Klamer, David Vittor, Hido Hasimbegovic, Charlie Castaneda, and Robert Castaneda, who are all part of the CustomWare Asia Pacific team working on numerous Java and integration-based projects in Australia and the Asia Pacific region. Their web site is <http://www.customware.net>.

Acknowledgments

This book has been a long time coming, with various starts and stops, and getting sidetracked a few times along the way. Now that it is all done, I need to thank those who helped.

For starters, I want to thank everyone at Apress who hung in there and had patience when dealing with me throughout the project, especially project manager Beth Christmas, who I'm sure I drove nuts at times, and editor Steve Anglin, who kept nudging me along. On the production side, I'd like to thank Marilyn Smith for all the input and updates, Ellie Fountain for her hard work at ensuring little changes got done right, and, of course, my technical reviewer Rob Castaneda and the team at CustomWare for all the input on my rough work. Congrats on that marriage thing.

Some of the images used in the sample programs were made by Deb Felts, who ran a web site called the Image Addict's Attic. The site doesn't seem to be online any more, but the images are used with permission and she does retain copyright on them. Sun also maintains the Java Look and Feel Graphics Repository at <http://java.sun.com/developer/techDocs/hi/repository/>, with its own set of images to be used for Java applications.

For all the readers out there, thanks for asking me to do the update. Without your continued support, you wouldn't be holding this book in your hands.

For their continued encouragement along the way, I'd like to personally thank the following: Joe Sam Shirah, thanks for doing that long drive to visit while I was in Florida for the conference; my Aunt Mary Hamfeldt, congrats on your first grandchild; our Realtor Nancy Moore, thanks for putting up with us for so long; Miguel Muniz, thanks for all the bug reports at SavaJe; Matthew B. Doar, thanks for JDiff (<http://www.jdiff.org/>), a great little Java doclet for reporting API differences. Happy tenth birthday, Duke and Java.

I am forever grateful to my wife, Lisa, for her support, and our dog, Jaeger, for his playfulness. Thanks to Dad, too. Good luck at the casinos.

Introduction

Welcome to *Learn Java 5.0 Swing in a Nutshell for Dummies in 21 Days*. Since the beginning of Java time (1995), the component libraries have been actively evolving. What began as a small set of nine AWT components, plus menus and containers, has grown to a more complete and complex set of around 50 Swing components—all just to create graphical user interfaces (GUIs) for your Java client-side programs. That’s where this book comes in. Its purpose is to make your life easier in creating those GUIs.

Earlier editions of this book took the approach that if the class wasn’t found in the `javax.swing` package, it wasn’t covered in the book. This third edition takes a more complete view of creating GUIs. For instance, instead of just describing the Swing layout managers, there is also material on the AWT layout managers, since you’re likely to be using them.

The first edition of this book was written for a mix of the Java 1.1 and 1.2 developer. The second edition hit the 1.3 platform. This edition is wholly for the 5.0 developer. Almost all the programs will not work on a 1.4 platform, though with a little tweaking, they can be made to do so.

In this book, you’ll find a tutorial-like approach to learning about the Swing libraries and related capabilities. It is not an API reference book, nor is it a primer that describes how to install the Java Development Kit (JDK), compile your programs, or run them. If you need help in those areas, consider using an integrated development environment (IDE)—such as IntelliJ IDEA, Eclipse, or Borland’s JBuilder—or get one of Apress’s other books, such as *Beginning Java Objects*, by Jacquie Barker.

Is this book for you? If you are new to the Java platform, you might want to start with a more introductory text first, before jumping on the Swing bandwagon. On the other hand, if you’ve been working with Java for a while and have decided it’s time to start using the Swing component set, you’ll find this book extremely useful. With this book, you won’t have to drudge through the countless Swing classes for a way to accomplish that impossible task. You’ll become much more productive more quickly, and you’ll be able to make the most of the many reusable components and techniques available with Swing.

Book Structure

This book can be read from cover to cover, but it doesn’t have to be done that way. It’s true that later sections of the book assume you’ve absorbed knowledge from the earlier sections. However, if you want to find something on a topic covered in a later chapter, you don’t need to read all the chapters that precede it first. If you come across something that’s unfamiliar to you, you can always go back to the earlier chapter or search the index to locate the information you need.

The contents of this book are grouped into three logical sections:

Chapters 1 through 4 provide general knowledge that will prove to be useful as you read through the remainder of the book. In Chapter 1, you'll find an overview of the Swing component set. Chapter 2 details event handling with the Swing component set. It describes the delegation-based event model and focus management policies used by Swing. In Chapter 3, you'll learn about the Model-View-Controller (MVC) architecture. You can avoid using MVC if you wish, but to take full advantage of everything that Swing has to offer, it helps to have a good grasp of MVC concepts. In Chapter 4, you'll find the beginning coverage of the specific Swing components. All Swing components share many of the same attributes, and in Chapter 4, you'll learn the foundation for those common behaviors.

In Chapters 5 through 15, you'll discover the many aspects of the reusable Swing components. You'll find out about menus, toolbars, borders, high-level containers, pop-up dialogs, layout managers, advanced Swing containers, bounded range components, toggle components, list model components, spinners, and text components. Most of what you'll want to accomplish with the Swing libraries is discussed in these chapters.

In Chapters 16 through 22, some of the more advanced Swing topics are covered. These tend to be the areas that even the experienced developers find the most confusing. Chapter 16 goes beyond the basics of text component handling found in Chapter 15. Chapters 17 and 18 deal with the Swing tree and table components. These components allow you to display hierarchical or tabular data. In Chapter 19, you'll learn about drag-and-drop support in Swing. Chapter 20 explores how to customize the appearance of your application. Because the Swing libraries are completely Java-based, if you don't like the way something is done or how it appears, you can change it. In Chapter 21, you'll learn about the undo framework, which offers undo and redo support for your applications. Finally, in Chapter 22, you finish off with a look into the accessibility framework offered by Swing, such as support for screen readers and magnifying glasses to help those needing assistive technologies.

The Appendix contains a list of about 1,000 settable properties the user interface manager employs to configure the appearance of the Swing components for the current look and feel. The Swing components manage various defaults, such as colors and fonts applied to components, so you don't need to subclass a component in order to customize its appearance. Appendix A gathers all of the property settings listed throughout the chapters into one comprehensive list for easy reference.

Support

You can head to many places online to get technical support for Swing and answers to general Java questions. Here's a list of some of the more useful places around:

- The Java Ranch at <http://www.javaranch.com/> offers forums for just about everything in the Big Moose Saloon.
- Java Forums at <http://forums.java.sun.com/> are Sun's online forums for Java development issues.

- developerWorks at <http://www.ibm.com/developerworks/java/> is the IBM's developer community for Java with forums and tutorials.
- jGuru at <http://www.jguru.com> offers a series of FAQs and forums for finding answers.
- Marcus Green's Java Certification Exam Discussion Forum at <http://www.jchq.net/discus/> provides support for those going the certification route.

While I would love to be able to answer all reader questions, I get swamped with e-mail and real-life responsibilities. Please consider using these resources to get help.

About Java

Java is one of 13,000 islands that makes up Indonesia, whose capital is Jakarta. It is home to about 120 million people with an area about 50,000 square miles (132,000 square kilometers). While on the island, you can hear traditional music such as gamelan or angklung and enjoy Java's main export, a coffee that is considered spicy and full-bodied, with a strong, slightly acidic flavor. The island also has a dangerous volcano named Merapi, which makes up part of the Pacific "Ring of Fire." In 1891, on the island, Eugene Dubois discovered fossils from *Pithecanthropus erectus*, better known as Java man (*homo javanensis*).

For more information, see [http://encyclopedia.lockergnome.com/s/b/Java_\(island\)](http://encyclopedia.lockergnome.com/s/b/Java_(island)).



Swing Overview

According to *Encyclopedia Britannica*, Swing was a popular music in the United States, circa 1930–1945. Okay, maybe not in the Java sense. Instead, on May 23, 1995, John Gage, then director of the Science Office for Sun, introduced Java to the world. With its birth came something called the Abstract Window Toolkit, or AWT. In turn, with AWT came native widgets, and with this early native widget set came . . . trouble.

The original component set that came with the Java platform, AWT, was dependent on too many idiosyncrasies of the underlying platform. Instead of providing a mature-looking component set, Java offered the lowest common denominator version. If a feature wasn't available on all Java platforms, it wasn't available on any Java platform. And then you had to deal with all the browser/platform differences. Each Java runtime environment relied on how the component set was connected with the underlying platform-specific native widget set. If there were issues with the connection, first, they were specific to the platform (and/or browser) and second, you had to code around these problems so your programs could be write-once, run anywhere (WORA), the Java mantra of the time.

As Java technologies became more popular, users realized AWT was extremely slow and unreliable, and you couldn't really do much with the provided components. Very few of them were available, and you couldn't use them in a visual programming environment. So, new technologies were introduced, such as just-in-time (JIT) compilers to improve performance and, with Borland's help, JavaBeans for a component-based development.

With these new technologies came more and more widget sets, for the AWT component set itself was very basic. So, applet download times grew and grew, because these new widget sets weren't part of the core Java platform, and Java archive (JAR) files were introduced to improve delivery time. Eventually, each of the major browser vendors added its favorite component library to its virtual machine—AFC, IFC, and WFC, to name just a few. Yet all the libraries used different design models, and there were no true cross-browser standards.

Eventually, Sun Microsystems teamed up with Netscape Communication and other partners to create yet another library called the Java Foundation Classes, or JFC. Part of JFC is something called the Swing component set. This Swing component set is what this book is all about.

Note Later technologies were introduced to help people use the Swing components within a browser and with web-based application delivery. These include the Java Plug-in (<http://java.sun.com/products/plugin/>) and Java Web Start (<http://java.sun.com/products/javawebstart/>). Alternatives to Swing, like the SWT component set with Eclipse (<http://www.eclipse.org/swt/>), have also been created. These are not discussed here.

This chapter will familiarize you with the various Swing pieces. For starters, there is the component set. Without these, there is no Swing. Next, you'll peek at the world of event handling and layout management common to both AWT and Swing components. After that, you'll take a quick look at the undo/redo framework available within the Swing architecture. Then you'll explore the SwingSet2 demonstration provided with the Java 2 Platform Standard Edition 5.0 Development Kit (JDK 5.0) so that you can see some of the capabilities. Lastly, I'll point out where in the book all these capabilities are discussed in detail.

Getting to Know the Swing Components

The book will serve as a guide to development using the Swing component set. Over the course of its pages, you'll look at every package in the `javax.swing` package hierarchy, as shown in Figure 1-1.




Figure 1-1. *The Swing package hierarchy*

Note The `javax.swing.plaf` package contains several subpackages and related packages, some of which are located outside the `javax.swing` package hierarchy. *Plaf* stands for pluggable look and feel—a Swing concept that will be described more fully in Chapter 20.

The Swing component set is one big group of components. While the JDK 5.0 release didn't add any new Swing components to the mix, logically, you can think of them as those with duplicate components within AWT and those without.

AWT Component Replacements

The Swing component set was originally created because the basic AWT components that came with the original version of the Java libraries were insufficient for real-world, forms-based applications. All the basic components were there, but the existing set was too small and far too restrictive. For instance, you couldn't even put an image on a button. To alleviate this situation, the Swing component set offers replacements for each of the AWT components. The Swing components support all the capabilities of the original set and offer a whole lot more besides. As such, you should never need to deal with any of the basic AWT components.

Note Although the Swing components replace the AWT components, you'll still need to understand several basic AWT concepts, such as layout managers, event handling, and drawing support. In addition, you'll need to grasp the concept that all of Swing is built on top of the core AWT libraries.

The basic distinction between the Swing and equivalent AWT components is, in most cases, the Swing component class names begin with a *J* and the AWT ones don't. Swing's `JButton` is a replacement for the AWT `Button` component. One exception is the `JComboBox`, which replaces the AWT `Choice` component.

At the application programming interface (API) level, the Swing components are almost always a superset of the features the AWT components support. While they support additional capabilities, the basic AWT capabilities are there for everything but the `JList` component, whose API is completely unlike that of the AWT `List` component. Table 1-1 maps the original AWT components to their replacement Swing components.

Table 1-1. *AWT to Swing Component Mapping*

AWT Component	Nearest Swing Replacement
Button	<code>JButton</code>
Canvas	<code>JPanel</code>
Checkbox	<code>JCheckBox</code>
Checkbox in <code>CheckboxGroup</code>	<code>JRadioButton</code> in <code>ButtonGroup</code>
Choice	<code>JComboBox</code>
Component	<code>JComponent</code>
Container	<code>JPanel</code>
Label	<code>JLabel</code>
List	<code>JList</code>

Table 1-1. *AWT to Swing Component Mapping (Continued)*

AWT Component	Nearest Swing Replacement
Menu	JMenu
MenuBar	JMenuBar
MenuItem	JMenuItem
Panel	JPanel
PopupMenu	JPopupMenu
Scrollbar	JScrollbar
ScrollPane	JScrollPane
TextArea	JTextArea
TextField	JTextField

Note For most people, the fact that the Swing components replace AWT components is irrelevant. Just treat the Swing components as an *independent* component set, and you'll be perfectly okay.

To help you understand how to use the Swing components, you'll examine each of the components in this book. For instance, Chapter 4 looks at how the JButton component works, with just a single line of text as its label, like an AWT Button, but adds capabilities, such as using image icons on buttons and working with multiple lines of text. To find out where each component is discussed in this book, see the "Swing Component to Chapter Mapping" section later in this chapter.

In addition to replacing each of the basic components, the Swing component set has a replacement for the higher-level window objects. Although the only change in most of the components' names is the beginning *J*, you'll discover in Chapter 8 how the high-level container objects are much different in the Swing world. Swing's replacement for the old FileDialog object differs even more and is discussed in Chapter 9. Table 1-2 maps the high-level window objects from the AWT component world to the Swing universe.

Table 1-2. *AWT to Swing Window Mapping*

AWT Window	Nearest Swing Replacement
Applet	JApplet
Dialog	JDialog
FileDialog	JFileChooser
Frame	JFrame
Window	JWindow

Whereas the AWT components rely on the user's operating system to provide the actual component to a Java program, Swing components are all controlled from within the Java runtime. The AWT approach is called either the *heavyweight* or the *peered* approach; most Swing components are *lightweight* or *peerless*. You'll explore the basics of this approach in Chapter 4 with the JComponent. Additional features for customizing the look and feel of components are discussed in Chapter 20.

Non-AWT Upgraded Components

In addition to offering replacements for all the basic AWT components, the Swing component set includes twice as many new components.

Note If you're new to Java, just think of all of these components—both the AWT component replacements and those that were not in the AWT—as one big set of components, versus two distinct sets.

Here's a look at those components that didn't originate in the AWT world:

- JPasswordField: This specialized text field is for password entry, as shown in Figure 1-2. You cannot use cut or copy operations within the component, but you can paste text into it.




Figure 1-2. The Swing JPasswordField

- JEditorPane and JTextPane: These two components provide support for displaying and editing multiple-attributed content, such as an HTML and RTF viewer. Figure 1-3 shows a JEditorPane component.




Figure 1-3. The Swing JEditorPane

- **JSpinner:** This component, shown in Figure 1-4, provides selection from an ordered set of predefined values, offering arrows to scroll through the next and previous choices. The predefined values can be an array of strings, a sequential set of numbers, or a date.




Figure 1-4. *The Swing JSpinner*

- **JToggleButton:** This component offers a button that stays depressed when selected. In the example shown in Figure 1-5, the North, East, and South buttons are depressed.




Figure 1-5. *The Swing JToggleButton*

- **JSlider:** This component is like the Scrollbar component of AWT (or JScrollbar in the Swing component set). However, its purpose in Swing is for user input. It offers various clues to help the user choose a value. Figure 1-6 shows an example of a JSlider component.




Figure 1-6. *The Swing JSlider*

- **JProgressBar:** This component allows the user to visually see the progress of an activity. Some options available include showing static text or percentage done, as shown in Figure 1-7.




Figure 1-7. *The Swing JProgressBar*

- `JFormattedTextField`: This component provides for the input of formatted text, like numeric values, phone numbers, dates, or social security numbers. Figure 1-8 shows two examples of this component.




Figure 1-8. *The Swing `JFormattedTextField`*

- `JTable`: This component provides for the display of two-dimensional row and column information, such as stock quotes, as in the example shown in Figure 1-9.



Symbol	Name	Price
AMZN	Amazon	38.94
DCLK	DoubleClick	7.70
EBAY	eBay	112.65
GOOG	Google	181.05
MKTW	MarketWatch	18.08
SAP	SAP AG	45.35
SUNW	Sun Microsyst...	5.51
TWXX	Time Warner	17.82
VOD	Vodafone Group	27.39
YHOO	Yahoo!	38.17

Figure 1-9. *The Swing `JTable`*

- `JTree`: This component supports the display of hierarchical data. Figure 1-10 shows an example of a `JTree` component.




Figure 1-10. *The Swing `JTree`*

- `JToolTip`: Through this component, all Swing components support pop-up text for offering useful tips. Figure 1-11 shows an example of a `JToolTip` component added to a `JSlider`.




Figure 1-11. *The Swing JToolTip*

- **JToolBar:** This container offers a draggable toolbar to be included within any program window, as shown in Figure 1-12.




Figure 1-12. *The Swing JToolBar*

- **JRadioButtonMenuItem:** This component is an addition to the set of menu components. With it, you can have radio buttons on a menu for mutually exclusive choices, as shown in the example in Figure 1-13. There's also a **JCheckBoxMenuItem** component, for when you don't need mutually exclusive choices.




Figure 1-13. *The Swing JRadioButtonMenuItem*

- **JSeparator:** The menu's separator bar is now its own component and can be used outside of menus, too, as shown in Figure 1-14.




Figure 1-14. *The Swing JSeparator*

- **JDesktopPane** and **JInternalFrame:** This pair of components allows you to develop applications using the familiar Windows Multiple Document Interface (MDI). Figure 1-15 shows an example.




Figure 1-15. *The Swing JDesktopPane and JInternalFrame*

- JOptionPane: This component allows you to easily create pop-up windows with varied content, as shown in Figure 1-16.




Figure 1-16. *The Swing JOptionPane*

- JColorChooser: This component is for choosing a color, with different views available to select the color, as shown in Figure 1-17.




Figure 1-17. *The Swing JColorChooser*

- `JSplitPane`: This container allows you to place multiple components in a window. It also allows the user control over how much of each component is visible. Figure 1-18 shows an example of a `JSplitPane`.




Figure 1-18. *The Swing JSplitPane*

- `JTabbedPane`: This component is like a container whose layout manager is `CardLayout` (discussed in Chapter 10), with labeled tabs automatically provided to allow the user to swap cards. This provides you with the familiar property-sheet motif, as shown in Figure 1-19.




Figure 1-19. *The Swing JTabbedPane*

You'll learn about all of these components throughout this book. Refer to the "Swing Component to Chapter Mapping" section later in this chapter to see where each component is covered.

Event Handling and Layout Management

To use the Swing components successfully, you must understand the underlying parts of the original AWT component set. For instance, the Swing components all support the delegation-based event model, which was introduced with JDK 1.1 and is supported by the AWT 1.1 component set. In addition, layout managers control screen layout.

Note The Swing components don't support the original JDK 1.0 event model. They no longer use the public boolean `handleEvent(Event)` method and all its helper methods. If you need to convert an AWT program that uses the JDK 1.0 event model to one that uses the Swing components, you'll need to convert the program to use the delegation-based event model, in addition to changing the component set.

Although directly porting old Java AWT programs (or programmers!) to Swing programs is done most easily by continuing to use the delegation-based event model, this solution is rarely the best one. Besides supporting the delegation-based event model, the Swing components provide other, more efficient ways of dealing with events for components. In Chapter 2, you'll explore the delegation-based event model and look at the other ways of managing event handling.

In addition to the delegation-based event-handling support, the Swing components use the Model-View-Controller (MVC) design to separate their user interfaces from their underlying data models. Using the MVC architecture provides yet another way of event handling with a Swing component. While MVC might be new to most developers, the basic constructs use the delegation-based event model. MVC provides the optimal way of working with the Swing components. You'll find an overview of the MVC architecture in Chapter 3.

Besides all the support for extended event handling with the Swing classes, these classes share the need to use a layout manager for positioning components on the screen. In addition to using the layout managers that come with AWT, you can use other layout managers that come with the Swing classes. In Chapter 10, you'll learn about both the AWT and Swing layout managers.

Undo Framework

Situated within the `javax.swing` class hierarchy are the `javax.swing.undo` classes. These classes offer a framework for supporting undo and redo capabilities within Java programs. Instead of creating the basic framework yourself, the framework is provided as part of the Swing classes.

Although the undo classes don't use anything directly outside their package, the Swing text components use the undo functionality. Chapter 21 provides a detailed explanation of undo.

SwingSet Demonstration

As part of the `demo/jfc` directory with the Java 2 platform, you have available a Swing demonstration program called `SwingSet2`. This program provides a quick preview of the majority of the Swing capabilities. All the source code is included, so if you see something you like and are interested in learning how it was done, just dig through the code to find the appropriate lines.

With the Java 2 platform, you start up this demonstration from the `SwingSet2` directory with the `java -jar SwingSet2.jar` command. After starting the `SwingSet2` demonstration, you see the opening screen, as shown in Figure 1-20.




Figure 1-20. *SwingSet2 startup screen*

Choose the different buttons and tabs to see many of the features supported by the Swing components.

Swing Component to Chapter Mapping

The Swing packages contain many classes and components. To help you find where all the different components are discussed, Table 1-3 provides a handy reference (with the components listed alphabetically).

Table 1-3. *Mapping of Swing Components to Chapters in This Book*

Swing Component	Chapter
Box	11
JApplet	8
JButton	4
JCheckBox	5
JCheckBoxMenuItem	6
JColorChooser	9
JComboBox	13
JComponent	4
JDesktopPane	8
JDialog	8
JEditorPane	15
JFileChooser	9
JFormattedTextField	15
JFrame	8
JInternalFrame	8
JLabel	4
JLayeredPane	8
JList	13
JMenu	6
JMenuBar	6
JMenuItem	6
JOptionPane	9
JPanel	4
JPasswordField	15
JPopupMenu	6
JProgressBar	12
JRadioButton	5
JRadioButtonMenuItem	6

Table 1-3. *Mapping of Swing Components to Chapters in This Book (Continued)*

Swing Component	Chapter
JRootPane	8
JScrollBar	12
JScrollPane	11
JSeparator	6
JSlider	12
JSpinner	14
JSplitPane	11
JTabbedPane	11
JTable	18
JTextArea	15
TextField	15
JTextPane	15
JToggleButton	5
JToolBar	6
JToolTip	4
JTree	17
JViewport	11
JWindow	8

In addition to information about using the different components, the following chapters feature a table for each component that lists the JavaBeans properties defined by that component. Each table notes whether a property has a setter (*setPropertyName(newValue)*), a getter (*getPropertyName()*), or an *isPropertyName()* method defined by the class, and whether a property is bound (you can listen for a *PropertyChangeEvent*). In these property tables, inherited properties aren't listed, so even though a property for a component is listed as write-only, the parent class might still provide a getter method. As an example, Table 1-4 shows the property table for the *JScrollBar* component.

Table 1-4. *JScrollBar Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
adjustmentListeners	AdjustmentListener[]	Read-only
blockIncrement	int	Read-write bound
enabled	boolean	Write-only

Table 1-4. *JScrollBar Properties (Continued)*

Property Name	Data Type	Access
maximum	int	Read-write
maximumSize	Dimension	Read-only
minimum	int	Read-write
minimumSize	Dimension	Read-only
model	BoundedRangeModel	Read-write bound
orientation	int	Read-write bound
UI	ScrollBarUI	Read-write bound
UIClassID	String	Read-only
unitIncrement	int	Read-write bound
value	int	Read-write bound
valueIsAdjusting	boolean	Read-write bound
visibleAmount	int	Read-write

Besides the property tables, you'll find information about important aspects of each component and the techniques for using them.

Note This book is not intended to be an API reference, nor does it cover everything about each component. For the lesser-used aspects of a component, see the online `javadoc` documentation.

Summary

This chapter provided a brief overview of what will be covered in this book, such as the many essential parts of the Swing component set you need to understand in order to use Swing components. The combined set of `javax.swing` packages is larger than the entire first JDK, if not the first two.

In Chapter 2, you'll explore how to deal with the many aspects of event handling using the Swing components. In addition to reviewing the delegation-based event model, you'll look at different ways you can deal with events when using Swing components and get a grasp of the focus traversal policies involved with Swing.



Event Handling with the Swing Component Set

Chapter 1 provided a brief overview of the Swing component set. In this chapter, you will start to look at the details of one aspect of using Swing components: event handling. When working with the Swing component set, the delegation-based event-handling mechanism is available, but you can also take advantage of several additional ways to respond to user-initiated actions (as well as to programmatic events). In this chapter, you'll explore all these event-handling response mechanisms. You'll also learn how Swing manages input focus and some techniques for controlling how focus is handled.

As you explore event-handling capabilities, you will start to look at some actual Swing components. In this chapter, you will be using the components in the simplest manner possible. Feel free to first read up on the components covered in later chapters of this book, and then come back to this chapter for a general discussion of event handling. The later chapters of this book also contain specific details on event handling for each component.

Delegation-Based Event Handling

Sun Microsystems introduced the delegation-based event-handling mechanism into the Java libraries with the release of JDK 1.1 and JavaBeans. Although the Java 1.0 libraries included the Observer–Observable pair of objects that followed the Observer behavioral design pattern, this wasn't an adequate long-term solution for user-interface programming. (The Java 1.0 containment event-handling mechanism was even worse.)

Event Delegation Model

The delegation-based event-handling mechanism is a specialized form of the Observer design pattern. The Observer pattern is used when an Observer wants to know when a watched object's state changes and what that state change is. In the case of the delegation-based event-handling mechanism, instead of the Observer listening for a state change, the Observer listens for events to happen.

Figure 2-1 shows the structure of the modified Observer pattern as it relates to the specific classes within the Java libraries for event handling. The generic Subject participant in the pattern manages a list (or lists) of generic Observer objects for each event that the subject can generate. The Observer objects in the list must provide a specific interface through which the Subject participant can notify them. When an event that the Observer objects are interested in happens within the Subject participant, all the registered Observer objects are notified. In the Java world, the specific interface for the Observer objects to implement must extend the `java.util.EventListener` interface. The specific event the Subject participant must create needs to extend the `java.util.EventObject` class.




Figure 2-1. *The modified Observer pattern*

To make this a little clearer, let's take a second look at the delegation-based event-handling mechanism without all the design pattern terms. GUI components (and JavaBeans) manage lists of listeners with a pair of methods for each listener type: `addXXXListener()` and `removeXXXListener()`. When an event happens within the subject component, the component notifies all registered listeners of the event. Any observer class interested in such an event needs to register with the component an implementer of the appropriate interface. Then each implementation is notified when the event happens. Figure 2-2 illustrates this sequence.

Note Some users like to call the event delegation model a *publish-subscribe* model, in which components publish a set of available listeners for subscription, and others can subscribe to them.




Figure 2-2. *Event delegation sequence diagram*

Event Listeners As Observers

Using event listeners to handle an event is a three-step process:

1. Define a class that implements the appropriate listener interface (this includes providing implementations for all the methods of the interface).
2. Create an instance of this listener.
3. Register this listener to the component whose events you're interested in.

Let's take a look at the three specific steps for creating a simple button that responds to selection by printing a message.

Defining the Listener

To set up event handling for a selectable button, you need to create an `ActionListener`, because the `JButton` generates `ActionEvent` objects when selected.

```

class AnActionListener implements ActionListener {
    public void actionPerformed(ActionEvent actionEvent) {
        System.out.println("I was selected.");
    }
}

```

Note Part of the problem of creating responsive user interfaces is figuring out which event listener to associate with a component to get the appropriate response for the event you're interested in. For the most part, this process becomes more natural with practice. Until then, you can examine the different component APIs for a pair of add/remove listener methods, or reference the appropriate component material in this book.

Creating an Instance of the Listener

Next, you simply create an instance of the listener you just defined.

```
ActionListener actionListener = new AnActionListener();
```

If you use anonymous inner classes for event listeners, you can combine steps 1 and 2:

```
ActionListener actionListener = new ActionListener() {  
    public void actionPerformed(ActionEvent actionEvent) {  
        System.out.println("I was selected.");  
    }  
};
```

Registering the Listener with a Component

Once you've created the listener, you can associate it with the appropriate component. Assuming the JButton has already been created with a reference stored in the variable `button`, this would merely entail calling the button's `addActionListener()` method:

```
button.addActionListener(actionListener);
```

If the class that you're currently defining is the class that implements the event listener interface, you don't need to create a separate instance of the listener. You just need to associate your class as the listener for the component. The following source demonstrates this:

```
public class YourClass implements ActionListener {  
    ... // Other code for your class  
    public void actionPerformed(ActionEvent actionEvent) {  
        System.out.println("I was selected.");  
    }  
    // Code within some method  
    JButton button = new JButton(...);  
    button.addActionListener(this);  
    // More code within some method  
}
```

Using event handlers such as creating a listener and associating it to a component is the basic way to respond to events with the Swing components. The specifics of which listener works with which component are covered in later chapters, when each component is described. In the following sections, you'll learn about some additional ways to respond to events.

■ **Tip** Personally, I don't like the approach of just associating a class as the event listener, because it doesn't scale well when the situation gets more complicated. For instance, as soon as you add another button onto the screen and want the same event listener to handle its selection, the `actionPerformed()` method must figure out which button triggered the event before it can respond. Although creating a separate event listener for each component adds another class to the set of deliverables, creating separate listeners is more maintainable than sharing a listener across multiple components. In addition, most integrated development environment (IDE) tools, such as Borland's JBuilder, can automatically create the listener objects as separate classes.

Multithreaded Swing Event Handling

To increase their efficiency and decrease the complexity, all Swing components were designed to *not* be thread-safe. Although this might sound scary, it simply means that all access to Swing components needs to be done from a single thread—the event-dispatch thread. If you are unsure that you're in a particular thread, you can ask the `EventQueue` class with its public static boolean `isDispatchThread()` method or the `SwingUtilities` class with its public static boolean `isEventDispatchThread()` method. The latter just acts as a proxy to the former.

■ **Note** Earlier versions of this book showed one particular way of creating Swing programs. They were wrong. It was thought that accessing invisible (unrealized) components from outside the event-dispatch thread was okay. However, that's not true. Doing something with a Swing component can trigger a reaction within the component, and that other action would be done on the event-dispatch thread, violating the single-threaded access.

With the help of the `EventQueue` class, you create `Runnable` objects to execute on the event-dispatch thread to properly access components. If you need to execute a task on the event-dispatch thread, but you don't need any results and don't care exactly when the task finishes, you can use the public static void `invokeLater(Runnable runnable)` method of `EventQueue`. If, on the other hand, you can't continue with what you're doing until the task completes and returns a value, you can use the public static void `invokeAndWait(Runnable runnable)` method of `EventQueue`. The code to get the value is left up to *you* and is not the return value to the `invokeAndWait()` method.

■ **Caution** The `invokeAndWait(Runnable)` method can throw an `InterruptedException` or an `InvocationTargetException`.

To demonstrate the proper way to create a Swing-based program, Listing 2-1 shows the source for a selectable button.

Listing 2-1. *Swing Application Framework*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class ButtonSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Button Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                JButton button = new JButton("Select Me");

                // Define ActionListener
                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        System.out.println("I was selected.");
                    }
                };

                // Attach listeners
                button.addActionListener(actionListener);

                frame.add(button, BorderLayout.SOUTH);
                frame.setSize(300, 100);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

This code produces the button shown in Figure 2-3.



Figure 2-3. *Button sample*

First, let's look at the `invokeLater()` method. It requires a `Runnable` object as its argument. You just create a `Runnable` object and pass it along to the `invokeLater()` method. Some time after the current event dispatching is done, this `Runnable` object will execute.

```
Runnable runnable = new Runnable() {  
    public void run() {  
        // Do work to be done  
    }  
}  
EventQueue.invokeLater(runnable);
```

If you want your Swing GUI creation to be thread-safe, you should follow this pattern with all of your Swing code. If you need to access the command-line arguments, just add the `final` keyword to the argument declaration: `public static void main(final String args[])`. This may seem like overkill for a simple example like this, but it does ensure the thread safety of your program, making sure that all Swing component access is done from the event-dispatch thread. (However, calls to `repaint()`, `revalidate()`, and `invalidate()` don't need to be done from the event-dispatch thread.)

Note In addition to the `invokeLater()` and `invokeAndWait()` methods of the `EventQueue` class, there are wrapper methods of the same name in the `SwingUtilities` class. Since the `SwingUtilities` calls just redirect the calls on to the `EventQueue` class, you should avoid the extra layer of indirection and access `EventQueue` directly. These wrapper methods were created for an early Swing version, prior to the existence of the `EventQueue` class.

One additional line from Listing 2-1 requires some extra explanation:

```
frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
```

By default, if you click the little X in the title bar of the window shown in Figure 2-3, the application does not close; instead, the frame is made invisible. Setting the default close operation to `JFrame.EXIT_ON_CLOSE`, as in Listing 2-1, causes the application to exit if the user clicks the X. You'll learn more about this behavior in Chapter 8, which explores the `JFrame` class.

Using SwingUtilities for Mouse Button Identification

The Swing component set includes a utility class called `SwingUtilities` that provides a collection of generic helper methods. You will look at this class periodically throughout this book when a particular set of methods for this class seems useful. For the button example in Listing 2-1, the methods of interest are related to determining which mouse button has been selected.

The `MouseListener` interface consists of seven methods: `mouseClicked(MouseEvent)`, `mouseEntered(MouseEvent)`, `mouseExited(MouseEvent)`, `mousePressed(MouseEvent)`, and `mouseReleased(MouseEvent)` from `MouseListener`; and `mouseDragged(MouseEvent)` and `mouseMoved(MouseEvent)` from `MouseMotionListener`. If you need to determine which buttons on the mouse were selected (or released) when the event happened, check the modifiers property of `MouseEvent` and compare it to various mask-setting constants of the `InputEvent` class.

For instance, to check if a middle mouse button is pressed for a mouse press event, you could use the following code in your mouse listener's `mousePressed()` method:

```

public void mousePressed(MouseEvent mouseEvent) {
    int modifiers = mouseEvent.getModifiers();
    if ((modifiers & InputEvent.BUTTON2_MASK) == InputEvent.BUTTON2_MASK) {
        System.out.println("Middle button pressed.");
    }
}

```

Although this works fine and dandy, the `SwingUtilities` class has three methods to make this process much simpler:

```

SwingUtilities.isLeftMouseButton(MouseEvent mouseEvent)
SwingUtilities.isMiddleMouseButton(MouseEvent mouseEvent)
SwingUtilities.isRightMouseButton(MouseEvent mouseEvent)

```

Now, instead of needing to manually get the modifiers and compare them against the mask, you can simply ask the `SwingUtilities`, as follows:

```

if (SwingUtilities.isMiddleMouseButton(mouseEvent)) {
    System.out.println("Middle button released.");
}

```

This makes your code much more readable and easier to maintain.

Listing 2-2 contains an updated `ButtonSample` that adds another listener to detect which mouse button was pressed.

Listing 2-2. *Button Sample with Mouse Button Detection*

```

import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class ButtonSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Button Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                JButton button = new JButton("Select Me");

                // Define ActionListener
                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        System.out.println("I was selected.");
                    }
                };
            }
        };
    }
}

```

```
// Define MouseListener
MouseListener mouseListener = new MouseAdapter() {
    public void mousePressed(MouseEvent mouseEvent) {
        int modifiers = mouseEvent.getModifiers();
        if ((modifiers & InputEvent.BUTTON1_MASK) ==
            InputEvent.BUTTON1_MASK) {
            System.out.println("Left button pressed.");
        }
        if ((modifiers & InputEvent.BUTTON2_MASK) ==
            InputEvent.BUTTON2_MASK) {
            System.out.println("Middle button pressed.");
        }
        if ((modifiers & InputEvent.BUTTON3_MASK) ==
            InputEvent.BUTTON3_MASK) {
            System.out.println("Right button pressed.");
        }
    }
    public void mouseReleased(MouseEvent mouseEvent) {
        if (SwingUtilities.isLeftMouseButton(mouseEvent)) {
            System.out.println("Left button released.");
        }
        if (SwingUtilities.isMiddleMouseButton(mouseEvent)) {
            System.out.println("Middle button released.");
        }
        if (SwingUtilities.isRightMouseButton(mouseEvent)) {
            System.out.println("Right button released.");
        }
        System.out.println();
    }
};

// Attach listeners
button.addActionListener(actionListener);
button.addMouseListener(mouseListener);

frame.add(button, BorderLayout.SOUTH);
frame.setSize(300, 100);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}
```

Using Property Change Listeners As Observers

Besides the basic event-delegation mechanism, the JavaBeans framework introduced yet another incarnation of the Observer design pattern, this time through the property change listener. The `PropertyChangeListener` implementation is a truer representation of the Observer pattern. Each Observer watches for changes to an attribute of the Subject. The Observer is then notified of the new state when changed in the Subject. Figure 2-4 shows the structure of this Observer pattern as it relates to the specific classes within the JavaBeans libraries for property change handling. In this particular case, the observable Subject has a set of add/remove property change listener methods and a property (or properties) whose state is being watched.




Figure 2-4. The property change listener Observer pattern

With a `PropertyChangeListener`, the registered set of listeners is managed within the `PropertyChangeSupport` class. When the watched property value changes, this support class notifies any registered listeners of the new and old property state values.

Note Although `PropertyChangeListener` observers are registered at the class level, not all properties of the class might be bound. A property is bound when a change to the property causes the registered listeners to be notified. In addition, although the JavaBeans framework introduced the concept of property change listeners in JDK 1.1, none of the properties of the AWT components were bound, although this changed for the `Component` class in the 1.2 release. The Swing components have many of their properties bound. To find out which ones are bound, see the property tables for each Swing component that appear in later chapters of this book.

By registering `PropertyChangeListener` objects with the various components that support this type of listener, you can reduce the amount of source code you must generate after the initial listening setup. For instance, the background color of a Swing component is bound, meaning someone can register a `PropertyChangeListener` to a component to be notified when the background setting changes. When the value of the background property for that component changes, anyone listening is notified, allowing an `Observer` to change its background color to the new setting. Therefore, if you want all the components of your program to have the same background color, you can register them all with one component. Then, when that single component changes its background color, all the other components will be notified of the change and will modify their backgrounds to the new setting.

Note Although you can use a `PropertyChangeListener` to “share” a common property setting among components, you can also map the property of a subject to a different property of the `Observer`.

The program in Listing 2-3 demonstrates using a `PropertyChangeListener`. It creates two buttons. When either button is selected, the background of the selected button is changed to some random color. The second button is listening for property changes within the first button. When the background color changes for the first button, the background color of the second button is changed to that new value. The first button isn't listening for property changes for the second button. Therefore, when the second button is selected, changing its background color, this change doesn't propagate back to the first button.

Listing 2-3. *Property Change Listener Sample*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;
import java.beans.*;
import java.util.Random;

public class BoundSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Button Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                final JButton button1 = new JButton("Select Me");
                final JButton button2 = new JButton("No Select Me");
                final Random random = new Random();
```

```

// Define ActionListener
ActionListener actionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        JButton button = (JButton)actionEvent.getSource();
        int red = random.nextInt(255);
        int green = random.nextInt(255);
        int blue = random.nextInt(255);
        button.setBackground(new Color(red, green, blue));
    }
};

// Define PropertyChangeListener
PropertyChangeListener propertyChangeListener =
    new PropertyChangeListener() {
        public void propertyChange(PropertyChangeEvent propertyChangeEvent) {
            String property = propertyChangeEvent.getPropertyName();
            if ("background".equals(property)) {
                button2.setBackground((Color)propertyChangeEvent.getNewValue());
            }
        }
    };

// Attach listeners
button1.addActionListener(actionListener);
button1.addPropertyChangeListener(propertyChangeListener);
button2.addActionListener(actionListener);

frame.add(button1, BorderLayout.NORTH);
frame.add(button2, BorderLayout.SOUTH);
frame.setSize(300, 100);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Although this example causes only a color change from button selection, imagine if the background color of the first button could be changed from a couple of hundred different places other than the one action listener! Without a property change listener, each of those places would be required to also change the background color of the second button. With the property change listener, it's only necessary to modify the background color of the primary object—the first button, in this case. The change would then automatically propagate to the other components.

The Swing library also uses the `ChangeEvent/ChangeListener` pair to signify state changes. Although similar to the `PropertyChangeEvent/PropertyChangeListener` pair, the `ChangeEvent` doesn't carry with it the new and old data value settings. You can think of it as a lighter-weight version of a property change listener. The `ChangeEvent` is useful when more than one property value changes, because `ChangeEvent` doesn't need to package the changes.

■ **Tip** The Swing components use the `SwingPropertyChangeSupport` class, instead of the `PropertyChangeSupport` class, to manage and notify their `PropertyChangeListener` list. The Swing version, `SwingPropertyChangeSupport`, isn't thread-safe, but it is faster and takes up less memory. Assuming it is accessed from only the event-dispatch thread, the lack of thread safety is irrelevant.

Managing Listener Lists

If you're creating your own components and want those components to fire off events, you need to maintain a list of listeners to be notified. If the listener list is for AWT events (found in `java.awt.event`), you can use the `AWTEventMulticaster` class for help with list management. Prior to the Swing libraries, if the event wasn't a predefined AWT event type, you had to manage this list of listeners yourself. With the help of the `EventListenerList` class in the `javax.swing.event` package, you no longer need to manually manage the listener list and worry about thread safety. And, if you ever need to get the list of listeners, you can ask a `Component` with public `EventListener[] getListeners(Class listenerType)`, or one of the type-specific methods like the `getActionListeners()` method of `JButton`. This allows you to remove listeners from an internally managed list, which helps with garbage collection.

AWTEventMulticaster Class

Whether you realize it or not, the `AWTEventMulticaster` class is used by each and every AWT component to manage event listener lists. The class implements all the AWT event listeners (`ActionListener`, `AdjustmentListener`, `ComponentListener`, `ContainerListener`, `FocusListener`, `HierarchyBoundsListener`, `HierarchyListener`, `InputMethodListener`, `ItemListener`, `KeyListener`, `MouseListener`, `MouseMotionListener`, `MouseWheelListener`, `TextListener`, `WindowFocusListener`, `WindowListener`, and `WindowStateListener`). Whenever you call a component's method to add or remove a listener, the `AWTEventMulticaster` is used for support.

If you want to create your own component and manage a list of listeners for one of these AWT event/listener pairs, you can use the `AWTEventMulticaster`. As an example, let's look at how to create a generic component that generates an `ActionEvent` object whenever a key is pressed within the component. The component uses the public static `String getKeyText(int keyCode)` method of `KeyEvent` to convert the key code to its appropriate text string and passes this string back as the action command for the `ActionEvent`. Because the component is meant to serve as the source for `ActionListener` observers, it needs a pair of add/remove methods to handle the registration of listeners. This is where the `AWTEventMulticaster` comes in, because it will manage the adding and removing of listeners from your listener list variable:

```
private ActionListener actionListenerList = null;
public void addActionListener(ActionListener actionListener) {
    actionListenerList = AWTEventMulticaster.add(
        actionListenerList, actionListener);
}
public void removeActionListener(ActionListener actionListener) {
    actionListenerList = AWTEventMulticaster.remove(
        actionListenerList, actionListener);
}
```

The remainder of the class definition describes how to handle the internal events. An internal `KeyListener` needs to be registered in order to send keystrokes to an `ActionListener`. In addition, the component must be able to get the input focus; otherwise, all keystrokes will go to other components. The complete class definition is shown in Listing 2-4. The line of source code for notification of the listener list is in boldface. That one line notifies all the registered listeners.

Listing 2-4. *Managing Listener Lists with `AWTEventMulticaster`*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;

public class KeyTextComponent extends JComponent {
    private ActionListener actionListenerList = null;

    public KeyTextComponent() {
        setBackground(Color.CYAN);
        KeyListener internalKeyListener = new KeyAdapter() {
            public void keyPressed(KeyEvent keyEvent) {
                if (actionListenerList != null) {
                    int keyCode = keyEvent.getKeyCode();
                    String keyText = KeyEvent.getKeyText(keyCode);
                    ActionEvent actionEvent = new ActionEvent(
                        this,
                        ActionEvent.ACTION_PERFORMED,
                        keyText);
                    actionListenerList.actionPerformed(actionEvent);
                }
            }
        };

        MouseListener internalMouseListener = new MouseAdapter() {
            public void mousePressed(MouseEvent mouseEvent) {
                requestFocusInWindow();
            }
        };

        addKeyListener(internalKeyListener);
        addMouseListener(internalMouseListener);
    }

    public void addActionListener(ActionListener actionListener) {
        actionListenerList = AWTEventMulticaster.add(
            actionListenerList, actionListener);
    }
}
```

```

public void removeActionListener(ActionListener actionListener) {
    actionListenerList = AWTEventMulticaster.remove(
        actionListenerList, actionListener);
}

public boolean isFocusable() {
    return true;
}
}

```

Figure 2-5 shows the component in use. The top portion of the figure is the component, and the bottom is a text field. An `ActionListener` is registered with the `KeyTextComponent` that updates the text field in order to display the text string for the key pressed.




Figure 2-5. *Demonstrating the KeyTextComponent*

The source code for the example shown in Figure 2-5 follows in Listing 2-5.

Listing 2-5. *Sample Program with an AWTEventMulticaster Component*

```

import java.awt.*;
import java.awt.event.*;
import javax.swing.*;

public class KeyTextTester {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Key Text Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                KeyTextComponent keyTextComponent = new KeyTextComponent();
                final JTextField textField = new JTextField();

                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        String keyText = actionEvent.getActionCommand();
                        textField.setText(keyText);
                    }
                };
            }
        };
    }
}

```

```

        keyTextComponent.addActionListener(actionListener);

        frame.add(keyTextComponent, BorderLayout.CENTER);
        frame.add(textField, BorderLayout.SOUTH);
        frame.setSize(300, 200);
        frame.setVisible(true);
    }
};
    EventQueue.invokeLater(runner);
}
}

```

EventListenerList Class

Although the `AWTEventMulticaster` class is easy to use, it doesn't work for managing lists of custom event listeners or any of the Swing event listeners found in `javax.swing.event`. You could create a custom extension of the class for each type of event listener list you need to manage (not practical), or you could just store the list in a data structure such as a `Vector` or `LinkedList`. Although using a `Vector` or `LinkedList` works satisfactorily, when you use this method, you need to worry about synchronization issues. If you don't program the list management properly, the listener notification may happen with the wrong set of listeners.

To help simplify this situation, the Swing component library includes a special event-listener support class, `EventListenerList`. One instance of the class can manage all the different types of event listeners for a component. To demonstrate the class usage, let's see how the previous example can be rewritten to use `EventListenerList` instead of `AWTEventMulticaster`. Note that in this particular example, using the `AWTEventMulticaster` class is actually the simpler solution. However, imagine a similar situation in which the event listener isn't one of the predefined AWT event listeners or if you need to maintain multiple listener lists.

The adding and removing of listeners is similar to the technique used with the `AWTEventMulticaster` in the previous example. You need to create a variable of the appropriate type—this time `EventListenerList`—as well as define add and remove listener methods. One key difference between the two approaches is that the initial `EventListenerList` is non-null, whereas the other starts off being null. A reference to an empty `EventListenerList` must be created to start. This removes the need for several checks for a null list variable later. The adding and removing of listeners is also slightly different. Because an `EventListenerList` can manage a list of listeners of any type, when you add or remove the listener, you must provide the class type for the listener being acted on.

```

EventListenerList actionListenerList = new EventListenerList();
public void addActionListener(ActionListener actionListener) {
    actionListenerList.add(ActionListener.class, actionListener);
}
public void removeActionListener(ActionListener actionListener) {
    actionListenerList.remove(ActionListener.class, actionListener);
}

```

This leaves only the notification of the listeners to be handled. No generic method exists in the class to notify all the listeners of a particular type that an event has happened, so you must create the code yourself. A call to the following code (`fireActionPerformed(actionEvent)`) will replace the one line of boldfaced source code:

```
(actionListenerList.actionPerformed(actionEvent))
```

from the previous example. The code gets a copy of all the listeners of a particular type from the list as an array (in a thread-safe manner). You then need to loop through the list and notify the appropriate listeners.

```
protected void fireActionPerformed(ActionEvent actionEvent) {
    EventListener listenerList[] =
        actionListenerList.getListeners(ActionListener.class);
    for (int i=0, n=listenerList.length; i<n; i++) {
        ((ActionListener)listenerList[i]).actionPerformed(actionEvent);
    }
}
```

The complete source for the new and improved class follows in Listing 2-6. When using the `EventListenerList` class, don't forget that the class is in the `javax.swing.event` package. Other than the component class name, the testing program doesn't change.

Listing 2-6. *Managing Listener Lists with EventListenerList*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import javax.swing.event.*;
import java.util.EventListener;

public class KeyTextComponent2 extends JComponent {
    private EventListenerList actionListenerList = new EventListenerList();

    public KeyTextComponent2() {
        setBackground(Color.CYAN);
        KeyListener internalKeyListener = new KeyAdapter() {
            public void keyPressed(KeyEvent keyEvent) {
                if (actionListenerList != null) {
                    int keyCode = keyEvent.getKeyCode();
                    String keyText = KeyEvent.getKeyText(keyCode);
                    ActionEvent actionEvent = new ActionEvent(
                        this,
                        ActionEvent.ACTION_PERFORMED,
                        keyText);
                    fireActionPerformed(actionEvent);
                }
            }
        };
    }
};
```

```

        MouseListener internalMouseListener = new MouseAdapter() {
            public void mousePressed(MouseEvent mouseEvent) {
                requestFocusInWindow();
            }
        };

        addKeyListener(internalKeyListener);
        addMouseListener(internalMouseListener);
    }

    public void addActionListener(ActionListener actionListener) {
        actionListenerList.add(ActionListener.class, actionListener);
    }
    public void removeActionListener(ActionListener actionListener) {
        actionListenerList.remove(ActionListener.class, actionListener);
    }

    protected void fireActionPerformed(ActionEvent actionEvent) {
        EventListener listenerList[] =
            actionListenerList.getListeners(ActionListener.class);
        for (int i=0, n=listenerList.length; i<n; i++) {
            ((ActionListener)listenerList[i]).actionPerformed(actionEvent);
        }
    }

    public boolean isFocusable() {
        return true;
    }
}

```

Timer Class

In addition to the `invokeAndWait()` and `invokeLater()` methods of `EventQueue`, you can use the `Timer` class to create actions to be executed on the event-dispatch thread. A `Timer` provides a way of notifying an `ActionListener` after a predefined number of milliseconds. The timer can repeatedly notify the listeners, or just call them once.

Creating Timer Objects

Following is the single constructor for creating a `Timer` that specifies the millisecond delay time between calls to the `ActionListener`:

```

public Timer(int delay, ActionListener actionListener);
// 1 second interval
Timer timer = new Timer(1000, anActionListener);

```

Using Timer Objects

After a `Timer` object has been created, you need to `start()` it. Once the `Timer` is started, the `ActionListener` will be notified after the given number of milliseconds. If the system is busy, the delay could be longer, but it won't be shorter.

If there comes a time when you want to stop a `Timer`, call its `stop()` method. The `Timer` also has a `restart()` method, which calls `stop()` and `start()`, restarting the delay period.

To demonstrate, Listing 2-7 defines an `ActionListener` that simply prints a message. You then create a `Timer` to call this listener every half second. After creating the timer, you need to start it.

Listing 2-7. *Swing Timer Sample*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class TimerSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        System.out.println("Hello World Timer");
                    }
                };
                Timer timer = new Timer(500, actionListener);
                timer.start();
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

Note A `Timer` doesn't start up the AWT event-dispatch thread on its own.

Timer Properties

Table 2-1 lists the six properties of `Timer`. Four allow you to customize the behavior of the timer. `running` tells you if a timer has been started but not stopped, and `actionListeners` gets you the list of action listeners.

Table 2-1. *Timer Properties*

Property Name	Data Type	Access
actionListeners	ActionListener[]	Read-only
coalesce	boolean	Read-write
delay	int	Read-write
initialDelay	int	Read-write
repeats	boolean	Read-write
running	boolean	Read-only

The delay property is the same as the constructor argument. If you change the delay of a running timer, the new delay won't be used until the existing delay runs out.

The initialDelay property allows you to have another startup delay besides the periodic delay after the first execution. For instance, if you don't want to initially do a task for an hour, but then want to do it every 15 minutes thereafter, you need to change the initialDelay setting before you start the timer. By default, the initialDelay and delay properties are set to the same setting in the constructor.

The repeats property is true by default, which results in a repeating timer. When false, the timer notifies action listeners only once. You then need to restart() the timer to trigger the listener again. Nonrepeating timers are good for onetime notifications that need to happen after a triggering event.

The coalesce property allows for a busy system to throw away notifications that haven't happened yet when a new event needs to be fired to the registered ActionListener objects. By default, the coalesce value is true. This means if a timer runs every 500 milliseconds, but its system is bogged down and doesn't respond for a whole 2 seconds, the timer needs to send only one message, rather than also sending the missing ones. If the setting were false, four messages would still need to be sent.

In addition to the properties just listed, you can turn on log messages with the following line of code:

```
Timer.setLogTimers(true);
```

Log messages are good for actions that lack a visual element, allowing you to see when something happens.

Tip The `java.util.Timer` class works in a fashion similar to the `javax.swing.Timer` class, except that it doesn't run the scheduled task in the event-dispatch thread. In addition, it supports executing tasks at a fixed rate, versus after a fixed delay. The latter scheme permits the repeat rate to drift between executions if the event-dispatch thread is busy.

Swing-Specific Event Handling

Keeping in mind that the Swing components are built on top of the AWT libraries, the Swing component library has several improved capabilities to make event handling much easier. The capabilities improve on several of AWT's core event-handling features, from basic action listening to focus management.

To simplify event handling, the Swing library extends the original `ActionListener` interface with the `Action` interface to store visual attributes with the event handler. This allows the creation of event handlers independent of visual components. Then, when the `Action` is later associated with a component, the component automatically gets information (such as a button label) directly from the event handler. This includes notification of updates for the label when the `Action` is modified. The `AbstractAction` and `TextAction` classes are implementations of this concept.

The Swing library also adds a `KeyStroke` class that allows you to more easily respond to key events. Instead of watching all key events for a specific key, you can tell a component that when a specific keystroke sequence is pressed, it must respond with a particular action. These keystroke-to-action mappings are stored in a combination of `InputMap` and `ActionMap` objects. The `InputMap` is specifically a `ComponentInputMap` when the component's window has the focus. The Swing text components can use these more readily to store the mapping of keystrokes to actions with the help of the `Keymap` interface. The mappings for the `TextAction` support are described in more detail in Chapter 16, along with the remainder of the text event-handling capabilities.

The `KeyboardFocusManager` and `DefaultKeyboardFocusManager`, along with the help of the `FocusTraversalPolicy` and its implementations, manage the focus subsystem. The `InputVerifier` helps, too, for validation of user input. These are discussed in the "Swing Focus Management" section later in this chapter.

Action Interface

The `Action` interface is an extension to the `ActionListener` interface that's very flexible for defining shared event handlers independent of the components that act as the triggering agents. The interface implements `ActionListener` and defines a lookup table data structure whose keys act as bound properties. Then, when an `Action` is associated with a component, these display properties are automatically carried over to it. The following is the interface definition:

```
public interface Action implements ActionListener {
    // Constants
    public final static String ACCELERATOR_KEY;
    public final static String ACTION_COMMAND_KEY;
    public final static String DEFAULT;
    public final static String LONG_DESCRIPTION;
    public final static String MNEMONIC_KEY;
    public final static String NAME;
    public final static String SHORT_DESCRIPTION;
    public final static String SMALL_ICON;
```

```

// Listeners
public void addPropertyChangeListener(PropertyChangeListener listener);
public void removePropertyChangeListener(PropertyChangeListener listener);
// Properties
public boolean isEnabled();
public void setEnabled(boolean newValue);
// Other methods
public Object getValue(String key);
public void putValue(String key, Object value);
}

```

Because Action is merely an interface, the Swing libraries offer a class to implement the interface. That class is `AbstractAction`.

AbstractAction Class

The `AbstractAction` class provides a default implementation of the Action interface. This is where the bound property behavior is implemented.

Using Actions

Once you define an `AbstractAction` by subclassing and providing a `public void actionPerformed(ActionEvent actionEvent)` method, you can then pass it along to some special Swing components. `JButton`, `JCheckBox`, `JRadioButton`, `JToggleButton`, `JMenuItem`, `JCheckBoxMenuItem`, and `JRadioButtonMenuItem` provide constructors for creating the components from actions, whereas the Swing text components have their own built-in support for Action objects through their `Keymap`, `InputMap`, and `ActionMap`.

When the component with the associated Action is added to the respective Swing container, selection triggers the calling of the `actionPerformed(ActionEvent actionEvent)` method of the Action. The display of the component is defined by the property elements added to the internal data structure. To demonstrate, Listing 2-8 presents an Action with a “Print” label and an image icon. When this is activated, a “Hello, World” message is printed.

Listing 2-8. Action Usage Example

```

import java.awt.event.*;
import javax.swing.*;

public class PrintHelloAction extends AbstractAction {
    private static final Icon printIcon = new ImageIcon("Print.gif");
    PrintHelloAction() {
        super("Print", printIcon);
        putValue(Action.SHORT_DESCRIPTION, "Hello, World");
    }
    public void actionPerformed(ActionEvent actionEvent) {
        System.out.println("Hello, World");
    }
}

```

Once the Action has been defined, you can create the Action and associate it with as many other components as you want.

```
Action printAction = new PrintHelloAction();
menu.add(new JMenuItem(printAction));
toolbar.add(new JButton(printAction));
```

After the Action has been associated with the various objects, if you find that you need to modify the properties of the Action, you need to change the setting in only one place. Because the properties are all bound, they propagate to any component that uses the Action. For instance, disabling the Action (`printAction.setEnabled(false)`) will disable the `JMenuItem` and `JButton` created on the `JMenu` and `JToolBar`, respectively. In contrast, changing the name of the Action with `printAction.putValue(Action.NAME, "Hello, World")` changes the text label of the associated components.

Figure 2-6 shows what the `PrintHelloAction` might look like on a `JToolBar` and a `JMenu`. Selectable buttons are provided to enable or disable the Action, as well as to change its name.




Figure 2-6. *The `PrintHelloAction` in use*

The complete source code for this example follows in Listing 2-9. Don't worry just yet about the specifics of creating toolbars and menu bars. They'll be discussed in more detail in Chapter 6.

Listing 2-9. *PrintHelloAction Example*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;

public class ActionTester {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Action Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                final Action printAction = new PrintHelloAction();

                JMenuBar menuBar = new JMenuBar();
```

```

JMenu menu = new JMenu("File");
menuBar.add(menu);
menu.add(new JMenuItem(printAction));

JToolBar toolbar = new JToolBar();
toolbar.add(new JButton(printAction));

JButton enableButton = new JButton("Enable");
ActionListener enableActionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        printAction.setEnabled(true);
    }
};
enableButton.addActionListener(enableActionListener);

JButton disableButton = new JButton("Disable");
ActionListener disableActionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        printAction.setEnabled(false);
    }
};
disableButton.addActionListener(disableActionListener);

JButton relabelButton = new JButton("Relabel");
ActionListener relabelActionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        printAction.putValue(Action.NAME, "Hello, World");
    }
};
relabelButton.addActionListener(relabelActionListener);

JPanel buttonPanel = new JPanel();
buttonPanel.add(enableButton);
buttonPanel.add(disableButton);
buttonPanel.add(relabelButton);

frame.setJMenuBar(menuBar);

frame.add(toolbar, BorderLayout.SOUTH);
frame.add(buttonPanel, BorderLayout.NORTH);
frame.setSize(300, 200);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

AbstractAction Properties

As Table 2-2 shows, the `AbstractAction` class has three available properties.

Table 2-2. *AbstractAction Properties*

Property Name	Data Type	Access
<code>enabled</code>	<code>boolean</code>	Read-write bound
<code>keys</code>	<code>Object []</code>	Read-only
<code>propertyChangeListener</code>	<code>PropertyChangeListener[]</code>	Read-only

The remainder of the bound properties are placed in the lookup table with `putValue` (`String key`, `Object value`). Getting the current keys property setting allows you to find out which ones can be set en masse, instead of asking for each one individually. Table 2-3 describes the predefined set of Action constants that can be used as the key. You can also add your own constants, to look up later when the action happens.

Table 2-3. *AbstractAction Lookup Property Keys*

Constant	Description
<code>NAME</code>	Action name, used as button label
<code>SMALL_ICON</code>	Icon for the Action, used as button label
<code>SHORT_DESCRIPTION</code>	Short description of the Action; could be used as tooltip text, but not by default
<code>LONG_DESCRIPTION</code>	Long description of the Action; could be used for accessibility (see Chapter 22)
<code>ACCELERATOR</code>	<code>KeyStroke</code> string; can be used as the accelerator for the Action
<code>ACTION_COMMAND_KEY</code>	<code>InputMap</code> key; maps to the Action in the <code>ActionMap</code> of the associated <code>JComponent</code>
<code>MNEMONIC_KEY</code>	Key code; can be used as mnemonic for action
<code>DEFAULT</code>	Unused constant that could be used for your own property

Once a property has been placed in the lookup table, you can get it with `public Object getValue(String key)`. It works similarly to the `java.util.Hashtable` class or `java.util.Map` interface, with one distinction: if you try to put a key/value pair into the table with a null value, the table removes the key, if it's present.

KeyStroke Class

The `KeyStroke` class and the `inputMap` and `actionMap` properties of a specific `JComponent` provide a simple replacement for registering `KeyListener` objects to components and watching for

specific keys to be pressed. The `KeyStroke` class allows you to define a single combination of keystrokes, such as Shift-Ctrl-P or F4. You can then activate the keystroke by registering it with a component and telling the keystroke what to do when the component recognizes it, causing the `ActionListener` to be notified.

Before finding out how to create keystrokes, let's look at the different conditions that can be activated and thus added to different input maps. Three conditions can activate a registered keystroke, and there are four constants in `JComponent` to help. The fourth is for an undefined state. The four available constants are listed in Table 2-4.

Table 2-4. *Keystroke Registration Conditions*

Constant	Description
WHEN_FOCUSED	Activates the keystroke when the actual component has the input focus
WHEN_IN_FOCUSED_WINDOW	Activates the keystroke when the window that the component is in has the input focus
WHEN_ANCESTOR_OF_FOCUSED_COMPONENT	Activates the keystroke when pressed in the component or a container of the component
UNDEFINED_CONDITION	For when no condition is defined

Note In the special instance in which the keystrokes are supposed to be active only when the component is in the focused window, the `InputMap` is actually a `ComponentInputMap`.

Creating a `KeyStroke`

The `KeyStroke` class is a subclass of `AWTKeyStroke` and has no public constructor. You create a keystroke by using one of the following methods:

```
public static KeyStroke getKeyStroke(char keyChar)
public static KeyStroke getKeyStroke(String representation)
public static KeyStroke getKeyStroke(int keyCode, int modifiers)
public static KeyStroke getKeyStroke(int keyCode, int modifiers,
    boolean onKeyRelease)
public static KeyStroke getKeyStrokeForEvent(KeyEvent keyEvent)
```

The first version in this list, `public static KeyStroke getKeyStroke(char keyChar)`, allows you to create a keystroke from a `char` variable, such as `Z`.

```
KeyStroke space = KeyStroke.getKeyStroke('Z');
```

Note I prefer to avoid using a `char` variable to create a keystroke, because you don't know whether to specify an uppercase or lowercase letter. There is also an outdated, or deprecated, version of this method that adds a boolean `onKeyRelease` argument. This, too, should be avoided.

The public static `KeyStroke getKeyStroke(String representation)` version is the most interesting of the lot. It allows you to specify a keystroke as a text string, such as "control F4". The set of modifiers to the string are `shift`, `control`, `meta`, `alt`, `button1`, `button2`, and `button3`, and multiple modifiers can be specified. The remainder of the string comes from one of the many `VK_*` constants of the `KeyEvent` class. For example, the following defines a keystroke for Ctrl-Alt-7:

```
KeyStroke controlAlt7 = KeyStroke.getKeyStroke("control alt 7");
```

The public static `KeyStroke getKeyStroke(int keyCode, int modifiers)` and public static `KeyStroke getKeyStroke(int keyCode, int modifiers, boolean onKeyRelease)` methods are the most straightforward. They allow you to directly specify the `VK_*` key constant and the `InputEvent` masks for the modifiers (or zero for no modifiers). When not specified, `onKeyRelease` is `false`.

```
KeyStroke enter = KeyStroke.getKeyStroke(KeyEvent.VK_ENTER, 0, true);
KeyStroke shiftF4 = KeyStroke.getKeyStroke(KeyEvent.VK_F4, InputEvent.SHIFT_MASK);
```

The last version listed, `public static KeyStroke getKeyStrokeForEvent(KeyEvent keyEvent)`, maps a specific `KeyEvent` directly to a `KeyStroke`. This is useful when you want to allow a user to supply the keystroke to activate an event. You ask the user to press a key for the event, and then register the `KeyEvent` so that the next time it happens, the event is activated.

```
KeyStroke fromKeyEvent = KeyStroke.getKeyStrokeForEvent(keyEvent);
```

Registering a KeyStroke

After you've created the keystroke, you need to register it with a component. When you register a keystroke with a component, you provide an `Action` to call when pressed (or released). Registration involves providing a mapping from keystroke to `Action`. First, you get the appropriate `InputMap` for the component based on the focus activation condition (from Table 2-4) with `getInputMap(condition)`. If no condition is provided, `WHEN_FOCUSED` is assumed. You then add a mapping from keystroke to text string in the `InputMap`:

```
component.getInputMap().put(keystroke, string)
```

If you know the action string for an existing action, you can use that; otherwise, you define the string. You then work with the `ActionMap` to map that string to an `Action`:

```
component.getActionMap.put(string, action)
```

You can share actions between components by sharing `ActionMap` instances. The example in Listing 2-10 creates four buttons, each with a different keystroke registered to it and possibly a different focus-activation condition, as listed in Table 2-4. The button label signifies the keystroke-activation conditions. The `Action` simply prints out a message and the activating button label.

Listing 2-10. *KeyStroke Listening*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class KeyStrokeSample {
    private static final String ACTION_KEY = "theAction";
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("KeyStroke Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JButton buttonA =
                    new JButton("<html><center>FOCUSED<br>control alt 7");
                JButton buttonB =
                    new JButton("<html><center>FOCUS/RELEASE<br>VK_ENTER");
                JButton buttonC =
                    new JButton("<html><center>ANCESTOR<br>VK_F4+SHIFT_MASK");
                JButton buttonD =
                    new JButton("<html><center>WINDOW<br>' '");

                // Define ActionListener
                Action actionListener = new AbstractAction() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        JButton source = (JButton)actionEvent.getSource();
                        System.out.println("Activated: " + source.getText());
                    }
                };

                KeyStroke controlAlt7 = KeyStroke.getKeyStroke("control alt 7");
                InputMap inputMap = buttonA.getInputMap();
                inputMap.put(controlAlt7, ACTION_KEY);
                ActionMap actionMap = buttonA.getActionMap();
                actionMap.put(ACTION_KEY, actionListener);

                KeyStroke enter = KeyStroke.getKeyStroke(KeyEvent.VK_ENTER, 0, true);
                inputMap = buttonB.getInputMap();
                inputMap.put(enter, ACTION_KEY);
                buttonB.setActionMap(actionMap);
            }
        };
        runner.run();
    }
}
```

```

KeyStroke shiftF4 =
    KeyStroke.getKeyStroke(KeyEvent.VK_F4, InputEvent.SHIFT_MASK);
inputMap =
    buttonC.getInputMap(JComponent.WHEN_ANCESTOR_OF_FOCUSED_COMPONENT);
inputMap.put(shiftF4, ACTION_KEY);
buttonC.setActionMap(actionMap);

KeyStroke space = KeyStroke.getKeyStroke(' ');
inputMap = buttonD.getInputMap(JComponent.WHEN_IN_FOCUSED_WINDOW);
inputMap.put(space, ACTION_KEY);
buttonD.setActionMap(actionMap);

frame.setLayout(new GridLayout(2,2));
frame.add(buttonA);
frame.add(buttonB);
frame.add(buttonC);
frame.add(buttonD);

frame.setSize(400, 200);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Tip For text components, you can get the Keymap and bind an Action to a KeyStroke in one step with `addActionForKeyStroke(KeyStroke, Action)`.

Figure 2-7 shows what the running program looks like.



Figure 2-7. *KeyStroke listening example*

Using Mnemonics and Accelerators

The Swing libraries also use `KeyStroke` objects for several internal functions. Two such functions are component mnemonics and accelerators, which work as follows:

- In a component *mnemonic*, one character in a label appears underlined. When that character is pressed along with a platform-specific hotkey combination, the component is activated. For instance, pressing Alt-A in the window shown in Figure 2-8 would select the About button on a Windows XP platform.
- A menu *accelerator* activates a menu item when it is not visible. For instance, pressing Ctrl-P would select the Print menu item in the window shown in Figure 2-8 when the File menu isn't visible.




Figure 2-8. *Mnemonics and menu shortcuts*

You'll learn more about mnemonics and accelerators in Chapter 6.

Swing Focus Management

The term *focus* refers to when a component acquires the input focus. When a component has the input focus, it serves as the source for all key events, such as text input. In addition, certain components have some visual markings to indicate that they have the input focus, as shown in Figure 2-9. When certain components have the input focus, you can trigger selection with a keyboard key (usually the spacebar or Enter key), in addition to selection with a mouse. For instance, with a button, pressing the spacebar activates it.




Figure 2-9. *A JButton showing it has input focus*

Note The focus subsystem had a major overhaul with the 1.4 release of J2SE. All the older guts are still present, but should be avoided. The older stuff didn't work well and was very buggy. Sun's fix was to essentially throw everything away and start over, but old APIs are still present. In your quest to work with the focus subsystem, learn to use only the updated APIs, not the older ones. Classes like `javax.swing.FocusManager` and `javax.swing.DefaultFocusManager` are completely obsolete now.

An important concept in focus management is the *focus cycle*, which maps the focus traversal order for the closed set of components within a specific Container. The following classes are also major players in focus management:

- `FocusTraversalPolicy`: A `java.awt` class that defines the algorithm used to determine the next and previous focusable components.
- `KeyboardFocusManager`: A `java.awt` class that acts as the controller for keyboard navigation and focus changes. To request a focus change, you tell the manager to change focusable components; you don't request focus on a particular component.

You can find out when the Swing component gets the input focus by registering a `FocusListener`. The listener allows you to find out when a component gains or loses focus, which component lost focus when another component gained it, and which component got focus when another component lost focus. Additionally, a temporary focus change can happen for something like a pop-up menu. The component that lost focus will receive it again when the menu goes down.

The installed focus traversal policy describes how to move between the focusable components of a window. By default, the next component is defined by the order in which components are added to a container, as shown in Figure 2-10. For Swing applications, this focus traversal starts at the top left of the figure and goes across each row and down to the bottom right. This is the default policy, `LayoutFocusTraversalPolicy`. When all the components are in the same container, this traversal order is called a *focus cycle* and can be limited to remain within that container.

Note A user can press Tab or Shift-Tab to move forward or backward through the components in a container, thus transferring the input focus.




Figure 2-10. *Default focus ordering*

Moving the Focus

As an example of some basic capabilities, let's look at how to create two listeners to handle input focus: a `MouseListener` that moves the input focus to a component when the mouse enters its space, and an `ActionListener` that transfers the input focus to the next component.

The `MouseListener` merely needs to call `requestFocusInWindow()` when the mouse enters the component.

```
import java.awt.*;
import java.awt.event.*;
public class MouseEnterFocusMover extends MouseAdapter {
    public void mouseEntered(MouseEvent mouseEvent) {
        Component component = mouseEvent.getComponent();
        if (!component.hasFocus()) {
            component.requestFocusInWindow();
        }
    }
}
```

For the `ActionListener`, you need to call the `focusNextComponent()` method for the `KeyboardFocusManager`.

```
import java.awt.*;
import java.awt.event.*;
```

```

public class ActionFocusMover implements ActionListener {
    public void actionPerformed(ActionEvent actionEvent) {
        KeyboardFocusManager manager =
            KeyboardFocusManager.getCurrentKeyboardFocusManager();
        manager.focusNextComponent();
    }
}

```

The `ActionFocusMover` and `MouseEnterFocusMover` show two different ways of programmatically moving focus around. The `ActionFocusMover` uses the `KeyboardFocusManager` for traversal. In `MouseEnterFocusMover`, the call to `requestFocusInWindow()` says that you would like for the suggested component to get focus for the window of the application. However, getting focus can be turned off. If the component isn't focusable, either because the default setting of the focusable property is false or you called `component.setFocusable(false)`, then the component will be skipped over and the next component after it gets focus; the component is removed from the tab focus cycle. (Think of a scrollbar that isn't in the focus cycle, but is draggable to change a setting.)

The program in Listing 2-11 uses the two event handlers for moving focus around. It creates a 3×3 grid of buttons, in which each button has an attached mouse listener and a focus listener. The even buttons are selectable but aren't focusable.

Listing 2-11. *Focus Traversal Sample*

```

import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class FocusSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Focus Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                ActionListener actionListener = new ActionFocusMover();
                MouseListener mouseListener = new MouseEnterFocusMover();

                frame.setLayout(new GridLayout(3,3));
                for (int i=1; i<10; i++) {
                    JButton button = new JButton(Integer.toString(i));
                    button.addActionListener(actionListener);
                    button.addMouseListener(mouseListener);
                    if ((i%2) != 0) { // odd - enabled by default
                        button.setFocusable(false);
                    }
                    frame.add(button);
                }
            }
        };
    }
}

```

```
        frame.setSize(300, 200);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}
```

Figure 2-11 shows the main window of the program.




Figure 2-11. *Focus management example*

Examining Focus Cycles

One customization option available at the Swing container level is the focus cycle. Remember that the focus cycle for a container is a map of the focus traversal order for the closed set of components. You can limit the focus cycle to stay within the bounds of a container by setting the `focusCycleRoot` property to be `true`, thus restricting the focus traversal from going beyond an inner container. Then, when the Tab key is pressed within the last component of the container, the focus cycle will wrap back to the first component in the container, instead of moving the input focus to the first component outside the container. When Shift-Tab is pressed in the first component, it wraps to the last component of the container, instead of to the prior component in the outer container.

Figure 2-12 illustrates how the focus ordering would look if you placed the middle three buttons from Figure 2-10 within a container restricted in this way. In this cycle, you cannot get to the first component on the third row by pressing the Tab key to move forward. To be able to tab into the second row container, you need to set the `focusTraversalPolicyProvider` property to `true`. Otherwise, while the panel will keep the traversal policy within the second row, tabbing will never get you into the third row.




Figure 2-12. *Restrictive focus cycle*

The program in Listing 2-12 demonstrates the behavior illustrated in Figure 2-12. The on-screen program will look just like Figure 2-11; it just behaves differently.

Listing 2-12. *Restricting the Focus Cycle*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class FocusCycleSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Focus Cycle Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                frame.setLayout(new GridBagLayout());
                GridBagConstraints constraints = new GridBagConstraints();
                constraints.weightx = 1.0;
                constraints.weighty = 1.0;
                constraints.gridwidth = 1;
                constraints.gridheight = 1;
                constraints.fill = GridBagConstraints.BOTH;
```

```

        // Row One
        constraints.gridy=0;
        for (int i=0; i<3; i++) {
            JButton button = new JButton("" + i);
            constraints.gridx=i;
            frame.add(button, constraints);
        }

        // Row Two
        JPanel panel = new JPanel();
        panel.setFocusCycleRoot(true);
        panel.setFocusTraversalPolicyProvider(true);
        panel.setLayout(new GridLayout(1,3));
        for (int i=0; i<3; i++) {
            JButton button = new JButton("" + (i+3));
            panel.add(button);
        }
        constraints.gridx=0;
        constraints.gridy=1;
        constraints.gridwidth=3;
        frame.add(panel, constraints);

        // Row Three
        constraints.gridy=2;
        constraints.gridwidth=1;
        for (int i=0; i<3; i++) {
            JButton button = new JButton("" + (i+6));
            constraints.gridx=i;
            frame.add(button, constraints);
        }

        frame.setSize(300, 200);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

FocusTraversalPolicy Class

The `FocusTraversalPolicy` is responsible for determining the focus traversal order. It allows you to specify the next and previous components in the order. This class offers six methods for controlling traversal order:

- `getComponentAfter(Container aContainer, Component aComponent)`
- `getComponentBefore(Container aContainer, Component aComponent)`
- `getDefaultComponent(Container aContainer)`
- `getFirstComponent(Container aContainer)`
- `getInitialComponent(Window window)`
- `getLastComponent(Container aContainer)`

Swing provides five predefined traversal policies, as listed in Table 2-5. By picking the right traversal policy for your application, or rolling your own, you can determine how users will navigate around the screens.

Table 2-5. *Predefined Traversal Policies*

Policy	Description
<code>ContainerOrderFocusTraversalPolicy</code>	The components are traversed in the order they are added to their container. The component must be visible, displayable, enabled, and focusable to be part of the focus cycle.
<code>DefaultFocusTraversalPolicy</code>	The default policy for AWT programs, this extends <code>ContainerOrderFocusTraversalPolicy</code> to check with the component peer (the operating system) if the component hasn't explicitly set focusability. The focusability of a peer depends on the Java runtime implementation.
<code>InternalFrameFocusTraversalPolicy</code>	Special policy for <code>JInternalFrame</code> , with behavior to determine initial focusable component based on the default component of the frame.
<code>SortingFocusTraversalPolicy</code>	Here, you provide a <code>Comparator</code> to the policy constructor to define the focus cycle order.
<code>LayoutFocusTraversalPolicy</code>	The default policy for Swing programs, this takes into account geometric settings of components (height, width, position), and then goes top down, left to right to determine navigation order. The top-down, left-right order is determined by the current <code>ComponentOrientation</code> setting for your locale. For instance, Hebrew would be in right-left order instead.

To demonstrate, the program in Listing 2-13 reverses the functionality of `Tab` and `Shift-Tab`. When you run the program, it looks the same as the screen shown earlier in Figure 2-11, with the 3×3 set of buttons. However, with this version, the initial focus starts on the 9 button, and pressing `Tab` takes you to 8, then 7, and so on. `Shift-Tab` goes in the other, more normal, order.

Listing 2-13. *Reversing Focus Traversal*

```

import javax.swing.*;
import java.awt.*;
import java.awt.event.*;
import java.util.Comparator;
import java.util.Arrays;
import java.util.List;

public class NextComponentSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Reverse Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                frame.setLayout(new GridLayout(3,3));
                // for (int i=1; i<10; i++) {
                for (int i=9; i>0; i--) {
                    JButton button = new JButton(Integer.toString(i));
                    frame.add(button, 0);
                }

                final Container contentPane = frame.getContentPane();
                Comparator<Component> comp = new Comparator<Component>() {
                    public int compare(Component c1, Component c2) {
                        Component comps[] = contentPane.getComponents();
                        List list = Arrays.asList(comps);
                        int first = list.indexOf(c1);
                        int second = list.indexOf(c2);
                        return second - first;
                    }
                };

                FocusTraversalPolicy policy = new SortingFocusTraversalPolicy(comp);
                frame.setFocusTraversalPolicy(policy);

                frame.setSize(300, 200);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

KeyboardFocusManager Class

The abstract `KeyboardFocusManager` class in the AWT library serves as the control mechanism framework for the input focus behavior of Swing components. The `DefaultKeyboardFocusManager` is the concrete implementation. The focus manager allows you to both programmatically discover who currently has the input focus and to change it.

The component with the current input focus is called the *focus owner*. This is accessible via the `focusOwner` property of `KeyboardFocusManager`. You can also discover the `focusedWindow` and `activeWindow` properties. The focused window is the window containing the focus owner, and the active window is either the focused window or the frame or dialog containing the focus owner.

The simple concept of moving to the previous or next component is supported in many different ways. First, you can use the shortcut API methods of `Component` and `Container`:

- `Component.transferFocus()`
- `Component.transferFocusBackward()`
- `Component.transferFocusUpCycle()`
- `Container.transferFocusDownCycle()`

The first two methods request focus to move to the next or previous component, respectively. The up and down cycle methods request that you move up out of the current focus cycle or down into the next cycle.

The following methods map directly to methods of the `KeyboardFocusManager`:

- `focusNextComponent()`
- `focusPreviousComponent()`
- `upFocusCycle()`
- `downFocusCycle()`

A second set of the same four methods accepts a second parameter of a `Component`. If the component isn't specified, these methods change the focused component based on the current focus owner. If a component is provided, the change is based on that component.

`Tab` and `Shift-Tab` are used for keyboard focus traversal because they are defined as the default focus traversal keys for most, if not all, components. To define your own traversal keys, you can replace or append to a key set via the `setFocusTraversalKeys()` method of `Component`. Different sets are available for forward, backward, and up-cycle, as specified by the `FORWARD_TRAVERSAL_KEYS`, `BACKWARD_TRAVERSAL_KEYS`, and `UP_CYCLE_TRAVERSAL_KEYS` constants of `KeyboardFocusManager`. You can set and get key sets for each. For instance, to add the `F3` key as an up-cycle key for a component, use the following code:

```
Set<AWTKeyStroke> set = component.setFocusTraversalKeys(  
    KeyboardFocusManager.UP_CYCLE_TRAVERSAL_KEYS);  
KeyStroke stroke = KeyStroke.getKeyStroke("F3");  
set.add(stroke);  
component.setFocusTraversalKeys(KeyboardFocusManager.UP_CYCLE_TRAVERSAL_KEYS, set);
```

Verifying Input During Focus Traversal

Swing offers the abstract `InputVerifier` class for component-level verification during focus traversal with any `JComponent`. Just subclass `InputVerifier` and provide your own public `boolean verify(JComponent)` method to verify the contents of the component.

Listing 2-14 provides a simple numeric text field verification example, showing three text fields, of which only two have verification. Unless fields one and three are valid, you can't tab out of them.

Listing 2-14. *Numeric Input Verifier*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;

public class VerifierSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Verifier Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                JTextField textField1 = new JTextField();
                JTextField textField2 = new JTextField();
                JTextField textField3 = new JTextField();

                InputVerifier verifier = new InputVerifier() {
                    public boolean verify(JComponent comp) {
                        boolean returnValue;
                        JTextField textField = (JTextField)comp;
                        try {
                            Integer.parseInt(textField.getText());
                            returnValue = true;
                        } catch (NumberFormatException e) {
                            returnValue = false;
                        }
                        return returnValue;
                    }
                };

                textField1.setInputVerifier(verifier);
                textField3.setInputVerifier(verifier);

                frame.add(textField1, BorderLayout.NORTH);
                frame.add(textField2, BorderLayout.CENTER);
                frame.add(textField3, BorderLayout.SOUTH);
                frame.setSize(300, 100);
                frame.setVisible(true);
            }
        };
    }
}
```

```
    };  
    EventQueue.invokeLater(runner);  
  }  
}
```

■ **Tip** To make sure that cancel-type buttons get the input focus no matter what when using `InputVerifier`, use the `setVerifyInputWhenFocusTarget(false)` method with the component.

Summary

In this chapter, you looked at the many ways of dealing with event handling when using Swing components. Because Swing components are built *on top of* AWT components, you can use the delegation-based event-handling mechanism common with those components. You then learned about the multithreading limitations of the Swing components and how to get around them with the `invokeAndWait()` and `invokeLater()` methods of `EventQueue`. You also explored how the Swing components use the `JavaBeansPropertyChangeListener` approach for notification of bound property changes.

Besides exploring the similarities between the Swing components and AWT components, you also looked at several of the new features that the Swing library offers. You explored the `Action` interface and how it can simplify complex user-interface development by completely separating the event-handling task from the visual component. You looked at the technique for registering `KeyStroke` objects to components to simplify listening for key events. Finally, you explored Swing's focus management capabilities and how to customize the focus cycle and use the `FocusTraversalPolicy` and `KeyboardFocusManager`, as well as validating input with the `InputVerifier`.

In Chapter 3, you'll meet the Model-View-Controller (MVC) architecture of the Swing component set. You'll learn how MVC can make your user interface development efforts much easier.



The Model-View-Controller Architecture

Chapter 2 explored how to deal with event producers and consumers with regard to Swing components. We looked at how event handling with Swing components goes beyond the event-handling capabilities of the original AWT components. In this chapter, we will take the Swing component design one step further to examine what is called the Model-View-Controller (MVC) architecture.

Understanding the Flow of MVC

First introduced in Smalltalk in the late 1980s, the MVC architecture is a special form of the Observer pattern described in Chapter 2. The *model* part of the MVC holds the state of a component and serves as the Subject. The *view* part of the MVC serves as the Observer of the Subject to display the model's state. The view creates the *controller*, which defines how the user interface reacts to user input.

MVC Communication

Figure 3-1 shows how the MVC elements communicate—in this case, with Swing's multiline text component, the `JTextArea`. In MVC terms, the `JTextArea` serves as the view part within the MVC architecture. Displayed within the component is a `Document`, which is the model for the `JTextArea`. The `Document` stores the state information for the `JTextArea`, such as the text contents. Within the `JTextArea` is the controller, in the form of an `InputMap`. It maps keyboard input to commands in an `ActionMap`, and those commands are mapped to `TextAction` objects, which can modify the `Document`. When the modification happens, the `Document` creates a `DocumentEvent` and sends it back to the `JTextArea`.




Figure 3-1. MVC communication mechanism

UI Delegates for Swing Components

This example demonstrates an important aspect of the MVC architecture within the Swing world. Complex interactions need to happen between the view and the controller. The Swing design combines these two elements into a *delegate* object to simplify the overall design. This results in each Swing component having a UI delegate that is in charge of rendering the current state of the component and dealing with user input events.

Sometimes, the user events result in changes to the view that don't affect the model. For instance, the cursor position is an attribute of the view. The model doesn't care about the position of the cursor, only the text contents. User input that affects the cursor position isn't passed along to the model. At other times, user input that affects the contents of the Document (for example, pressing the Backspace key) is passed along. Pressing the Backspace key results in a character being removed from the model. Because of this tight coupling, each Swing component has a UI delegate.

To demonstrate, Figure 3-2 shows the makeup of the JTextArea, with respect to the model and UI delegate. The UI delegate for the JTextArea starts with the TextUI interface, with its basic implementation in the BasicTextUI class. In turn, this is specialized with the BasicTextAreaUI for the JTextArea. The BasicTextAreaUI creates a view that is either a PlainView or a WrappedPlainView. On the model side, things are much simpler. The Document interface is implemented by the AbstractDocument class, which is further specialized by the PlainDocument.

The text components will be explained more fully in Chapters 15 and 16. As the diagram in Figure 3-2 demonstrates, much is involved in working with the text components. In most cases, you don't need to deal with the specifics to the degree shown in this figure. However, all of these classes are working behind the scenes. The UI-delegate part of the MVC architecture will be discussed further in Chapter 20, when we explore how to customize delegates.




Figure 3-2. The JTextArea MVC architecture

Sharing Data Models

Because data models store only the state information, you can share a model across multiple components. Then each component view can be used to modify the model.

In the case of Figure 3-3, three different JTextArea components are used to modify one Document model. If a user modifies the contents of one JTextArea, the model is changed, causing the other text areas to automatically reflect the updated document state. It isn't necessary for any Document view to manually notify others sharing the model.




Figure 3-3. *Sharing MVC data models*

Sharing of a data model can be done in either one of two ways:

- You can create the data model apart from any component and tell each component to use the data model.
- You can create one component first, get the model from the first component, and then share it with the other components.

Listing 3-1 demonstrates how to share a data model using the latter technique.

Listing 3-1. *Sharing an MVC Model*

```

import java.awt.*;
import javax.swing.*;
import javax.swing.text.*;

public class ShareModel {
    public static void main (String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Sharing Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                Container content = frame.getContentPane();
                JTextArea textarea1 = new JTextArea();
                Document document = textarea1.getDocument();
                JTextArea textarea2 = new JTextArea(document);
                JTextArea textarea3 = new JTextArea(document);
                content.setLayout(new BoxLayout(content, BoxLayout.Y_AXIS));
                content.add(new JScrollPane(textarea1));
            }
        };
        Thread t = new Thread(runner);
        t.start();
    }
}
  
```

```

        content.add(new JScrollPane(textarea2));
        content.add(new JScrollPane(textarea3));
        frame.setSize (300, 400);
        frame.setVisible (true);
    }
};
EventQueue.invokeLater(runner);
}
}
}

```

Figure 3-4 shows how this program might look after editing the shared document. Notice that the three text areas are capable of viewing (or modifying) different areas of the document. They aren't limited to adding text only at the end, for instance. This is because each text area manages the position and cursor separately. The position and cursor are attributes of the view, not the model.




Figure 3-4. *Sharing a document between JTextArea components*

Understanding the Predefined Data Models

When working with Swing components, it's helpful to understand the data models behind each of the components because the data models store their state. Understanding the data model for each component helps you to separate the parts of the component that are visual (and thus part of the view) from those that are logical (and thus part of the data model). For example, by understanding this separation, you can see why the cursor position within a `JTextArea` isn't part of the data model, but rather is part of the view.

Table 3-1 provides a complete listing of the Swing components, the interface that describes the data model for each component, as well as the specific implementations. If a component isn't listed, that component inherits its data model from its parent class, most likely

`AbstractButton`. In addition, in some cases, multiple interfaces are used to describe a component, because the data is stored in one model and the selection of the data is in a second model. In the case of the `JComboBox`, the `MutableComboBoxModel` interface extends from `ComboBoxModel`. No predefined class implements the `ComboBoxModel` interface without also implementing the `MutableComboBoxModel` interface.

Table 3-1. *Swing Component Models*

Component	Data Model Interface	Implementations
<code>AbstractButton</code>	<code>ButtonModel</code>	<code>DefaultButtonModel</code>
<code>JColorChooser</code>	<code>ColorSelectionModel</code>	<code>DefaultColorSelectionModel</code>
<code>JComboBox</code>	<code>ComboBoxModel</code>	N/A
	<code>MutableComboBoxModel</code>	<code>DefaultComboBoxModel</code>
<code>JFileChooser</code>	<code>ListModel</code>	<code>BasicDirectoryModel</code>
<code>JList</code>	<code>ListModel</code>	<code>AbstractListModel</code>
		<code>DefaultListModel</code>
		<code>DefaultListSelectionModel</code>
<code>JMenuBar</code>	<code>SingleSelectionModel</code>	<code>DefaultSingleSelectionModel</code>
<code>JPopupMenu</code>	<code>SingleSelectionModel</code>	<code>DefaultSingleSelectionModel</code>
<code>JProgressBar</code>	<code>BoundedRangeModel</code>	<code>DefaultBoundedRangeModel</code>
<code>JScrollBar</code>	<code>BoundedRangeModel</code>	<code>DefaultBoundedRangeModel</code>
<code>JSlider</code>	<code>BoundedRangeModel</code>	<code>DefaultBoundedRangeModel</code>
<code>JSpinner</code>	<code>SpinnerModel</code>	<code>AbstractSpinnerModel</code>
		<code>SpinnerDateModel</code>
		<code>SpinnerListModel</code>
		<code>SpinnerNumberModel</code>
<code>JTabbedPane</code>	<code>SingleSelectionModel</code>	<code>DefaultSingleSelectionModel</code>
<code>JTable</code>	<code>TableModel</code>	<code>AbstractTableModel</code>
		<code>DefaultTableModel</code>
	<code>TableColumnModel</code>	<code>DefaultTableColumnModel</code>
	<code>ListSelectionModel</code>	<code>DefaultListSelectionModel</code>
<code>JTextComponent</code>	<code>Document</code>	<code>AbstractDocument</code>
		<code>PlainDocument</code>
		<code>StyledDocument</code>
		<code>DefaultStyleDocument</code>
		<code>HTMLDocument</code>

Table 3-1. *Swing Component Models (Continued)*

Component	Data Model Interface	Implementations
JToggleButton	ButtonModel	JToggleButton
		ToggleButtonModel
JTree	TreeModel	DefaultTreeModel
	TreeSelectionModel	DefaultTreeSelectionModel
		JTree.EmptySelectionModel

When directly accessing the model of a Swing component, if you change the model, all registered views are automatically notified. This, in turn, causes the views to revalidate themselves to ensure that the components display their proper current states. This automatic propagation of state changes is one reason why MVC has become so popular. In addition, using the MVC architecture helps programs become more maintainable as they change over time and their complexity grows. No longer will you need to worry about losing state information if you change visual component libraries!

Summary

This chapter provided a quick look at how the Swing components use a modified MVC architecture. You explored what makes up this modified architecture and how one particular component, the `JTextArea`, maps into this architecture. In addition, the chapter discussed the sharing of data models between components and listed all the data models for the different Swing components.

In Chapter 4, you'll start to look at the individual components that make up the Swing component library. In addition, you'll explore the Swing component class hierarchy as you examine the base `JComponent` component from the Swing library.



Core Swing Components

In Chapter 3, you received a quick introduction to the Model-View-Controller (MVC) pattern used by the components of the JFC/Swing project. In this chapter, you'll begin to explore how to use the key parts of the many available components.

All Swing components start with the `JComponent` class. Although some parts of the Swing libraries aren't rooted with the `JComponent` class, all the components share `JComponent` as the common parent class at some level of their ancestry. It's with this `JComponent` class that common behavior and properties are defined. In this chapter, you'll look at common functionality such as component painting, customization, tooltips, and sizing.

As far as specific `JComponent` descendent classes are concerned, you'll specifically look at the `JLabel`, `JButton`, and `JPanel`, three of the more commonly used Swing component classes. They require an understanding of the `Icon` interface for displaying images within components, as well as of the `ImageIcon` class for when using predefined images and the `GrayFilter` class for support. In addition, you'll look at the `AbstractButton` class, which serves as the parent class to the `JButton`. The data model shared by all `AbstractButton` subclasses is the `ButtonModel` interface; you'll explore that and the specific implementation class, the `DefaultButtonModel`.

JComponent Class

The `JComponent` class serves as the abstract root class from which all Swing components descend. The `JComponent` class has 42 descendent subclasses, each of which inherits much of the `JComponent` functionality. Figure 4-1 shows this hierarchy.

Although the `JComponent` class serves as the common root class for all Swing components, many classes in the libraries for the Swing project descend from classes other than `JComponent`. Those include all the high-level container objects such as `JFrame`, `JApplet`, and `JInternalFrame`; all the MVC-related classes; event-handling-related interfaces and classes; and much more. All of these will be discussed in later chapters.

Although all Swing components extend `JComponent`, the `JComponent` class extends the `AWT Container` class, which, in turn, extends from the `AWT Component` class. This means that many aspects of the `JComponent` are shared with both the `AWT Component` and `Container` classes.




Figure 4-1. *JComponent class hierarchy diagram*

Note `JComponent` extends from the `Container` class, but most of the `JComponent` subclasses aren't themselves containers of other components. To see if a particular Swing component is truly a container, check the `BeanInfo` for the class to see if the `isContainer` property is set to `true`. To get the `BeanInfo` for a class, ask the `Introspector`.

Component Pieces

The `JComponent` class defines many aspects of AWT components that go above and beyond the capabilities of the original AWT component set. This includes customized painting behavior and several different ways to customize display settings, such as colors, fonts, and any other client-side settings.

Painting `JComponent` Objects

Because the Swing `JComponent` class extends from the `Container` class, the basic AWT painting model is followed: All painting is done through the `paint()` method, and the `repaint()` method is used to trigger updates. However, many tasks are done differently. The `JComponent` class optimizes many aspects of painting for improved performance and extensibility. In addition, the `RepaintManager` class is available to customize painting behavior even further.

Note The public `void update(Graphics g)` method, inherited from `Component`, is never invoked on Swing components.

To improve painting performance and extensibility, the `JComponent` splits the painting operation into three tasks. The public `void paint(Graphics g)` method is subdivided into three separate protected method calls. In the order called, they are `paintComponent(g)`, `paintBorder(g)`, and `paintChildren(g)`, with the `Graphics` argument passed through from the original `paint()` call. The component itself is first painted through `paintComponent(g)`. If you want to customize the painting of a Swing component, you override `paintComponent()` instead of `paint()`. Unless you want to completely replace all the painting, you would call `super.paintComponent()` first, as shown here, to get the default `paintComponent()` behavior.

```
public class MyComponent extends JPanel {
    protected void paintComponent(Graphics g) {
        super.paintComponent(g);
        // Customize after calling super.paintComponent(g)
    }
    ...
}
```

Note When running a program that uses Swing components in Java 5.0, the `Graphics` argument passed to the `paint()` method and on to `paintComponent()` is technically a `Graphics2D` argument. Therefore, after casting the `Graphics` argument to a `Graphics2D` object, you could use the Java 2D capabilities of the platform, as you would when defining a drawing `Stroke`, `Shape`, or `AffineTransform`.

The `paintBorder()` and `paintChildren()` methods tend not to be overridden. The `paintBorder()` method draws a border around the component, a concept described more fully in Chapter 7. The `paintChildren()` method draws the components within the Swing container object, if any are present.

To optimize painting, the `JComponent` class provides three additional painting properties: `opaque`, `optimizedDrawingEnabled`, and `doubleBuffered`. These work as follows:

- **Opacity:** The `opaque` property for a `JComponent` defines whether a component is transparent. When transparent, the container of the `JComponent` must paint the background behind the component. To improve performance, you can leave the `JComponent` opaque and let the `JComponent` draw its own background, instead of relying on the container to draw the covered background.
- **Optimization:** The `optimizedDrawingEnabled` property determines whether immediate children can overlap. If children cannot overlap, the repaint time is reduced considerably. By default, optimized drawing is enabled for most Swing components, except for `JDesktopPane`, `JLayeredPane`, and `JViewport`.
- **Double buffering:** By default, all Swing components double buffer their drawing operations into a buffer shared by the complete container hierarchy; that is, all the components within a window (or subclass). This greatly improves painting performance, because when double buffering is enabled (with the `doubleBuffered` property), there is only a single screen update drawn.

Note For synchronous painting, you can call one of the public `void paintImmediately()` methods. (Arguments are either a `Rectangle` or its parts—position and dimensions.) However, you'll rarely need to call this directly unless your program has real-time painting requirements.

The public `void revalidate()` method of `JComponent` also offers painting support. When this method is called, the high-level container of the component validates itself. This is unlike the AWT approach requiring a direct call to the `revalidate()` method of that high-level component.

The last aspect of the Swing component painting enhancements is the `RepaintManager` class.

RepaintManager Class

The `RepaintManager` class is responsible for ensuring the efficiency of repaint requests on the currently displayed Swing components, making sure the smallest “dirty” region of the screen is updated when a region becomes invalid.

Although rarely customized, `RepaintManager` is public and provides a static installation routine to use a custom manager: `public static void setCurrentManager(RepaintManager manager)`. To get the current manager, just ask with `public static void currentManager(JComponent)`. The argument is usually `null`, unless you've customized the manager to provide component-level support. Once you have the manager, one thing you can do is get the off-screen buffer for a component as an `Image`. Because the buffer is what is eventually shown on

the screen, this effectively allows you to do a screen dump of the inside of a window (or any JComponent).

```
Component comp = ...
RepaintManager manager = RepaintManager.currentManager(null);
Image htmlImage = manager.getOffscreenBuffer(comp, comp.getWidth(),
    comp.getHeight());
// or
Image volatileImage = manager.getVolatileOffscreenBuffer(comp, comp.getWidth(),
    comp.getHeight());
```

Table 4-1 shows the two properties of RepaintManager. They allow you to disable double buffering for all drawing operations of a component (hierarchy) and to set the maximum double buffer size, which defaults to the end user's screen size.

Table 4-1. *RepaintManager Properties*

Property Name	Data Type	Access
doubleBufferingEnabled	boolean	Read-write
doubleBufferMaximumSize	Dimension	Read-write

Tip To globally disable double-buffered drawing, call `RepaintManager.currentManager(aComponent).setDoubleBufferingEnabled(false)`.

Although it's rarely done, providing your own RepaintManager subclass does allow you to customize the mechanism of painting dirty regions of the screen, or at least track when the painting is finished. Overriding any of the following four methods allows you to customize the mechanisms:

```
public synchronized void addDirtyRegion(JComponent component, int x, int y,
    int width, int height)
public Rectangle getDirtyRegion(JComponent component)
public void markCompletelyClean(JComponent component)
public void markCompletelyDirty(JComponent component)
```

UIDefaults Class

The UIDefaults class represents a lookup table containing the display settings installed for the current look and feel, such as which font to use within a JList, as well as what color or icon should be displayed within a JTree node. The use of UIDefaults will be detailed in Chapter 20 with the coverage of Java's pluggable look and feel architecture. Here, you will get a brief introduction to the UIDefaults table.

Whenever you create a component, the component automatically asks the `UIManager` to look in the `UIDefaults` table for the current settings for that component. Most color- and font-related component settings, as well as some others not related to colors and fonts, are configurable. If you don't like a particular setting, you can simply change it by updating the appropriate entry in the `UIDefaults` lookup table.

Note All predefined resource settings in the `UIDefaults` table implement the `UIResource` interface, which allows the components to monitor which settings have been customized just by looking for those settings that don't implement the interface.

First, you need to know the name of the `UIDefaults` setting you want to change. You can find the setting names in Appendix A of this book, which contains a complete alphabetical listing of all known settings for the predefined look and feel types in J2SE 5.0. (These differ a little from release to release.) In addition, included with the description of each component is a table containing the `UIResource`-related property elements. (To find the specific component section in the book, consult the table of contents or the index.)

Once you know the name of a setting, you can store a new setting with the `public static void put(Object key, Object value)` method of `UIManager`, where `key` is the key string. For instance, the following code will change the default background color of newly created buttons to black and the foreground color to red:

```
UIManager.put("Button.background", Color.BLACK);
UIManager.put("Button.foreground", Color.RED);
```

Fetching `UIResource` Properties

If you're creating your own components, or just need to find out the current value setting, you can ask the `UIManager`. Although the `public static Object get(Object key)` method is the most generic, it requires you to cast the return value to the appropriate class type. Alternatively, you could use one of the more specific `getXXX()` methods, which does the casting for you, to return the appropriate type:

```
public static boolean getBoolean(Object key)
public static Border getBorder(Object key)
public static Color getColor(Object key)
public static Dimension getDimension(Object key)
public static Font getFont(Object key)
public static Icon getIcon(Object key)
public static Insets getInsets(Object key)
public static int getInt(Object key)
public static String getString(Object key)
public static ComponentUI getUI(JComponent target)
```

There is a second set of overloaded methods that accept a second argument for the `Locale`.

Note You can also work with the `UIDefaults` directly, by calling the public static `UIDefaults` `getDefaults()` method of `UIManager`.

Client Properties

In addition to the `UIManager` maintaining a table of key/value pair settings, each instance of every component can manage its own set of key/value pairs. This is useful for maintaining aspects of a component that may be specific to a particular look and feel, or for maintaining data associated with a component without requiring the definition of new classes or methods to store such data.

```
public final void putClientProperty(Object key, Object value)
public final Object getClientProperty(Object key)
```

Note Calling `putClientProperty()` with a value of `null` causes the key to be removed from the client property table.

For instance, the `JTree` class has a property with the `Metal` look and feel for configuring the line style for connecting or displaying nodes within a `JTree`. Because the setting is specific to one look and feel, it doesn't make sense to add something to the tree API. Instead, you set the property by calling the following on a particular tree instance:

```
tree.putClientProperty("JTree.lineStyle", "None")
```

Then, when the look and feel is the default `Metal`, lines will connect the nodes of the tree. If another look and feel is installed, the client property will be ignored. Figure 4-2 shows a tree with and without lines.




Figure 4-2. A `JTree`, with and without angled lines

Note The list of client properties is probably one of the least documented aspects of Swing. Chapter 20 lists the available properties I was able to determine. Also, while Metal is the default look and feel, what you see is called Ocean. Ocean is a theme of the Metal look and feel and makes Metal look a bit flashier.

JComponent Properties

You’ve seen some of the pieces shared by the different JComponent subclasses. Now it’s time to look at the JavaBeans properties. Table 4-2 shows the complete list of properties defined by JComponent, including those inherited through the AWT Container and Component classes.

Table 4-2. *JComponent Properties*

Property Name	Data Type	Component Access	Container Access	JComponent Access
accessibleContext	AccessibleContext	Read-only	N/A	Read-only
actionMap	ActionMap	N/A	N/A	Read-write
alignmentX	float	Read-only	Read-only	Read-write
alignmentY	float	Read-only	Read-only	Read-write
ancestorListeners	AncestorListener[]	N/A	N/A	Read-only
autoscrolls	boolean	N/A	N/A	Read-write
background	Color	Read-write bound	N/A	Write-only
backgroundSet	boolean	Read-only	N/A	N/A
border	Border	N/A	N/A	Read-write bound
bounds	Rectangle	Read-write	N/A	N/A
colorModel	ColorModel	Read-only	N/A	N/A
componentCount	int	N/A	Read-only	N/A
componentListeners	ComponentListener[]	Read-only	N/A	N/A
componentOrientation	ComponentOrientation	Read-write bound	N/A	N/A
componentPopupMenu	JPopupMenu	N/A	N/A	Read-write
components	Component[]	N/A	Read-only	N/A
containerListeners	ContainerListener[]	N/A	Read-only	N/A
cursor	Cursor	Read-write	N/A	N/A
cursorSet	boolean	Read-only	N/A	N/A
debugGraphicsOptions	int	N/A	N/A	Read-write
displayable	boolean	Read-only	N/A	N/A

Table 4-2. *JComponent Properties (Continued)*

Property Name	Data Type	Component Access	Container Access	JComponent Access
doubleBuffered	boolean	Read-only	N/A	Read-write
dropTarget	DropTarget	Read-write	N/A	N/A
enabled	boolean	Read-write	N/A	Write-only bound
focusable	boolean	Read-write bound	N/A	N/A
focusCycleRoot	boolean	N/A	Read-write bound	N/A
focusCycleRootAncestor	Container	Read-only	N/A	N/A
focusListeners	FocusListener[]	Read-only	N/A	N/A
focusOwner	boolean	Read-only	N/A	N/A
focusTraversalKeysEnabled	boolean	Read-write bound	N/A	N/A
focusTraversalPolicy	FocusTraversalPolicy	N/A	Read-write bound	N/A
focusTraversalPolicyProvider	boolean	N/A	Read-write bound	N/A
focusTraversalPolicySet	boolean	N/A	Read-only	N/A
font	Font	Read-write bound	Write-only	Write-only
fontSet	boolean	Read-only	N/A	N/A
foreground	Color	Read-write bound	N/A	Write-only
foregroundSet	boolean	Read-only	N/A	N/A
graphics	Graphics	Read-only	N/A	Read-only
graphicsConfiguration	GraphicsConfiguration	Read-only	N/A	N/A
height	int	Read-only	N/A	Read-only
hierarchyBoundsListeners	HierarchyBoundsListener[]	Read-only	N/A	N/A
hierarchyListeners	HierarchyListener[]	Read-only	N/A	N/A
ignoreRepaint	boolean	Read-write	N/A	N/A
inheritsPopupMenu	boolean	N/A	N/A	Read-write
inputContext	InputContext	Read-only	N/A	N/A
inputMap	InputMap	N/A	N/A	Read-only
inputMethodListeners	InputMethodListener[]	Read-only	N/A	N/A
inputMethodRequests	InputMethodRequests	Read-only	N/A	N/A

Table 4-2. *JComponent Properties (Continued)*

Property Name	Data Type	Component Access	Container Access	JComponent Access
inputVerifier	InputVerifier	N/A	N/A	Read-write bound
insets	Insets	N/A	Read-only	Read-only
keyListeners	KeyListener[]	Read-only	N/A	N/A
layout	LayoutManager	N/A	Read-write	N/A
lightweight	boolean	Read-only	N/A	N/A
locale	Locale	Read-write bound	N/A	N/A
location	Point	Read-write	N/A	N/A
locationOnScreen	Point	Read-only	N/A	N/A
maximumSize	Dimension	Read-write bound	Read-only	Read-write
maximumSizeSet	boolean	Read-only	N/A	N/A
minimumSize	Dimension	Read-write bound	Read-only	Read-write
minimumSizeSet	boolean	Read-only	N/A	N/A
mouseListeners	MouseListener[]	Read-only	N/A	N/A
mouseMotionListeners	MouseMotionListener[]	Read-only	N/A	N/A
mousePosition	Point	Read-only	N/A	N/A
mouseWheelListeners	MouseWheelListener	Read-only	N/A	N/A
name	String	Read-write bound	N/A	N/A
opaque	boolean	Read-only	N/A	Read-write bound
optimizedDrawingEnabled	boolean	N/A	N/A	Read-only
paintingTile	boolean	N/A	N/A	Read-only
parent	Container	Read-only	N/A	N/A
preferredSize	Dimension	Read-write bound	Read-only	Read-write
preferredSizeSet	boolean	Read-only	N/A	N/A
propertyChangeListeners	PropertyChangeListener[]	Read-only	N/A	N/A
registeredKeyStrokes	KeyStroke[]	N/A	N/A	Read-only
requestFocusEnabled	boolean	N/A	N/A	Read-write
rootPane	JRootPane	N/A	N/A	Read-only

Table 4-2. *JComponent Properties (Continued)*

Property Name	Data Type	Component Access	Container Access	JComponent Access
showing	boolean	Read-only	N/A	N/A
size	Dimension	Read-write	N/A	N/A
toolkit	Toolkit	Read-only	N/A	N/A
tooltipText	String	N/A	N/A	Read-write
topLevelAncestor	Container	N/A	N/A	Read-only
transferHandler	TransferHandler	N/A	N/A	Read-write bound
treeLock	Object	Read-only	N/A	N/A
uiClassID	String	N/A	N/A	Read-only
valid	boolean	Read-only	N/A	N/A
validateRoot	boolean	N/A	N/A	Read-only
verifyInputWhenFocusTarget	boolean	N/A	N/A	Read-write bound
vetoableChangeListeners	VetoableChangeListener[]	N/A	N/A	Read-only
visible	boolean	Read-write	N/A	Write-only
visibleRect	Rectangle	N/A	N/A	Read-only
width	int	Read-only	N/A	Read-only
x	int	Read-only	N/A	Read-only
y	int	Read-only	N/A	Read-only

Note Additionally, there's a read-only `class` property defined at the `Object` level, the parent of the `Component` class.

Including the properties from the parent hierarchy, approximately 92 properties of `JComponent` exist. As that number indicates, the `JComponent` class is extremely well suited for visual development. There are roughly ten categories of `JComponent` properties, as described in the following sections.

Position-Oriented Properties

The `x` and `y` properties define the location of the component relative to its parent. The `locationOnScreen` is just another location for the component, this time relative to the screen's origin (the upper-left corner). The `width` and `height` properties define the size of the component. The `visibleRect` property describes the part of the component visible within the `topLevelAncestor`, whereas the `bounds` property defines the component's area, whether visible or not.

Component-Set-Oriented Properties

The `components` and `componentCount` properties enable you to find out what the children components are of the particular `JComponent`. For each component in the `components` property array, the current component would be its parent. In addition to determining a component's parent, you can find out its `rootPane` or `topLevelAncestor`.

Focus-Oriented Properties

The `focusable`, `focusCycleRoot`, `focusCycleRootAncestor`, `focusOwner`, `focusTraversalKeysEnabled`, `focusTraversalPolicy`, `focusTraversalPolicyProvider`, `focusTraversablePolicySet`, `requestFocusEnabled`, `verifyInputWhenFocusTarget`, and `inputVerifier` properties define the set of focus-oriented properties. These properties control the focus behavior of `JComponent` and were discussed in Chapter 2.

Layout-Oriented Properties

The `alignmentX`, `alignmentY`, `componentOrientation`, `layout`, `maximumSize`, `minimumSize`, `preferredSize`, `maximumSizeSet`, `minimumSizeSet`, and `preferredSizeSet` properties are used to help with layout management.

Painting Support Properties

The `background` and `foreground` properties describe the current drawing colors. The `font` property describes the text style to draw. The `backgroundSet`, `foregroundSet`, and `fontSet` properties describe if the properties are explicitly set. The `insets` and `border` properties are intermixed to describe the drawing of a border around a component. The `graphics` property permits real-time drawing, although the `paintImmediately()` method might now suffice.

To improve performance, there are the `opaque` (false is transparent), `doubleBuffered`, `ignoreRepaint`, and `optimizedDrawingEnabled` properties. The `colorModel` and `paintingTile` properties store intermediate drawing information. The `graphicsConfiguration` property adds support for virtual devices.

`debugGraphicsOption` allows you to slow down the drawing of your component if you can't figure out why it's not painted properly. The `debugGraphicsOption` property is set to one or more of the settings shown in Table 4-3.

Table 4-3. *DebugGraphics Settings*

DebugGraphics Settings	Description
<code>DebugGraphics.BUFFERED_OPTION</code>	Causes a window to pop up, displaying the drawing of the double-buffered image
<code>DebugGraphics.FLASH_OPTION</code>	Causes the drawing to be done more slowly, flashing between steps
<code>DebugGraphics.LOG_OPTION</code>	Causes a message to be printed to the screen as each step is done
<code>DebugGraphics.NONE_OPTION</code>	Disables all options

You can combine multiple `DebugGraphics` settings with the bitwise OR (`|`) operator, as in this example:

```
JComponent component = new ...();  
component.setDebugGraphicsOptions(DebugGraphics.BUFFERED_OPTION |  
    DebugGraphics.FLASH_OPTION | DebugGraphics.LOG_OPTION);
```

Internationalization Support Properties

The `inputContext`, `inputMethodRequests`, and `locale` properties help when creating multilingual operations.

State Support Properties

To get state information about a component, all you have to do is ask; there's much you can discover. The `autoscrolls` property lets you place a component within a `JViewport` and it automatically scrolls when dragged. The `validateRoot` property is used when `revalidate()` has been called and returns `true` when the current component is at the point it should stop. The remaining seven properties are self-explanatory: `displayable`, `dropTarget`, `enabled`, `lightweight`, `showing`, `valid`, and `visible`.

Event Support Properties

The `registeredKeyStrokes`, `inputMap`, and `actionMap` properties allow you to register keystroke responses with a window. All the `getXXXListeners()` methods allow you to get the current set of listeners for a particular listener type.

Pop-Up Support Properties

There are two types of pop-ups associated with a component: tooltips and pop-up menus. The `toolTipText` property is set to display pop-up support text over a component. The `componentPopupMenu` and `inheritsPopupMenu` properties are related to automatically showing pop-up menus associated with the component. The `mousePosition` property helps to position these.

Other Properties

The remaining properties don't seem to have any kind of logical grouping. The `accessibleContext` property is for support with the `javax.accessibility` package. The `cursor` property lets you change the cursor to one of the available cursors, where `cursorSet` is used to recognize when the property is explicitly set. The `toolkit` property encapsulates platform-specific behaviors for accessing system resources. The `transferHandler` property is there for drag-and-drop support. The `name` property gives you the means to recognize a particular instance of a class. The `treeLock` property is the component tree-synchronization locking resource. The `uiClassID` property is new; it allows subclasses to return the appropriate class ID for their specific instance.

Handling JComponent Events

There are many different types of events that all JComponent subclasses share. Most of these come from parent classes, like Component and Container. First, you'll explore the use of PropertyChangeListener, which is inherited from Container. Then you'll look at the use of two event-handling capabilities shared by all JComponent subclasses: VetoableChangeListener and AncestorListener. Finally, you'll see the complete set of listeners inherited from Component.

Listening to Component Events with a PropertyChangeListener

The JComponent class has several component bound properties, directly and indirectly. By binding a PropertyChangeListener to the component, you can listen for particular JComponent property changes, and then respond accordingly.

```
public interface PropertyChangeListener extends EventListener {  
    public void propertyChange(PropertyChangeEvent propertyChangeEvent);  
}
```

To demonstrate, the PropertyChangeListener in Listing 4-1 demonstrates the behavior you might need when listening for changes to an Action type property within a JButton component. The property that changes determines which if block is executed.

Listing 4-1. *Watching for Changes to a JButton*

```
import java.beans.*;  
import javax.swing.*;  
  
public class ActionChangeListener implements PropertyChangeListener {  
  
    private JButton button;  
  
    public ActionChangeListener(JButton button) {  
        this.button = button;  
    }  
  
    public void propertyChange(PropertyChangeEvent e) {  
        String propertyName = e.getPropertyName();  
        if (e.getPropertyName().equals(Action.NAME)) {  
            String text = (String)e.getNewValue();  
            button.setText(text);  
            button.repaint();  
        } else if (propertyName.equals("enabled")) {  
            Boolean enabledState = (Boolean)e.getNewValue();  
            button.setEnabled(enabledState.booleanValue());  
            button.repaint();  
        }  
    }  
}
```

```

    } else if (e.getPropertyName().equals(Action.SMALL_ICON)) {
        Icon icon = (Icon)e.getNewValue();
        button.setIcon(icon);
        button.invalidate();
        button.repaint();
    }
}
}
}

```

Note You can bind a `PropertyChangeListener` to a specific property by adding the listener with `addPropertyChangeListener(String propertyName, PropertyChangeListener listener)`. This allows your listener to avoid having to check for the specific property that changed.

Listening to JComponent Events with a `VetoableChangeListener`

The `VetoableChangeListener` is another JavaBeans listener that Swing components use. It works with constrained properties, whereas the `PropertyChangeListener` works with only bound properties. A key difference between the two is that the public `void vetoableChange(PropertyChangeEvent propertyChangeEvent)` method can throw a `PropertyVetoException` if the listener doesn't like the requested change.

```

public interface VetoableChangeListener extends EventListener {
    public void vetoableChange(PropertyChangeEvent propertyChangeEvent)
        throws PropertyVetoException;
}

```

Note Only one Swing class, `JInternalFrame`, has constrained properties. The listener is meant primarily for programmers to use with their own newly created components.

Listening to JComponent Events with an `AncestorListener`

You can use an `AncestorListener` to find out when a component moves, is made visible, or is made invisible. It's useful if you permit your users to customize their screens by moving components around and possibly removing components from the screens.

```

public interface AncestorListener extends EventListener {
    public void ancestorAdded(AncestorEvent ancestorEvent);
    public void ancestorMoved(AncestorEvent ancestorEvent);
    public void ancestorRemoved(AncestorEvent ancestorEvent);
}

```

To demonstrate, Listing 4-2 associates an `AncestorListener` with the root pane of a `JFrame`. You'll see the messages `Removed`, `Added`, and `Moved` when the program first starts up. In addition, you'll see `Moved` messages when you drag the frame around.

Listing 4-2. *Listening for Ancestor Events*

```
import java.awt.*;
import javax.swing.*;
import javax.swing.event.*;

public class AncestorSampler {
    public static void main (String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Ancestor Sampler");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                AncestorListener ancestorListener = new AncestorListener() {
                    public void ancestorAdded(AncestorEvent ancestorEvent) {
                        System.out.println ("Added");
                    }
                    public void ancestorMoved(AncestorEvent ancestorEvent) {
                        System.out.println ("Moved");
                    }
                    public void ancestorRemoved(AncestorEvent ancestorEvent) {
                        System.out.println ("Removed");
                    }
                };
                frame.getRootPane().addAncestorListener(ancestorListener);
                frame.setSize(300, 200);
                frame.setVisible(true);
                frame.getRootPane().setVisible(false);
                frame.getRootPane().setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

Listening to Inherited Events of a `JComponent`

In addition to the ability to listen for an instance of an `AncestorEvent` or `PropertyChangeEvent` with a `JComponent`, the `JComponent` inherits the ability to listen to many other events from its `Container` and `Component` superclasses.

Table 4-4 lists ten event listeners. You may find yourself using the JComponent listener interfaces quite a bit, but the older ones work, too. Use the ones most appropriate for the task at hand.

Table 4-4. *JComponent Inherited Event Listeners*

Class	Event Listener	Event Object
Component	ComponentListener	componentHidden(ComponentEvent)
		componentMoved(ComponentEvent)
		componentResized(ComponentEvent)
		componentShown(ComponentEvent)
Component	FocusListener	focusGained(FocusEvent)
		focusLost(FocusEvent)
Component	HierarchyBoundsListener	ancestorMoved(HierarchyEvent)
		ancestorResized(HierarchyEvent)
Component	HierarchyListener	hierarchyChanged(HierarchyEvent)
Component	InputMethodListener	caretPositionChanged (InputMethodEvent)
		inputMethodTextChanged (InputMethodEvent)
Component	KeyListener	keyPressed(KeyEvent)
		keyReleased(KeyEvent)
		keyTyped(KeyEvent)
Component	MouseListener	mouseClicked(MouseEvent)
		mouseEntered(MouseEvent)
		mouseExited(MouseEvent)
		mousePressed(MouseEvent)
		mouseReleased(MouseEvent)
Component	MouseMotionListener	mouseDragged(MouseEvent)
		mouseMoved(MouseEvent)
Component	MouseWheelListener	mouseWheelMoved(MouseWheelEvent)
Container	ContainerListener	componentAdded(ContainerEvent)
		componentRemoved(ContainerEvent)

JToolTip Class

The Swing components support the ability to display brief pop-up messages when the cursor rests over them. The class used to display pop-up messages is `JToolTip`.

Creating a JToolTip

Calling the public void `setToolTipText(String text)` method of `JComponent` automatically causes the creation of a `JToolTip` instance when the mouse rests over a component with the installed pop-up message. You don't normally call the `JToolTip` constructor directly. There's only one constructor, and it's of the no-argument variety.

Tooltip text is normally one line long. However, if the text string begins with `<html>` (in any case), then the contents can be any HTML 3.2 formatted text. For instance, the following line causes the pop-up message shown in Figure 4-3:

```
component.setToolTipText("<html>Tooltip<br>Message");
```




Figure 4-3. *HTML-based tooltip text*

Creating Customized JToolTip Objects

You can easily customize the display characteristics for all pop-up messages by setting `UIResource` elements for `JToolTip`, as shown in the “Customizing a `JToolTip` Look and Feel” section later in this chapter.

The `JComponent` class defines an easy way for you to customize the display characteristics of the tooltip when it's placed over a specific component. Simply subclass the component you want to customize and override its inherited public `JToolTip createToolTip()` method. The `createToolTip()` method is called when the `ToolTipManager` has determined that it's time to display the pop-up message.

To customize the pop-up tooltip appearance, just override the method and customize the `JToolTip` returned from the inherited method. For instance, the following source demonstrates the setting of a custom coloration for the tooltip for a `JButton`, as shown in Figure 4-4.

```
JButton b = new JButton("Hello, World") {
    public JToolTip createToolTip() {
        JToolTip tip = super.createToolTip();
        tip.setBackground(Color.YELLOW);
        tip.setForeground(Color.RED);
        return tip;
    }
};
```




Figure 4-4. *Tooltip text displayed with custom colors*

After the `JToolTip` has been created, you can configure the inherited `JComponent` properties or any of the properties specific to `JToolTip`, as shown in Table 4-5.

Table 4-5. *JToolTip Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>component</code>	<code>JComponent</code>	Read-write
<code>tipText</code>	<code>String</code>	Read-write
<code>UI</code>	<code>ToolTipUI</code>	Read-only
<code>UIClassID</code>	<code>String</code>	Read-only

Displaying Positional Tooltip Text

Swing components can even support the display of different tooltip text, depending on where the mouse pointer is located. This requires overriding the public boolean `contains(int x, int y)` method, which originates from the `Component` class.

For instance, after enhancing the customized `JButton` created in the previous section (Figure 4-4), the tooltip text will differ, depending on whether or not the mouse pointer is within 50 pixels from the left edge of the component.

```
JButton button = new JButton("Hello, World") {
    public JToolTip createToolTip() {
        JToolTip tip = super.createToolTip();
        tip.setBackground(Color.YELLOW);
        tip.setForeground(Color.RED);
        return tip;
    }
    public boolean contains(int x, int y) {
        if (x < 50) {
            setToolTipText("Got Green Eggs?");
        } else {
            setToolTipText("Got Ham?");
        }
        return super.contains(x, y);
    }
};
```

Customizing a JToolTip Look and Feel

Each installable Swing look and feel provides a different JToolTip appearance and a set of default UIResource value settings. Figure 4-5 shows the appearance of the JToolTip component for the preinstalled set of look and feel types: Motif, Windows, and Ocean.




Figure 4-5. *JToolTip under different look and feel types*

The available set of UIResource-related properties for a JToolTip is shown in Table 4-6. For the JToolTip component, there are nine different properties.

Table 4-6. *JToolTip UIResource Elements*

Property String	Object Type
ToolTip.background	Color
ToolTip.backgroundInactive	Color
ToolTip.border	Border
ToolTip.borderInactive	Color
ToolTip.font	Font
ToolTip.foreground	Color
ToolTip.foregroundInactive	Color
ToolTip.hideAccelerator	Boolean
ToolTipUI	String

As noted earlier in this chapter, the JToolTip class supports the display of arbitrary HTML content. This permits the display of multiple-column and multiple-row input.

ToolTipManager Class

Although the JToolTip is something of a passive object, in the sense that the JComponent creates and shows the JToolTip on its own, there are many more configurable aspects of its usage. However, these configurable aspects are the responsibility of the class that manages tooltips, not the JToolTip itself. The class that manages tooltip usage is aptly named ToolTipManager. With the Singleton design pattern, no constructor for ToolTipManager exists. Instead, you have access to the current manager through the static sharedInstance() method of ToolTipManager.

ToolTipManager Properties

Once you have accessed the shared instance of `ToolTipManager`, you can customize when and if tooltip text appears. As Table 4-7 shows, there are five configurable properties.

Table 4-7. *ToolTipManager Properties*

Property Name	Data Type	Access
<code>dismissDelay</code>	<code>int</code>	Read-write
<code>enabled</code>	<code>boolean</code>	Read-write
<code>initialDelay</code>	<code>int</code>	Read-write
<code>lightWeightPopupEnabled</code>	<code>boolean</code>	Read-write
<code>reshowDelay</code>	<code>int</code>	Read-only

Initially, tooltips are enabled, but you can disable them with `ToolTipManager.sharedInstance().setEnabled(false)`. This allows you to always associate tooltips with components, while letting the end user enable and disable them when desired.

There are three timing-oriented properties: `initialDelay`, `dismissDelay`, and `reshowDelay`. They all measure time in milliseconds. The `initialDelay` property is the number of milliseconds the user must rest the mouse inside the component before the appropriate tooltip text appears. The `dismissDelay` specifies the length of time the text appears while the mouse remains motionless; if the user moves the mouse, it also causes the text to disappear. The `reshowDelay` determines how long a user must remain outside a component before reentry would cause the pop-up text to reappear.

The `lightWeightPopupEnabled` property is used to determine the pop-up window type to hold the tooltip text. If the property is `true` and the pop-up text fits entirely within the bounds of the top-level window, the text appears within a `Swing JPanel`. If this property is `false` and the pop-up text fits entirely within the bounds of the top-level window, the text appears within an `AWT Panel`. If part of the text wouldn't appear within the top-level window no matter what the property setting is, the pop-up text would appear within a `Window`.

Although not properties of `ToolTipManager`, two other methods of `ToolTipManager` are worth mentioning:

```
public void registerComponent(JComponent component)
public void unregisterComponent(JComponent component)
```

When you call the `setToolTipText()` method of `JComponent`, this causes the component to register itself with the `ToolTipManager`. There are times, however, when you need to register a component directly. This is necessary when the display of part of a component is left to another renderer. With `JTree`, for instance, a `TreeCellRenderer` displays each node of the tree. When the renderer displays the tooltip text, you “register” the `JTree` and tell the renderer what text to display.

```
JTree tree = new JTree(...);
ToolTipManager.sharedInstance().registerComponent(tree);
TreeCellRenderer renderer = new ATreeCellRenderer(...);
tree.setCellRenderer(renderer);
...
public class ATreeCellRenderer implements TreeCellRenderer {
...
    public Component getTreeCellRendererComponent(JTree tree, Object value,
        boolean selected, boolean expanded, boolean leaf, int row, boolean hasFocus) {
        ...
        renderer.setToolTipText("Some Tip");
        return renderer;
    }
}
```

Note If this sounds confusing, don't worry. We'll revisit the `JTree` in Chapter 17.

JLabel Class

The first real Swing component to examine closely is the simplest, the `JLabel`. The `JLabel` serves as the replacement component for the AWT `Label` but it can do *much* more. Whereas the AWT `Label` is limited to a single line of text, the Swing `JLabel` can have text, images, or both. The text can be a single line of text or HTML. In addition `JLabel` can support different enabled and disabled images. Figure 4-6 shows some sample `JLabel` components.




Figure 4-6. Sample `JLabel` components

Note A `JLabel` subclass is used as the default renderer for each of the `JList`, `JComboBox`, `JTable`, and `JTree` components.

Creating a JLabel

There are six constructors for JLabel:

```
public JLabel()
JLabel label = new JLabel();

public JLabel(Icon image)
Icon icon = new ImageIcon("dog.jpg");
JLabel label = new JLabel(icon);

public JLabel(Icon image, int horizontalAlignment)
Icon icon = new ImageIcon("dog.jpg");
JLabel label = new JLabel(icon, JLabel.RIGHT);

public JLabel(String text)
JLabel label = new JLabel("Dog");

public JLabel(String text, int horizontalAlignment)
JLabel label = new JLabel("Dog", JLabel.RIGHT);

public JLabel(String text, Icon icon, int horizontalAlignment)
Icon icon = new ImageIcon("dog.jpg");
JLabel label = new JLabel("Dog", icon, JLabel.RIGHT);
```

With the constructors for JLabel, you can customize any of three properties of the JLabel: text, icon, or horizontalAlignment. By default, the text and icon properties are empty, whereas the initial horizontalAlignment property setting depends on the constructor arguments. These settings can be any of JLabel.LEFT, JLabel.CENTER, or JLabel.RIGHT. In most cases, not specifying the horizontalAlignment setting results in a left-aligned label. However, if only the initial icon is specified, then the default alignment is centered.

JLabel Properties

Table 4-8 shows the 14 properties of JLabel. They allow you to customize the content, position, and (in a limited sense) the behavior of the JLabel.

Table 4-8. *JLabel Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
disabledIcon	Icon	Read-write bound
displayedMnemonic	char	Read-write bound
displayedMnemonicIndex	int	Read-write bound
horizontalAlignment	int	Read-write bound
horizontalTextPosition	int	Read-write bound

Table 4-8. *JLabel Properties (Continued)*

Property Name	Data Type	Access
icon	Icon	Read-write bound
iconTextGap	int	Read-write bound
labelFor	Component	Read-write bound
text	String	Read-write bound
UI	LabelUI	Read-write
UIClassID	String	Read-only
verticalAlignment	int	Read-write bound
verticalTextPosition	int	Read-write bound

The content of the `JLabel` is the text and its associated image. Displaying an image within a `JLabel` will be discussed in the “Interface Icon” section later in this chapter. However, you can display different icons, depending on whether the `JLabel` is enabled or disabled. By default, the icon is a grayscale version of the enabled icon, if the enabled icon comes from an `Image` object (`ImageIcon`, as described later in the chapter). If the enabled icon doesn’t come from an `Image`, there’s no icon when `JLabel` is disabled, unless manually specified.

The position of the contents of the `JLabel` is described by four different properties: `horizontalAlignment`, `horizontalTextPosition`, `verticalAlignment`, and `verticalTextPosition`. The `horizontalAlignment` and `verticalAlignment` properties describe the position of the contents of the `JLabel` within the container in which it’s placed.

Note Alignments have an effect only if there’s extra space for the layout manager to position the component. If you’re using a layout manager such as `FlowLayout`, which sizes components to their preferred size, these settings will effectively be ignored.

The horizontal position can be any of the `JLabel` constants `LEFT`, `RIGHT`, or `CENTER`. The vertical position can be `TOP`, `BOTTOM`, or `CENTER`. Figure 4-7 shows various alignment settings, with the label reflecting the alignments.

The text position properties reflect where the text is positioned relative to the icon when both are present. The properties can be set to the same constants as the alignment constants. Figure 4-8 shows various text position settings, with each label reflecting the setting.

Note The constants for the different positions come from the `SwingConstants` interface that the `JLabel` class implements.




Figure 4-7. Various *JLabel* alignments




Figure 4-8. Various *JLabel* text positions

JLabel Event Handling

No event-handling capabilities are specific to the `JLabel`. Besides the event-handling capabilities inherited through `JComponent`, the closest thing there is for event handling with the `JLabel` is the combined usage of the `displayedMnemonic`, `displayedMnemonicIndex`, and `labelFor` properties.

When the `displayedMnemonic` and `labelFor` properties are set, pressing the keystroke specified by the mnemonic, along with the platform-specific hotkey (usually `Alt`), causes the input focus to shift to the component associated with the `labelFor` property. This can be helpful when a component doesn't have its own manner of displaying a mnemonic setting, such as with all the text input components. Here is an example, which results in the display shown in Figure 4-9:

```
JLabel label = new JLabel("Username");
JTextField textField = new JTextField();
label.setDisplayedMnemonic(KeyEvent.VK_U);
label.setLabelFor(textField);
```




Figure 4-9. Using a *JLabel* to display the mnemonic for another component

The displayedMnemonicIndex property adds the ability for the mnemonic highlighted to not be the first instance of mnemonic in the label's text. The index you specify represents the position in the text, not the instance of the mnemonic. To highlight the second *e* in Username, you would specify an index of 7: `label.setDisplayedMnemonicIndex(7)`.

Note The component setting of the `labelFor` property is stored as a client property of the `JLabel` with the `LABELLED_BY_PROPERTY` key constant. The setting is used for accessibility purposes.

Customizing a JLabel Look and Feel

Each installable Swing look and feel provides a different `JLabel` appearance and set of default `UIResource` value settings. Although appearances differ based on the current look and feel, the differences are minimal within the preinstalled set of look and feel types. Table 4-9 shows the available set of `UIResource`-related properties for a `JLabel`. There are eight different properties for the `JLabel` component.

Table 4-9. *JLabel UIResource Elements*

Property String	Object Type
<code>Label.actionMap</code>	<code>ActionMap</code>
<code>Label.background</code>	<code>Color</code>
<code>Label.border</code>	<code>Border</code>
<code>Label.disabledForeground</code>	<code>Color</code>
<code>Label.disabledShadow</code>	<code>Color</code>
<code>Label.font</code>	<code>Font</code>
<code>Label.foreground</code>	<code>Color</code>
<code>LabelUI</code>	<code>String</code>

Interface Icon

The `Icon` interface is used to associate glyphs with various components. A *glyph* (like a symbol on a highway sign that conveys information nonverbally, such as “winding road ahead!”) can be a simple drawing or a GIF image loaded from disk with the `ImageIcon` class. The interface contains two properties describing the size and a method to paint the glyph.

```
public interface Icon {
    // Properties
    public int getIconHeight();
    public int getIconWidth();
    // Other methods
    public void paintIcon(Component c, Graphics g, int x, int y);
}
```

Creating an Icon

Creating an Icon is as simple as implementing the interface. All you need to do is specify the size of the icon and what to draw. Listing 4-3 shows one such Icon implementation. The icon is a diamond-shaped glyph in which the size, color, and filled-status are all configurable.

Tip In implementing the `paintIcon()` method of the Icon interface, translate the drawing coordinates of the graphics context based on the x and y position passed in, and then translate them back when the drawing is done. This greatly simplifies the different drawing operations.

Listing 4-3. Reusable Diamond Icon Definition

```
import javax.swing.*;
import java.awt.*;

public class DiamondIcon implements Icon {
    private Color color;
    private boolean selected;
    private int width;
    private int height;
    private Polygon poly;
    private static final int DEFAULT_WIDTH = 10;
    private static final int DEFAULT_HEIGHT = 10;

    public DiamondIcon(Color color) {
        this(color, true, DEFAULT_WIDTH, DEFAULT_HEIGHT);
    }

    public DiamondIcon(Color color, boolean selected) {
        this(color, selected, DEFAULT_WIDTH, DEFAULT_HEIGHT);
    }

    public DiamondIcon(Color color, boolean selected, int width, int height) {
        this.color = color;
        this.selected = selected;
        this.width = width;
        this.height = height;
        initPolygon();
    }

    private void initPolygon() {
        poly = new Polygon();
        int halfWidth = width/2;
        int halfHeight = height/2;
        poly.addPoint(0, halfHeight);
        poly.addPoint(halfWidth, 0);
    }
}
```

```
        poly.addPoint(width, halfHeight);
        poly.addPoint(halfWidth, height);
    }

    public int getIconHeight() {
        return height;
    }

    public int getIconWidth() {
        return width;
    }

    public void paintIcon(Component c, Graphics g, int x, int y) {
        g.setColor(color);
        g.translate(x, y);
        if (selected) {
            g.fillPolygon(poly);
        } else {
            g.drawPolygon(poly);
        }
        g.translate(-x, -y);
    }
}
```

Using an Icon

Once you have your `Icon` implementation, using the `Icon` is as simple as finding a component with an appropriate property. For example, here's the icon with a `JLabel`:

```
Icon icon = new DiamondIcon(Color.RED, true, 25, 25);
JLabel label = new JLabel(icon);
```

Figure 4-10 shows what such a label might look like.




Figure 4-10. *Using an Icon in a JLabel*

ImageIcon Class

The `ImageIcon` class presents an implementation of the `Icon` interface for creating glyphs from AWT `Image` objects, whether from memory (a `byte[]`), off a disk (a file name), or over the network (a URL). Unlike with regular `Image` objects, the loading of an `ImageIcon` is immediately started when the `ImageIcon` is created, though it might not be fully loaded when used. In addition,

unlike `Image` objects, `ImageIcon` objects are serializable so that they can be easily used by JavaBean components.

Creating an ImageIcon

There are nine constructors for an `ImageIcon`:

```
public ImageIcon()
Icon icon = new ImageIcon();
icon.setImage(anImage);

public ImageIcon(Image image)
Icon icon = new ImageIcon(anImage);

public ImageIcon(String filename)
Icon icon = new ImageIcon(filename);

public ImageIcon(URL location)
Icon icon = new ImageIcon(url);

public ImageIcon(byte imageData[])
Icon icon = new ImageIcon(aByteArray);

public ImageIcon(Image image, String description)
Icon icon = new ImageIcon(anImage, "Duke");

public ImageIcon(String filename, String description)
Icon icon = new ImageIcon(filename, filename);

public ImageIcon(URL location, String description)
Icon icon = new ImageIcon(url, location.getFile());

public ImageIcon(byte imageData[], String description)
Icon icon = new ImageIcon(aByteArray, "Duke");
```

The no-argument version creates an uninitialized version (empty). The remaining eight offer the ability to create an `ImageIcon` from an `Image`, byte array, file name `String`, or `URL`, with or without a description.

Using an ImageIcon

Using an `ImageIcon` is as simple as using an `Icon`: just create the `ImageIcon` and associate it with a component.

```
Icon icon = new ImageIcon("Warn.gif");
JLabel label3 = new JLabel("Warning", icon, JLabel.CENTER)
```

ImageIcon Properties

Table 4-10 shows the six properties of `ImageIcon`. The height and width of the `ImageIcon` are the height and width of the actual `Image` object. The `imageLoadStatus` property represents the results of the loading of the `ImageIcon` from the hidden `MediaTracker`, either `MediaTracker.ABORTED`, `MediaTracker.ERRORERD`, or `MediaTracker.COMPLETE`.

Table 4-10. *ImageIcon Properties*

Property Name	Data Type	Access
<code>description</code>	<code>String</code>	Read-write
<code>iconHeight</code>	<code>int</code>	Read-only
<code>iconWidth</code>	<code>int</code>	Read-only
<code>image</code>	<code>Image</code>	Read-write
<code>imageLoadStatus</code>	<code>int</code>	Read-only
<code>imageObserver</code>	<code>ImageObserver</code>	Read-write

Sometimes, it's useful to use an `ImageIcon` to load an `Image`, and then just ask for the `Image` object from the `Icon`.

```
ImageIcon imageIcon = new ImageIcon(...);
Image image = imageIcon.getImage();
```

There is one major problem with using `ImageIcon` objects: They don't work when the image and class file using the icon are both loaded in a JAR (Java archive) file, unless you explicitly specify the full URL for the file within the JAR (`jar:http://www.example.com/directory/foo.jar!/com/example/image.gif`). You can't just specify the file name as a `String` and let the `ImageIcon` find the file. You must manually get the image data first, and then pass the data along to the `ImageIcon` constructor.

To help with loading images outside JAR files, Listing 4-4 shows an `ImageLoader` class that provides a public static `Image getImage(Class relativeClass, String filename)` method. You specify both the base class where the image file relative is found and the file name for the image file. Then you just need to pass the `Image` object returned to the constructor of `ImageIcon`.

Listing 4-4. *Image Loading Support Class*

```
import java.awt.*;
import java.io.*;

public final class ImageLoader {

    private ImageLoader() {
    }
```

```

public static Image getImage(Class relativeClass, String filename) {
    Image returnValue = null;
    InputStream is = relativeClass.getResourceAsStream(filename);
    if (is != null) {
        BufferedInputStream bis = new BufferedInputStream(is);
        ByteArrayOutputStream baos = new ByteArrayOutputStream();
        try {
            int ch;
            while ((ch = bis.read()) != -1) {
                baos.write(ch);
            }
            returnValue = Toolkit.getDefaultToolkit().createImage(baos.toByteArray());
        } catch (IOException exception) {
            System.err.println("Error loading: " + filename);
        }
    }
    return returnValue;
}
}

```

Here's how you use the helper class:

```

Image warnImage = ImageLoader.getImage(LabelJarSample.class, "Warn.gif");
Icon warnIcon = new ImageIcon(warnImage);
JLabel label2 = new JLabel(warnIcon);

```

■ **Tip** Keep in mind that the Java platform supports GIF89A animated images.

GrayFilter Class

One additional class worth mentioning here is `GrayFilter`. Many of the Swing component classes rely on this class to create a disabled version of an `Image` to be used as an `Icon`. The components use the class automatically, but there might be times when you need an AWT `ImageFilter` that does grayscales. You can convert an `Image` from normal to grayed out with a call to the one useful method of the class: `public static Image createDisabledImage(Image image)`.

```

Image normalImage = ...
Image grayImage = GrayFilter.createDisabledImage(normalImage)

```

You can now use the grayed-out image as the `Icon` on a component:

```

Icon warningIcon = new ImageIcon(grayImage);
JLabel warningLabel = new JLabel(warningIcon);

```

AbstractButton Class

The `AbstractButton` class is an important Swing class that works behind the scenes as the parent class of all the Swing button components, as shown at the top of Figure 4-1. The `JButton`, described in the “`JButton` Class” section later in this chapter, is the simplest of the subclasses. The remaining subclasses are described in later chapters.

Each of the `AbstractButton` subclasses uses the `ButtonModel` interface to store their data model. The `DefaultButtonModel` class is the default implementation used. In addition, you can group any set of `AbstractButton` objects into a `ButtonGroup`. Although this grouping is most natural with the `JRadioButton` and `JRadioButtonMenuItem` components, any of the `AbstractButton` subclasses will work.

AbstractButton Properties

Table 4-11 lists the 32 properties (with mnemonic listed twice) of `AbstractButton` shared by all its subclasses. They allow you to customize the appearance of all the buttons.

Table 4-11. *AbstractButton Properties*

Property Name	Data Type	Access
<code>action</code>	<code>Action</code>	Read-write bound
<code>actionCommand</code>	<code>String</code>	Read-write
<code>actionListeners</code>	<code>ActionListener[]</code>	Read-only
<code>borderPainted</code>	<code>boolean</code>	Read-write bound
<code>changeListeners</code>	<code>ChangeListener[]</code>	Read-only
<code>contentAreaFilled</code>	<code>boolean</code>	Read-write bound
<code>disabledIcon</code>	<code>Icon</code>	Read-write bound
<code>disabledSelectedIcon</code>	<code>Icon</code>	Read-write bound
<code>displayedMnemonicIndex</code>	<code>int</code>	Read-write bound
<code>enabled</code>	<code>boolean</code>	Write-only
<code>focusPainted</code>	<code>boolean</code>	Read-write bound
<code>horizontalAlignment</code>	<code>int</code>	Read-write bound
<code>horizontalTextPosition</code>	<code>int</code>	Read-write bound
<code>icon</code>	<code>Icon</code>	Read-write bound
<code>iconTextGap</code>	<code>int</code>	Read-write bound
<code>itemListeners</code>	<code>ItemListener[]</code>	Read-only
<code>layout</code>	<code>LayoutManager</code>	Write-only
<code>margin</code>	<code>Insets</code>	Read-write bound
<code>mnemonic</code>	<code>char</code>	Read-write bound

Table 4-11. *AbstractButton Properties (Continued)*

Property Name	Data Type	Access
<code>mnemonic</code>	<code>int</code>	Write-only
<code>model</code>	<code>ButtonModel</code>	Read-write bound
<code>multiClickThreshold</code>	<code>long</code>	Read-write
<code>pressedIcon</code>	<code>Icon</code>	Read-write bound
<code>rolloverEnabled</code>	<code>boolean</code>	Read-write bound
<code>rolloverIcon</code>	<code>Icon</code>	Read-write bound
<code>rolloverSelectedIcon</code>	<code>Icon</code>	Read-write bound
<code>selected</code>	<code>boolean</code>	Read-write
<code>selectedIcon</code>	<code>Icon</code>	Read-write bound
<code>selectedObjects</code>	<code>Object[]</code>	Read-only
<code>text</code>	<code>String</code>	Read-write bound
<code>UI</code>	<code>ButtonUI</code>	Read-write
<code>verticalAlignment</code>	<code>int</code>	Read-write bound
<code>verticalTextPosition</code>	<code>int</code>	Read-write bound

Note `AbstractButton` has a deprecated `label` property. You should use the equivalent `text` property instead.

One property worth mentioning is `multiClickThreshold`. This property represents a time, in milliseconds. If a button is selected with a mouse multiple times within this time period, additional action events won't be generated. By default, the value is zero, meaning each press generates an event. To avoid accidental duplicate submissions from happening in important dialogs, set this value to some reasonable level above zero.

Tip Keep in mind that all `AbstractButton` children can use HTML with its `text` property to display HTML content within the label. Just prefix the property setting with the string `<html>`.

ButtonModel/Class `DefaultButtonModel` Interface

The `ButtonModel` interface is used to describe the current state of the `AbstractButton` component. In addition, it describes the set of event listeners objects that are supported by all the different `AbstractButton` children. Its definition follows:

```

public interface ButtonModel extends ItemSelectable {
    // Properties
    public String getActionCommand();
    public void setActionCommand(String newValue);
    public boolean isArmed();
    public void setArmed(boolean newValue);
    public boolean isEnabled();
    public void setEnabled(boolean newValue);
    public void setGroup(ButtonGroup newValue);
    public int getMnemonic();
    public void setMnemonic(int newValue);
    public boolean isPressed();
    public void setPressed(boolean newValue);
    public boolean isRollover();
    public void setRollover(boolean newValue);
    public boolean isSelected();
    public void setSelected(boolean newValue);
    // Listeners
    public void addActionListener(ActionListener listener);
    public void removeActionListener(ActionListener listener);
    public void addChangeListener(ChangeListener listener);
    public void removeChangeListener(ChangeListener listener);
    public void addItemListener(ItemListener listener);
    public void removeItemListener(ItemListener listener);
}

```

The specific implementation of `ButtonModel` you'll use, unless you create your own, is the `DefaultButtonModel` class. The `DefaultButtonModel` class defines all the event registration methods for the different event listeners and manages the button state and grouping within a `ButtonGroup`. Its set of nine properties is shown in Table 4-12. They all come from the `ButtonGroup` interface, except `selectedObjects`, which is new to the `DefaultButtonModel` class, but more useful to the `JToggleButton.ToggleButtonModel`, which is discussed in Chapter 5.

Table 4-12. *DefaultButtonModel Properties*

Property Name	Data Type	Access
<code>actionCommand</code>	<code>String</code>	Read-write
<code>armed</code>	<code>boolean</code>	Read-write
<code>enabled</code>	<code>boolean</code>	Read-write
<code>group</code>	<code>ButtonGroup</code>	Read-write
<code>mnemonic</code>	<code>int</code>	Read-write
<code>pressed</code>	<code>boolean</code>	Read-write
<code>rollover</code>	<code>boolean</code>	Read-write
<code>selected</code>	<code>boolean</code>	Read-write
<code>selectedObjects</code>	<code>Object[]</code>	Read-only

Most of the time, you don't access the `ButtonModel` directly. Instead, the components that use the `ButtonModel` wrap their property calls to update the model's properties.

Note The `DefaultButtonModel` also lets you get the listeners for a specific type with `public EventListener[] getListeners(Class listenerType)`.

Understanding AbstractButton Mnemonics

A *mnemonic* is a special keyboard accelerator that when pressed causes a particular action to happen. In the case of the `JLabel` discussed earlier in the “`JLabel Class`” section, pressing the displayed mnemonic causes the associated component to get the input focus. In the case of an `AbstractButton`, pressing the mnemonic for a button causes its selection.

The actual pressing of the mnemonic requires the pressing of a look-and-feel-specific hotkey (the key tends to be the `Alt` key). So, if the mnemonic for a button were the `B` key, you would need to press `Alt-B` to activate the button with the `B`-key mnemonic. When the button is activated, registered listeners will be notified of appropriate state changes. For instance, with the `JButton`, all `ActionListener` objects would be notified.

If the mnemonic key is part of the text label for the button, you'll see the character underlined. This does depend on the current look and feel and could be displayed differently. In addition, if the mnemonic isn't part of the text label, there will not be a visual indicator for selecting the particular mnemonic key, unless the look and feel shows it in the tooltip text.

Figure 4-11 shows two buttons: one with a `W`-key mnemonic, and the other with an `H`-key mnemonic. The left button has a label with `W` in its contents, so it shows the first `W` underlined. The second component doesn't benefit from this behavior on the button, but in the `Ocean` look and feel, identifies it only if the tooltip text is set and shown.




Figure 4-11. *AbstractButton mnemonics*

To assign a mnemonic to an abstract button, you can use either one of the `setMnemonic()` methods. One accepts a `char` argument and the other an `int`. Personally, I prefer the `int` variety, in which the value is one of the many `VK_*` constants from the `KeyEvent` class. You can also specify the mnemonic by position via the `displayedMnemonicIndex` property.

```
AbstractButton button1 = new JButton("Warning");
button1.setMnemonic(KeyEvent.VK_W);
content.add(button1);
```

Understanding AbstractButton Icons

`AbstractButton` has seven specific icon properties. The natural or default icon is the `icon` property. It is used for all cases unless a different icon is specified or there is a default behavior provided by the component. The `selectedIcon` property is the icon used when the button is selected. The `pressedIcon` is used when the button is pressed. Which of these two icons is used depends on the component, because a `JButton` is pressed but not selected, whereas a `JCheckBox` is selected but not pressed.

The `disabledIcon` and `disabledSelectedIcon` properties are used when the button has been disabled with `setEnabled(false)`. By default, if the icon is an `ImageIcon`, a grayscale version of the icon will be used.

The remaining two icon properties, `rolloverIcon` and `rolloverSelectedIcon`, allow you to display different icons when the mouse moves over the button (and `rolloverEnabled` is `true`).

Understanding Internal AbstractButton Positioning

The `horizontalAlignment`, `horizontalTextPosition`, `verticalAlignment`, and `verticalTextPosition` properties share the same settings and behavior as the `JLabel` class. They're listed in Table 4-13.

Table 4-13. *AbstractButton Position Constants*

Position Property	Available Settings
<code>horizontalAlignment</code>	LEFT, CENTER, RIGHT
<code>horizontalTextPosition</code>	LEFT, CENTER, RIGHT
<code>verticalAlignment</code>	TOP, CENTER, BOTTOM
<code>verticalTextPosition</code>	TOP, CENTER, BOTTOM

Handling AbstractButton Events

Although you do not create `AbstractButton` instances directly, you do create subclasses. All of them share a common set of event-handling capabilities. You can register `PropertyChangeListener`, `ActionListener`, `ItemListener`, and `ChangeListener` objects with abstract buttons. The `PropertyChangeListener` object will be discussed here, and the remaining objects listed will be discussed in later chapters, with the appropriate components.

Like the `JComponent` class, the `AbstractButton` component supports the registering of `PropertyChangeListener` objects to detect when bound properties of an instance of the class change. Unlike the `JComponent` class, the `AbstractButton` component provides the following set of class constants to signify the different property changes:

- `BORDER_PAINTED_CHANGED_PROPERTY`
- `CONTENT_AREA_FILLED_CHANGED_PROPERTY`
- `DISABLED_ICON_CHANGED_PROPERTY`
- `DISABLED_SELECTED_ICON_CHANGED_PROPERTY`
- `FOCUS_PAINTED_CHANGED_PROPERTY`

- HORIZONTAL_ALIGNMENT_CHANGED_PROPERTY
- HORIZONTAL_TEXT_POSITION_CHANGED_PROPERTY
- ICON_CHANGED_PROPERTY
- MARGIN_CHANGED_PROPERTY
- MNEMONIC_CHANGED_PROPERTY
- MODEL_CHANGED_PROPERTY
- PRESSED_ICON_CHANGED_PROPERTY
- ROLLOVER_ENABLED_CHANGED_PROPERTY
- ROLLOVER_ICON_CHANGED_PROPERTY
- ROLLOVER_SELECTED_ICON_CHANGED_PROPERTY
- SELECTED_ICON_CHANGED_PROPERTY
- TEXT_CHANGED_PROPERTY
- VERTICAL_ALIGNMENT_CHANGED_PROPERTY
- VERTICAL_TEXT_POSITION_CHANGED_PROPERTY

Therefore, instead of hard-coding specific text strings, you can create a `PropertyChangeListener` that uses these constants, as shown in Listing 4-5.

Listing 4-5. *Base `PropertyChangeListener` for `AbstractButton`*

```
import javax.swing.*;
import java.beans.*;

public class AbstractButtonPropertyChangeListener
    implements PropertyChangeListener {

    public void propertyChange(PropertyChangeEvent e) {
        String propertyName = e.getPropertyName();
        if (e.getPropertyName().equals(AbstractButton.TEXT_CHANGED_PROPERTY)) {
            String newText = (String) e.getNewValue();
            String oldText = (String) e.getOldValue();
            System.out.println(oldText + " changed to " + newText);
        } else if (e.getPropertyName().equals(AbstractButton.ICON_CHANGED_PROPERTY)) {
            Icon icon = (Icon) e.getNewValue();
            if (icon instanceof ImageIcon) {
                System.out.println("New icon is an image");
            }
        }
    }
}
```

JButton Class

The JButton component is the basic AbstractButton component that can be selected. It supports text, images, and HTML-based labels, as shown in Figure 4-12.




Figure 4-12. Sample JButton components

Creating a JButton

The JButton class has five constructors:

```
public JButton()
```

```
JButton button = new JButton();
```

```
public JButton(Icon image)
```

```
Icon icon = new ImageIcon("dog.jpg");
```

```
JButton button = new JButton(icon);
```

```
public JButton(String text)
```

```
JButton button = new JButton("Dog");
```

```
public JButton(String text, Icon icon)
```

```
Icon icon = new ImageIcon("dog.jpg");
```

```
JButton button = new JButton("Dog", icon);
```

```
public JButton(Action action)
```

```
Action action = ...;
```

```
JButton button = new JButton(action);
```

You can create a button with or without a text label or icon. The icon represents the default or selected icon property from AbstractButton.

Note Creating a JButton from an Action initializes the text label, icon, enabled status, and tooltip text. In addition, the ActionListener of the Action will be notified upon button selection.

JButton Properties

The JButton component doesn't add much to the AbstractButton. As Table 4-14 shows, of the four properties of JButton, the only new behavior added is enabling the button to be the default.

Table 4-14. *JButton Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
defaultButton	boolean	Read-only
defaultCapable	boolean	Read-write bound
UIClassID	String	Read-only

The default button tends to be drawn with a different and darker border than the remaining buttons. When a button is the default, pressing the Enter key while in the top-level window causes the button to be selected. This works only as long as the component with the input focus, such as a text component or another button, doesn't consume the Enter key. Because the defaultButton property is read-only, how (you might be asking) do you set a button as the default? All top-level Swing windows contain a JRootPane, to be described in Chapter 8. You tell this JRootPane which button is the default by setting its defaultButton property. Only buttons whose defaultCapable property is true can be configured to be the default. Figure 4-13 shows the top-right button set as the default.




Figure 4-13. *Setting a default button*

Listing 4-6 demonstrates setting the default button component, as well as using a basic JButton. If the default button appearance doesn't seem that obvious in Figure 4-13, wait until the JOptionPane is described in Chapter 9, where the difference in appearance will be more obvious. Figure 4-13 uses a 2-by-2 GridLayout for the screen. The extra two arguments to the constructor represent gaps to help make the default button's appearance more obvious.

Listing 4-6. *Configuring a Default Button*

```

import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class DefaultButton {

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("DefaultButton");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                frame.setLayout(new GridLayout(2, 2, 10, 10));

                JButton button1 = new JButton("Text Button");
                button1.setMnemonic(KeyEvent.VK_B);
                frame.add(button1);

                Icon warnIcon = new ImageIcon("Warn.gif");
                JButton button2 = new JButton(warnIcon);
                frame.add(button2);

                JButton button3 = new JButton("Warning", warnIcon);
                frame.add(button3);

                String htmlButton = "<html><sup>HTML</sup> <sub><em>Button</em></sub><br>" +
                    "<font color=\"#FF0080\"><u>Multi-line</u></font>";
                JButton button4 = new JButton(htmlButton);
                frame.add(button4);

                JRootPane rootPane = frame.getRootPane();
                rootPane.setDefaultButton(button2);

                frame.setSize(300, 200);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

Handling JButton Events

The JButton component itself has no specific event-handling capabilities. They're all inherited from AbstractButton. Although you can listen for change events, item events, and property change events, the most helpful listener with the JButton is the ActionListener.

When the JButton component is selected, all registered ActionListener objects are notified. When the button is selected, an ActionEvent is passed to each listener. This event passes along the actionPerformed property of the button to help identify which button was selected when a shared listener is used across multiple components. If the actionPerformed property hasn't been explicitly set, the current text property is passed along instead. The explicit use of the actionPerformed property is helpful with localization. Because the text property of the JButton is what the user sees, you as the handler of the button selection event listener cannot rely on a localized text label for determining which button was selected. So, while the text property can be localized so that a Yes button in English can say Sí in a Spanish version, if you explicitly set the actionPerformed to be the "Yes" string, then no matter which language the user is running in, the actionPerformed will remain "Yes" and not take on the localized text property setting.

Listing 4-7 adds the event-handling capabilities to the default button example in Listing 4-6 (see Figure 4-13). Notice that the default button behavior works properly: press Enter from any component, and button 2 (the default) will be activated.

Listing 4-7. *Watching Button Selection Events*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class ActionButtonSample {

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("DefaultButton");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        String command = actionEvent.getActionCommand();
                        System.out.println("Selected: " + command);
                    }
                };

                frame.setLayout(new GridLayout(2, 2, 10, 10));

                JButton button1 = new JButton("Text Button");
                button1.setMnemonic(KeyEvent.VK_B);
                button1.setActionCommand("First");
                button1.addActionListener(actionListener);
                frame.add(button1);
```

```

Icon warnIcon = new ImageIcon("Warn.gif");
JButton button2 = new JButton(warnIcon);
button2.setActionCommand("Second");
button2.addActionListener(actionListener);
frame.add(button2);

JButton button3 = new JButton("Warning", warnIcon);
button3.setActionCommand("Third");
button3.addActionListener(actionListener);
frame.add(button3);

String htmlButton = "<html><sup>HTML</sup> <sub><em>Button</em></sub><br>" +
    "<font color=\"#FF0080\"><u>Multi-line</u></font>";
JButton button4 = new JButton(htmlButton);
button4.setActionCommand("Fourth");
button4.addActionListener(actionListener);
frame.add(button4);

JRootPane rootPane = frame.getRootPane();
rootPane.setDefaultButton(button2);

frame.setSize(300, 200);
frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Customizing a JButton Look and Feel

Each installable Swing look and feel provides a different JButton appearance and set of default UIResource value settings. Figure 4-14 shows the appearance of the JButton component for the preinstalled set of look and feel types: Motif, Windows, and Ocean.




Figure 4-14. JButton under different look and feel types

The available set of `UIResource`-related properties for a `JButton` is shown in Table 4-15. For the `JButton` component, there are 34 different properties.

Table 4-15. *JButton UIResource Elements*

Property String	Object Type
<code>Button.actionMap</code>	<code>ActionMap</code>
<code>Button.background</code>	<code>Color</code>
<code>Button.border</code>	<code>Border</code>
<code>Button.contentAreaFilled</code>	<code>Boolean</code>
<code>Button.darkShadow</code>	<code>Color</code>
<code>Button.dashedRectGapHeight</code>	<code>Integer</code>
<code>Button.dashedRectGapWidth</code>	<code>Integer</code>
<code>Button.dashedRectGapX</code>	<code>Integer</code>
<code>Button.dashedRectGapY</code>	<code>Integer</code>
<code>Button.defaultButtonFollowsFocus</code>	<code>Boolean</code>
<code>Button.disabledForeground</code>	<code>Color</code>
<code>Button.disabledGrayRange</code>	<code>Integer[]</code>
<code>Button.disabledShadow</code>	<code>Color</code>
<code>Button.disabledText</code>	<code>Color</code>
<code>Button.disabledToolBarBorderBackground</code>	<code>Color</code>
<code>Button.focus</code>	<code>Color</code>
<code>Button.focusInputMap</code>	<code>InputMap</code>
<code>Button.font</code>	<code>Font</code>
<code>Button.foreground</code>	<code>Color</code>
<code>Button.gradient</code>	<code>List</code>
<code>Button.highlight</code>	<code>Color</code>
<code>Button.icon</code>	<code>Icon</code>
<code>Button.iconTextGap</code>	<code>Integer</code>
<code>Button.light</code>	<code>Color</code>
<code>Button.margin</code>	<code>Insets</code>
<code>Button.rollover</code>	<code>Boolean</code>
<code>Button.rolloverIconType</code>	<code>String</code>
<code>Button.select</code>	<code>Color</code>
<code>Button.shadow</code>	<code>Color</code>
<code>Button.showMnemonics</code>	<code>Boolean</code>

Table 4-15. *JButton UIResource Elements (Continued)*

Property String	Object Type
Button.textIconGap	Integer
Button.textShiftOffset	Integer
Button.toolBarBorderBackground	Color
ButtonUI	String

JPanel Class

The last of the basic Swing components is the JPanel component. The JPanel component serves as both a general-purpose container object, replacing the AWT Panel container, and a replacement for the Canvas component, for those times when you need a drawable Swing component area.

Creating a JPanel

There are four constructors for JPanel:

```
public JPanel()
JPanel panel = new JPanel();

public JPanel(boolean isDoubleBuffered)
JPanel panel = new JPanel(false);

public JPanel(LayoutManager manager)
JPanel panel = new JPanel(new GridLayout(2,2));

public JPanel(LayoutManager manager, boolean isDoubleBuffered)
JPanel panel = new JPanel(new GridLayout(2,2), false);
```

With the constructors, you can either change the default layout manager from FlowLayout or change the default double buffering that is performed from true to false.

Using a JPanel

You can use JPanel as your general-purpose container or as a base class for a new component. For the general-purpose container, the procedure is simple: Just create the panel, set its layout manager if necessary, and add components using the add() method.

```
JPanel panel = new JPanel();
JButton okButton = new JButton("OK");
panel.add(okButton);
JButton cancelButton = new JButton("Cancel");
panel.add(cancelButton);
```

When you want to create a new component, subclass `JPanel` and override the public `void paintComponent(Graphics g)` method. Although you can subclass `JComponent` directly, it seems more appropriate to subclass `JPanel`. Listing 4-8 demonstrates a simple component that draws an oval to fit the size of the component; it also includes a test driver.

Listing 4-8. *Oval Panel Component*

```
import java.awt.*;
import javax.swing.*;

public class OvalPanel extends JPanel {

    Color color;

    public OvalPanel() {
        this(Color.black);
    }
    public OvalPanel(Color color) {
        this.color = color;
    }
    public void paintComponent(Graphics g) {
        int width = getWidth();
        int height = getHeight();
        g.setColor(color);
        g.drawOval(0, 0, width, height);
    }

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Oval Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                frame.setLayout(new GridLayout(2, 2));

                Color colors[] = {Color.RED, Color.BLUE, Color.GREEN, Color.YELLOW};
                for (int i=0; i<4; i++) {
                    OvalPanel panel = new OvalPanel(colors[i]);
                    frame.add(panel);
                }

                frame.setSize(300, 200);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

Figure 4-15 shows the test driver program results.




Figure 4-15. *The new OvalPanel component*

Note By default, JPanel components are opaque. This differs from JComponent, whose opacity property setting by default is false. A false setting for opacity means the component is transparent.

Customizing a JPanel Look and Feel

The available set of UIResource-related properties for a JPanel is shown in Table 4-16. For the JPanel component, there are five different properties. These settings may have an effect on the components within the panel.

Table 4-16. *JPanel UIResource Elements*

Property String	Object Type
Panel.background	Color
Panel.border	Border
Panel.font	Font
Panel.foreground	Color
PanelUI	String

Summary

In this chapter, you explored the root of all Swing components: the JComponent class. From there, you looked at some of the common elements of all components, such as tooltips, as well as specific components such as JLabel. You also learned how to put glyphs (nonverbal images) on components with the help of the Icon interface and the ImageIcon class, and the GrayFilter image filter for disabled icons.

You also learned about the `AbstractButton` component, which serves as the root component for all Swing button objects. You looked at its data model interface, `ButtonModel`, and the default implementation of this interface, `DefaultButtonModel`. Next, you looked at the `JButton` class, which is the simplest of the `AbstractButton` implementations. And lastly, you looked at the `JPanel` as the basic Swing container object.

In Chapter 5, you'll start to dig into some of the more complex `AbstractButton` implementations: the toggle buttons.



Toggle Buttons

Now that you've seen the capabilities of the relatively simple Swing components `JLabel` and `JButton`, it's time to take a look at more active components, specifically those that can be toggled. These so-called toggleable components—`JToggleButton`, `JCheckBox`, and `JRadioButton`—provide the means for your users to select from among a set of options. These options are either on or off, or enabled or disabled. When presented in a `ButtonGroup`, only one of the options in the group can be selected at a time. To deal with this selection state, the components share a common data model with `ToggleButtonModel`. Let's take a look at the data model, the components' grouping mechanism with `ButtonGroup`, and the individual components.

ToggleButtonModel Class

The `JToggleButton.ToggleButtonModel` class is a public inner class of `JToggleButton`. The class customizes the behavior of the `DefaultButtonModel` class, which, in turn, is an implementation of the `ButtonModel` interface.

The customization affects the data models of all `AbstractButton` components in the same `ButtonGroup`—a class explored next. In short, a `ButtonGroup` is a logical grouping of `AbstractButton` components. At any one time, only one of the `AbstractButton` components in the `ButtonGroup` can have the selected property of its data model set to true. The remaining ones must be false. This does not mean that only one selected component in the group can exist at a time. If multiple components in a `ButtonGroup` share a `ButtonModel`, multiple selected components in the group can exist. If no components share a model, at most, the user can select one component in the group. Once the user has selected that one component, the user cannot interactively deselect the selection. However, programmatically, you can deselect *all* group elements.

The definition of `JToggleButton.ToggleButtonModel` follows.

```
public class ToggleButtonModel extends DefaultButtonModel {  
    // Constructors  
    public ToggleButtonModel();  
    // Properties  
    public boolean isSelected();  
    public void setPressed(boolean newValue);  
    public void setSelected(boolean newvalue);  
}
```

The `ToggleButtonModel` class defines the default data model for both the `JToggleButton` and its subclasses `JCheckBox` and `JRadioButton`, described in this chapter, as well as the `JCheckBoxMenuItem` and `JRadioButtonMenuItem` classes described in Chapter 6.

Note Internally, Swing's HTML viewer component uses the `ToggleButtonModel` for its check box and radio button input form elements.

ButtonGroup Class

Before describing the `ButtonGroup` class, let's demonstrate its usage. The program shown in Listing 5-1 creates objects that use the `ToggleButtonModel` and places them into a single group. As the program demonstrates, in addition to adding the components into the screen's container, you must add each component to the same `ButtonGroup`. This results in a pair of `add()` method calls for each component. Furthermore, the container for the button group tends to place components in a single column and to label the grouping for the user with a titled border, though neither of these treatments are required. Figure 5-1 shows the output of the program.

Listing 5-1. *Odd Collection of Button Components*

```
import javax.swing.*;
import javax.swing.border.*;
import java.awt.*;

public class AButtonGroup {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Button Group");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                JPanel panel = new JPanel(new GridLayout(0, 1));
                Border border =
                    BorderFactory.createTitledBorder("Examples");
                panel.setBorder(border);
                ButtonGroup group = new ButtonGroup();
                AbstractButton abstract1 =
                    new JToggleButton("Toggle Button");
                panel.add(abstract1);
                group.add(abstract1);
                AbstractButton abstract2 =
                    new JRadioButton("Radio Button");
                panel.add(abstract2);
                group.add(abstract2);
            }
        };
        frame.add(panel);
        frame.setVisible(true);
    }
}
```

```

        AbstractButton abstract3 =
            new JCheckBox("Check Box");
        panel.add(abstract3);
        group.add(abstract3);
        AbstractButton abstract4 =
            new JRadioButtonMenuItem("Radio Button Menu Item");
        panel.add(abstract4);
        group.add(abstract4);
        AbstractButton abstract5 =
            new JCheckBoxMenuItem("Check Box Menu Item");
        panel.add(abstract5);
        group.add(abstract5);
        frame.add(panel, BorderLayout.CENTER);
        frame.setSize(300, 200);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}
}

```



Figure 5-1. *ButtonGroup/ToggleButtonModel example*

As previously stated, the `ButtonGroup` class represents a logical grouping of `AbstractButton` components. The `ButtonGroup` is not a visual component; therefore, there's nothing visual on screen when a `ButtonGroup` is used. Any `AbstractButton` component can be added to the grouping with public void `add(AbstractButton abstractButton)`. Although any `AbstractButton` component can belong to a `ButtonGroup`, only when the data model for the component is `ToggleButtonModel` will the grouping have any effect. The result of having a component with a data model of `ToggleButtonModel` in a `ButtonGroup` is that after the component is selected, the `ButtonGroup` deselects any currently selected component in the group.

Note Technically speaking, the model doesn't need to be `ToggleButtonModel` as long as the custom model exhibits the same behavior of limiting the number of selected component models to one.

Although the `add()` method is typically the only `ButtonGroup` method you'll ever need, the following class definition shows that it's not the only method of `ButtonGroup` in existence:

```
public class ButtonGroup implements Serializable {
    // Constructor
    public ButtonGroup();
    // Properties
    public int getButtonCount();
    public Enumeration getElements();
    public ButtonModel getSelection();
    // Other methods
    public void add(AbstractButton aButton);
    public boolean isSelected(ButtonModel theModel) ;
    public void remove(AbstractButton aButton);
    public void setSelected(ButtonModel theModel, boolean newValue);
}
```

One interesting thing the class definition shows is that given a `ButtonGroup`, you cannot directly find out the selected `AbstractButton`. You can directly ask only which `ButtonModel` is selected. However, `getElements()` returns an `Enumeration` of all the `AbstractButton` elements in the group. You can then loop through all the buttons to find the selected one (or ones) by using code similar to the following:

```
Enumeration elements = group.getElements();
while (elements.hasMoreElements()) {
    AbstractButton button = (AbstractButton)elements.nextElement();
    if (button.isSelected()) {
        System.out.println("The winner is: " + button.getText());
        break; // Don't break if sharing models -- could show multiple buttons selected
    }
}
```

The other interesting method of `ButtonGroup` is `setSelected()`. The two arguments of the method are a `ButtonModel` and a `boolean`. If the `boolean` value is `false`, the selection request is ignored. If the `ButtonModel` isn't the model for a button in the `ButtonGroup`, then the `ButtonGroup` deselects the currently selected model, causing no buttons in the group to be selected. The proper usage of the method is to call the method with a model of a component in the group and a new state of `true`. For example, if `aButton` is an `AbstractButton` and `aGroup` is the `ButtonGroup`, then the method call would look like `aGroup.setSelected(aButton.getModel(), true)`.

Note If you add a selected button to a `ButtonGroup` that already has a previously selected button, the previous button retains its state and the newly added button loses its selection.

Now, let's look at the various components whose data model is the `ToggleButtonModel`.

JToggleButton Class

The `JToggleButton` is the first of the toggleable components. It's discussed first because it's the parent class of the two other components that are not menu-oriented: `JCheckBox` and `JRadioButton`. The `JToggleButton` is like a `JButton` that stays depressed when selected, instead of bouncing back to an unselected state. To deselect the selected component, you must reselect it. `JToggleButton` isn't a commonly used component, but you might find it useful on a toolbar, such as in Microsoft Word (for paragraph alignment, among other instances) or in a file dialog box, as shown in the upper-right corner of Figure 5-2.




Figure 5-2. Sample `JToggleButton` components from file chooser

Defining the `JToggleButton` structure are two objects that customize the `AbstractButton` parent class: `ToggleButtonModel` and `ToggleButtonUI`. The `ToggleButtonModel` class represents a customized `ButtonModel` data model for the component, whereas `ToggleButtonUI` is the user interface delegate.

Now that you know about the different pieces of a `JToggleButton`, let's find out how to use them.

Creating `JToggleButton` Components

Eight constructors are available for `JToggleButton`:

```
public JToggleButton()
```

```
JToggleButton aToggleButton = new JToggleButton();
```

```
public JToggleButton(Icon icon)
```

```
JToggleButton aToggleButton = new JToggleButton(new DiamondIcon(Color.PINK))
```

```

public JToggleButton(Icon icon, boolean selected)
JToggleButton aToggleButton = new JToggleButton(new DiamondIcon(Color.PINK), true);

public JToggleButton(String text)
JToggleButton aToggleButton = new JToggleButton("Sicilian");

public JToggleButton(String text, boolean selected)
JToggleButton aToggleButton = new JToggleButton("Thin Crust", true);

public JToggleButton(String text, Icon icon)
JToggleButton aToggleButton = new JToggleButton("Thick Crust",
    new DiamondIcon(Color.PINK));

public JToggleButton(String text, Icon icon, boolean selected)
JToggleButton aToggleButton = new JToggleButton("Stuffed Crust",
    new DiamondIcon(Color.PINK), true);

public JToggleButton(Action action)
Action action = ...;
JToggleButton aToggleButton = new JToggleButton(action);

```

Each allows you to customize one or more of the label, icon, or initial selection state. Unless specified otherwise, the label is empty with no text or icon, and the button initially is not selected.

Note Surprisingly, Swing lacks a constructor that accepts only an initial state of a boolean setting. Lacking this constructor, you need to create a `JToggleButton` with the no-argument constructor variety, and then call `setSelected(boolean newValue)` directly or work with an `Action`.

JToggleButton Properties

After creating a `JToggleButton`, you can modify each of its many properties. Although there are about 100 inherited properties, Table 5-1 shows only the two introduced with `JToggleButton`. The remaining properties come from `AbstractButton`, `JComponent`, `Container`, and `Component`.

Table 5-1. *JToggleButton Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>UIClassID</code>	<code>String</code>	Read-only

You can change one or more of the text, icon, or selected properties set in the constructor, as well as any of the other `AbstractButton` properties described in Chapter 4. You configure

the primary three properties with the appropriate getter and setter methods: `get/setText()`, `get/setIcon()`, and `is/setSelected()`, or `setAction(action)`. The other properties have corresponding getter and setter methods.

The more visual configurable options of `JToggleButton` (and its subclasses) include the various icons for the different states of the button. Besides the standard icon, you can display a different icon when the button is selected, among other state changes. However, if you're changing icons based on the currently selected state, then `JToggleButton` probably isn't the most appropriate component to use. You should use one of its subclasses, `JCheckBox` or `JRadioButton`, explored later in this chapter.

Note Keep in mind that the `JButton` component ignores the `selectedIcon` property.

Handling `JToggleButton` Selection Events

After configuring a `JToggleButton`, you can handle selection events in one of three ways: with an `ActionListener`, an `ItemListener`, or a `ChangeListener`. This is in addition to providing an `Action` to the constructor, which would be notified like an `ActionListener`.

Listening to `JToggleButton` Events with an `ActionListener`

If you're interested only in what happens when a user selects or deselects the `JToggleButton`, you can attach an `ActionListener` to the component. After the user selects the button, the component notifies any registered `ActionListener` objects. Unfortunately, this isn't the desired behavior, because you must then actively determine the state of the button so that you can respond appropriately for selecting or deselecting. To find out the selected state, you must get the model for the event source, and then ask for its selection state, as the following sample `ActionListener` source shows:

```
ActionListener actionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        AbstractButton abstractButton = (AbstractButton)actionEvent.getSource();
        boolean selected = abstractButton.getModel().isSelected();
        System.out.println("Action - selected=" + selected + "\n");
    }
};
```

Listening to `JToggleButton` Events with an `ItemListener`

The better listener to attach to a `JToggleButton` is the `ItemListener`. The `ItemEvent` passed to the `itemStateChanged()` method of `ItemListener` includes the current selection state of the button. This allows you to respond appropriately, without needing to search for the current button state.

To demonstrate, the following `ItemListener` reports the state of a selected `ItemEvent`-generating component:

```

ItemListener itemListener = new ItemListener() {
    public void itemStateChanged(ItemEvent itemEvent) {
        int state = itemEvent.getStateChange();
        if (state == ItemEvent.SELECTED) {
            System.out.println("Selected");
        } else {
            System.out.println("Deselected");
        }
    }
};

```

Listening to JToggleButton Events with a ChangeListener

Attaching a `ChangeListener` to a `JToggleButton` provides even more flexibility. Any attached listener will be notified of the data model changes for the button, corresponding to changes in its `armed`, `pressed`, and `selected` properties. Listening for notification from the three listeners—`ActionListener`, `ItemListener`, and `ChangeListener`—allows you to react seven different times. Figure 5-3 shows the sequencing of the `ButtonModel` property changes, and when the model notifies each of the listeners.




Figure 5-3. *JToggleButton* notification sequencing diagram

To demonstrate the `ChangeListener` notifications, the following code fragment defines a `ChangeListener` that reports the state changes to the three properties of the button model:

```

ChangeListener changeListener = new ChangeListener() {
    public void stateChanged(ChangeEvent changeEvent) {
        AbstractButton abstractButton = (AbstractButton)changeEvent.getSource();
        ButtonModel buttonModel = abstractButton.getModel();
        boolean armed = buttonModel.isArmed();
        boolean pressed = buttonModel.isPressed();
        boolean selected = buttonModel.isSelected();
        System.out.println("Changed: " + armed + "/" + pressed + "/" + selected);
    }
};

```

After you attach the `ChangeListener` to a `JToggleButton` and select the component by pressing and releasing the mouse over the component, the following output results:

```
Changed: true/false/false
Changed: true/true/false
Changed: true/true/true
Changed: true/false/true
Changed: false/false/true
```

With all three listeners attached to the same button, notification of registered `ItemListener` objects would happen after the selected property changes—in other words, between lines 3 and 4. Listing 5-2 demonstrates all three listeners attached to the same `JToggleButton`. With regard to the registered `ActionListener` objects, notification happens after releasing the button, but before the armed state changes to false, falling between lines 4 and 5.

Listing 5-2. *Listening for Toggle Selection*

```
import javax.swing.*;
import javax.swing.event.*;
import java.awt.*;
import java.awt.event.*;

public class SelectingToggle {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Selecting Toggle");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                JToggleButton toggleButton = new JToggleButton("Toggle Button");
                // Define ActionListener
                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        AbstractButton abstractButton = (AbstractButton)actionEvent.getSource();
                        boolean selected = abstractButton.getModel().isSelected();
                        System.out.println("Action - selected=" + selected + "\n");
                    }
                };
                // Define ChangeListener
                ChangeListener changeListener = new ChangeListener() {
                    public void stateChanged(ChangeEvent changeEvent) {
                        AbstractButton abstractButton = (AbstractButton)changeEvent.getSource();
                        ButtonModel buttonModel = abstractButton.getModel();
                        boolean armed = buttonModel.isArmed();
                        boolean pressed = buttonModel.isPressed();
                        boolean selected = buttonModel.isSelected();
                        System.out.println("Changed: " + armed + "/" + pressed + "/" +
                            selected);
                    }
                };
            }
        };
    }
}
```

```

// Define ItemListener
ItemListener itemListener = new ItemListener() {
    public void itemStateChanged(ItemEvent itemEvent) {
        int state = itemEvent.getStateChange();
        if (state == ItemEvent.SELECTED) {
            System.out.println("Selected");
        } else {
            System.out.println("Deselected");
        }
    }
};

// Attach Listeners
toggleButton.addActionListener(actionListener);
toggleButton.addChangeListener(changeListener);
toggleButton.addItemListener(itemListener);
frame.add(toggleButton, BorderLayout.NORTH);
frame.setSize(300, 125);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Customizing a JToggleButton Look and Feel

Each installable Swing look and feel provides a different JToggleButton appearance and set of default UIResource values. Figure 5-4 shows the appearance of the JToggleButton component for the preinstalled set of look and feel types: Motif, Windows, and Ocean. As the button labels might indicate, the first button is selected, the second has the input focus (and isn't selected), and the third button isn't selected.




Figure 5-4. JToggleButton under different look and feel types

The available set of `UIResource`-related properties for a `JToggleButton` is shown in Table 5-2. The `JToggleButton` component has 17 different properties.

Table 5-2. *JToggleButton UIResource Elements*

Property String	Object Type
<code>ToggleButton.background</code>	<code>Color</code>
<code>ToggleButton.border</code>	<code>Border</code>
<code>ToggleButton.darkShadow</code>	<code>Color</code>
<code>ToggleButton.disabledText</code>	<code>Color</code>
<code>ToggleButton.focus</code>	<code>Color</code>
<code>ToggleButton.focusInputMap</code>	<code>Object[]</code>
<code>ToggleButton.font</code>	<code>Font</code>
<code>ToggleButton.foreground</code>	<code>Color</code>
<code>ToggleButton.gradient</code>	<code>List</code>
<code>ToggleButton.highlight</code>	<code>Color</code>
<code>ToggleButton.light</code>	<code>Color</code>
<code>ToggleButton.margin</code>	<code>Insets</code>
<code>ToggleButton.select</code>	<code>Color</code>
<code>ToggleButton.shadow</code>	<code>Color</code>
<code>ToggleButton.textIconGap</code>	<code>Integer</code>
<code>ToggleButton.textShiftOffset</code>	<code>Integer</code>
<code>ToggleButtonUI</code>	<code>String</code>

JCheckBox Class

The `JCheckBox` class represents the toggle component that, by default, displays a check box icon next to the text label for a two-state option. The check box icon uses an optional check mark to show the current state of the object, instead of keeping the button depressed, as with the `JToggleButton`. With the `JCheckBox`, the icon shows the state of the object, whereas with the `JToggleButton`, the icon is part of the label and isn't usually used to show state information. With the exception of the UI-related differences between `JCheckBox` and `JToggleButton`, the two components are identical. Figure 5-5 demonstrates how check box components might appear in a pizza-ordering application.




Figure 5-5. *Sample JCheckBox components*

The JCheckBox is made up of several pieces. Like JToggleButton, the JCheckBox uses a ToggleButtonModel to represent its data model. The user interface delegate is CheckBoxUI. Although the ButtonGroup is available to group together check boxes, it isn't normally appropriate. When multiple JCheckBox components are within a ButtonGroup, they behave like JRadioButton components but look like JCheckBox components. Because of this visual irregularity, you shouldn't put JCheckBox components into a ButtonGroup.

Now that you've seen the different pieces of a JCheckBox, let's find out how to use them.

Creating JCheckBox Components

Eight constructors exist for JCheckBox:

```
public JCheckBox()
```

```
JCheckBox aCheckBox = new JCheckBox();
```

```
public JCheckBox(Icon icon)
```

```
JCheckBox aCheckBox = new JCheckBox(new DiamondIcon(Color.RED, false));
aCheckBox.setSelectedIcon(new DiamondIcon(Color.PINK, true));
```

```
public JCheckBox(Icon icon, boolean selected)
```

```
JCheckBox aCheckBox = new JCheckBox(new DiamondIcon(Color.RED, false), true);
aCheckBox.setSelectedIcon(new DiamondIcon(Color.PINK, true));
```

```
public JCheckBox(String text)
```

```
JCheckBox aCheckBox = new JCheckBox("Spinach");
```

```
public JCheckBox(String text, boolean selected)
```

```
JCheckBox aCheckBox = new JCheckBox("Onions", true);
```

```
public JCheckBox(String text, Icon icon)
```

```
JCheckBox aCheckBox = new JCheckBox("Garlic", new DiamondIcon(Color.RED, false));
aCheckBox.setSelectedIcon(new DiamondIcon(Color.PINK, true));
```

```

public JCheckBox(String text, Icon icon, boolean selected)
JCheckBox aCheckBox = new JCheckBox("Anchovies", new DiamondIcon(Color.RED,
    false), true);
aCheckBox.setSelectedIcon(new DiamondIcon(Color.PINK, true));

public JCheckBox(Action action)
Action action = ...;
JCheckBox aCheckBox = new JCheckBox(action);

```

Note Configuring a JCheckBox from an Action sets the label, state, and tooltip text, but not the icon.

Each allows you to customize either none or up to three properties for the label, icon, or initial selection state. Unless specified otherwise, there's no text in the label and the default selected/unselected icon for the check box appears unselected.

If you do initialize the icon in the constructor, it's the icon for the unselected state of the check box, with the same icon displayed when the check box is selected. You must also either initialize the selected icon with the `setSelectedIcon(Icon newValue)` method, described later, or make sure the icon is state-aware and updates itself. If you don't configure the selected icon and don't use a state-aware icon, the same icon will appear for both the selected and unselected state. Normally, an icon that doesn't change its visual appearance between selected and unselected states isn't desirable for a JCheckBox.

Note A state-aware icon is one that asks the associated component for the value of the selected property.

JCheckBox Properties

After creating a JCheckBox, you can modify each of its many properties. Two properties specific to JCheckBox (shown in Table 5-3) override the behavior of its parent JToggleButton. The third `borderPaintedFlat` property was introduced in the 1.3 release of the JDK. All the remaining properties are inherited through parents of JToggleButton.

Table 5-3. *JCheckBox Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>borderPaintedFlat</code>	<code>boolean</code>	Read-write bound
<code>UIClassID</code>	<code>String</code>	Read-only

The `borderPaintedFlat` property permits a look and feel to display the border around the check icon as two-dimensional (flat) instead of three-dimensional. By default, the `borderPaintedFlat` property is `false`, meaning the border will be three-dimensional. Figure 5-6 shows what a flat border looks like, where the first, third, and fifth borders are flat, and the second and fourth are not. A look and feel may choose to ignore this property. However, it is useful for renderers for components such as tables and trees, where they show only state and are not selectable. The Windows and Motif look and feel types take advantage of the property; Metal (and Ocean) does not.




Figure 5-6. Alternating flat `JCheckBox` borders for the Windows look and feel: Anchovies, Onions, and Spinach are flat; Garlic and Pepperoni are not.

As the constructor listing demonstrated, if you choose to set an icon with a constructor, the constructor sets only one icon for the unselected state. If you want the check box icon to show the correct state visually, you must use a state-aware icon or associate a different icon for the selected state with `setSelectedIcon()`. Having two different visual state representations is what most users expect from a `JCheckBox`, so unless you have a good reason to do otherwise, it's best to follow the design convention for normal user interfaces.

The fourth button at the bottom of the screen shown in Figure 5-7 demonstrates confusing icon usage within a `JCheckBox`. The check box always appears selected. The figure displays what the screen looks like with Pizza selected, Calzone unselected, Anchovies unselected, and Stuffed Crust unselected (although the last one *appears* selected).




Figure 5-7. Multiple `JCheckBox` components with various icons

Listing 5-3 demonstrates three valid means of creating JCheckBox components with different icons, one using a state-aware icon. The last check box shows bad icon usage.

Listing 5-3. *Sampling JCheckBox*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class IconCheckBoxSample {
    private static class CheckBoxIcon implements Icon {
        private ImageIcon checkedIcon = new ImageIcon("Plus.gif");
        private ImageIcon uncheckedIcon = new ImageIcon("Minus.gif");

        public void paintIcon(Component component, Graphics g, int x, int y) {
            AbstractButton abstractButton = (AbstractButton)component;
            ButtonModel buttonModel = abstractButton.getModel();
            g.translate(x,y);
            ImageIcon imageIcon = buttonModel.isSelected() ?
                checkedIcon : uncheckedIcon;
            Image image = imageIcon.getImage();
            g.drawImage(image, 0, 0, component);
            g.translate(-x,-y);
        }
        public int getIconWidth() {
            return 20;
        }
        public int getIconHeight() {
            return 20;
        }
    }

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Iconizing CheckBox");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                Icon checked = new DiamondIcon (Color.BLACK, true);
                Icon unchecked = new DiamondIcon (Color.BLACK, false);
                JCheckBox aCheckBox1 = new JCheckBox("Pizza", unchecked);
                aCheckBox1.setSelectedIcon(checked);
                JCheckBox aCheckBox2 = new JCheckBox("Calzone");
                aCheckBox2.setIcon(unchecked);
                aCheckBox2.setSelectedIcon(checked);
            }
        };
    }
}
```

```

        Icon checkBoxIcon = new CheckBoxIcon();
        JCheckBox aCheckBox3 = new JCheckBox("Anchovies", checkBoxIcon);
        JCheckBox aCheckBox4 = new JCheckBox("Stuffed Crust", checked);
        frame.setLayout(new GridLayout(0,1));
        frame.add(aCheckBox1);
        frame.add(aCheckBox2);
        frame.add(aCheckBox3);
        frame.add(aCheckBox4);
        frame.setSize(300, 200);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Handling JCheckBox Selection Events

As with the `JToggleButton`, you can handle `JCheckBox` events in any one of three ways: with an `ActionListener`, an `ItemListener`, or a `ChangeListener`. The constructor that accepts an `Action` just adds the parameter as an `ActionListener`.

Listening to JCheckBox Events with an ActionListener

Subscribing to `ActionEvent` generation with an `ActionListener` allows you to find out when the user toggles the state of the `JCheckBox`. As with `JToggleButton`, the subscribed listener is told of the selection, but not the new state. To find out the selected state, you must get the model for the event source and ask, as the following sample `ActionListener` source shows. This listener modifies the check box label to reflect the selection state.

```

ActionListener actionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        AbstractButton abstractButton = (AbstractButton)actionEvent.getSource();
        boolean selected = abstractButton.getModel().isSelected();
        String newLabel = (selected ? SELECTED_LABEL : DESELECTED_LABEL);
        abstractButton.setText(newLabel);
    }
};

```

Listening to JCheckBox Events with an ItemListener

For `JCheckBox`, as with `JToggleButton`, the better listener to subscribe to is an `ItemListener`. The `ItemEvent` passed to the `itemStateChanged()` method of `ItemListener` includes the current state of the check box. This allows you to respond appropriately, without need to find out the current button state.

To demonstrate, the following `ItemListener` swaps the foreground and background colors based on the state of a selected component. In this `ItemListener`, the foreground and background colors are swapped only when the state is selected.

```

ItemListener itemListener = new ItemListener() {
    public void itemStateChanged(ItemEvent itemEvent) {
        AbstractButton abstractButton = (AbstractButton)itemEvent.getSource();
        Color foreground = abstractButton.getForeground();
        Color background = abstractButton.getBackground();
        int state = itemEvent.getStateChange();
        if (state == ItemEvent.SELECTED) {
            abstractButton.setForeground(background);
            abstractButton.setBackground(foreground);
        }
    }
};

```

Listening to JCheckBox Events with a ChangeListener

The `ChangeListener` responds to the `JCheckBox` just as with the `JToggleButton`. A subscribed `ChangeListener` would be notified when the button is armed, pressed, selected, or released. In addition, the `ChangeListener` is also notified of changes to the `ButtonModel`, such as for the keyboard mnemonic (`KeyEvent.VK_S`) of the check box. Because there are no `ChangeListener` differences to demonstrate between a `JToggleButton` and a `JCheckBox`, you could just attach the same listener from `JToggleButton` to the `JCheckBox`, and you'll get the same selection responses.

The sample program in Listing 5-4 demonstrates all the listeners subscribed to the events of a single `JCheckBox`. To demonstrate that the `ChangeListener` is notified of changes to other button model properties, a keyboard mnemonic is associated with the component. Given that the `ChangeListener` is registered before the mnemonic property is changed, the `ChangeListener` is notified of the property change. Because the foreground and background colors and text label aren't button model properties, the `ChangeListener` isn't told of these changes made by the other listeners.

Note If you did want to listen for changes to the foreground or background color properties, you would need to attach a `PropertyChangeListener` to the `JCheckBox`.

Listing 5-4. *Listening for JCheckBox Selection*

```

import javax.swing.*;
import javax.swing.event.*;
import java.awt.*;
import java.awt.event.*;

public class SelectingCheckBox {
    private static String DESELECTED_LABEL = "Deselected";
    private static String SELECTED_LABEL = "Selected";

```

```

public static void main(String args[]) {
    Runnable runner = new Runnable() {
        public void run() {
            JFrame frame = new JFrame("Selecting CheckBox");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
            JCheckBox checkBox = new JCheckBox(DESELECTED_LABEL);
            // Define ActionListener
            ActionListener actionListener = new ActionListener() {
                public void actionPerformed(ActionEvent actionEvent) {
                    AbstractButton abstractButton =
                        (AbstractButton)actionEvent.getSource();
                    boolean selected = abstractButton.getModel().isSelected();
                    String newLabel = (selected ? SELECTED_LABEL : DESELECTED_LABEL);
                    abstractButton.setText(newLabel);
                }
            };
            // Define ChangeListener
            ChangeListener changeListener = new ChangeListener() {
                public void stateChanged(ChangeEvent changeEvent) {
                    AbstractButton abstractButton =
                        (AbstractButton)changeEvent.getSource();
                    ButtonModel buttonModel = abstractButton.getModel();
                    boolean armed = buttonModel.isArmed();
                    boolean pressed = buttonModel.isPressed();
                    boolean selected = buttonModel.isSelected();
                    System.out.println("Changed: " + armed + "/" + pressed + "/" +
                        selected);
                }
            };
            // Define ItemListener
            ItemListener itemListener = new ItemListener() {
                public void itemStateChanged(ItemEvent itemEvent) {
                    AbstractButton abstractButton =
                        (AbstractButton)itemEvent.getSource();
                    Color foreground = abstractButton.getForeground();
                    Color background = abstractButton.getBackground();
                    int state = itemEvent.getStateChange();
                    if (state == ItemEvent.SELECTED) {
                        abstractButton.setForeground(background);
                        abstractButton.setBackground(foreground);
                    }
                }
            };
            // Attach Listeners
            checkBox.addActionListener(actionListener);
            checkBox.addChangeListener(changeListener);
            checkBox.addItemListener(itemListener);
        }
    };
}

```

```

        checkBox.setMnemonic(KeyEvent.VK_S);
        frame.add(checkBox, BorderLayout.NORTH);
        frame.setSize(300, 100);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

The `SelectingCheckBox` class produces the screen shown in Figure 5-8, after selecting and deselecting the `JCheckBox`.



Figure 5-8. *SelectingCheckBox* program screen

Customizing a JCheckBox Look and Feel

Each installable Swing look and feel provides a different `JCheckBox` appearance and set of default `UIResource` values. Figure 5-9 shows the appearance of the `JCheckBox` component for the preinstalled set of look and feel types: Motif, Windows, and Ocean. The first, third, and fifth check boxes are selected; the third has the input focus.



Figure 5-9. *JCheckBox* under different look and feel types

Table 5-4 shows the set of available UIResource-related properties for a JCheckBox. The JCheckBox component has 20 different properties.

Table 5-4. *JCheckBox UIResource Elements*

Property String	Object Type
CheckBox.background	Color
CheckBox.border	Border
CheckBox.darkShadow	Color
CheckBox.disabledText	Color
CheckBox.focus	Color
CheckBox.focusInputMap	Object[]
CheckBox.font	Font
CheckBox.foreground	Color
CheckBox.gradient	List
CheckBox.highlight	Color
CheckBox.icon	Icon
CheckBox.interiorBackground	Color
CheckBox.light	Color
CheckBox.margin	Insets
CheckBox.rollover	Boolean
checkbox.select*	Color
CheckBox.shadow	Color
CheckBox.textIconGap	Integer
CheckBox.textShiftOffset	Integer
CheckBoxUI	String

* Lowercase *b* is correct.

JRadioButton Class

You use JRadioButton when you want to create a mutually exclusive group of toggleable components. Although, technically speaking, you could place a group of JCheckBox components into a ButtonGroup and only one would be selectable at a time, they wouldn't look quite right. At least with the predefined look and feel types, JRadioButton and JCheckBox components look different, as Figure 5-10 shows. This difference in appearance tells the end user to expect specific behavior from the components.




Figure 5-10. Comparing *JRadioButton* to *JCheckBox* appearance

The *JRadioButton* is made up of several pieces. Like *JToggleButton* and *JCheckBox*, the *JRadioButton* uses a *ToggleButtonModel* to represent its data model. It uses a *ButtonGroup* through *AbstractButton* to provide the mutually exclusive grouping, and the user interface delegate is the *RadioButtonUI*.

Let's now explore how to use the different pieces of a *JRadioButton*.

Creating *JRadioButton* Components

As with *JCheckBox* and *JToggleButton*, there are eight constructors for *JRadioButton*:

```
public JRadioButton()
```

```
JRadioButton aRadioButton = new JRadioButton();
```

```
public JRadioButton(Icon icon)
```

```
JRadioButton aRadioButton = new JRadioButton(new DiamondIcon(Color.CYAN, false));  
aRadioButton.setSelectedIcon(new DiamondIcon(Color.BLUE, true));
```

```
public JRadioButton(Icon icon, boolean selected)
```

```
JRadioButton aRadioButton = new JRadioButton(new DiamondIcon(Color.CYAN, false),  
true);  
aRadioButton.setSelectedIcon(new DiamondIcon(Color.BLUE, true));
```

```
public JRadioButton(String text)
```

```
JRadioButton aRadioButton = new JRadioButton("4 slices");
```

```
public JRadioButton(String text, boolean selected)
```

```
JRadioButton aRadioButton = new JRadioButton("8 slices", true);
```

```
public JRadioButton(String text, Icon icon)
```

```
JRadioButton aRadioButton = new JRadioButton("12 slices",  
new DiamondIcon(Color.CYAN, false));  
aRadioButton.setSelectedIcon(new DiamondIcon(Color.BLUE, true));
```

```
public JRadioButton(String text, Icon icon, boolean selected)
```

```
JRadioButton aRadioButton = new JRadioButton("16 slices",  
new DiamondIcon(Color.CYAN, false), true);  
aRadioButton.setSelectedIcon(new DiamondIcon(Color.BLUE, true));
```

```
public JRadioButton(Action action)
Action action = ...;
JRadioButton aRadioButton = new JRadioButton(action);
```

Note As with a JCheckBox, configuring a JRadioButton from an Action sets the label, state, and tooltip text, but not the icon.

Each allows you to customize one or more of the label, icon, or initial selection state properties. Unless specified otherwise, there’s no text in the label, and the default selected/unselected icon for the check box appears unselected. After creating a group of radio button components, you need to place each into a single ButtonGroup so that they work as expected, with only one button in the group selectable at a time. If you do initialize the icon in the constructor, it’s the icon for the unselected state of the check box, with the same icon displayed when the check box is selected. You must also either initialize the selected icon with the setSelectedIcon(Icon newValue) method, described with JCheckBox, or make sure the icon is state-aware and updates itself.

JRadioButton Properties

JRadioButton has two properties that override the behavior of its parent JToggleButton, as listed in Table 5-5.

Table 5-5. *JRadioButton Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
UIClassID	String	Read-only

Grouping JRadioButton Components in a ButtonGroup

The JRadioButton is the only JToggleButton subclass that should be placed in a ButtonGroup in order to work properly. Merely creating a bunch of radio buttons and placing them on the screen isn’t enough to make them behave appropriately. In addition to adding each radio button to a container, you need to create a ButtonGroup and add each radio button to the same ButtonGroup. Once all the JRadioButton items are in a group, whenever an unselected radio button is selected, the ButtonGroup causes the currently selected radio button to be deselected.

Placing a set of JRadioButton components within a ButtonGroup on the screen is basically a four-step process:

1. Create a container for the group.

```
JPanel aPanel = new JPanel(new GridLayout(0, 1));
```

Note The Box class described in Chapter 11 serves as a good container for a group of JRadioButton components.

2. Place a border around the container, to label the grouping. This is an optional step, but you'll frequently want to add a border to label the group for the user. You can read more about borders in Chapter 7.

```
Border border = BorderFactory.createTitledBorder("Slice Count");
aPanel.setBorder(border);
```

3. Create a ButtonGroup.

```
ButtonGroup aGroup = new ButtonGroup();
```

4. For each selectable option, create a JRadioButton, add it to a container, and then add it to the group.

```
JRadioButton aRadioButton = new JRadioButton(...);
aPanel.add(aRadioButton);
aGroup.add(aRadioButton);
```

You might find the whole process, especially the fourth step, a bit tedious after a while, especially when you add another step for handling selection events. The helper class shown in Listing 5-5, with its static `createRadioButtonGrouping(String elements[], String title)` method, could prove useful. It takes a `String` array for the radio button labels as well as the border title, and then it creates a set of `JRadioButton` objects with a common `ButtonGroup` in a `JPanel` with a titled border.

Listing 5-5. *Initial Support Class for Working with JRadioButton*

```
import javax.swing.*;
import javax.swing.border.*;
import java.awt.*;

public class RadioButtonUtils {
    private RadioButtonUtils() {
        // Private constructor so you can't create instances
    }
    public static Container createRadioButtonGrouping (String elements[],
        String title) {
        JPanel panel = new JPanel(new GridLayout(0, 1));
        // If title set, create titled border
        if (title != null) {
            Border border = BorderFactory.createTitledBorder(title);
            panel.setBorder(border);
        }
    }
}
```

```

// Create group
    ButtonGroup group = new ButtonGroup();
    JRadioButton aRadioButton;
// For each String passed in:
// Create button, add to panel, and add to group
    for (int i=0, n=elements.length; i<n; i++) {
        aRadioButton = new JRadioButton(elements[i]);
        panel.add(aRadioButton);
        group.add(aRadioButton);
    }
    return panel;
}
}

```

Now, you can create the grouping much more easily, as with the sample program in Listing 5-6.

Listing 5-6. *Sampling JRadioButton*

```

import javax.swing.*.*;
import java.awt.*.*;

public class GroupRadio {
    private static final String sliceOptions[] =
        {"4 slices", "8 slices", "12 slices", "16 slices"};
    private static final String crustOptions[] =
        {"Sicilian", "Thin Crust", "Thick Crust", "Stuffed Crust"};
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Grouping Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                Container sliceContainer =
                    RadioButtonUtils.createRadioButtonGrouping(
                        sliceOptions, "Slice Count");
                Container crustContainer =
                    RadioButtonUtils.createRadioButtonGrouping(
                        crustOptions, "Crust Type");
                frame.add(sliceContainer, BorderLayout.WEST);
                frame.add(crustContainer, BorderLayout.EAST);
                frame.setSize(300, 200);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

When you run this example, you'll see the screen shown in Figure 5-11.




Figure 5-11. Grouping *JRadioButton* components with the *RadioButtonUtils* helper class

Note If you're familiar with the standard AWT library, the *JRadioButton*/*ButtonGroup* combination works exactly like the *Checkbox*/*CheckboxGroup* pair.

Handling *JRadioButton* Selection Events

Like *JToggleButton* and *JCheckBox*, *JRadioButton* supports the registration of an *ActionListener*, an *ItemListener*, and a *ChangeListener*. And again, their usage with *JRadioButton* is somewhat different than with the other components.

Listening to *JRadioButton* Events with an *ActionListener*

With a *JRadioButton*, it's common to attach the same *ActionListener* to all the radio buttons in a *ButtonGroup*. That way, when one of the radio buttons is selected, the subscribed *ActionListener* will be notified. By overloading the earlier *createRadioButtonGrouping()* method, the method can accept an *ActionListener* argument and attach the listener object to each of the buttons as they're created.

```
public static Container createRadioButtonGrouping (String elements[], String title,
    ActionListener actionListener) {
    JPanel panel = new JPanel(new GridLayout(0, 1));
    // If title set, create titled border
    if (title != null) {
        Border border = BorderFactory.createTitledBorder(title);
        panel.setBorder(border);
    }
    // Create group
    ButtonGroup group = new ButtonGroup();
    JRadioButton aRadioButton;
    // For each String passed in:
    // Create button, add to panel, and add to group
```

```

for (int i=0, n=elements.length; i<n; i++) {
    aRadioButton = new JRadioButton (elements[i]);
    panel.add(aRadioButton);
    group.add(aRadioButton);
    if (actionListener != null) {
        aRadioButton.addActionListener(actionListener);
    }
}
return panel;
}

```

Now if a group is created with the following source, the same `ActionListener` will be notified for each of the `JRadioButton` components created. Here, the listener prints out only the currently selected value. How you choose to respond may vary.

```

ActionListener sliceActionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        AbstractButton aButton = (AbstractButton)actionEvent.getSource();
        System.out.println("Selected: " + aButton.getText());
    }
};
Container sliceContainer =
    RadioButtonUtils.createRadioButtonGrouping(sliceOptions, "Slice Count",
        sliceActionListener);

```

However, note that there are two problems with this approach. First, if a `JRadioButton` is already selected and then selected again, any attached `ActionListener` objects will still be notified once more. Although you cannot stop the double notification of subscribed `ActionListener` objects, with a little work, you can handle it properly. You need to retain a reference to the last selected item and check for reselection. The following modified `ActionListener` checks for this:

```

ActionListener crustActionListener = new ActionListener() {
    String lastSelected;
    public void actionPerformed(ActionEvent actionEvent) {
        AbstractButton aButton = (AbstractButton)actionEvent.getSource();
        String label = aButton.getText();
        String msgStart;
        if (label.equals(lastSelected)) {
            msgStart = "Reselected: ";
        } else {
            msgStart = "Selected: ";
        }
        lastSelected = label;
        System.out.println(msgStart + label);
    }
};

```

The second problem has to do with determining which `JRadioButton` is selected at any given time. With the overloaded `RadioButtonUtils.createRadioButtonGrouping()` helper methods, neither the `ButtonGroup` nor the individual `JRadioButton` components are visible outside the

method. As a result, there's no direct route to find out which `JRadioButton` object (or objects) is selected within the `ButtonGroup` of the returned container. This may be necessary, for example, if there were an Order Pizza button on the screen and you wanted to find out which pizza-order options were selected after the user clicked that button.

The following helper method, `public Enumeration getSelectedElements(Container container)`, when added to the previously created `RadioButtonUtils` class (Listing 5-5), will provide the necessary answer. The helper method will work only if the container passed into the method is full of `AbstractButton` objects. This is true for those containers created with the previously described `createRadioButtonGrouping()` methods, although the `getSelectedElements()` method can be used separately.

```
public static Enumeration<String> getSelectedElements(Container container) {
    Vector<String> selections = new Vector<String>();
    Component components[] = container.getComponents();
    for (int i=0, n=components.length; i<n; i++) {
        if (components[i] instanceof AbstractButton) {
            AbstractButton button = (AbstractButton)components[i];
            if (button.isSelected()) {
                selections.addElement(button.getText());
            }
        }
    }
    return selections.elements();
}
```

To use the `getSelectedElements()` method, you just need to pass the container returned from `createRadioButtonGrouping()` to the `getSelectedElements()` method to get an `Enumeration` of the selected items as `String` objects. The following example demonstrates this.

```
final Container crustContainer =
    RadioButtonUtils.createRadioButtonGrouping(crustOptions, "Crust Type");

ActionListener buttonActionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        Enumeration selected = RadioButtonUtils.getSelectedElements(crustContainer);
        while (selected.hasMoreElements()) {
            System.out.println ("Selected -> " + selected.nextElement());
        }
    }
};

JButton button = new JButton ("Order Pizza");
button.addActionListener(buttonActionListener);
```

It may be necessary for `getSelectedElements()` to return more than one value, because if the same `ButtonModel` is shared by multiple buttons in the container, multiple components of the `ButtonGroup` will be selected. Sharing a `ButtonModel` between components isn't the norm. If you're sure your button model won't be shared, then you may want to provide a similar method that returns only a `String`.

Listening to JRadioButton Events with an ItemListener

Depending on what you're trying to do, using an `ItemListener` with a `JRadioButton` is usually not the desired event-listening approach. When an `ItemListener` is registered, a new `JRadioButton` selection notifies the listener twice: once for deselecting the old value and once for selecting the new value. For reselections (selecting the same choice again), the listener is notified only once.

To demonstrate, the following listener will detect reselections, as the `ActionListener` did earlier, and will report the selected (or deselected) element.

```
ItemListener itemListener = new ItemListener() {
    String lastSelected;
    public void itemStateChanged(ItemEvent itemEvent) {
        AbstractButton aButton = (AbstractButton)itemEvent.getSource();
        int state = itemEvent.getStateChange();
        String label = aButton.getText();
        String msgStart;
        if (state == ItemEvent.SELECTED) {
            if (label.equals(lastSelected)) {
                msgStart = "Reselected -> ";
            } else {
                msgStart = "Selected -> ";
            }
            lastSelected = label;
        } else {
            msgStart = "Deselected -> ";
        }
        System.out.println(msgStart + label);
    }
};
```

To work properly, some new methods will be needed for `RadioButtonUtils` to enable you to attach the `ItemListener` to each `JRadioButton` in the `ButtonGroup`. They're listed in the following section with the source for the complete example.

Listening to JRadioButton Events with a ChangeListener

The `ChangeListener` responds to the `JRadioButton` just as it does with the `JToggleButton` and `JCheckBox`. A subscribed listener is notified when the selected radio button is armed, pressed, selected, or released and for various other properties of the button model. The only difference with `JRadioButton` is that the `ChangeListener` is also notified of the state changes of the radio button being deselected. The `ChangeListener` from the earlier examples could be attached to the `JRadioButton` as well. It will just be notified more frequently.

The sample program shown in Listing 5-7 demonstrates all the listeners registered to the events of two different `JRadioButton` objects. In addition, a `JButton` reports on the selected elements of one of the radio buttons. Figure 5-12 shows the main window of the program.

Listing 5-7. *Radio Button Group Sample*

```

import javax.swing.*;
import javax.swing.event.*;
import java.awt.*;
import java.awt.event.*;
import java.util.Enumuration;

public class GroupActionRadio {
    private static final String sliceOptions[] =
        {"4 slices", "8 slices", "12 slices", "16 slices"};
    private static final String crustOptions[] =
        {"Sicilian", "Thin Crust", "Thick Crust", "Stuffed Crust"};
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Grouping Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                // Slice Parts
                ActionListener sliceActionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        AbstractButton aButton = (AbstractButton)actionEvent.getSource();
                        System.out.println("Selected: " + aButton.getText());
                    }
                };
                Container sliceContainer =
                    RadioButtonUtils.createRadioButtonGrouping(sliceOptions,
                        "Slice Count", sliceActionListener);

                // Crust Parts
                ActionListener crustActionListener = new ActionListener() {
                    String lastSelected;
                    public void actionPerformed(ActionEvent actionEvent) {
                        AbstractButton aButton = (AbstractButton)actionEvent.getSource();
                        String label = aButton.getText();
                        String msgStart;
                        if (label.equals(lastSelected)) {
                            msgStart = "Reselected: ";
                        } else {
                            msgStart = "Selected: ";
                        }
                        lastSelected = label;
                        System.out.println(msgStart + label);
                    }
                };
            }
        };
    }
}

```

```

ItemListener itemListener = new ItemListener() {
    String lastSelected;
    public void itemStateChanged(ItemEvent itemEvent) {
        AbstractButton aButton = (AbstractButton)itemEvent.getSource();
        int state = itemEvent.getStateChange();
        String label = aButton.getText();
        String msgStart;
        if (state == ItemEvent.SELECTED) {
            if (label.equals(lastSelected)) {
                msgStart = "Reselected -> ";
            } else {
                msgStart = "Selected -> ";
            }
            lastSelected = label;
        } else {
            msgStart = "Deselected -> ";
        }
        System.out.println(msgStart + label);
    }
};

ChangeListener changeListener = new ChangeListener() {
    public void stateChanged(ChangeEvent changEvent) {
        AbstractButton aButton = (AbstractButton)changEvent.getSource();
        ButtonModel aModel = aButton.getModel();
        boolean armed = aModel.isArmed();
        boolean pressed = aModel.isPressed();
        boolean selected = aModel.isSelected();
        System.out.println("Changed: " + armed + "/" + pressed + "/" +
            selected);
    }
};

final Container crustContainer =
    RadioButtonUtils.createRadioButtonGrouping(crustOptions,
        "Crust Type", crustActionListener, itemListener, changeListener);

// Button Parts
ActionListener buttonActionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        Enumeration<String> selected =
            RadioButtonUtils.getSelectedElements(crustContainer);
        while (selected.hasMoreElements()) {
            System.out.println ("Selected -> " + selected.nextElement());
        }
    }
};

```

```

        JButton button = new JButton ("Order Pizza");
        button.addActionListener(buttonActionListener);

        frame.add(sliceContainer, BorderLayout.WEST);
        frame.add(crustContainer, BorderLayout.EAST);
        frame.add(button, BorderLayout.SOUTH);
        frame.setSize(300, 200);
        frame.setVisible(true);
    }
};
    EventQueue.invokeLater(runner);
}
}

```




Figure 5-12. *The GroupActionRadio program sample screen*

A few more changes were made to the `RadioButtonUtils` class to deal with registering `ChangeListener` objects to all the radio buttons in a `ButtonGroup`. The complete and final class definition is shown in Listing 5-8.

Listing 5-8. *Complete Support Class for Working with JRadioButton*

```

import javax.swing.*;
import javax.swing.event.*;
import javax.swing.border.*;
import java.awt.*;
import java.awt.event.*;
import java.util.Enumuration;
import java.util.Vector;

public class RadioButtonUtils {
    private RadioButtonUtils() {
        // Private constructor so you can't create instances
    }
}

```

```

public static Enumeration<String> getSelectedElements(Container container) {
    Vector<String> selections = new Vector<String>();
    Component components[] = container.getComponents();
    for (int i=0, n=components.length; i<n; i++) {
        if (components[i] instanceof AbstractButton) {
            AbstractButton button = (AbstractButton)components[i];
            if (button.isSelected()) {
                selections.addElement(button.getText());
            }
        }
    }
    return selections.elements();
}

public static Container createRadioButtonGrouping (String elements[]) {
    return createRadioButtonGrouping(elements, null, null, null, null);
}

public static Container createRadioButtonGrouping (String elements[],
    String title) {
    return createRadioButtonGrouping(elements, title, null, null, null);
}

public static Container createRadioButtonGrouping(String elements[],
    String title, ItemListener itemListener) {
    return createRadioButtonGrouping(elements, title, null, itemListener, null);
}

public static Container createRadioButtonGrouping(String elements[],
    String title, ActionListener actionListener) {
    return createRadioButtonGrouping(elements, title, actionListener, null,
        null);
}

public static Container createRadioButtonGrouping(String elements[],
    String title, ActionListener actionListener, ItemListener itemListener) {
    return createRadioButtonGrouping(elements, title, actionListener,
        itemListener, null);
}

public static Container createRadioButtonGrouping(String elements[],
    String title, ActionListener actionListener, ItemListener itemListener,
    ChangeListener changeListener) {
    JPanel panel = new JPanel(new GridLayout(0, 1));
    // If title set, create titled border

```

```
if (title != null) {
    Border border = BorderFactory.createTitledBorder(title);
    panel.setBorder(border);
}
// Create group
ButtonGroup group = new ButtonGroup();
JRadioButton aRadioButton;
// For each String passed in:
// Create button, add to panel, and add to group
for (int i=0, n=elements.length; i<n; i++) {
    aRadioButton = new JRadioButton (elements[i]);
    panel.add(aRadioButton);
    group.add(aRadioButton);
    if (actionListener != null) {
        aRadioButton.addActionListener(actionListener);
    }
    if (itemListener != null) {
        aRadioButton.addItemListener(itemListener);
    }
    if (changeListener != null) {
        aRadioButton.addChangeListener(changeListener);
    }
}
return panel;
}
```

Note One thing not shown here but explained in Chapter 4 in the discussion of `ButtonModel` and `DefaultButtonModel` is how to get the `ButtonGroup` when given a `JRadioButton`. If you want to find the `ButtonGroup` that a `JRadioButton` is in, you need to ask the `DefaultButtonModel`: `ButtonGroup group = ((DefaultButtonModel)aJRadioButton.getModel()).getButtonGroup()`.

Customizing a `JRadioButton` Look and Feel

Each installable Swing look and feel provides a different `JRadioButton` appearance and set of default `UIResource` values. Figure 5-13 shows the appearance of the `JRadioButton` component for the preinstalled set of look and feel types: Motif, Windows, and Ocean. All three screens show 4 slices of Thin Crust pizza as the order. In addition, the Thick Crust option has the input focus.




Figure 5-13. *JRadioButton* under different look and feel types

Table 5-6 shows the set of available UIResource-related properties for a `JRadioButton`. The `JRadioButton` component has 20 different properties available.

Table 5-6. *JRadioButton* UIResource Elements

Property String	Object Type
<code>RadioButton.background</code>	Color
<code>RadioButton.border</code>	Border
<code>RadioButton.darkShadow</code>	Color
<code>RadioButton.disabledText</code>	Color
<code>RadioButton.focus</code>	Color
<code>RadioButton.focusInputMap</code>	Object[]
<code>RadioButton.font</code>	Font
<code>RadioButton.foreground</code>	Color
<code>RadioButton.gradient</code>	List
<code>RadioButton.highlight</code>	Color
<code>RadioButton.icon</code>	Icon
<code>RadioButton.interiorBackground</code>	Color
<code>RadioButton.light</code>	Color
<code>RadioButton.margin</code>	Insets

Table 5-6. *JRadioButton UIResource Elements (Continued)*

Property String	Object Type
RadioButton.rollover	Boolean
RadioButton.select	Color
RadioButton.shadow	Color
RadioButton.textIconGap	Integer
RadioButton.textShiftOffset	Integer
RadioButtonUI	String

Summary

This chapter described the components that can be toggled: `JToggleButton`, `JCheckBox`, and `JRadioButton`. You've seen how each component uses the `JToggleButton.ToggleButtonModel` class for its data model and how you can group the components into a `ButtonGroup`. In addition, you also saw how to handle selection events for each of the components.

Chapter 6 explains how to work with the various menu-oriented Swing components.



Swing Menus and Toolbars

Many of the low-level Swing components were covered in the previous two chapters of this book. This chapter will delve into Swing's menu-related components. Menus and toolbars help make your applications more user-friendly by providing visual command options. Users can avoid the somewhat archaic multiple-key command sequences that are holdovers from programs such as the early word processor WordStar and the more current emacs programmer's editor. Although Swing menus do support multiple-key command sequences, the menus (and toolbars) are designed primarily for on-screen graphical selection with a mouse, rather than the keyboard.

The menu components discussed in this chapter are used as follows:

- For each cascading menu, you create a `JMenu` component and add it to the `JMenuBar`.
- For the selections available from the `JMenu`, you create `JMenuItem` components and add them to the `JMenu`.
- To create submenus, you add a new `JMenu` to a `JMenu` and place `JMenuItem` options on the new menu.
- Then, when a `JMenu` is selected, the system displays its current set of components within a `JPopupMenu`.

In addition to the basic `JMenuItem` elements, this chapter covers other menu items, such as `JCheckBoxMenuItem` and `JRadioButtonMenuItem`, which you can place within a `JMenu`. You'll also explore the `JSeparator` class, which serves to divide menu items into logical groups. You'll find out how to use the `JPopupMenu` class for general support of pop-up menus that appear after a `JMenu` is selected, or in context for any component. As with abstract buttons (the `AbstractButton` class was introduced in Chapter 4), each menu element can have a mnemonic associated with it for keyboard selection. You'll also learn about the support for keyboard accelerators, which allow users to avoid going through all the menuing levels for selection.

Besides the individual menu-related components, in this chapter you'll look at the `JMenuBar` selection model and event-related classes specific to menus. The selection model interface to examine is the `SingleSelectionModel` interface, as well as its default implementation `DefaultSingleSelectionModel`. You'll explore the menu-specific listeners and events `MenuListener/MenuEvent`, `MenuKeyListener/MenuKeyEvent`, and `MenuDragMouseListener/MenuDragMouseEvent`. In addition, you'll examine creating other pop-up components with `Popup` and `PopupFactory`, as well as using toolbars with the `JToolBar` class.

Working with Menus

Let's begin with an example that demonstrates how all the menu components fit together. To start, create a frame with a menu bar, as shown in Figure 6-1.




Figure 6-1. Menu component examples

This simple menuing example has the following features:

- On the menu bar are two ubiquitous menus: File and Edit. Under the File menu, the familiar options of New, Open, Close, and Exit will appear (although they aren't shown in Figure 6-1). Under the Edit menu are options for Cut, Copy, Paste, and Find, and a submenu of Find options. The Options submenu will contain choices for search direction—forward or backward—and a toggle for case sensitivity.
- In various places within the different menus, menu separators divide the options into logical sets.
- Each of the menu options has a mnemonic associated with it to help with keyboard navigation and selection. The mnemonic allows users to make menu selections via the keyboard, for instance, by pressing Alt-F on a Windows platform to open the File menu.
- In addition to the keyboard mnemonic, a keystroke associated with several options acts as a keyboard accelerator. Unlike the mnemonic, the accelerator can directly activate a menu option, even when the menu option isn't visible.
- The Options submenu has an icon associated with it. Although only one icon is shown in Figure 6-1, all menu components can have an icon, except for the JSeparator and JPopupMenu components.

Note that for this beginning example, none of the menu choices will do anything other than print which menu choice was selected. For example, selecting the Copy option from the Edit menu displays Selected: Copy.

Listing 6-1 shows the complete source for the class that generated the example in Figure 6-1.

Listing 6-1. *The MenuSample Class Definition*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;

public class MenuSample {
    static class MenuActionListener implements ActionListener {
        public void actionPerformed (ActionEvent actionEvent) {
            System.out.println ("Selected: " + actionEvent.getActionCommand());
        }
    }

    public static void main(final String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                ActionListener menuListener = new MenuActionListener();
                JFrame frame = new JFrame("MenuSample Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                JMenuBar menuBar = new JMenuBar();

                // File Menu, F - Mnemonic
                JMenu fileMenu = new JMenu("File");
                fileMenu.setMnemonic(KeyEvent.VK_F);
                menuBar.add(fileMenu);

                // File->New, N - Mnemonic
                JMenuItem newMenuItem = new JMenuItem("New", KeyEvent.VK_N);
                newMenuItem.addActionListener(menuListener);
                fileMenu.add(newMenuItem);

                // File->Open, O - Mnemonic
                JMenuItem openMenuItem = new JMenuItem("Open", KeyEvent.VK_O);
                openMenuItem.addActionListener(menuListener);
                fileMenu.add(openMenuItem);

                // File->Close, C - Mnemonic
                JMenuItem closeMenuItem = new JMenuItem("Close", KeyEvent.VK_C);
                closeMenuItem.addActionListener(menuListener);
                fileMenu.add(closeMenuItem);
            }
        };
        runner.run();
    }
}
```

```
// Separator
fileMenu.addSeparator();

// File->Save, S - Mnemonic
JMenuItem saveMenuItem = new JMenuItem("Save", KeyEvent.VK_S);
saveMenuItem.addActionListener(menuListener);
fileMenu.add(saveMenuItem);

// Separator
fileMenu.addSeparator();

// File->Exit, X - Mnemonic
JMenuItem exitMenuItem = new JMenuItem("Exit", KeyEvent.VK_X);
exitMenuItem.addActionListener(menuListener);
fileMenu.add(exitMenuItem);

// Edit Menu, E - Mnemonic
JMenu editMenu = new JMenu("Edit");
editMenu.setMnemonic(KeyEvent.VK_E);
menuBar.add(editMenu);

// Edit->Cut, T - Mnemonic, CTRL-X - Accelerator
JMenuItem cutMenuItem = new JMenuItem("Cut", KeyEvent.VK_T);
cutMenuItem.addActionListener(menuListener);
KeyStroke ctrlXKeyStroke = KeyStroke.getKeyStroke("control X");
cutMenuItem.setAccelerator(ctrlXKeyStroke);
editMenu.add(cutMenuItem);

// Edit->Copy, C - Mnemonic, CTRL-C - Accelerator
JMenuItem copyMenuItem = new JMenuItem("Copy", KeyEvent.VK_C);
copyMenuItem.addActionListener(menuListener);
KeyStroke ctrlCKeyStroke = KeyStroke.getKeyStroke("control C");
copyMenuItem.setAccelerator(ctrlCKeyStroke);
editMenu.add(copyMenuItem);

// Edit->Paste, P - Mnemonic, CTRL-V - Accelerator, Disabled
JMenuItem pasteMenuItem = new JMenuItem("Paste", KeyEvent.VK_P);
pasteMenuItem.addActionListener(menuListener);
KeyStroke ctrlVKeyStroke = KeyStroke.getKeyStroke("control V");
pasteMenuItem.setAccelerator(ctrlVKeyStroke);
pasteMenuItem.setEnabled(false);
editMenu.add(pasteMenuItem);

// Separator
editMenu.addSeparator();
```

```
// Edit->Find, F - Mnemonic, F3 - Accelerator
JMenuItem findMenuItem = new JMenuItem("Find", KeyEvent.VK_F);
findMenuItem.addActionListener(menuListener);
KeyStroke f3KeyStroke = KeyStroke.getKeyStroke("F3");
findMenuItem.setAccelerator(f3KeyStroke);
editMenu.add(findMenuItem);

// Edit->Options Submenu, O - Mnemonic, at.gif - Icon Image File
JMenu findOptionsMenu = new JMenu("Options");
Icon atIcon = new ImageIcon("at.gif");
findOptionsMenu.setIcon(atIcon);
findOptionsMenu.setMnemonic(KeyEvent.VK_O);

// ButtonGroup for radio buttons
ButtonGroup directionGroup = new ButtonGroup();

// Edit->Options->Forward, F - Mnemonic, in group
JRadioButtonMenuItem forwardMenuItem =
    new JRadioButtonMenuItem("Forward", true);
forwardMenuItem.addActionListener(menuListener);
forwardMenuItem.setMnemonic(KeyEvent.VK_F);
findOptionsMenu.add(forwardMenuItem);
directionGroup.add(forwardMenuItem);

// Edit->Options->Backward, B - Mnemonic, in group
JRadioButtonMenuItem backwardMenuItem =
    new JRadioButtonMenuItem("Backward");
backwardMenuItem.addActionListener(menuListener);
backwardMenuItem.setMnemonic(KeyEvent.VK_B);
findOptionsMenu.add(backwardMenuItem);
directionGroup.add(backwardMenuItem);

// Separator
findOptionsMenu.addSeparator();

// Edit->Options->Case Sensitive, C - Mnemonic
JCheckBoxMenuItem caseMenuItem =
    new JCheckBoxMenuItem("Case Sensitive");
caseMenuItem.addActionListener(menuListener);
caseMenuItem.setMnemonic(KeyEvent.VK_C);
findOptionsMenu.add(caseMenuItem);
editMenu.add(findOptionsMenu);
```

```

        frame.setJMenuBar(menuBar);
        frame.setSize(350, 250);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Menu Class Hierarchy

Now that you've seen an example of how to create the cascading menus for an application, you should have an idea of what's involved in using the Swing menu components. To help clarify, Figure 6-2 illustrates how all the Swing menu components are interrelated.




Figure 6-2. Swing menu class hierarchy

The most important concept illustrated in Figure 6-2 is that all the Swing menu elements, as subclasses of `JComponent`, are AWT components in their own right. You can place `JMenuItem`, `JMenu`, and `JMenuBar` components anywhere that AWT components can go, not just on a frame. In addition, because `JMenuItem` inherits from `AbstractButton`, `JMenuItem` and its subclasses inherit support for various icons and for HTML text labels, as described in Chapter 5.

Note Although technically possible, placing menus in locations where users wouldn't expect them to be is poor user interface design.

In addition to being part of the basic class hierarchy, each of the selectable menu components implements the `MenuItem` interface. The interface describes the menu behavior necessary to support keyboard and mouse navigation. The predefined menu components already implement this behavior, so you don't have to. But if you're interested in how this interface works, see the "MenuItem Interface" section later in this chapter.

Now let's take a look at the different Swing menu components.

JMenuBar Class

Swing's menu bar component is the `JMenuBar`. Its operation requires you to fill the menu bar with `JMenu` elements that have `MenuItem` elements. Then you add the menu bar to a `JFrame` or some other user interface component requiring a menu bar. The menu bar then relies on the assistance of a `SingleSelectionModel` to determine which `JMenu` to display or post after it's selected.

Creating JMenuBar Components

`JMenuBar` has a single constructor of the no-argument variety: `public JMenuBar()`. Once you create the menu bar, you can add it to a window with the `setJMenuBar()` method of `JApplet`, `JDialog`, `JFrame`, `JInternalFrame`, or `JRootPane`. (Yes, even applets can have menu bars.)

```
JMenuBar menuBar = new JMenuBar();
// Add items to it
...
JFrame frame = new JFrame("MenuSample Example");
frame.setJMenuBar(menuBar);
```

With the system-provided look and feel types, the menu bar appears at the top of the window, below any window title (if present), with `setJMenuBar()`. Other look and feel types, like Aqua for the Macintosh, place the menu bar elsewhere.

You can also use the `add()` method of a `Container` to add a `JMenuBar` to a window. When added with the `add()` method, a `JMenuBar` is arranged by the layout manager of the `Container`.

After you have a `JMenuBar`, the remaining menu classes all work together to fill the menu bar.

Adding Menus to and Removing Menus from Menu Bars

You need to add `JMenu` objects to a `JMenuBar`. Otherwise, the only thing displayed is the border with nothing in it. There's a single method for adding menus to a `JMenuBar`:

```
public JMenu add(JMenu menu)
```

By default, consecutively added menus are displayed from left to right. This makes the first menu added the leftmost menu and the last menu added the rightmost menu. Menus added in between are displayed in the order in which they're added. For instance, in the sample program from Listing 6-1, the menus were added as follows:

```
JMenu fileMenu = new JMenu("File");
menuBar.add(fileMenu);
JMenu editMenu = new JMenu("Edit");
menuBar.add(editMenu);
```

Note Placing a `JMenuBar` in the `EAST` or `WEST` area of a `BorderLayout` does not make the menus appear vertically, stacked one on top of another. You must customize the menu bar if you want menus to appear this way. See Figure 6-4, later in this chapter, for one implementation of a top-down menu bar.

In addition to the `add()` method from `JMenuBar`, several overloaded varieties of the `add()` method inherited from `Container` offer more control over menu positioning. Of particular interest is the `add(Component component, int index)` method, which allows you to specify the position in which the new `JMenu` is to appear. Using this second variety of `add()` allows you to place the `File` and `Edit` `JMenu` components in a `JMenuBar` in a different order, but with the same results:

```
menuBar.add(editMenu);
menuBar.add(fileMenu, 0);
```

If you've added a `JMenu` component to a `JMenuBar`, you can remove it with either the `remove(Component component)` or `remove(int index)` method inherited from `Container`:

```
bar.remove(edit);
bar.remove(0);
```

Tip Adding or removing menus from a menu bar is likely to confuse users. However, sometimes it's necessary to do so—especially if you want to have an expert mode that enables a certain functionality that a nonexpert mode hides. A better approach is to disable/enable individual menu items or entire menus. If you do add or remove menus, you must then `revalidate()` the menu bar to display the changes.

JMenuBar Properties

Table 6-1 shows the 11 properties of `JMenuBar`. Half the properties are read-only, allowing you only to query the current state of the menu bar. The remaining properties allow you to alter the appearance of the menu bar by deciding whether the border of the menu bar is painted and selecting the size of the margin between menu elements. The selected property and selection model control which menu on the menu bar, if any, is currently selected. When the selected

component is set to a menu on the menu bar, the menu components appear in a pop-up menu within a window.

Caution The `helpMenu` property, although available with a set-and-get method, is unsupported in the Swing releases through 5.0. Calling either accessor method will throw an error. With some future release of Swing, the `helpMenu` property will likely make a specific `JMenu` the designated help menu. Exactly what happens when a menu is flagged as the help menu is specific to the installed look and feel. What tends to happen is that the menu becomes the last, or rightmost, menu.

Table 6-1. *JMenuBar Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>borderPainted</code>	<code>boolean</code>	Read-write
<code>component</code>	<code>Component</code>	Read-only
<code>helpMenu</code>	<code>JMenu</code>	Read-write
<code>margin</code>	<code>Insets</code>	Read-write
<code>menuCount</code>	<code>int</code>	Read-only
<code>selected</code>	<code>boolean/Component</code>	Read-write
<code>selectionModel</code>	<code>SingleSelectionModel</code>	Read-write
<code>subElements</code>	<code>MenuElement[]</code>	Read-only
<code>UI</code>	<code>MenuBarUI</code>	Read-write
<code>UIClassID</code>	<code>String</code>	Read-only

Note The `selected` property of `JMenuBar` is nonstandard. The getter method returns a `boolean` to indicate if a menu component is selected on the menu bar. The setter method accepts a `Component` argument to select a component on the menu bar.

Customizing a JMenuBar Look and Feel

Each predefined Swing look and feel provides a different appearance and set of default `UIResource` values for the `JMenuBar` and each of the menu components. Figure 6-3 shows the appearance of all these menu components for the preinstalled set of look and feel types: Motif, Windows, and Ocean.




Figure 6-3. Menu components under different look and feel types

In regard to the specific appearance of the `JMenuBar`, the available set of `UIResource`-related properties is shown in Table 6-2. There are 12 properties available for the `JMenuBar` component.

Table 6-2. `JMenuBar` `UIResource` Elements

Property String	Object Type
<code>MenuBar.actionMap</code>	<code>ActionMap</code>
<code>MenuBar.background</code>	<code>Color</code>
<code>MenuBar.border</code>	<code>Border</code>
<code>MenuBar.borderColor</code>	<code>Color</code>
<code>MenuBar.darkShadow</code>	<code>Color</code>
<code>MenuBar.font</code>	<code>Font</code>
<code>MenuBar.foreground</code>	<code>Color</code>
<code>MenuBar.gradient</code>	<code>List</code>
<code>MenuBar.highlight</code>	<code>Color</code>
<code>MenuBar.shadow</code>	<code>Color</code>
<code>MenuBar.windowBindings</code>	<code>Object[]</code>
<code>MenuBarUI</code>	<code>String</code>

If you want a vertical menu bar, instead of a horizontal one, simply change the `LayoutManager` of the menu bar component. A setup such as a 0 row by 1 column `GridLayout` does the job, as shown in the following example, because the number of rows will grow infinitely for each `JMenu` added:

```
import java.awt.*;
import javax.swing.*;
public class VerticalMenuBar extends JMenuBar {
    private static final LayoutManager grid = new GridLayout(0,1);
    public VerticalMenuBar() {
        setLayout(grid);
    }
}
```

Moving the menu bar shown in Figure 6-1 to the east side of a `BorderLayout` and making it a `VerticalMenuBar` instead of a `JMenuBar` produces the setup shown in Figure 6-4. Although the vertical menu bar may look a little unconventional here, it's more desirable to have menu items appearing stacked vertically, rather than horizontally, on the right (or left) side of a window. You may, however, want to change the `MenuBar.border` property to a more appropriate border.



Figure 6-4. *Using the VerticalMenuBar*

Note Changing the layout manager of the `JMenuBar` has one negative side effect: Because top-level menus are pull-down menus, open menus on a vertical bar will obscure the menu bar. If you want to correct this pop-up placement behavior, you must extend the `JMenu` class and override its protected `getPopupMenuOrigin()` method in order to make the pop-up menu span out, rather than drop down.

SingleSelectionModel Interface

The `SingleSelectionModel` interface describes an index into an integer-indexed data structure where an element can be selected. The data structure behind the interface facade is most likely an array or vector in which repeatedly accessing the same position is guaranteed to return the same object. The `SingleSelectionModel` interface is the selection model for a `JMenuBar` as well as a `JPopupMenu`. In the case of a `JMenuBar`, the interface describes the currently selected `JMenu` that needs to be painted. In the case of a `JPopupMenu`, the interface describes the currently selected `JMenuItem`.

Note `SingleSelectionModel` also serves as the selection model for `JTabbedPane`, a class described in Chapter 11.

The interface definition for `SingleSelectionModel` follows:

```
public interface SingleSelectionModel {
    // Listeners
    public void addChangeListener(ChangeListener listener);
    public void removeChangeListener(ChangeListener listener);
    // Properties
    public int getSelectedIndex();
    public void setSelectedIndex(int index);
    public boolean isSelected();
    // Other Methods
    public void clearSelection();
}
```

As you can see, in addition to the selection index, the interface requires maintenance of a `ChangeListener` list to be notified when the selection index changes.

The default Swing-provided implementation of `SingleSelectionModel` is the `DefaultSingleSelectionModel` class. For both `JMenuBar` and `JPopupMenu`, it's very unlikely that you will change their selection model from this default implementation.

The `DefaultSingleSelectionModel` implementation manages the list of `ChangeListener` objects. In addition, the model uses a value of `-1` to signify that nothing is currently selected. When the selected index is `-1`, `isSelected()` returns `false`; otherwise, the method returns `true`. When the selected index changes, any registered `ChangeListener` objects will be notified.

JMenuItem Class

The `JMenuItem` component is the predefined component that a user selects on a menu bar. As a subclass of `AbstractButton`, `JMenuItem` acts as a specialized button component that behaves similarly to a `JButton`. Besides being a subclass of `AbstractButton`, the `JMenuItem` class shares the data model of `JButton` (`ButtonModel` interface and `DefaultButtonModel` implementation).

Creating JMenuItem Components

Six constructors for `JMenuItem` follow. They allow you to initialize the menu item's string or icon label and the mnemonic of the menu item. There's no explicit constructor permitting you to set all three options at creation time, unless you make them part of an `Action`.

```
public JMenuItem()  
JMenuItem jMenuItem = new JMenuItem();  
  
public JMenuItem(Icon icon)  
Icon atIcon = new ImageIcon("at.gif");  
JMenuItem jMenuItem = new JMenuItem(atIcon);  
  
public JMenuItem(String text)  
JMenuItem jMenuItem = new JMenuItem("Cut");  
  
public JMenuItem(String text, Icon icon)  
Icon atIcon = new ImageIcon("at.gif");  
JMenuItem jMenuItem = new JMenuItem("Options", atIcon);  
  
public JMenuItem(String text, int mnemonic)  
JMenuItem jMenuItem = new JMenuItem("Cut", KeyEvent.VK_T);  
  
public JMenuItem(Action action)  
Action action = ...;  
JMenuItem jMenuItem = new JMenuItem(action);
```

The mnemonic allows you to select the menu through keyboard navigation. For instance, you can simply press Alt-T on a Windows platform to select the Cut menu item if the item appears on an Edit menu that is already open. The mnemonic for a menu item usually appears underlined within the text label for the menu. However, if the letter doesn't appear within the text label or if there is no text label, the user will have no visual clue as to its setting. Letters are specified by the different key constants within the `java.awt.event.KeyEvent` class.

Other platforms might offer other meta-keys for selecting mnemonics. On UNIX, the meta-key is also an Alt key; on a Macintosh, it's the Command key.

Note Adding a `JMenuItem` with a label of “-” doesn't create a menu separator as it did with AWT's `MenuItem`.

JMenuItem Properties

The `JMenuItem` class has many properties. Roughly 100 properties are inherited through its various superclasses. The 10 properties specific to `JMenuItem` are shown in Table 6-3.

Table 6-3. *JMenuItem Properties*

Property Name	Data Type	Access
accelerator	KeyStroke	Read-write bound
accessibleContext	AccessibleContext	Read-only
armed	boolean	Read-write
component	Component	Read-only
enabled	boolean	Write-only bound
menuDragMouseListeners	MenuDragMouseListener[]	Read-only
menuKeyListeners	MenuKeyListener[]	Read-only
subElements	MenuElement[]	Read-only
UI	MenuElementUI	Write-only bound
UIClassID	String	Read-only

One truly interesting property is `accelerator`. As explained in Chapter 2, `KeyStroke` is a factory class that lets you create instances based on key and modifier combinations. For instance, the following statements, from the example in Listing 6-1 earlier in this chapter, associate `Ctrl-X` as the accelerator for one particular menu item:

```
KeyStroke ctrlXKeyStroke=KeyStroke.getKeyStroke("control X");
cutMenuItem.setAccelerator(ctrlXKeyStroke);
```

The read-only `component` and `subElements` properties are part of the `MenuElement` interface, which `JMenuItem` implements. The `component` property is the menu item renderer (the `JMenuItem` itself). The `subElements` property is empty (that is, an empty array, not null), because a `JMenuItem` has no children.

Note Swing menus don't use AWT's `MenuShortcut` class.

Handling JMenuItem Events

You can handle events within a `JMenuItem` in at least five different ways. The component inherits the ability to allow you to listen for the firing of `ChangeEvent` and `ActionEvent` through the `ChangeListener` and `ActionListener` registration methods of `AbstractButton`. In addition, the `JMenuItem` component supports registering `MenuKeyListener` and `MenuDragMouseListener` objects when `MenuKeyEvent` and `MenuDragMouseEvent` events happen. These techniques are discussed in the following sections. A fifth way is to pass an `Action` to the `JMenuItem` constructor, which is like a specialized way of listening with an `ActionListener`. For more on using `Action`, see the discussion of using `Action` objects with menus, in the “`JMenu Class`” section a little later in this chapter.

Listening to JMenuItem Events with a ChangeListener

Normally, you wouldn't register a `ChangeListener` with a `JMenuItem`. However, demonstrating one hypothetical case helps to clarify the data model changes of the `JMenuItem` with respect to its `ButtonModel`. The changes with regard to arming, pressing, and selecting are the same as with a `JButton`. However, their naming might be a little confusing because the selected property of the model is never set.

A `JMenuItem` is *armed* when the mouse passes over the menu choice and it becomes selected. A `JMenuItem` is *pressed* when the user releases the mouse button over it. Immediately after being pressed, the menu item becomes unpressed and unarmed. Between the menu item being pressed and unpressed, the `AbstractButton` is notified of the model changes, causing any registered `ActionListener` objects of the menu item to be notified. The button model for a plain `JMenuItem` never reports being selected. If you move the mouse to another menu item without selecting, the first menu item automatically becomes unarmed. To help you better visualize the different changes, Figure 6-5 shows a sequence diagram.




Figure 6-5. `JMenuItem` selection sequence diagram

Note Subclasses of `JMenuItem` can have their button model selected property set, like a radio button—but the predefined `JMenuItem` cannot.

Listening to JMenuItem Events with an ActionListener

The better listener to attach to a JMenuItem is the ActionListener, or passing an Action to the constructor. It allows you to find out when a menu item is selected. Any registered ActionListener objects would be notified when a user releases the mouse button over a JMenuItem that is part of an open menu. Registered listeners are also notified if the user employs the keyboard (whether with arrow keys or mnemonics) or presses the menu item's keyboard accelerator to make a selection.

You must add an ActionListener to every JMenuItem for which you want an action to happen when selected. There's no automatic shortcut allowing you to register an ActionListener with a JMenu or JMenuBar and have all their contained JMenuItem objects notify a single ActionListener.

The sample program shown in Listing 6-1 associates the same ActionListener with every JMenuItem:

```
class MenuActionListener implements ActionListener {
    public void actionPerformed(ActionEvent e) {
        System.out.println("Selected: " + e.getActionCommand());
    }
}
```

However, more frequently, you would associate a different action with each item, so that each menu item can respond differently.

Tip Instead of creating a custom ActionListener for the component, and adding it as a listener, you can also create a custom Action and call `setAction()` on the component.

Listening to JMenuItem Events with a MenuKeyListener

The MenuKeyEvent is a special kind of KeyEvent used internally by the user interface classes for a JMenu and JMenuItem, allowing the components to listen for when their keyboard mnemonic is pressed. To listen for this keyboard input, each menu component registers a MenuKeyListener to pay attention to the appropriate input. If the keyboard mnemonic is pressed, the event is consumed and not passed to any registered listeners. If the keyboard mnemonic is not pressed, any registered key listeners (instead of menu key listeners) are notified.

The MenuKeyListener interface definition follows:

```
public interface MenuKeyListener extends EventListener {
    public void menuKeyPressed(MenuKeyEvent e);
    public void menuKeyReleased(MenuKeyEvent e);
    public void menuKeyTyped(MenuKeyEvent e);
}
```

Normally, you wouldn't register objects as this type of listener yourself, although you could if you wanted to. If you do, and if a MenuKeyEvent happens (that is, a key is pressed/released), every JMenu on the JMenuBar will be notified, as will every JMenuItem (or subclass) on an open menu with a registered MenuKeyListener. That includes disabled menu items so that they can consume a pressed mnemonic. The definition of the MenuKeyEvent class follows:

```
public class MenuKeyEvent extends KeyEvent {
    public MenuKeyEvent(Component source, int id, long when, int modifiers,
        int keyCode, char keyChar, MenuElement path[], MenuSelectionManager mgr);
    public MenuSelectionManager getMenuSelectionManager();
    public MenuElement[] getPath();
}
```

It's the job of the `MenuSelectionManager` to determine the current selection path. The selection path is the set of menu elements from the top-level `JMenu` on the `JMenuBar` to the selected components. For the most part, the manager works behind the scenes, and you never need to worry about it.

Listening to JMenuItem Events with a MenuDragMouseListener

Like `MenuKeyEvent`, the `MenuDragMouseEvent` is a special kind of event used internally by the user interface classes for `JMenu` and `JMenuItem`. As its name implies, the `MenuDragMouseEvent` is a special kind of `MouseEvent`. By monitoring when a mouse is moved within an open menu, the user interface classes use the listener to maintain the selection path, thus determining the currently selected menu item. Its definition follows:

```
public interface MenuDragMouseListener extends EventListener {
    public void menuDragMouseDragged(MenuDragMouseEvent e);
    public void menuDragMouseEntered(MenuDragMouseEvent e);
    public void menuDragMouseExited(MenuDragMouseEvent e);
    public void menuDragMouseReleased(MenuDragMouseEvent e);
}
```

As with the `MenuKeyListener`, normally you don't listen for this event yourself. If you're interested in when a menu or submenu is about to be displayed, the better listener to register is the `MenuListener`, which can be registered with the `JMenu`, but not with an individual `JMenuItem`. You'll look at this in the next section, which describes `JMenu`.

The definition of the `MenuDragMouseEvent` class, the argument to each of the `MenuDragMouseListener` methods, is as follows:

```
public class MenuDragMouseEvent extends MouseEvent {
    public MenuDragMouseEvent(Component source, int id, long when, int modifiers,
        int x, int y, int clickCount, boolean popupTrigger, MenuElement path[],
        MenuSelectionManager mgr);
    public MenuSelectionManager getMenuSelectionManager();
    public MenuElement[] getPath();
}
```

Customizing a JMenuItem Look and Feel

As with the `JMenuBar`, the predefined look and feel types each provide a different `JMenuItem` appearance and set of default `UIResource` values. Figure 6-3 showed the appearance of the `JMenuItem` component for the preinstalled set: `Motif`, `Windows`, and `Ocean`.

The available set of `UIResource`-related properties for a `JMenuItem` are shown in Table 6-4. The `JMenuItem` component offers 20 different properties.

Table 6-4. *JMenuItem UIResource Elements*

Property String	Object Type
MenuItem.acceleratorDelimiter	String
MenuItem.acceleratorFont	Font
MenuItem.acceleratorForeground	Color
MenuItem.acceleratorSelectionForeground	Color
MenuItem.actionMap	ActionMap
MenuItem.arrowIcon	Icon
MenuItem.background	Color
MenuItem.border	Border
MenuItem.borderPainted	Boolean
MenuItem.checkIcon	Icon
MenuItem.commandSound	String
MenuItem.disabledForeground	Color
MenuItem.font	Font
MenuItem.foreground	Color
MenuItem.margin	Insets
MenuItem.opaque	Boolean
MenuItem.selectionBackground	Color
MenuItem.selectionForeground	Color
MenuItem.textIconGap	Integer
MenuItemUI	String

JMenu Class

The JMenu component is the basic menu item container that is placed on a JMenuBar. When a JMenu is selected, the menu displays the contained menu items within a JPopupMenu. As with JMenuItem, the data model for the JMenu is an implementation of ButtonModel, or more specifically, DefaultButtonModel.

Creating JMenu Components

Four constructors for JMenu allow you to initialize the string label of the menu if desired:

```
public JMenu()  
JMenu jMenu = new JMenu();  
  
public JMenu(String label)  
JMenu jMenu = new JMenu("File");  
  
public JMenu(String label, boolean useTearOffs)  
  
public JMenu(Action action)  
Action action = ...;  
JMenu jMenu = new JMenu(action);
```

One constructor is for using a tear-off menu. However, tear-off menus aren't currently supported; therefore, the argument is ignored. The fourth constructor pulls the properties of the menu from an Action.

Note Tear-off menus are menus that appear in a window and remain open after selection, instead of automatically closing.

Adding Menu Items to a JMenu

Once you have a JMenu, you need to add JMenuItem objects to it; otherwise, the menu will not display any choices. There are five methods for adding menu items defined within JMenu and one for adding a separator:

```
public JMenuItem add(JMenuItem menuItem);  
public JMenuItem add(String label);  
public Component add(Component component);  
public Component add(Component component, int index);  
public JMenuItem add(Action action);  
public void addSeparator();
```

In Listing 6-1 earlier in this chapter, all the JMenuItem components were added to JMenu components with the first add() method. As a shortcut, you can pass the text label for a JMenuItem to the add() method of JMenu. This will create the menu item, set its label, and pass back the new menu item component. You can then bind a menu item event handler to this newly obtained menu item. The third add() method shows that you can place any Component on a JMenu, not solely a JMenuItem. The fourth add() lets you position the component. The last add() variety, with the Action argument, will be discussed in the next section of this chapter.

You can add separator bars with the addSeparator() method of JMenu. For instance, in Listing 6-1, the File menu was created with code similar to the following:

```

JMenu fileMenu = new JMenu("File");
JMenuItem newMenuItem = new JMenuItem("New");
fileMenu.add(newMenuItem);
JMenuItem openMenuItem = new JMenuItem("Open");
fileMenu.add(openMenuItem);
JMenuItem closeMenuItem = new JMenuItem("Close");
fileMenu.add(closeMenuItem);
fileMenu.addSeparator();
JMenuItem saveMenuItem = new JMenuItem("Save");
fileMenu.add(saveMenuItem);
fileMenu.addSeparator();
JMenuItem exitMenuItem = new JMenuItem("Exit");
fileMenu.add(exitMenuItem);

```

Notice the `addSeparator()` calls wrapped around the call to add the Save menu item.

In addition to adding menu items at the end of a menu, you can insert them at specific positions or insert a separator at a specific position, as follows:

```

public JMenuItem insert(JMenuItem menuItem, int pos);
public JMenuItem insert(Action a, int pos);
public void insertSeparator(int pos);

```

When a menu item is added to a `JMenu`, it's added to an internal `JPopupMenu`.

Using Action Objects with Menus

The `Action` interface and its associated classes are described in Chapter 2. An `Action` is an extension of the `ActionListener` interface and contains some special properties for customizing components associated with its implementations.

With the help of the `AbstractAction` implementation, you can easily define text labels, icons, mnemonics, tooltip text, enabled status, and an `ActionListener` apart from a component. Then you can create a component with an associated `Action` and not need to give the component a text label, icon, mnemonics, tooltip text, enabled status, or `ActionListener`, because those attributes would come from the `Action`. For a more complete description, refer to Chapter 2.

To demonstrate, Listing 6-2 creates a specific implementation of `AbstractAction` and adds it to a `JMenu` multiple times. Once the `Action` is added to a `JMenu`, selecting the `JMenuItem` will display a pop-up dialog box with the help of the `JOptionPane` class, a topic covered in Chapter 9.

Listing 6-2. *About Action Definition*

```

import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
public class ShowAction extends AbstractAction {
    Component parentComponent;
    public ShowAction(Component parentComponent) {
        super("About");
        putValue(Action.MNEMONIC_KEY, new Integer(KeyEvent.VK_A));
        this.parentComponent = parentComponent;
    }
}

```

```

public void actionPerformed(ActionEvent actionEvent) {
    Runnable runnable = new Runnable() {
        public void run() {
            JOptionPane.showMessageDialog(
                parentComponent, "About Swing",
                "About Box V2.0", JOptionPane.INFORMATION_MESSAGE);
        }
    };
    EventQueue.invokeLater(runnable);
}
}

```

The next source creates a `ShowAction` and a `JMenuItem` for the File and Edit menus in the sample program (Listing 6-1). Without explicitly setting the menu item properties, it will then have an “About” text label and an A mnemonic, and will perform the defined `actionPerformed()` method as its `ActionListener`. In fact, you can create the Action once, and then associate it with as many places as necessary (or other components that support adding Action objects).

```

Action showAction = new ShowAction(aComponent);
JMenuItem fileAbout = new JMenuItem(showAction);
fileMenu.add(fileAbout);
JMenuItem editAbout = new JMenuItem(showAction);
editMenu.add(editAbout);

```

One complexity-busting side effect when using `AbstractAction` is that it lets you disable the Action with `setEnabled(false)`, which, in turn, will disable all components created from it.

JMenu Properties

Besides the 100-plus inherited properties of `JMenu`, 16 properties are available from `JMenu`-specific methods, as shown in Table 6-5. Several of the properties override the behavior of the inherited properties. For instance, the setter method for the `accelerator` property throws an error if you try to assign such a property. In other words, accelerators aren’t supported within `JMenu` objects. The remaining properties describe the current state of the `JMenu` object and its contained menu components.

Table 6-5. *JMenu Properties*

Property Name	Data Type	Access
<code>accelerator</code>	<code>KeyStroke</code>	Write-only
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>component</code>	<code>Component</code>	Read-only
<code>delay</code>	<code>int</code>	Read-write
<code>itemCount</code>	<code>int</code>	Read-only
<code>menuComponentCount</code>	<code>int</code>	Read-only
<code>menuComponents</code>	<code>Component[]</code>	Read-only

Table 6-5. *JMenu Properties (Continued)*

Property Name	Data Type	Access
menuListeners	MenuListener[]	Read-only
model	ButtonModel	Write-only bound
popupMenu	JPopupMenu	Read-only
popupMenuVisible	boolean	Read-write
selected	boolean	Read-write
subElements	MenuElement[]	Read-only
tearOff	boolean	Read-only
topLevelMenu	boolean	Read-only
UIClassID	String	Read-only

Tip Keep in mind that many property methods are inherited and that the parent class might offer a getter method where the current class defines only a new setter method, or vice versa.

The delay property represents the value for the time that elapses between selection of a JMenu and posting of the JPopupMenu. By default, this value is zero, meaning that the submenu will appear immediately. Trying to set the value to a negative setting will throw an IllegalArgumentException.

Caution Since there is no support for tear-off menus, if you try to access the `tearOff` property, an error will be thrown.

Selecting Menu Components

Normally, you don't need to listen for the selection of JMenu components. You listen for only selection of individual JMenuItem components. Nevertheless, you may be interested in the different ways that ChangeEvent works with a JMenu as compared with a JMenuItem. In addition, a MenuEvent can notify you whenever a menu is posted or canceled.

Listening to JMenu Events with a ChangeListener

As with a JMenuItem, you can register a ChangeListener with a JMenu if you're interested in making changes to the underlying ButtonModel. Surprisingly, the only possible state change to the ButtonModel with a JMenu is with the selected property. When selected, the JMenu displays its menu items. When not selected, the pop-up goes away.

Listening to JMenu Events with a MenuListener

The better way to listen for when a pop-up is displayed or hidden is by registering MenuListener objects with your JMenu objects. Its definition follows:

```
public interface MenuListener extends EventListener {
    public void menuCanceled(MenuEvent e);
    public void menuDeselected(MenuEvent e);
    public void menuSelected(MenuEvent e);
}
```

With a registered MenuListener, you're notified when a JMenu is selected before the pop-up menu is opened with the menu's choices. This allows you to customize its menu choices on the fly at runtime, with some potential interaction performance penalties. Besides being told when the associated pop-up menu is to be posted, you're also notified when the menu has been deselected and when the menu has been canceled. As the following MenuEvent class definition shows, the only piece of information that comes with the event is the source (the menu):

```
public class MenuEvent extends EventObject {
    public MenuEvent(Object source);
}
```

Tip If you choose to customize the items on a JMenu dynamically, be sure to call `revalidate()`, because the component waits until you are done before updating the display.

Customizing a JMenu Look and Feel

As with the JMenuBar and JMenuItem, the predefined look and feel classes provide a different JMenu appearance and set of default UIResource values. Figure 6-3 shows the appearance of the JMenu object for the preinstalled set of look and feel types.

The available set of UIResource-related properties for a JMenu is shown in Table 6-6. For the JMenu component, there are 30 different properties.

Table 6-6. *JMenu UIResource Elements*

Property String	Object Type
menu	Color
Menu.acceleratorDelimiter	String
Menu.acceleratorFont	Font
Menu.acceleratorForeground	Color
Menu.acceleratorSelectionForeground	Color
Menu.ActionMap	ActionMap
Menu.arrowIcon	Icon
Menu.background	Color
Menu.border	Border
Menu.borderPainted	Boolean
Menu.checkIcon	Icon
Menu.delay	Integer
Menu.disabledForeground	Color
Menu.font	Font
Menu.foreground	Color
Menu.margin	Insets
Menu.menuPopupOffsetX	Integer
Menu.menuPopupOffsetY	Integer
Menu.opaque	Boolean
Menu.selectionBackground	Color
Menu.selectionForeground	Color
Menu.shortcutKeys	int[]
Menu.submenuPopupOffsetX	Integer
Menu.submenuPopupOffsetY	Integer
Menu.textIconGap	Integer
Menu.useMenuBarBackgroundForTopLevel	Boolean
menuPressedItemB	Color
menuPressedItemF	Color
menuText	Color
MenuUI	String

JSeparator Class

The `JSeparator` class is a special component that acts as a separator on a `JMenu`. The `JPopupMenu` and `JToolBar` classes also support separators, but each uses its own subclass of `JSeparator`. In addition to being placed on a menu, the `JSeparator` can be used anywhere you want to use a horizontal or vertical line to separate different areas of a screen.

The `JSeparator` is strictly a visual component; therefore, it has no data model.

Creating JSeparator Components

To create a separator for a `JMenu`, you don't directly create a `JSeparator`, although you can. Instead, you call the `addSeparator()` method of `JMenu`, and the menu will create the separator and add the separator as its next item. The fact that it's a `JSeparator` (which isn't a `JMenuItem` subclass) is hidden. There's also an `insertSeparator(int index)` method of `JMenu` that allows you to add a separator at a specific position on the menu, that isn't necessarily the next slot.

If you plan to use a `JSeparator` away from a menu (for example, to visually separate two panels in a layout), you should use one of the two constructors for `JSeparator`:

```
public JSeparator()
```

```
JSeparator jSeparator = new JSeparator();
```

```
public JSeparator(int orientation)
```

```
JSeparator jSeparator = new JSeparator(JSeparator.VERTICAL);
```

These constructors allow you to create a horizontal or vertical separator. If an orientation isn't specified, the orientation is horizontal. If you want to explicitly specify an orientation, you use either of the `JSeparator` constants of `HORIZONTAL` and `VERTICAL`.

JSeparator Properties

After you have a `JSeparator`, you add it to the screen like any other component. The initial dimensions of the component are empty (zero width and height), so if the layout manager of the screen asks the component what size it would like to be, the separator will reply that it needs no space. On the other hand, if the layout manager offers a certain amount of space, the separator will use the space if the orientation is appropriate. For instance, adding a horizontal `JSeparator` to the north side of a `BorderLayout` panel draws a separator line across the screen. However, adding a horizontal `JSeparator` to the east side of the same panel would result in nothing being drawn. For a vertical `JSeparator`, the behavior is reversed: The north side would be empty and a vertical line would appear on the east side.

The four properties of `JSeparator` are listed in Table 6-7.

Table 6-7. *JSeparator Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>orientation</code>	<code>int</code>	Read-write bound
<code>UI</code>	<code>SeparatorUI</code>	Read-write bound
<code>UIClassID</code>	<code>String</code>	Read-only

Caution If the orientation property isn't set to a value equivalent to either `JSeparator.HORIZONTAL` or `JSeparator.VERTICAL`, an `IllegalArgumentException` is thrown.

Customizing a JSeparator Look and Feel

The appearance of the `JSeparator` under the preinstalled set of look and feel types is shown with the other menu components in Figure 6-3.

The available set of `UIResource`-related properties for a `JSeparator` is shown in Table 6-8. For the `JSeparator` component, five different properties are available.

Table 6-8. *JSeparator UIResource Elements*

Property String	Object Type
<code>Separator.background</code>	<code>Color</code>
<code>Separator.foreground</code>	<code>Color</code>
<code>Separator.insets</code>	<code>Insets</code>
<code>Separator.thickness</code>	<code>Integer</code>
<code>SeparatorUI</code>	<code>String</code>

Caution Two additional properties, `highlight` and `shadow`, are present but deprecated and should not be used.

JPopupMenu Class

The `JPopupMenu` component is the container for pop-up menu components, displayable anywhere and used for support by `JMenu`. When a programmer-defined triggering event happens, you display the `JPopupMenu`, and the menu displays the contained menu components. Like `JMenuBar`, `JPopupMenu` uses the `SingleSelectionModel` to manage the currently selected element.

Creating JPopupMenu Components

There are two constructors for `JPopupMenu`:

```
public JPopupMenu()  
JPopupMenu jPopupMenu = new JPopupMenu();  
  
public JPopupMenu(String title)  
JPopupMenu jPopupMenu = new JPopupMenu("Welcome");
```

Only one allows you to initialize the title for the menu, if desired. What happens with the title depends on the installed look and feel. The currently installed look and feel may ignore the title.

Adding Menu Items to a JPopupMenu

As with a JMenu, once you have a JPopupMenu, you need to add menu item objects to it; otherwise, the menu will be empty. There are three JPopupMenu methods for adding menu items and one for adding a separator:

```
public JMenuItem add(JMenuItem menuItem);
public JMenuItem add(String label);
public JMenuItem add(Action action);
public void addSeparator();
```

In addition, an add() method is inherited from Container for adding regular AWT components:

```
public Component add(Component component);
```

Note It generally isn't wise to mix lightweight Swing components with heavyweight AWT components. However, because pop-up menus are more apt to be on top, it's less of an issue in this case.

The natural way of adding menu items is with the first add() method. You create the menu item independently of the pop-up menu, including defining its behavior, and then you attach it to the menu. With the second variety of add(), you must attach an event handler to the menu item returned from the method; otherwise, the menu choice won't respond when selected. The following source demonstrates the two approaches. Which you use depends entirely on your preference. A visual programming environment like JBuilder will use the first. Because the first approach is inherently less complex, most, if not all, programmers should also use the first approach.

```
JPopupMenu popupMenu = new JPopupMenu();
ActionListener anActionListener = ...;
// The first way
JMenuItem firstItem = new JMenuItem("Hello");
firstItem.addActionListener(anActionListener);
popupMenu.add(firstItem);
// The second way
JMenuItem secondItem = popupMenu.add("World");
secondItem.addActionListener(anActionListener);
```

Using an Action to create a menu item works the same with JPopupMenu as it does with JMenu. However, according to the Javadoc for the JPopupMenu class, using the Action variety of the add() method is discouraged. Instead, pass the Action to the constructor for JMenuItem, or

configure it with `setAction()`, and then add that to the `JPopupMenu`. Why the method isn't just deprecated isn't clear.

Lastly, you can add a menu separator with the `addSeparator()` method.

As well as adding menu items at the end of a menu, you can insert them at specific positions or insert a separator at a specific position:

```
public JMenuItem insert(Component component, int position);  
public JMenuItem insert(Action action, int position);
```

There's no `insertSeparator()` method as there is with `JMenu`. But you can use the `add(Component component, int position)` method inherited from `Container`. If you want to remove components, use the `remove(Component component)` method specific to `JPopupMenu`.

Note Accelerators on attached `JMenuItem` objects are ignored. Mnemonics might also be ignored depending on the currently installed look and feel.

Displaying the JPopupMenu

Unlike the `JMenu`, simply populating the pop-up menu isn't sufficient to use it. You need to associate the pop-up menu with an appropriate component. Prior to the 5.0 release of Swing, you needed to add event-handling code to trigger the display of the pop-up menu. Now, all you need to do is call the `setComponentPopupMenu()` method for the Swing component you wish to associate the pop-up menu with. When the platform-specific triggering event happens, the pop-up menu is automatically displayed.

Note Why change the way pop-up menu display is triggered? The old code was very tightly tied to mouse events. It didn't connect well with the accessibility framework. And the same code was being added everywhere to just show the pop-up menu at the x, y coordinates of the invoker.

You simply need to create an instance of `JPopupMenu` and attach it to any component you want to have display the pop-up menu, as follows:

```
JPopupMenu popupMenu = ...;  
aComponent.setComponentPopupMenu(popupMenu);
```

The methods of `JComponent` that are important to pop-up menus are `getComponentPopupMenu()`, `setComponentPopupMenu()`, `getInheritsPopupMenu()`, `setInheritsPopupMenu()`, and `getPopupLocation()`. The `setInheritsPopupMenu()` method accepts a boolean argument. When true, and no component pop-up menu has been directly set for the component, the parent container will be explored for a pop-up.

JPopupMenu Properties

The 16 properties of JPopupMenu are listed in Table 6-9. Many more properties are also inherited through JComponent, Container, and Component.

Table 6-9. *JPopupMenu Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
borderPainted	boolean	Read-write
component	Component	Read-only
invoker	Component	Read-only
label	String	Read-write bound
lightWeightPopupEnabled	boolean	Read-write
margin	Insets	Read-only
menuKeyListeners	MenuKeyListener[]	Read-only
popupMenuListeners	PopupMenuListener[]	Read-only
popupSize	Dimension	Write-only
selected	Component	Write-only
selectionModel	SingleSelectionModel	Read-write
subElements	MenuElement[]	Read-only
UI	PopupMenuUI	Read-write bound
UIClassID	String	Read-only
visible	boolean	Read-write

The most interesting property of JPopupMenu is `lightWeightPopupEnabled`. Normally, the JPopupMenu tries to avoid creating new heavyweight components for displaying its menu items. Instead, the pop-up menu uses a JPanel when the JPopupMenu can be displayed completely within the outermost window boundaries. Otherwise, if the menu items don't fit, the JPopupMenu uses a JWindow. If, however, you're mixing lightweight and heavyweight components on different window layers, displaying the pop-up within a JPanel might not work, because a heavyweight component displayed in the layer of the menu will appear in front of the JPanel. To correct this behavior, the pop-up menu can use a Panel for displaying the menu choices. By default, the JPopupMenu never uses a Panel.

Note When the `JPopupMenu` is displayed in either a `JPanel` or a `Panel`, the outermost window relies on the layering effect of the `JRootPane` to ensure that the pop-up panel is displayed at the appropriate position in front of the other components. Chapter 8 describes the `JRootPane` class in more detail.

If you need to enable the display of a `Panel`, you can configure it at the individual `JPopupMenu` level or for your entire applet or application. At the individual pop-up level, just set the `lightWeightPopupEnabled` property to `false`. At the system level, this is done as follows:

```
// From now on, all JPopupMenu's will be heavyweight
JPopupMenu.setDefaultLightWeightPopupEnabled(false);
```

The method must be called before creating the pop-up menu. `JPopupMenu` objects created before the change will have the original value (the default is `true`).

Watching for Pop-Up Menu Visibility

Like the `JMenu`, the `JPopupMenu` has a special event/listener combination to watch for when the pop-up menu is about to become visible, invisible, or canceled. The event is `PopupMenuEvent`, and the listener is `PopupMenuListener`. The event class simply references the source pop-up menu of the event.

```
public class PopupMenuEvent extends EventObject {
    public PopupMenuEvent(Object source);
}
```

When a `JPopupMenu` fires the event, any registered `PopupMenuListener` objects are notified through one of its three interface methods. This lets you customize the current menu items based on the system state or who/what the pop-up menu invoker happens to be. The `PopupMenuListener` interface definition follows:

```
public interface PopupMenuListener extends EventListener {
    public void popupMenuCanceled(PopupMenuEvent e);
    public void popupMenuWillBecomeInvisible(PopupMenuEvent e);
    public void popupMenuWillBecomeVisible(PopupMenuEvent e);
}
```

Customizing a JPopupMenu Look and Feel

Each installable Swing look and feel provides a different `JPopupMenu` appearance and set of default `UIResource` values. Figure 6-6 shows the appearance of the `JPopupMenu` component for the preinstalled set of look and feel types: Motif, Windows, and Ocean. Notice that of the predefined look and feel classes, only Motif uses the `title` property of the `JPopupMenu`.




Figure 6-6. *JPopupMenu* under different look and feel types

The available set of `UIResource`-related properties for a `JPopupMenu` is shown in Table 6-10. For the `JPopupMenu` component, there are five different properties.

Table 6-10. *JPopupMenu* `UIResource` Elements

Property String	Object Type
<code>PopupMenu.actionMap</code>	<code>ActionMap</code>
<code>PopupMenu.background</code>	<code>Color</code>
<code>PopupMenu.border</code>	<code>Border</code>
<code>PopupMenu.consumeEventOnClose</code>	<code>Boolean</code>
<code>PopupMenu.font</code>	<code>Font</code>
<code>PopupMenu.foreground</code>	<code>Color</code>
<code>PopupMenu.popupSound</code>	<code>String</code>
<code>PopupMenu.selectedWindowInputMapBindings</code>	<code>Object[]</code>
<code>PopupMenu.selectedWindowInputMapBindings.RightToLeft</code>	<code>Object[]</code>
<code>PopupMenuSeparatorUI</code>	<code>String</code>
<code>PopupMenuUI</code>	<code>String</code>

JPopupMenu.Separator Class

The JPopupMenu class maintains its own separator to permit a custom look and feel for the separator when it's on a JPopupMenu. This custom separator is an inner class to the JPopupMenu.

When you call the `addSeparator()` of JPopupMenu, an instance of this class is automatically created and added to the pop-up menu. In addition, you can create this separator by calling its no-argument constructor:

```
JSeparator popupSeparator = new JPopupMenu.Separator();
```

Both methods create a horizontal separator.

Note If you want to change the orientation of the separator, you must call the `setOrientation()` method inherited from JSeparator with an argument of `JPopupMenu.Separator.VERTICAL`. However, having a vertical separator on a pop-up menu is inappropriate.

A Complete Pop-Up Menu Usage Example

The program in Listing 6-3 puts together all the pieces of using a JPopupMenu, including listening for selection of all the items on the menu, as well as listening for when it's displayed. The output for the program is shown in Figure 6-7, with the pop-up visible.




Figure 6-7. JPopupMenu usage example output

Listing 6-3. PopupSample Class Definition

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import javax.swing.event.*;

public class PopupSample {
```

```
// Define ActionListener
static class PopupActionListener implements ActionListener {
    public void actionPerformed(ActionEvent actionEvent) {
        System.out.println("Selected: " + actionEvent.getActionCommand());
    }
}

// Define PopupMenuListener
static class MyPopupMenuListener implements PopupMenuListener {
    public void popupMenuCanceled(PopupMenuEvent popupMenuEvent) {
        System.out.println("Canceled");
    }
    public void popupMenuWillBecomeInvisible(PopupMenuEvent popupMenuEvent) {
        System.out.println("Becoming Invisible");
    }
    public void popupMenuWillBecomeVisible(PopupMenuEvent popupMenuEvent) {
        System.out.println("Becoming Visible");
    }
}

public static void main(final String args[]) {
    Runnable runner = new Runnable() {
        public void run() {
            // Create frame
            JFrame frame = new JFrame("PopupSample Example");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

            ActionListener actionListener = new PopupActionListener();
            PopupMenuListener popupMenuListener = new MyPopupMenuListener();

            // Create popup menu, attach popup menu listener
            JPopupMenu popupMenu = new JPopupMenu("Title");
            popupMenu.addPopupMenuListener(popupMenuListener);

            // Cut
            JMenuItem cutMenuItem = new JMenuItem("Cut");
            cutMenuItem.addActionListener(actionListener);
            popupMenu.add(cutMenuItem);

            // Copy
            JMenuItem copyMenuItem = new JMenuItem("Copy");
            copyMenuItem.addActionListener(actionListener);
            popupMenu.add(copyMenuItem);
        }
    };
    new Thread(runner).start();
}
```

```

        // Paste
        JMenuItem pasteMenuItem = new JMenuItem("Paste");
        pasteMenuItem.addActionListener(actionListener);
        pasteMenuItem.setEnabled(false);
        popupMenu.add(pasteMenuItem);

        // Separator
        popupMenu.addSeparator();

        // Find
        JMenuItem findMenuItem = new JMenuItem("Find");
        findMenuItem.addActionListener(actionListener);
        popupMenu.add(findMenuItem);
        JButton label = new JButton();
        frame.add(label);
        label.setComponentPopupMenu(popupMenu);

        frame.setSize(350, 250);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

JCheckBoxMenuItem Class

Swing's `JCheckBoxMenuItem` component behaves as if you have a `JCheckBox` on a menu as a `JMenuItem`. The data model for the menu item is the `ToggleButtonModel`, described in Chapter 5. It allows the menu item to have a selected or unselected state, while showing an appropriate icon for the state. Because the data model is the `ToggleButtonModel`, when `JCheckBoxMenuItem` is placed in a `ButtonGroup`, only one component in the group is ever selected. However, this isn't the natural way to use a `JCheckBoxMenuItem` and is likely to confuse users. If you need this behavior, use `JRadioButtonMenuItem`, as described later in this chapter.

Creating JCheckBoxMenuItem Components

There are seven constructors for `JCheckBoxMenuItem`. They allow you to initialize the text label, icon, and initial state.

```
public JCheckBoxMenuItem()
```

```
JCheckBoxMenuItem jMenuItem = new JCheckBoxMenuItem();
```

```
public JCheckBoxMenuItem(String text)
```

```
JCheckBoxMenuItem jMenuItem = new JCheckBoxMenuItem("Boy");
```

```

public JCheckBoxMenuItem(Icon icon)
Icon boyIcon = new ImageIcon("boy-r.jpg");
JCheckBoxMenuItem jCheckBoxMenuItem = new JCheckBoxMenuItem(boyIcon);

public JCheckBoxMenuItem(String text, Icon icon)
JCheckBoxMenuItem jCheckBoxMenuItem = new JCheckBoxMenuItem("Boy", boyIcon);

public JCheckBoxMenuItem(String text, boolean state)
JCheckBoxMenuItem jCheckBoxMenuItem = new JCheckBoxMenuItem("Girl", true);

public JCheckBoxMenuItem(String text, Icon icon, boolean state)
Icon girlIcon = new ImageIcon("girl-r.jpg");
JCheckBoxMenuItem jCheckBoxMenuItem = new JCheckBoxMenuItem("Girl", girlIcon, true);

public JCheckBoxMenuItem(Action action)
Action action = ...;
JCheckBoxMenuItem jCheckBoxMenuItem = new JCheckBoxMenuItem(action);

```

Unlike the `JCheckBox`, the icon is part of the label and not a separate device to indicate whether something is checked. If either the text label or the icon isn't passed to the constructor, that part of the item label will be set to its default value of empty. By default, a `JCheckBoxMenuItem` is unselected.

Note Creating a `JCheckBoxMenuItem` with an icon has no effect on the appearance of the check box next to the menu item. It's strictly part of the label for the `JCheckBoxMenuItem`.

JCheckBoxMenuItem Properties

Most of the `JCheckBoxMenuItem` properties are inherited from the many superclasses of `JCheckBoxMenuItem`. Table 6-11 lists the four properties defined by `JCheckBoxMenuItem`.

Table 6-11. *JCheckBoxMenuItem Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>selectedObjects</code>	<code>Object[]</code>	Read-only
<code>state</code>	<code>boolean</code>	Read-write
<code>UIClassID</code>	<code>String</code>	Read-only

Handling JCheckBoxMenuItem Selection Events

With a JCheckBoxMenuItem, you can attach many different listeners for a great variety of events:

- MenuDragMouseListener and MenuKeyListener from JMenuItem
- ActionListener, ChangeListener, and ItemListener from AbstractButton
- AncestorListener and VetoableChangeListener from JComponent
- ContainerListener and PropertyChangeListener from Container
- ComponentListener, FocusListener, HierarchyBoundsListener, HierarchyListener, InputMethodListener, KeyListener, MouseListener, MouseMotionListener, and MouseWheelListener from Component

Although you can listen for 18 different types of events, the most interesting are ActionEvent and ItemEvent, described next.

Listening to JCheckBoxMenuItem Events with an ActionListener

Attaching an ActionListener to a JCheckBoxMenuItem allows you to find out when the menu item is selected. The listener is told of the selection, but not of the new state. To find out the selected state, you must get the model for the event source and query the selection state, as the following sample ActionListener source shows. This listener modifies both the check box text and the icon label, based on the current selection state.

```
ActionListener alistener = new ActionListener() {
    public void actionPerformed(ActionEvent event) {
        Icon girlIcon = new ImageIcon("girl-r.jpg");
        Icon boyIcon = new ImageIcon("boy-r.jpg");
        AbstractButton aButton = (AbstractButton)event.getSource();
        boolean selected = aButton.getModel().isSelected();
        String newLabel;
        Icon newIcon;
        if (selected) {
            newLabel = "Girl";
            newIcon = girlIcon;
        } else {
            newLabel = "Boy";
            newIcon = boyIcon;
        }
        aButton.setText(newLabel);
        aButton.setIcon(newIcon);
    }
};
```

Note Keep in mind that you can also associate an Action from the constructor that can do the same thing.

Listening to JCheckBoxMenuItem with an ItemListener

If you listen for JCheckBoxMenuItem selection with an ItemListener, you don't need to query the event source for the selection state—the event already carries that information. Based on this state, you respond accordingly. Re-creating the ActionListener behavior with an ItemListener requires just a few minor changes to the previously listed source, as follows:

```
ItemListener ilistener = new ItemListener() {
    public void itemStateChanged(ItemEvent event) {
        Icon girlIcon = new ImageIcon("girl-r.jpg");
        Icon boyIcon = new ImageIcon("boy-r.jpg");
        AbstractButton aButton = (AbstractButton)event.getSource();
        int state = event.getStateChange();
        String newLabel;
        Icon newIcon;
        if (state == ItemEvent.SELECTED) {
            newLabel = "Girl";
            newIcon = girlIcon;
        } else {
            newLabel = "Boy";
            newIcon = boyIcon;
        }
        aButton.setText(newLabel);
        aButton.setIcon(newIcon);
    }
};
```

Customizing a JCheckBoxMenuItem Look and Feel

The appearance of the JCheckBoxMenuItem under the preinstalled set of look and feel types is shown with the other menu components in Figure 6-3.

The available set of UIResource-related properties for a JCheckBoxMenuItem is shown in Table 6-12. The JCheckBoxMenuItem component has 19 different properties.

Table 6-12. *JCheckBoxMenuItem UIResource Elements*

Property String	Object Type
CheckBoxMenuItem.acceleratorFont	Font
CheckBoxMenuItem.acceleratorForeground	Color
CheckBoxMenuItem.acceleratorSelectionForeground	Color
CheckBoxMenuItem.actionMap	ActionMap
CheckBoxMenuItem.arrowIcon	Icon
CheckBoxMenuItem.background	Color
CheckBoxMenuItem.border	Border
CheckBoxMenuItem.borderPainted	Boolean

Table 6-12. *JCheckBoxMenuItem UIResource Elements (Continued)*

Property String	Object Type
CheckBoxMenuItem.checkIcon	Icon
CheckBoxMenuItem.commandSound	String
CheckBoxMenuItem.disabledForeground	Color
CheckBoxMenuItem.font	Font
CheckBoxMenuItem.foreground	Color
CheckBoxMenuItem.gradient	List
CheckBoxMenuItem.margin	Insets
CheckBoxMenuItem.opaque	Boolean
CheckBoxMenuItem.selectionBackground	Color
CheckBoxMenuItem.selectionForeground	Color
CheckBoxMenuItemUI	String

The Icon associated with the `CheckBoxMenuItem.checkIcon` property key is the one displayed on the `JCheckBoxMenuItem`. If you don't like the default icon, you can change it with the following line of source, assuming the new icon has already been defined and created:

```
UIManager.put("CheckBoxMenuItem.checkIcon", someIcon);
```

For this new icon to display an appropriate selected image, the Icon implementation must check the state of the associated menu component within its `paintIcon()` method. The `DiamondIcon` created in Chapter 4 wouldn't work for this icon because it doesn't ask the component for its state. Instead, the state is fixed at constructor time. Listing 6-4 shows a class that represents one icon that could be used.

Listing 6-4. *State-Aware Icon Definition*

```
import java.awt.*;
import javax.swing.*;

public class DiamondAbstractButtonStateIcon implements Icon {
    private final int width = 10;
    private final int height = 10;
    private Color color;
    private Polygon polygon;
    public DiamondAbstractButtonStateIcon(Color color) {
        this.color = color;
        initPolygon();
    }
}
```

```

private void initPolygon() {
    polygon = new Polygon();
    int halfWidth = width/2;
    int halfHeight = height/2;
    polygon.addPoint (0, halfHeight);
    polygon.addPoint (halfWidth, 0);
    polygon.addPoint (width, halfHeight);
    polygon.addPoint (halfWidth, height);
}
public int getIconHeight() {
    return width;
}
public int getIconWidth() {
    return height;
}
public void paintIcon(Component component, Graphics g, int x, int y) {
    boolean selected = false;
    g.setColor (color);
    g.translate (x, y);
    if (component instanceof AbstractButton) {
        AbstractButton abstractButton = (AbstractButton)component;
        selected = abstractButton.isSelected();
    }
    if (selected) {
        g.fillPolygon (polygon);
    } else {
        g.drawPolygon (polygon);
    }
    g.translate (-x, -y);
}
}

```

Note If the `DiamondAbstractButtonStateIcon` icon were used with a component that isn't an `AbstractButton` type, the icon would always be deselected, because the selection state is a property of `AbstractButton`.

JRadioButtonMenuItem Class

The `JRadioButtonMenuItem` component has the longest name of all the Swing components. It works like a `JRadioButton`, but resides on a menu. When placed with other `JRadioButtonMenuItem` components within a `ButtonGroup`, only one component will be selected at a time. As with the `JRadioButton`, the button model for the `JRadioButtonMenuItem` is the `JToggleButton.ToggleButtonModel`.

Creating JRadioButtonMenuItem Components

The `JRadioButtonMenuItem` has seven constructors. They allow you to initialize the text label, icon, and initial state.

```
public JCheckBoxMenuItem()  
JCheckBoxMenuItem jCheckBoxMenuItem = new JCheckBoxMenuItem();  
  
public JCheckBoxMenuItem(String text)  
JCheckBoxMenuItem jCheckBoxMenuItem = new JCheckBoxMenuItem("Boy");  
  
public JCheckBoxMenuItem(Icon icon)  
Icon boyIcon = new ImageIcon("boy-r.jpg");  
JCheckBoxMenuItem jCheckBoxMenuItem = new JCheckBoxMenuItem(boyIcon);  
  
public JCheckBoxMenuItem(String text, Icon icon)  
JCheckBoxMenuItem jCheckBoxMenuItem = new JCheckBoxMenuItem("Boy", boyIcon);  
  
public JCheckBoxMenuItem(String text, boolean state)  
JCheckBoxMenuItem jCheckBoxMenuItem = new JCheckBoxMenuItem("Girl", true);  
  
public JCheckBoxMenuItem(String text, Icon icon, boolean state)  
Icon girlIcon = new ImageIcon("girl-r.jpg");  
JCheckBoxMenuItem jCheckBoxMenuItem = new JCheckBoxMenuItem("Girl", girlIcon, true);  
  
public JCheckBoxMenuItem(Action action)  
Action action = ...;  
JCheckBoxMenuItem jCheckBoxMenuItem = new JCheckBoxMenuItem(action);
```

Similar to the `JCheckBoxMenuItem` component, the icon for the `JRadioButtonMenuItem` is part of the label. This is unlike the `JRadioButton`, in which the icon indicates whether the radio button is selected. If either the text label or icon isn't part of the constructor, that part of the item label will be empty. By default, a `JRadioButtonMenuItem` is unselected. If you create a `JRadioButtonMenuItem` that is selected and then add it to a `ButtonGroup`, the button group will deselect the menu item if the group already has a selected item in the group.

Note After creating `JRadioButtonMenuItem` instances, remember to add them to a `ButtonGroup`, so they will work as a mutually exclusive group.

Handling JRadioButtonMenuItem Selection Events

The `JRadioButtonMenuItem` shares the same 18 different event/listener pairs with `JCheckBoxMenuItem`. To listen for selection, attaching an `ActionListener` is the normal approach. In addition, you might want to attach the same listener to all the `JRadioButtonMenuItem` objects in a `ButtonGroup`—after all, they're in a group for a reason. If you use the same listener, that listener can employ the current selection to perform some common operation. In other cases, such as that in Figure 6-1, selection of any `JRadioButtonMenuItem` option does nothing.

Only when someone selects the Find menu element would the current selection of the `ButtonGroup` for the set of `JRadioButtonMenuItem` components have any meaning.

Configuring `JRadioButtonMenuItem` Properties

As with `JCheckBoxMenuItem`, most of the `JRadioButtonMenuItem` properties are inherited. The two shown in Table 6-13 merely override the behavior from the superclass.

Table 6-13. *JRadioButtonMenuItem Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>UIClassID</code>	<code>String</code>	Read-only

Customizing a `JRadioButtonMenuItem` Look and Feel

The appearance of the `JRadioButtonMenuItem` under the preinstalled set of look and feel types is shown with the other menu components in Figure 6-3.

The available set of `UIResource`-related properties for a `JRadioButtonMenuItem` is shown in Table 6-14. For the `JRadioButtonMenuItem` component, there are 19 different properties.

Table 6-14. *JRadioButtonMenuItem UIResource Elements*

Property String	Object Type
<code>RadioButtonMenuItem.acceleratorFont</code>	<code>Font</code>
<code>RadioButtonMenuItem.acceleratorForeground</code>	<code>Color</code>
<code>RadioButtonMenuItem.acceleratorSelectionForeground</code>	<code>Color</code>
<code>RadioButtonMenuItem.actionMap</code>	<code>ActionMap</code>
<code>RadioButtonMenuItem.arrowIcon</code>	<code>Icon</code>
<code>RadioButtonMenuItem.background</code>	<code>Color</code>
<code>RadioButtonMenuItem.border</code>	<code>Border</code>
<code>RadioButtonMenuItem.borderPainted</code>	<code>Boolean</code>
<code>RadioButtonMenuItem.checkIcon</code>	<code>Icon</code>
<code>RadioButtonMenuItem.commandSound</code>	<code>String</code>
<code>RadioButtonMenuItem.disabledForeground</code>	<code>Color</code>
<code>RadioButtonMenuItem.font</code>	<code>Font</code>
<code>RadioButtonMenuItem.foreground</code>	<code>Color</code>
<code>RadioButtonMenuItem.gradient</code>	<code>List</code>
<code>RadioButtonMenuItem.margin</code>	<code>Insets</code>
<code>RadioButtonMenuItem.opaque</code>	<code>Boolean</code>

Table 6-14. *JRadioButtonMenuItem UIResource Elements (Continued)*

Property String	Object Type
RadioButtonMenuItem.selectionBackground	Color
RadioButtonMenuItem.selectionForeground	Color
RadioButtonMenuItemUI	String

A Complete JRadioButtonMenuItem Usage Example

To help you understand the JRadioButtonMenuItem usage, the program shown in Listing 6-5 demonstrates how to put everything together, including listening for selection of all the items on the menu, from either an ActionListener or an ItemListener. The output for the program is shown in Figure 6-8.




Figure 6-8. *JRadioButtonMenuItem usage example output*

Listing 6-5. *The RadioButtonSample Class Definition*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class RadioButtonSample {
    static Icon threeIcon = new ImageIcon("3.gif");
    static Icon fourIcon = new ImageIcon("4.gif");
    static Icon fiveIcon = new ImageIcon("5.gif");
    static Icon sixIcon = new ImageIcon("6.gif");

    public static class ButtonActionListener implements ActionListener {
        public void actionPerformed (ActionEvent actionEvent) {
            AbstractButton aButton = (AbstractButton)actionEvent.getSource();
            boolean selected = aButton.getModel().isSelected();
            System.out.println (actionEvent.getActionCommand() +
                " - selected? " + selected);
        }
    }
}
```

```

public static class ButtonItemListener implements ItemListener {
    public void itemStateChanged(ItemEvent itemEvent) {
        AbstractButton aButton = (AbstractButton)itemEvent.getSource();
        int state = itemEvent.getStateChange();
        String selected =
            ((state == ItemEvent.SELECTED) ? "selected" : "not selected");
        System.out.println (aButton.getText() + " - selected? " + selected);
    }
}

```

```

public static void main(String args[]) {

    Runnable runner = new Runnable() {
        public void run() {

            final ActionListener actionListener = new ButtonActionListener();
            final ItemListener itemListener = new ButtonItemListener();

            JFrame frame = new JFrame("Radio Menu Example");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

            JMenuBar menuBar = new JMenuBar();
            JMenu menu = new JMenu("Menu");
            ButtonGroup buttonGroup = new ButtonGroup();
            menu.setMnemonic(KeyEvent.VK_M);

            JRadioButtonMenuItem emptyMenuItem =
                new JRadioButtonMenuItem();
            emptyMenuItem.setActionCommand("Empty");
            emptyMenuItem.addActionListener(actionListener);
            buttonGroup.add(emptyMenuItem);
            menu.add(emptyMenuItem);

            JRadioButtonMenuItem oneMenuItem =
                new JRadioButtonMenuItem("Partridge");
            oneMenuItem.addActionListener(actionListener);
            buttonGroup.add(oneMenuItem);
            menu.add(oneMenuItem);

            JRadioButtonMenuItem twoMenuItem =
                new JRadioButtonMenuItem("Turtle Doves", true);
            twoMenuItem.addActionListener(actionListener);
            buttonGroup.add(twoMenuItem);
            menu.add(twoMenuItem);

```

```

        JRadioButtonMenuItem threeMenuItem =
            new JRadioButtonMenuItem("French Hens", threeIcon);
        threeMenuItem.addItemListener(itemListener);
        buttonGroup.add(threeMenuItem);
        menu.add(threeMenuItem);

        JRadioButtonMenuItem fourMenuItem =
            new JRadioButtonMenuItem("Calling Birds", fourIcon, true);
        fourMenuItem.addActionListener(actionListener);
        buttonGroup.add(fourMenuItem);
        menu.add(fourMenuItem);

        JRadioButtonMenuItem fiveMenuItem =
            new JRadioButtonMenuItem(fiveIcon);
        fiveMenuItem.addActionListener(actionListener);
        fiveMenuItem.setActionCommand("Rings");
        buttonGroup.add(fiveMenuItem);
        menu.add(fiveMenuItem);

        JRadioButtonMenuItem sixMenuItem =
            new JRadioButtonMenuItem(sixIcon, true);
        sixMenuItem.addActionListener(actionListener);
        sixMenuItem.setActionCommand("Geese");
        buttonGroup.add(sixMenuItem);
        menu.add(sixMenuItem);

        menuBar.add(menu);
        frame.setJMenuBar(menuBar);
        frame.setSize(350, 250);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

■ **Note** Notice that the `actionCommand` property is set for those menu items lacking text labels. This allows registered `ActionListener` objects to determine the selected object. This is only necessary when listeners are shared across components.

Creating Custom MenuElement Components: The MenuElement Interface

One thing all the selectable menu components have in common is that they implement the `MenuElement` interface. The `JSeparator` doesn't implement the interface, but that's okay because it isn't selectable. The purpose of the `MenuElement` interface is to allow the `MenuSelectionManager` to notify the different menu elements as a user moves around a program's menu structure.

As the following interface definition shows, the `MenuElement` interface is made up of five methods:

```
public interface MenuElement {
    public Component getComponent();
    public MenuElement[] getSubElements();
    public void menuSelectionChanged(boolean isInclude);
    public void processKeyEvent(KeyEvent event, MenuElement path[],
        MenuSelectionManager mgr);
    public void processMouseEvent(MouseEvent event, MenuElement path[],
        MenuSelectionManager mgr);
}
```

The `getComponent()` method returns the menu's rendering component. This is usually the menu component itself, although that isn't a requirement. The `getSubElements()` method returns an array of any menu elements contained within this element. If this menu element isn't the top of a submenu, the method should return a zero-length array of `MenuElement` objects, not null.

The `menuSelectionChanged()` method is called whenever the menu item is placed in or taken out of the selection path for the menu selection manager.

The two `processKeyEvent()` and `processMouseEvent()` methods are for processing a key event or mouse event that's generated over a menu. How your menu item processes events depends on what the component supports. For instance, unless you support accelerators, you probably want to respond to key events only when your menu item is in the current selection path.

Note If, for example, your new menu element was something like a `JComboBoxMenuItem`, where the `MenuElement` acted like a `JComboBox`, the `processKeyEvent()` might pass along the key character to the `KeySelectionManager`. See Chapter 13 for more on the `KeySelectionManager`.

To demonstrate the `MenuElement` interface, Listing 6-6 creates a new menu component called a `JToggleButtonMenuItem`. This component will look and act like a `JToggleButton`, although it can be on a menu. It's important to ensure that the menu goes away once the item is selected and that the component is displayed differently when in the current selection path.

Note Although you can add any component to a menu, if the component doesn't implement the `MenuItem` interface, it won't act properly when a mouse moves over the component or when the component is selected.

Listing 6-6. *Toggle Button As Menu Item Class Definition*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import javax.swing.event.*;

public class JToggleButtonMenuItem extends JToggleButton implements MenuItem {
    Color savedForeground = null;
    private static MenuItem NO_SUB_ELEMENTS[] = new MenuItem[0];
    public JToggleButtonMenuItem() {
        init();
    }
    public JToggleButtonMenuItem(String label) {
        super(label);
        init();
    }
    public JToggleButtonMenuItem(String label, Icon icon) {
        super(label, icon);
        init();
    }
    public JToggleButtonMenuItem(Action action) {
        super(action);
        init();
    }
    private void init() {
        updateUI();
        setRequestFocusEnabled(false);
        // Borrows heavily from BasicMenuUI
        MouseInputListener mouseInputListener = new MouseInputListener() {
            // If mouse released over this menu item, activate it
            public void mouseReleased(MouseEvent mouseEvent) {
                MenuSelectionManager menuSelectionManager =
                    MenuSelectionManager defaultManager();
                Point point = mouseEvent.getPoint();
                if ((point.x >= 0) &&
                    (point.x < getWidth()) &&
                    (point.y >= 0) &&
                    (point.y < getHeight())) {
                    menuSelectionManager.clearSelectedPath();
                    // Component automatically handles "selection" at this point
                    // doClick(0); // not necessary
                }
            }
        };
    }
}
```

```

    } else {
        menuSelectionManager.processMouseEvent(mouseEvent);
    }
}
// If mouse moves over menu item, add to selection path, so it becomes armed
public void mouseEntered(MouseEvent mouseEvent) {
    MenuSelectionManager menuSelectionManager =
        MenuSelectionManager defaultManager();
    menuSelectionManager.setSelectedPath(getPath());
}
// When mouse moves away from menu item, disarm it and select something else
public void mouseExited(MouseEvent mouseEvent) {
    MenuSelectionManager menuSelectionManager =
        MenuSelectionManager defaultManager();
    MenuElement path[] = menuSelectionManager.getSelectedPath();
    if (path.length > 1) {
        MenuElement newPath[] = new MenuElement[path.length-1];
        for(int i=0, c=path.length-1; i<c; i++) {
            newPath[i] = path[i];
        }
        menuSelectionManager.setSelectedPath(newPath);
    }
}
// Pass along drag events
public void mouseDragged(MouseEvent mouseEvent) {
    MenuSelectionManager defaultManager().processMouseEvent(mouseEvent);
}
public void mouseClicked(MouseEvent mouseEvent) {
}
public void mousePressed(MouseEvent mouseEvent) {
}
public void mouseMoved(MouseEvent mouseEvent) {
}
};
addMouseListener(mouseInputListener);
addMouseMotionListener(mouseInputListener);
}

// MenuElement methods
public Component getComponent() {
    return this;
}

public MenuElement[] getSubElements() {
    // No subelements
    return NO_SUB_ELEMENTS;
}

```

```

public void menuSelectionChanged(boolean isIncluded) {
    ButtonModel model = getModel();
    // Only change armed state if different
    if(model.isArmed() != isIncluded) {
        model.setArmed(isIncluded);
    }

    if (isIncluded) {
        savedForeground = getForeground();
        if (!savedForeground.equals(Color.BLUE)) {
            setForeground(Color.BLUE);
        } else {
            // In case foreground blue, use something different
            setForeground(Color.RED);
        }
    } else {
        setForeground(savedForeground);
        // If null, get foreground from installed look and feel
        if (savedForeground == null) {
            updateUI();
        }
    }
}

public void processKeyEvent(KeyEvent keyEvent,
                           MenuElement path[],
                           MenuSelectionManager manager) {
    // If user presses space while menu item armed, select it
    if (getModel().isArmed()) {
        int keyChar = keyEvent.getKeyChar();
        if (keyChar == KeyEvent.VK_SPACE) {
            manager.clearSelectedPath();
            System.out.println("Selected: JToggleButtonMenuItem, by KeyEvent");
            doClick(0); // inherited from AbstractButton
        }
    }
}

public void processMouseEvent(MouseEvent mouseEvent, MenuElement path[],
                             MenuSelectionManager manager) {
    // For when mouse dragged over menu and button released
    if (mouseEvent.getID() == MouseEvent.MOUSE_RELEASED) {
        manager.clearSelectedPath();
        System.out.println("Selected: JToggleButtonMenuItem, by MouseEvent");
        doClick(0); // inherited from AbstractButton
    }
}

```

```
// Borrows heavily from BasicMenuItemUI.getPath()
private MenuElement[] getPath() {
    MenuSelectionManager menuSelectionManager =
        MenuSelectionManager defaultManager();
    MenuElement oldPath[] = menuSelectionManager.getSelectedPath();
    MenuElement newPath[];
    int oldPathLength = oldPath.length;
    if (oldPathLength == 0)
        return new MenuElement[0];
    Component parent = getParent();
    if (oldPath[oldPathLength-1].getComponent() == parent) {
        // Going deeper under the parent menu
        newPath = new MenuElement[oldPathLength+1];
        System.arraycopy(oldPath, 0, newPath, 0, oldPathLength);
        newPath[oldPathLength] = this;
    } else {
        // Sibling/child menu item currently selected
        int newPathPosition;
        for (newPathPosition = oldPath.length-1; newPathPosition >= 0;
            newPathPosition--) {
            if (oldPath[newPathPosition].getComponent() == parent) {
                break;
            }
        }
        newPath = new MenuElement[newPathPosition+2];
        System.arraycopy(oldPath, 0, newPath, 0, newPathPosition+1);
        newPath[newPathPosition+1] = this;
    }
    return newPath;
}
}
```

Note The `MouseListener` defined in the `init()` method and the `getPath()` method borrow heavily from the system `BasicMenuUI` class. Normally, the user interface delegate deals with what happens when the mouse moves over a menu component. Because the `JToggleButton` isn't a predefined menu component, its UI class doesn't deal with it. For better modularity, these two methods should be moved into an extended `ToggleButtonUI`.

Once you've created this `JToggleButtonMenuItem` class, you can use it like any other menu item:

```
JToggleButtonMenuItem toggleItem = new JToggleButtonMenuItem("Balloon Help");
editMenu.add(toggleItem);
```

Working with Pop-Ups: The Popup Class

Not everything you want to pop up needs to be a menu. Through the `Popup` and `PopupFactory` classes, you can pop up any component over another. This is different from tooltips, which are in a read-only, unselectable label. You can pop up selectable buttons, trees, or tables.

Creating Pop-Up Components

`Popup` is a simple class with two methods—`hide()` and `show()`—with two protected constructors. Instead of creating `Popup` objects directly, you acquire them from the `PopupFactory` class.

```
PopupFactory factory = PopupFactory.getSharedInstance();
Popup popup = factory.getPopup(owner, contents, x, y);
```

The `Popup` with the `contents` component created by `PopupFactory` will thus be “above” other components within the owner component.

A Complete Popup/PopupFactory Usage Example

Listing 6-7 demonstrates the usage of `Popup` and `PopupFactory` to show a `JButton` above another `JButton`. Selecting the initial `JButton` will cause the second one to be created above the first, at some random location. When the second button is visible, each is selectable. Selecting the initially visible button multiple times will cause even more pop-up buttons to appear, as shown in Figure 6-9. Each pop-up button will disappear after three seconds. In this example, selecting the pop-up button just displays a message to the console.




Figure 6-9. *Popup/PopupFactory example*

Listing 6-7. *The ButtonPopupSample Class Definition*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import java.util.Random;

public class ButtonPopupSample {
```

```

static final Random random = new Random();

// Define ActionListener
static class ButtonActionListener implements ActionListener {
    public void actionPerformed(ActionEvent actionEvent) {
        System.out.println("Selected: " + actionEvent.getActionCommand());
    }
}

// Define Show Popup ActionListener
static class ShowPopupActionListener implements ActionListener {
    private Component component;
    ShowPopupActionListener(Component component) {
        this.component = component;
    }
    public synchronized void actionPerformed(ActionEvent actionEvent) {
        JButton button = new JButton("Hello, World");
        ActionListener listener = new ButtonActionListener();
        button.addActionListener(listener);
        PopupFactory factory = PopupFactory.getSharedInstance();
        int x = random.nextInt(200);
        int y = random.nextInt(200);
        final Popup popup = factory.getPopup(component, button, x, y);
        popup.show();
        ActionListener hider = new ActionListener() {
            public void actionPerformed(ActionEvent e) {
                popup.hide();
            }
        };
        // Hide popup in 3 seconds
        Timer timer = new Timer(3000, hider);
        timer.start();
    }
}

public static void main(final String args[]) {
    Runnable runner = new Runnable() {
        public void run() {
            // Create frame
            JFrame frame = new JFrame("Button Popup Sample");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

            ActionListener actionListener = new ShowPopupActionListener(frame);

            JButton start = new JButton("Pick Me for Popup");
            start.addActionListener(actionListener);
            frame.add(start);
        }
    };
    new Thread(runner).start();
}

```

```

        frame.setSize(350, 250);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Working with Toolbars: The JToolBar Class

Toolbars are an integral part of the main application windows in a modern user interface. Toolbars provide users with easy access to the more commonly used commands, which are usually buried within a hierarchical menuing structure. The Swing component that supports this capability is the `JToolBar`.

The `JToolBar` is a specialized Swing container for holding components. This container can then be used as a toolbar within your Java applet or application, with the potential for it to be floating or draggable, outside the main window of the program. `JToolBar` is a very simple component to use and understand.

Creating JToolBar Components

There are four constructors for creating `JToolBar` components:

```

public JToolBar()
JToolBar jToolBar = new JToolBar();

public JToolBar(int orientation)
JToolBar jToolBar = new JToolBar(JToolBar.VERTICAL);

public JToolBar(String name)
JToolBar jToolBar = new JToolBar("Window Title");

public JToolBar(String name,int orientation)
JToolBar jToolBar = new JToolBar("Window Title", JToolBar.VERTICAL);

```

By default, a toolbar is created in a horizontal direction. However, you can explicitly set the orientation by using either of the `JToolBar` constants of `HORIZONTAL` and `VERTICAL`.

Also by default, toolbars are floatable. Therefore, if you create the toolbar with one orientation, the user could change its orientation while dragging the toolbar around outside the window. When floating, the title will be visible on the toolbar's frame.

Adding Components to a JToolBar

Once you have a `JToolBar`, you need to add components to it. Any `Component` can be added to the toolbar. When dealing with horizontal toolbars, for aesthetic reasons, it's best if the toolbar components are all roughly the same height. For a vertical toolbar, it's best if they're roughly the same width. There's only one method defined by the `JToolBar` class for adding toolbar

items; the remaining methods, such as `add(Component)`, are inherited from `Container`. In addition, you can add a separator to a toolbar.

```
public JButton add(Action action);
public void addSeparator();
public void addSeparator(Dimension size);
```

When using the `add(Action)` method of `JToolBar`, the added `Action` is encapsulated within a `JButton` object. This is different from adding actions to `JMenu` or `JPopupMenu` components, in which `JMenuItem` objects are added instead. As with `JMenu` and `JPopupMenu`, adding an `Action` in this fashion is discouraged in the Javadoc for the class. For separators, if you don't specify the size, the installed look and feel forces a default size setting.

Note For more information about dealing with the `Action` interface, see Chapter 2 or the section “Using Action Objects with Menus” earlier in this chapter.

To remove components from a toolbar, use the following method:

```
public void remove(Component component)
```

JToolBar Properties

The `JToolBar` class defines nine properties, which are listed in Table 6-15.

Table 6-15. *JToolBar Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>borderPainted</code>	<code>boolean</code>	Read-write bound
<code>floatable</code>	<code>boolean</code>	Read-write bound
<code>layout</code>	<code>LayoutManager</code>	Write-only
<code>margin</code>	<code>Insets</code>	Read-write bound
<code>orientation</code>	<code>int</code>	Read-write bound
<code>rollover</code>	<code>boolean</code>	Read-write bound
<code>UI</code>	<code>ToolBarUI</code>	Read-write
<code>UIClassID</code>	<code>String</code>	Read-only

By default, the border of a `JToolBar` is painted. If you don't want the border painted, you can set the `borderPainted` property to `false`. Without using the `borderPainted` property, you would need to change the setting of the `border` property (inherited from the superclass `JComponent`).

The orientation property can be set to only one of the `HORIZONTAL` or `VERTICAL` constants of `JToolBar`. If another nonequivalent value is used, an `IllegalArgumentException` is thrown. Changing the orientation changes the layout manager of the toolbar. If you directly change the layout manager with `setLayout()`, changing the orientation will undo your layout change. Consequently, it's best not to manually change the layout manager of a `JToolBar`.

As previously mentioned, a toolbar is floatable by default. This means that a user can drag the toolbar from where you place it and move it elsewhere. To drag a toolbar, the user selects an empty part of it. The toolbar can then be left outside the original program window, floating above the main window in its own window, or dropped onto another area of the original program window. If the layout manager of the original window is `BorderLayout`, the droppable areas are the edges of the layout manager without any components. (You can't drop the toolbar in the center of the window.) Otherwise, the toolbar would be dropped into the last spot of the container. Figure 6-10 shows the different phases of the dragging and docking process.




Figure 6-10. *JToolBar* phases

The rollover property defines a behavior specific to the look and feel for when the user moves the mouse over the different components within the toolbar. This behavior could involve coloration or border differences.

Handling JToolBar Events

There are no events specific to the JToolBar. You need to attach listeners to each item on the JToolBar that you want to respond to user interaction. Of course, JToolBar is a Container, so you could listen to its events.

Customizing a JToolBar Look and Feel

Each installable Swing look and feel provides its own JToolBar appearance and set of default UIResource values. Most of this appearance is controlled by the components actually within the toolbar. Figure 6-11 shows the appearance of the JToolBar component for the preinstalled set of look and feel types: Motif, Windows, and Ocean. Each toolbar has five JButton components, with a separator between the fourth and fifth.




Figure 6-11. *JToolBar under different look and feel types*

The available set of UIResource-related properties for a JToolBar is shown in Table 6-16. For the JToolBar component, there are 22 different properties.

Table 6-16. *JToolBar UIResource Elements*

Property String	Object Type
ToolBar.actionMap	ActionMap
ToolBar.ancestorInputMap	InputMap
ToolBar.background	Color


Table 6-16. *JToolBar UIResource Elements (Continued)*

Property String	Object Type
ToolBar.border	Border
ToolBar.borderColor	Color
ToolBar.darkShadow	Color
ToolBar.dockingBackground	Color
ToolBar.dockingForeground	Color
ToolBar.floatingBackground	Color
ToolBar.floatingForeground	Color
ToolBar.font	Font
ToolBar.foreground	Color
ToolBar.handleIcon	Icon
ToolBar.highlight	Color
ToolBar.isRollover	Boolean
ToolBar.light	Color
ToolBar.nonrolloverBorder	Border
ToolBar.rolloverBorder	Border
ToolBar.separatorSize	Dimension
ToolBar.shadow	Color
ToolBarSeparatorUI	String
ToolBarUI	String

A Complete JToolBar Usage Example

The program in Listing 6-8 demonstrates a complete JToolBar example that results in a toolbar with a series of diamonds on the buttons. The program also reuses the ShowAction defined for the menuing example, presented in Listing 6-2 earlier in this chapter.

The rollover property is enabled to demonstrate the difference for the current look and feel. See Figure 6-12 for the output as you move your mouse over the different buttons.

**Figure 6-12.** *JToolBar example with isRollover enabled*

Listing 6-8. *The ToolBarSample Class Definition*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;

public class ToolBarSample {

    private static final int COLOR_POSITION = 0;
    private static final int STRING_POSITION = 1;
    static Object buttonColors[][] = {
        {Color.RED, "RED"},
        {Color.BLUE, "BLUE"},
        {Color.GREEN, "GREEN"},
        {Color.BLACK, "BLACK"},
        null, // separator
        {Color.CYAN, "CYAN"}
    };

    public static class TheActionListener implements ActionListener {
        public void actionPerformed (ActionEvent actionEvent) {
            System.out.println(actionEvent.getActionCommand());
        }
    };

    public static void main(final String args[]) {

        Runnable runner = new Runnable() {
            public void run() {

                JFrame frame = new JFrame("JToolBar Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                ActionListener actionListener = new TheActionListener();

                JToolBar toolbar = new JToolBar();
                toolbar.setRollover(true);

                for (Object[] color: buttonColors) {
                    if (color == null) {
                        toolbar.addSeparator();
                    } else {
                        Icon icon = new DiamondIcon((Color)color[COLOR_POSITION], true, 20, 20);
                        JButton button = new JButton(icon);
                        button.setActionCommand((String)color[STRING_POSITION]);
                        button.addActionListener(actionListener);
                        toolbar.add(button);
                    }
                }
            }
        };

        SwingUtilities.invokeLater(runner);
    }
}
```

```

        Action action = new ShowAction(frame);
        JButton button = new JButton(action);
        toolbar.add(button);

        Container contentPane = frame.getContentPane();
        contentPane.add(toolbar, BorderLayout.NORTH);
        JTextArea textArea = new JTextArea();
        JScrollPane pane = new JScrollPane(textArea);
        contentPane.add(pane, BorderLayout.CENTER);
        frame.setSize(350, 150);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

JToolBar.Separator Class

The `JToolBar` class maintains its own separator to permit a custom look and feel for the separator when on a `JToolBar`.

This separator is automatically created when you call the `addSeparator()` method of `JToolBar`. In addition, there are two constructors for creating a `JToolBar.Separator` if you want to manually create the component.

public JToolBar.Separator()

```
JSeparator toolBarSeparator = new JToolBar.Separator();
```

public JToolBar.Separator(Dimension size)

```
Dimension dimension = new Dimension(10, 10);
```

```
JSeparator toolBarSeparator = new JToolBar.Separator(dimension);
```

Both constructors create a horizontal separator. You can configure the size. If you don't specify this, the look and feel decides what size to make the separator.

As with `JPopupMenu.Separator`, if you want to change the orientation of the separator, you must call the `setOrientation()` method inherited from `JSeparator`, this time with an argument of `JToolBar.Separator.VERTICAL`.

Summary

This chapter introduced the many Swing menu-related classes and their interrelationships, and Swing's toolbar class. First, you learned about the `JMenuBar` and its selection model, and learned how menu bars can be used within applets as well as applications.

Next, you explored the `JMenuItem`, which is the menu element the user selects, along with two new event/listener pairs the system uses for dealing with events, `MenuKeyEvent/MenuKeyListener` and `MenuDragMouseEvent/MenuDragMouseListener`. Then, you moved on to the `JMenu` component, upon which `JMenuItem` instances are placed, along with its new event/listener pair, `MenuEvent/MenuListener`, which is used to determine when a menu is about to be posted.

Next, you learned about the `JSeparator` component and how you can use it as a menu separator or as a visual display separator outside of menus.

You then explored the `JPopupMenu`, which `JMenu` uses to display its set of `JMenuItem` components. For the `JPopupMenu`, you learned about the pop-up menu's own event/listener pair, `PopupMenuEvent/PopupMenuListener`.

Then the selectable menu elements in `JCheckBoxMenuItem` and `JRadioButtonMenuItem` were explored with their `MenuItem` interface, and you saw how to create a custom menu component.

Menus aren't the only things that might pop up, so you explored `Popup` and `PopupFactory`. Finally, the chapter covered the `JToolBar` class, a close cousin of Swing's menu classes.

In Chapter 7, you'll look at the different classes Swing provides for customizing the border around a Swing component.



Borders

Swing components offer the option of customizing the border area surrounding that component. With great ease, you can use any one of the eight predefined borders (including one compound border that is a combination of any of the other seven), or you can create your own individualized borders. In this chapter, you'll learn how to best use each of the existing borders and how to fashion your own.

Some Basics on Working with Borders

A border is a `JComponent` property with the standard `setBorder()` and `getBorder()` property methods. Therefore, every Swing component that is a subclass of `JComponent` can have a border. By default, a component doesn't have a custom border associated with it. (The `getBorder()` method of `JComponent` returns `null`.) Instead, the default border displayed for a component is the border appropriate for its state, based on the current look and feel. For instance, with a `JButton`, the border could appear pressed, unpressed, or disabled, with specific different borders for each look and feel (Metal, Windows, and so on).

Although the initial border property setting for every component is `null`, you can change the border of a component by calling the `setBorder(Border newValue)` method of `JComponent`. Once set, the changed value overrides the border for the current look and feel, and it draws the new border in the area of the component's insets. If at a later time, you want to reset the border back to a border that's appropriate for the state as well as the look and feel, change the border property to `null`, using `setBorder(null)`, and call `updateUI()` for the component. The `updateUI()` call notifies the look and feel to reset the border. If you don't call `updateUI()`, the component will have no border.

Note Those Swing components that aren't subclasses of `JComponent`, such as `JApplet` and `JFrame`, lack a `setBorder()` method to change their border. If you want them to have a border, you must add a `JPanel` or other Swing component to the container, and then change the border of that component.

Examine Figure 7-1 to see a sampling of the various border configurations around a `JLabel`, with a text label designating the border type. How to create the different borders will be discussed in later sections of this chapter.




Figure 7-1. Border examples, using a 4-by-2 `GridLayout` with 5-pixel horizontal and vertical gaps

Exploring the Border Interface

The `Border` interface can be found in the `javax.swing.border` package. This interface forms the basis of all the border classes. The interface is directly implemented by the `AbstractBorder` class, which is the parent class of all the predefined Swing border classes: `BevelBorder`, `CompoundBorder`, `EmptyBorder`, `EtchedBorder`, `LineBorder`, `MatteBorder`, `SoftBevelBorder`, and `TitledBorder`. Of additional interest is the `BorderFactory` class, found in the `javax.swing` package. This class uses the Factory design pattern to create borders, hiding the details of the concrete implementations and caching various operations to optimize shared usages.

The `Border` interface shown here consists of three methods: `paintBorder()`, `getBorderInsets()`, and `isBorderOpaque()`. These methods are described in the following sections.

`paintBorder()`

The `paintBorder()` method is the key method of the interface. It has the following definition:

```
public void paintBorder(Component c, Graphics g, int x, int y, int
    width, int height)
```

The actual drawing of the border is done in this method. Frequently, the `Border` implementation will ask for the `Insets` dimensions first, and then draw the border in the four rectangular outer regions, as shown in Figure 7-2. If a border is opaque, the `paintBorder()` implementation must fill the entire insets area. If a border is opaque and doesn't fill the area, then it's a bug and needs to be corrected.




Figure 7-2. *Areas of border insets*

Listing 7-1 shows a simple `paintBorder()` implementation that fills in the left and right sides with a brighter color than the top and bottom.

Listing 7-1. *Filled-in Border Inset Areas*

```
public void paintBorder(Component c, Graphics g, int x, int y, int width,
    int height) {
    Insets insets = getBorderInsets(c);
    Color color = c.getForeground();
    Color brighterColor = color.brighter();

    // Translate coordinate space
    g.translate(x, y);

    // Top
    g.setColor(color);
    g.fillRect(0, 0, width, insets.top);

    // Left
    g.setColor(brighterColor);
    g.fillRect(0, insets.top, insets.left, height-insets.top-insets.bottom);

    // Bottom
    g.setColor(color);
    g.fillRect(0, height-insets.bottom, width, insets.bottom);
}
```

```
// Right
g.setColor(brighterColor);
g.fillRect(width-insets.right, insets.top, insets.right,
    height-insets.top-insets.bottom);

// Translate coordinate space back
g.translate(-x, -y);

}
```

When creating your own borders, you'll frequently find yourself filling in the same nonoverlapping rectangular regions. The use of the `translate()` method of `Graphics` simplifies the specification of the drawing coordinates. Without translating the coordinates, you would need to offset the drawing by the origin (`x, y`).

Caution You cannot take a shortcut by inserting `g.fillRect(x, y, width, height)`, because this would fill in the entire component area, not just the border area.

`getBorderInsets()`

The `getBorderInsets()` method returns the space necessary to draw a border around the given component `c` as an `Insets` object. It has the following definition:

```
public Insets getBorderInsets(Component c)
```

These inset areas, shown in Figure 7-2, define the only legal area in which a border can be drawn. The `Component` argument allows you to use some of its properties to determine the size of the insets area.

Caution You can ask the component argument for font-sizing information to determine the insets' size, but if you ask about the size of the component, a `StackOverflowError` occurs because the size of the component is dependent on the size of the border insets.

`isBorderOpaque()`

Borders can be opaque or transparent. The `isBorderOpaque()` method returns `true` or `false`, to indicate which form the border is. It has the following definition:

```
public boolean isBorderOpaque()
```

When this method returns `true`, the border needs to be opaque, filling its entire insets area. When it returns `false`, any area not drawn will retain the background of the component in which the border is installed.

Introducing BorderFactory

Now that you have a basic understanding of how the `Border` interface works, let's take a quick look at the `BorderFactory` class as a means to create borders swiftly and easily. Found in the `javax.swing` package, the `BorderFactory` class offers a series of static methods for creating predefined borders. Instead of laboriously calling the specific constructors for different borders, you can create almost all the borders through this factory class. The factory class also caches the creation of some borders to avoid re-creating commonly used borders multiple times. The class definition follows.

```
public class BorderFactory {
    public static Border createBevelBorder(int type);
    public static Border createBevelBorder(int type, Color highlight,
        Color shadow);
    public static Border createBevelBorder(int type, Color highlightOuter,
        Color highlightInner, Color shadowOuter, Color shadowInner);

    public static CompoundBorder createCompoundBorder();
    public static CompoundBorder createCompoundBorder(Border outside,
        Border inside);

    public static Border createEmptyBorder();
    public static Border createEmptyBorder(int top, int left, int bottom,
        int right);

    public static Border createEtchedBorder();
    public static Border createEtchedBorder(Color highlight, Color shadow);
    public static Border createEtchedBorder(int type);
    public static Border createEtchedBorder(int type, Color highlight,
        Color shadow);

    public static Border createLineBorder(Color color);
    public static Border createLineBorder(Color color, int thickness);

    public static Border createLoweredBevelBorder();

    public static MatteBorder createMatteBorder(int top, int left, int bottom,
        int right, Color color);
    public static MatteBorder createMatteBorder(int top, int left, int bottom,
        int right, Icon icon);
```

```

public static Border createRaisedBevelBorder();

public static TitledBorder createTitledBorder(Border border);
public static TitledBorder createTitledBorder(Border border, String title);
public static TitledBorder createTitledBorder(Border border, String title,
    int justification, int position);
public static TitledBorder createTitledBorder(Border border, String title,
    int justification, int position, Font font);
public static TitledBorder createTitledBorder(Border border, String title,
    int justification, int position, Font font, Color color);
public static TitledBorder createTitledBorder(String title);
}

```

I'll describe the different methods of this class during the process of describing the specific border types they create. For instance, to create a border with a red line, you can use the following statement, and then attach the border to a component.

```
Border lineBorder = BorderFactory.createLineBorder(Color.RED);
```

Note Interestingly enough, no factory method exists for creating a `SoftBevelBorder`.

Starting with AbstractBorder

Before looking at the individual borders available within the `javax.swing.border` package, one system border deserves special attention: `AbstractBorder`. As previously mentioned, the `AbstractBorder` class is the parent border of all the other predefined borders.

Tip When creating your own borders, you should create a subclass of `AbstractBorder` and just override the necessary methods, instead of implementing the `Border` interface directly yourself. There are some internal optimizations in place for subclasses.

Creating Abstract Borders

There is one constructor for `AbstractBorder`:

```
public AbstractBorder()
```

Because `AbstractBorder` is the parent class of all the other standard borders, this constructor is eventually called automatically for all of them.

■ **Note** Borders are not meant to be used as JavaBean components. Some border classes even lack a no-argument (“no-arg” for short) constructor. Nevertheless, those border classes still call this constructor.

Examining AbstractBorder Methods

The `AbstractBorder` class provides implementations for the three methods of the `Border` interface.

```
public Insets getBorderInsets(Component c)
```

The insets of an `AbstractBorder` are zero all around. Each of the predefined subclasses overrides the `getBorderInsets()` method.

```
public boolean isBorderOpaque()
```

The default opaque property setting of an abstract border is false. This means that if you were to draw something like dashed lines, the component background would show through. Many predefined subclasses override the `isBorderOpaque()` method.

```
public void paintBorder(Component c, Graphics g, int x, int y,  
    int width, int height)
```

The painted border for an `AbstractBorder` is empty. All subclasses should override this behavior to actually draw a border, except perhaps `EmptyBorder`.

In addition to providing default implementations of the `Border` methods, `AbstractBorder` adds two other capabilities that you can take advantage of, or just let the system use. First, there’s an additional version of `getBorderInsets()` available that takes two arguments: `Component` and `Insets`:

```
public Insets getBorderInsets(Component c, Insets insets)
```

In this version of the method, instead of creating and returning a new `Insets` object, the `Insets` object passed in is first modified and then returned. Use of this method avoids the creation and later destruction of an additional `Insets` object each time the border insets is queried.

The second new method available is `getInteriorRectangle()`, which has both a static and a nonstatic version. Given the `Component`, `Border`, and four integer parameters (for `x`, `y`, `width`, and `height`), the method will return the inner `Rectangle` such that a component can paint itself only in the area within the border insets. (See the piece labeled “Component” in Figure 7-2, shown earlier in the chapter.)

■ **Note** Currently, `getBorderInsets()` is used only once in Sun’s Swing source. That place is the `MotifButtonUI` class found in the `com.sun.java.swing.plaf.motif` package.

Examining the Predefined Borders

Now that the basics have been described, let's look at the specifics of each of the predefined border classes, somewhat in order of complexity.

EmptyBorder Class

The empty border, logically enough, is a border with nothing drawn in it. You can use `EmptyBorder` where you might have otherwise overridden `insets()` or `getInsets()` with a regular AWT container. It allows you to reserve extra space around a component to spread your screen components out a little or to alter centering or justification somewhat. Figure 7-3 shows both an empty border and one that is not empty.




Figure 7-3. *EmptyBorder sample, with insets of 20 for top and left, 0 for right and bottom*

`EmptyBorder` has two constructors and two factory methods of `BorderFactory`:

```
public static Border createEmptyBorder()
Border emptyBorder = BorderFactory.createEmptyBorder();

public static Border createEmptyBorder(int top, int left, int bottom, int right)
Border emptyBorder = BorderFactory.createEmptyBorder(5, 10, 5, 10);

public EmptyBorder(Insets insets)
Insets insets = new Insets(5, 10, 5, 10);
Border emptyBorder = new EmptyBorder(insets);

public EmptyBorder(int top, int left, int bottom, int right)
Border emptyBorder = new EmptyBorder(5, 10, 5, 10);
```

Each allows you to customize the border insets in its own manner. The no-argument version creates a truly empty border with zero insets all around; otherwise, you can specify the insets as either an AWT `Insets` instance or as the inset pieces. The `EmptyBorder` is transparent by default.

Note When creating an empty border, with zeros all around, you should use the factory method to create the border, avoiding the direct constructors. This allows the factory to create one truly empty border to be shared by all. If all you want to do is hide the border, and the component is an `AbstractButton` subclass, just call `setBorderPainted(false)`.

LineBorder Class

The line border is a single-color line of a user-defined thickness that surrounds a component. It can have squared-off or rounded corners. If you want to alter the thickness on different sides, you'll need to use `MatteBorder`, which is described in the section “Matte Border Class” later in this chapter. Figure 7-4 shows a sampling of using `LineBorder`, with 1- and 12-pixel line thicknesses, with and without rounded corners.



Figure 7-4. *LineBorder sample*

Creating Line Borders

The `LineBorder` class has three constructors, two factory methods within it, and two factory methods of `BorderFactory`:

```
public LineBorder(Color color)
```

```
Border lineBorder = new LineBorder (Color.RED);
```

```
public LineBorder(Color color, int thickness)
```

```
Border lineBorder = new LineBorder (Color.RED, 5);
```

```
public LineBorder (Color color, int thickness, boolean roundedCorners)
```

```
Border lineBorder = new LineBorder (Color.RED, 5, true);
```

```
public static Border createBlackLineBorder()
```

```
Border blackLine = LineBorder.createBlackLineBorder();
```

```
public static Border createGrayLineBorder()
Border grayLine = LineBorder.createGrayLineBorder();

public static Border createLineBorder(Color color)
Border lineBorder = BorderFactory.createLineBorder(Color.RED);

public static Border createLineBorder(Color color, int thickness)
Border lineBorder = BorderFactory.createLineBorder(Color.RED, 5);
```

Note The `LineBorder` factory methods work as follows: If you create the same border twice, the same `LineBorder` object will be returned. However, as with all object comparisons, you should always use the `equals()` method for checking object equality.

Each allows you to customize the border color and line thickness. If a thickness isn't specified, a default value of 1 is used. The two factory methods of `LineBorder` are for the commonly used colors of black and gray. Because the border fills in the entire insets area, the `LineBorder` is opaque, unless there are rounded corners. So, the opacity of the border is the opposite of the rounded-corner setting.

Configuring Line Border Properties

Table 7-1 lists the inherited `borderOpaque` property from `AbstractBorder` and the immutable properties of `LineBorder`.

Table 7-1. *LineBorder* Properties

Property Name	Data Type	Access
<code>borderOpaque</code>	<code>boolean</code>	Read-only
<code>lineColor</code>	<code>Color</code>	Read-only
<code>roundedCorners</code>	<code>boolean</code>	Read-only
<code>thickness</code>	<code>int</code>	Read-only

BevelBorder Class

A bevel border draws a border with a three-dimensional appearance, which can appear to be raised or lowered. When the border is raised, a shadow effect appears along the bottom and right side of the border. When lowered, the position of the shading is reversed. Figure 7-5 shows raised and lowered bevel borders with default and custom colors.



Figure 7-5. *Raised and lowered BevelBorder sample*

Drawing two different pairs of 1-pixel-wide lines around the component produces a simulated three-dimensional appearance. The border sides that aren't shaded are drawn with what is called a *highlight* color, and the other two sides are drawn with a *shadow* color. The highlight color and shadow color are each drawn in two different shades for the outer and inner edges of the bevel. As such, a drawn bevel border uses four different colors in all. Figure 7-6 shows how these four colors fit together.




Figure 7-6. *Bevel color analysis*

There are three constructors and one factory method of `BevelBorder`, as well as five factory methods by which `BorderFactory` creates `BevelBorder` objects:

```
public BevelBorder(int bevelType)  
Border bevelBorder = new BevelBorder(BevelBorder.RAISED);
```

```
public static Border createBevelBorder(int bevelType)  
Border bevelBorder = BorderFactory.createBevelBorder(BevelBorder.RAISED);
```

```
public static Border createLoweredBevelBorder()  
Border bevelBorder = BorderFactory.createLoweredBevelBorder();
```

```

public static Border createRaisedBevelBorder()
Border bevelBorder = BorderFactory.createRaisedBevelBorder();

public BevelBorder(int bevelType, Color highlight, Color shadow)
Border bevelBorder = new BevelBorder(BevelBorder.RAISED, Color.PINK, Color.RED);

public static Border createBevelBorder(int bevelType, Color highlight, Color shadow)
Border bevelBorder = BorderFactory.createBevelBorder(BevelBorder.RAISED,
    Color.PINK, Color.RED);

public BevelBorder(int bevelType, Color highlightOuter, Color highlightInner,
    Color shadowOuter, Color shadowInner)
Border bevelBorder = new BevelBorder(BevelBorder.RAISED, Color.PINK,
    Color.PINK.brighter(), Color.RED, Color.RED.darker());

public static Border createBevelBorder(int bevelType, Color highlightOuter,
    Color highlightInner, Color shadowOuter, Color shadowInner)
Border bevelBorder = BorderFactory.createBevelBorder(BevelBorder.RAISED,
    Color.PINK, Color.PINK.brighter(), Color.RED, Color.RED.darker());

```

Each allows you to customize both the bevel type and the coloration of the highlighting and shadowing within the border. The bevel type is specified by one of two values: `BevelBorder.RAISED` or `BevelBorder.LOWERED`. If highlight and shadow colors aren't specified, the appropriate colors are generated by examining the background of the component for the border. If you do specify them, remember that the highlight color should be brighter, possibly done by calling the `Color.brighter()`. A `BevelBorder` is opaque, by default.

SoftBevelBorder Class

The soft bevel border is a close cousin of the bevel border. It rounds out the corners so that their edges aren't as sharp, and it draws only one line, using the appropriate outer color for the bottom and right sides. As Figure 7-7 shows, the basic appearance of the raised and lowered `SoftBevelBorder` is roughly the same as that of the `BevelBorder`.



Figure 7-7. Raised and lowered *SoftBevelBorder* sample

SoftBevelBorder has three constructors:

```
public SoftBevelBorder(int bevelType)
```

```
Border softBevelBorder = new SoftBevelBorder(SoftBevelBorder.RAISED);
```

```
public SoftBevelBorder(int bevelType, Color highlight, Color shadow)
```

```
Border softBevelBorder = new SoftBevelBorder(SoftBevelBorder.RAISED, Color.RED,  
    Color.PINK);
```

```
public SoftBevelBorder(int bevelType, Color highlightOuter, Color highlightInner,  
    Color shadowOuter, Color shadowInner)
```

```
Border softBevelBorder = new SoftBevelBorder(SoftBevelBorder.RAISED, Color.RED,  
    Color.RED.darker(), Color.PINK, Color.PINK.brighter());
```

Each allows you to customize both the bevel type and the coloration of the highlighting and shadowing within the border. The bevel type is specified by one of two values: `SoftBevelBorder.RAISED` or `SoftBevelBorder.LOWERED`. As with `BevelBorder`, the default coloration is derived from the background color. A soft bevel border doesn't completely fill in the given insets area, so a `SoftBevelBorder` is created to be transparent (not opaque).

There are no static `BorderFactory` methods to create these borders.

EtchedBorder Class

An `EtchedBorder` is a special case of a `BevelBorder`, but it's not a subclass. When the outer highlight color of a `BevelBorder` is the same color as the inner shadow color and the outer shadow color is the same color as the inner highlight color, you have an `EtchedBorder`. (See Figure 7-6 earlier in this chapter for a depiction of bevel colors.) Figure 7-8 shows what a raised and lowered etched border might look like.



Figure 7-8. *EtchedBorder* samples

There are four constructors for `EtchedBorder`, as well as four factory methods of `BorderFactory` for creating `EtchedBorder` objects:

```
public EtchedBorder()
Border etchedBorder = new EtchedBorder();

public EtchedBorder(int etchType)
Border etchedBorder = new EtchedBorder(EtchedBorder.RAISED);

public EtchedBorder(Color highlight, Color shadow)
Border etchedBorder = new EtchedBorder(Color.RED, Color.PINK);

public EtchedBorder(int etchType, Color highlight, Color shadow)
Border etchedBorder = new EtchedBorder(EtchedBorder.RAISED, Color.RED,
    Color.PINK);

public static Border createEtchedBorder()
Border etchedBorder = BorderFactory.createEtchedBorder();

public static Border createEtchedBorder(Color highlight, Color shadow)
Border etchedBorder = BorderFactory.createEtchedBorder(Color.RED, Color.PINK);

public static Border createEtchedBorder(EtchedBorder.RAISED)
Border etchedBorder = BorderFactory.createEtchedBorder(Color.RED, Color.PINK);

public static Border createEtchedBorder(int type, Color highlight, Color shadow)
Border etchedBorder = BorderFactory.createEtchedBorder(EtchedBorder.RAISED,
    Color.RED, Color.PINK);
```

Each allows you to customize both the etching type and the coloration of the highlighting and shadowing within the border. If no etching type is specified, the border is lowered. As with `BevelBorder` and `SoftBevelBorder`, you can specify the etching type through one of two constants: `EtchedBorder.RAISED` or `EtchedBorder.LOWERED`. Again, if no colors are specified, they're derived from the background color of the component passed into `paintBorder()`. By default, all `EtchedBorder` objects are created to be opaque.

MatteBorder Class

`MatteBorder` is one of the more versatile borders available. It comes in two varieties. The first is demonstrated in Figure 7-9 and shows a `MatteBorder` used like a `LineBorder` to fill the border with a specific color, but with a different thickness on each side (something a plain `LineBorder` cannot handle).




Figure 7-9. *MatteBorder color sample*

The second variety uses an `Icon` tiled throughout the border area. This `Icon` could be an `ImageIcon`, if created from an `Image` object, or it could be one you create yourself by implementing the `Icon` interface. Figure 7-10 demonstrates both implementations.




Figure 7-10. *MatteBorder icon samples*

Tip When tiling an icon, the right and bottom areas may not look very attractive if the border size, component size, and icon size fail to mesh well.

There are seven constructors and two factory methods of `BorderFactory` for creating `MatteBorder` objects:

```
public MatteBorder(int top, int left, int bottom, int right, Color color)
```

```
Border matteBorder = new MatteBorder(5, 10, 5, 10, Color.GREEN);
```

```
public MatteBorder(int top, int left, int bottom, int right, Icon icon)
```

```
Icon diamondIcon = new DiamondIcon(Color.RED);
```

```
Border matteBorder = new MatteBorder(5, 10, 5, 10, diamondIcon);
```

```
public MatteBorder(Icon icon)
```

```
Icon diamondIcon = new DiamondIcon(Color.RED);
```

```
Border matteBorder = new MatteBorder(diamondIcon);
```

```

public MatteBorder(Insets insets, Color color)
Insets insets = new Insets(5, 10, 5, 10);
Border matteBorder = new MatteBorder(insets, Color.RED);

public MatteBorder(Insets insets, Icon icon)
Insets insets = new Insets(5, 10, 5, 10);
Icon diamondIcon = new DiamondIcon(Color.RED);
Border matteBorder = new MatteBorder(insets, diamondIcon);

public static MatteBorder createMatteBorder(int top, int left, int bottom,
    int right, Color color)
Border matteBorder = BorderFactory.createMatteBorder(5, 10, 5, 10, Color.GREEN);

public static MatteBorder createMatteBorder(int top, int left, int bottom,
    int right, Icon icon)
Icon diamondIcon = new DiamondIcon(Color.RED);
Border matteBorder = BorderFactory.createMatteBorder(5, 10, 5, 10, diamondIcon);

```

Each allows you to customize what will be matted within the border area. When tiling an Icon, if you don't specify the border insets size, the actual icon dimensions will be used.

CompoundBorder Class

After `EmptyBorder`, the compound border is probably one of the simplest predefined borders to use. It takes two existing borders and combines them, using the Composite design pattern, into a single border. A Swing component can have only one border associated with it, therefore, the `CompoundBorder` allows you to combine borders *before* associating them with a component. Figure 7-11 shows two examples of `CompoundBorder` in action. The border on the left is a beveled, line border. The one on the right is a six-line border, with several borders combined together.



Figure 7-11. *CompoundBorder* samples

Creating Compound Borders

There are two constructors for `CompoundBorder` and two factory methods that `BorderFactory` offers for creating `CompoundBorder` objects (the no-argument constructor and factory methods are completely useless here, because there are no setter methods to later change the compounded borders, so no source examples are shown for them):

```
public CompoundBorder()
```

```
public static CompoundBorder createCompoundBorder()
```

```
public CompoundBorder(Border outside, Border inside)
Border compoundBorder = new CompoundBorder(lineBorder, matteBorder);
```

```
public static CompoundBorder createCompoundBorder(Border outside, Border inside)
Border compoundBorder = BorderFactory.createCompoundBorder(lineBorder,
    matteBorder);
```

Tip Keep in mind that `CompoundBorder` is itself a `Border`, so you can combine multiple borders into one border many levels deep.

The opacity of a compound border depends on the opacity of the contained borders. If both contained borders are opaque, so is the compound border. Otherwise, a compound border is considered transparent.

Configuring Properties

In addition to the `borderOpaque` property inherited from `AbstractBorder`, Table 7-2 lists the two read-only properties `CompoundBorder` adds.

Table 7-2. *CompoundBorder Properties*

Property Name	Data Type	Access
<code>borderOpaque</code>	<code>boolean</code>	Read-only
<code>insideBorder</code>	<code>Border</code>	Read-only
<code>outsideBorder</code>	<code>Border</code>	Read-only

TitledBorder Class

Probably the most interesting border, `TitledBorder` can also be the most complicated to use. The titled border allows you to place a text string around a component. In addition to surrounding a single component, you can place a titled border around a group of components, like `JRadioButton` objects, as long as they're placed within a container such as a `JPanel`. The `TitledBorder` can be difficult to use, but there are several ways to simplify its usage. Figure 7-12 shows both a simple titled border and one that's a little more complex.




Figure 7-12. *TitledBorder samples*

Creating TitledBorders

Six constructors and six `BorderFactory` factory methods exist for creating `TitledBorder` objects. Each allows you to customize the text, position, and appearance of a title within a specified border. When unspecified, the current look and feel controls the border, title color, and title font. The default location for the title is the upper-left corner, while the default title is the empty string. A titled border is always at least partially transparent because the area beneath the title text shows through. Therefore, `isBorderOpaque()` reports `false`.

If you look at each of the following methods, shown in pairs, this will be easier to understand. First shown is the constructor method; next shown is the equivalent `BorderFactory` method.

```
public TitledBorder(Border border)
```

```
Border titledBorder = new TitledBorder(lineBorder);
```

```
public static TitledBorder createTitledBorder(Border border)
```

```
Border titledBorder = BorderFactory.createTitledBorder(lineBorder);
```

```
public TitledBorder(String title)
```

```
Border titledBorder = new TitledBorder("Hello");
```

```
public static TitledBorder createTitledBorder(String title)
```

```
Border titledBorder = BorderFactory.createTitledBorder("Hello");
```

```
public TitledBorder(Border border, String title)
```

```
Border titledBorder = new TitledBorder(lineBorder, "Hello");
```

```
public static TitledBorder createTitledBorder(Border border, String title)
```

```
Border titledBorder = BorderFactory.createTitledBorder(lineBorder, "Hello");
```

```
public TitledBorder(Border border, String title, int justification, int position)
```

```
Border titledBorder = new TitledBorder(lineBorder, "Hello", TitledBorder.LEFT,  
    TitledBorder.BELOW_BOTTOM);
```

```

public static TitledBorder createTitledBorder(Border border, String title,
    int justification, int position)
Border titledBorder = BorderFactory.createTitledBorder(lineBorder, "Hello",
    TitledBorder.LEFT, TitledBorder.BELOW_BOTTOM);

public TitledBorder(Border border, String title, int justification, int position,
    Font font)
Font font = new Font("Serif", Font.ITALIC, 12);
Border titledBorder = new TitledBorder(lineBorder, "Hello", TitledBorder.LEFT,
    TitledBorder.BELOW_BOTTOM, font);

public static TitledBorder createTitledBorder(Border border, String title,
    int justification, int position, Font font)
Font font = new Font("Serif", Font.ITALIC, 12);
Border titledBorder = BorderFactory.createTitledBorder(lineBorder, "Hello",
    TitledBorder.LEFT, TitledBorder.BELOW_BOTTOM, font);

public TitledBorder(Border border, String title, int justification, int position,
    Font font, Color color)
Font font = new Font("Serif", Font.ITALIC, 12);
Border titledBorder = new TitledBorder(lineBorder, "Hello", TitledBorder.LEFT,
    TitledBorder.BELOW_BOTTOM, font, Color.RED);

public static TitledBorder createTitledBorder(Border border, String title,
    int justification, int position, Font font, Color color)
Font font = new Font("Serif", Font.ITALIC, 12);
Border titledBorder = BorderFactory.createTitledBorder(lineBorder, "Hello",
    TitledBorder.LEFT, TitledBorder.BELOW_BOTTOM, font, Color.RED);

```

Configuring Properties

Unlike all the other predefined borders, titled borders have six setter methods to modify their attributes *after* border creation. As shown in Table 7-3, you can modify a titled border's underlying border, title, drawing color, font, text justification, and text position.

Table 7-3. *TitledBorder Properties*

Property Name	Data Type	Access
border	Border	Read-write
borderOpaque	boolean	Read-only
title	String	Read-write
titleColor	Color	Read-write
titleFont	Font	Read-write
titleJustification	int	Read-write
titlePosition	int	Read-write

Tip To reduce screen redrawing, it's better to modify the properties of a titled border prior to placing the border around a component.

Text justification of the title string within a `TitledBorder` is specified by one of four class constants:

- `CENTER`: Place the title in the center.
- `DEFAULT_JUSTIFICATION`: Use the default setting to position the text. The value is equivalent to `LEFT`.
- `LEFT`: Place the title on the left edge.
- `RIGHT`: Place the title on the right edge.

Figure 7-13 shows the same `TitledBorder` with three different justifications.



Figure 7-13. *Title justifications*

You can position title strings in any one of six different locations, as specified by one of seven class constants:

- `ABOVE_BOTTOM`: Place the title above the bottom line.
- `ABOVE_TOP`: Place the title above the top line.
- `BELOW_BOTTOM`: Place the title below the bottom line.
- `BELOW_TOP`: Place the title below the top line.
- `BOTTOM`: Place the title on the bottom line.
- `DEFAULT_POSITION`: Use the default setting to place the text. This value is equivalent to `TOP`.
- `TOP`: Place the title on the top line.

Figure 7-14 shows the six different positions available for the title on a `TitledBorder`.



Figure 7-14. *Title positioning*

Because a `TitledBorder` contains another `Border`, you can combine more than one border to place multiple titles along a single border. For example, Figure 7-15 shows a title along the top *and* bottom of the border.




Figure 7-15. *Showing multiple titles on a `TitledBorder`*

The program used to generate Figure 7-15 is shown in Listing 7-2.

Listing 7-2. *Multiple Titles on a `TitledBorder`*

```
import javax.swing.*;
import javax.swing.border.*;
import java.awt.*;

public class DoubleTitle {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Double Title");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                TitledBorder topBorder = BorderFactory.createTitledBorder("Top");
                topBorder.setTitlePosition(TitledBorder.TOP);
                TitledBorder doubleBorder = new TitledBorder(topBorder, "Bottom",
                    TitledBorder.RIGHT, TitledBorder.BOTTOM);
                JButton doubleButton = new JButton();
                doubleButton.setBorder(doubleBorder);
                frame.add(doubleButton, BorderLayout.CENTER);
            }
        };
        SwingUtilities.invokeLater(runner);
    }
}
```

```
        frame.setSize(300, 100);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}
```

Customizing TitledBorder Look and Feel

The available set of UIResource-related properties for a TitledBorder is shown in Table 7-4. It has three different properties.

Table 7-4. TitledBorder UIResource Elements

Property String	Object Type
TitledBorder.font	Font
TitledBorder.titleColor	Color
TitledBorder.border	Border

Creating Your Own Borders

When you want to create your own distinctive border, you can either create a new class that implements the Border interface directly or you can extend the AbstractBorder class. As previously mentioned, extending the AbstractBorder class is the better way to go, because optimizations are built in to certain Swing classes to take advantage of some of the AbstractBorder-specific methods. For instance, if a border is an AbstractBorder, JComponent will reuse an Insets object when getting the Insets of a border. Thus, one fewer object will need to be created and destroyed each time the insets are fetched.

In addition to thinking about subclassing AbstractBorder versus implementing the Border interface yourself, you need to consider whether or not you want a static border. If you attach a border to a button, you want that button to be able to signal selection. You must examine the component passed into the paintBorder() method and react accordingly. In addition, you should also draw a disabled border to indicate when the component isn't selectable. Although setEnabled(false) disables the selection of the component, if the component has a border associated with it, the border still must be drawn, even when disabled. Figure 7-16 shows one border in action that looks at all these options for the component passed into the border's paintBorder() method.



Figure 7-16. Active custom border examples

The source for the custom border and the sample program is shown in Listing 7-3.

Listing 7-3. *Custom Colorized Border*

```
import javax.swing.*;
import javax.swing.border.*;
import java.awt.*;

public class RedGreenBorder extends AbstractBorder {
    public boolean isBorderOpaque() {
        return true;
    }
    public Insets getBorderInsets(Component c) {
        return new Insets(3, 3, 3, 3);
    }
    public void paintBorder(Component c, Graphics g, int x, int y, int width,
        int height) {
        Insets insets = getBorderInsets(c);
        Color horizontalColor;
        Color verticalColor;
        if (c.isEnabled()) {
            boolean pressed = false;
            if (c instanceof AbstractButton) {
                ButtonModel model = ((AbstractButton)c).getModel();
                pressed = model.isPressed();
            }
            if (pressed) {
                horizontalColor = Color.RED;
                verticalColor = Color.GREEN;
            } else {
                horizontalColor = Color.GREEN;
                verticalColor = Color.RED;
            }
        } else {
            horizontalColor = Color.LIGHT_GRAY;
            verticalColor = Color.LIGHT_GRAY;
        }
        g.setColor(horizontalColor);

        g.translate(x, y);

        // Top
        g.fillRect(0, 0, width, insets.top);
        // Bottom
        g.fillRect(0, height-insets.bottom, width, insets.bottom);
    }
}
```

```

        g.setColor(verticalColor);
        // Left
        g.fillRect(0, insets.top, insets.left, height-insets.top-insets.bottom);
        // Right
        g.fillRect(width-insets.right, insets.top, insets.right,
            height-insets.top-insets.bottom);
        g.translate(-x, -y);
    }
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("My Border");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                Border border = new RedGreenBorder();
                JButton helloButton = new JButton("Hello");
                helloButton.setBorder(border);
                JButton braveButton = new JButton("Brave New");
                braveButton.setBorder(border);
                braveButton.setEnabled(false);
                JButton worldButton = new JButton("World");
                worldButton.setBorder(border);
                frame.add(helloButton, BorderLayout.NORTH);
                frame.add(braveButton, BorderLayout.CENTER);
                frame.add(worldButton, BorderLayout.SOUTH);
                frame.setSize(300, 100);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

Note Another interesting custom border is one that displays an active component instead of a text title in a `TitledBorder`. Imagine a border that has a `JCheckBox` or `JRadioButton` instead of a text string for the title. You can also use a `JLabel` and pass in HTML for the text.

Summary

In this chapter, you learned about the use of the `Border` interface and its many predefined implementations. You also learned how to create predefined borders using the Factory design pattern provided by the `BorderFactory` class. Lastly, you saw how to define your own borders and why subclassing `AbstractBorder` is beneficial.

In Chapter 8, you'll move beyond low-level components and examine the window-like container objects available in Swing.



Root Pane Containers

In Chapter 7, you looked at working with borders around Swing components. In this chapter, you'll explore the high-level Swing containers and discover how they differ from their AWT counterparts.

Working with top-level containers in Swing is a bit different from working with top-level AWT containers. With the AWT containers of `Frame`, `Window`, `Dialog`, and `Applet`, you added components directly to the container, and there was only one place you could add them. In the Swing world, the top-level containers of `JFrame`, `JWindow`, `JDialog`, and `JApplet`, plus the `JInternalFrame` container, rely on something called a `JRootPane`. Instead of adding components directly to the container, you add them to a part of the *root pane*. The root pane then manages them all internally.

Why was this indirect layer added? Believe it or not, it was done to simplify things. The root pane manages its components in layers so that elements such as tooltip text will always appear *above* components, and you don't need to worry about dragging some components around behind others.

The one container without an AWT counterpart, `JInternalFrame`, also provides some additional capabilities when placed within a desktop (within a `JDesktopPane` to be specific). The `JInternalFrame` class can be used as the basis for creating a Multiple Document Interface (MDI) application architecture within a Swing program. You can manage a series of internal frames within your program, and they'll never go beyond the bounds of your main program window.

Let's begin by exploring the new `JRootPane` class, which manages the internals of all the top-level containers.

JRootPane Class

The `JRootPane` class acts as a container delegate for the top-level Swing containers. Because the container holds only a `JRootPane` when you add or remove components from a top-level container, instead of directly altering the components in the container, you indirectly add or remove components from its `JRootPane` instance. In effect, the top-level containers are acting as proxies, with the `JRootPane` doing all the work.

The `JRootPane` container relies on its inner class `RootLayout` for layout management and takes up all the space of the top-level container that holds it. There are only two components within a `JRootPane`: a `JLayeredPane` and a glass pane (`Component`). The glass pane is in front, can be any component, and tends to be invisible. The glass pane ensures that elements such as

tooltip text appear in front of any other Swing components. In the back is the `JLayeredPane`, which contains an optional `JMenuBar` on top and a content pane (Container) below it in another layer. It is within the content pane that you would normally place components in the `JRootPane`. Figure 8-1 should help you visualize how the `RootLayout` lays out the components.




Figure 8-1. *JRootPane* containment diagram

Note A `JLayeredPane` is just another Swing container (it's described later in this chapter). It can contain any components and has a special layering characteristic. The default `JLayeredPane` used within the `JRootPane` pane contains only a `JMenuBar` and a Container as its content pane. The content pane has its own layout manager, which is `BorderLayout` by default.

Creating a `JRootPane`

Although the `JRootPane` has a public no-argument constructor, a `JRootPane` isn't something you would normally create yourself. Instead, a class that implements the `RootPaneContainer` interface creates the `JRootPane`. Then, you can get the root pane from that component, through the `RootPaneContainer` interface, described shortly.

`JRootPane` Properties

As Table 8-1 shows, there are 11 properties of `JRootPane`. In most cases, when you get or set one of these properties for a top-level container, like `JFrame`, the container simply passes along the request to its `JRootPane`.

The glass pane for a `JRootPane` must not be opaque. Because the glass pane takes up the entire area in front of the `JLayeredPane`, an opaque glass pane would render the menu bar and content pane invisible. And, because the glass pane and content pane share the same bounds, the `optimizedDrawingEnabled` property returns the visibility of the glass pane as its setting.

Table 8-1. *JRootPane Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>contentPane</code>	<code>Container</code>	Read-write
<code>defaultButton</code>	<code>JButton</code>	Read-write bound
<code>glassPane</code>	<code>Component</code>	Read-write
<code>jMenuBar</code>	<code>JMenuBar</code>	Read-write
<code>layeredPane</code>	<code>JLayeredPane</code>	Read-write
<code>optimizedDrawingEnabled</code>	<code>boolean</code>	Read-only
<code>UI</code>	<code>RootPaneUI</code>	Read-write
<code>UIClassID</code>	<code>String</code>	Read-only
<code>validateRoot</code>	<code>boolean</code>	Read-only
<code>windowDecorationStyle</code>	<code>int</code>	Read-write bound

The `windowDecorationStyle` property is meant to describe the window adornments (border, title, buttons for closing window) for the window containing the `JRootPane`. It can be set to one of the following `JRootPane` class constants:

- `COLOR_CHOOSER_DIALOG`
- `ERROR_DIALOG`
- `FILE_CHOOSER_DIALOG`
- `FRAME`
- `INFORMATION_DIALOG`
- `NONE`
- `PLAIN_DIALOG`
- `QUESTION_DIALOG`
- `WARNING_DIALOG`

What exactly happens with the `windowDecorationStyle` setting depends on the current look and feel. It is just a hint. By default, this setting is `NONE`. If this setting is not `NONE`, the `setUndecorated()` method of `JDialog` or `JFrame` has been called with a value of `true`, and the `getSupportsWindowDecorations()` method of the current look and feel reports `true`, then the look and feel, rather than the window manager, will provide the window adornments. This allows you to have programs with top-level windows that look like they do not come from the platform the user is working on but from your own environment, though still providing iconify, maximize, minimize, and close buttons.

For the Metal look and feel (and Ocean theme), `getSupportsWindowDecorations()` reports `true`. The other system-provided look and feel types report `false`. Figure 8-2 demonstrates what a frame looks like with the window adornments provided by the Metal look and feel.




Figure 8-2. *Metal window adornments for a JFrame*

The source to produce Figure 8-2 is shown in Listing 8-1.

Listing 8-1. *Setting the Window Decoration Style*

```
import java.awt.*;
import javax.swing.*;

public class AdornSample {

    public static void main(final String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Adornment Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                frame.setUndecorated(true);
                frame.getRootPane().setWindowDecorationStyle(JRootPane.FRAME);
                frame.setSize(300, 100);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

Customizing a JRootPane Look and Feel

Table 8-2 shows the 12 `UIResource`-related properties for a `JRootPane`. Most of these settings have to do with the default border to use when configuring the window decoration style.

Table 8-2. *JRootPane UIResource Elements*

Property String	Object Type
<code>RootPane.actionMap</code>	<code>ActionMap</code>
<code>RootPane.ancestorInputMap</code>	<code>InputMap</code>
<code>RootPane.colorChooserDialogBorder</code>	<code>Border</code>

Table 8-2. *JRootPane UIResource Elements (Continued)*

Property String	Object Type
RootPane.defaultButtonWindowKeyBindings	Object[]
RootPane.errorDialogBorder	Border
RootPane.fileChooserDialogBorder	Border
RootPane.frameBorder	Border
RootPane.informationDialogBorder	Border
RootPane.plainDialogBorder	Border
RootPane.questionDialogBorder	Border
RootPane.warningDialogBorder	Border
RootPaneUI	String

RootPaneContainer Interface

The `RootPaneContainer` interface defines the setter/getter methods for accessing the different panes within the `JRootPane`, as well as accessing the `JRootPane` itself.

```
public interface RootPaneContainer {
    // Properties
    public Container getContentPane();
    public void setContentPane(Container contentPane);
    public Component getGlassPane();
    public void setGlassPane(Component glassPane);
    public JLayeredPane getLayeredPane();
    public void setLayeredPane(JLayeredPane layeredPane);
    public JRootPane getRootPane();
}
```

Among the predefined Swing components, the `JFrame`, `JWindow`, `JDialog`, `JApplet`, and `JInternalFrame` classes implement the `RootPaneContainer` interface. For the most part, these implementations simply pass along the request to a `JRootPane` implementation for the high-level container. The following source code is one such implementation for the glass pane of a `RootPaneContainer` implementer:

```
public Component getGlassPane() {
    return getRootPane().getGlassPane();
}
public void setGlassPane(Component glassPane) {
    getRootPane().setGlassPane(glassPane);
}
```

JLayeredPane Class

The `JLayeredPane` serves as the main component container of a `JRootPane`. The `JLayeredPane` manages the z-order, or layering, of components within itself. This ensures that the correct

component is drawn on top of other components for tasks such as creating tooltip text, pop-up menus, and dragging for drag-and-drop. You can use the system-defined layers, or you can create your own layers.

Although initially a `JLayeredPane` container has no layout manager, there's nothing to stop you from setting the layout property of the container, defeating the layering aspect of the container.

Creating a `JLayeredPane`

As with the `JRootPane`, you'll almost never create an instance of the `JLayeredPane` class yourself. When the default `JRootPane` is created for one of the predefined classes that implement `RootPaneContainer`, the `JRootPane` creates a `JLayeredPane` for its main component area, adding an initial content pane.

Adding Components in Layers

A layer setting for each added component manages the z-order of components within a `JLayeredPane`. The higher the layer setting, the closer to the top the component will be drawn. You can set the layer with the layout manager constraints when you add a component to a `JLayeredPane`:

```
Integer layer = new Integer(20);
aLayeredPane.add(aComponent, layer);
```

You can also call the public void `setLayer(Component comp, int layer)` or public void `setLayer(Component comp, int layer, int position)` method *before* adding the component to the `JLayeredPane`.

```
aLayeredPane.setLayer(aComponent, 10);
aLayeredPane.add(aComponent);
```

The `JLayeredPane` class predefines six constants for special values. In addition, you can find out the topmost current layer with public `int c` and the bottom layer with public `int lowestLayer()`. Table 8-3 lists the six predefined layer constants.

Table 8-3. *JLayeredPane Layer Constants*

Constant	Description
FRAME_CONTENT_LAYER	Level -30,000 for holding the menu bar and content pane; not normally used by developers
DEFAULT_LAYER	Level 0 for the normal component level
PALETTE_LAYER	Level 100 for holding floating toolbars and the like
MODAL_LAYER	Level 200 for holding pop-up dialog boxes that appear on top of components on the default layer, on top of palettes, and below pop-ups
POPUP_LAYER	Level 300 for holding pop-up menus and tooltips
DRAW_LAYER	Level 400 for ensuring that dragged objects remain on top

Although you can use your own constants for layers, use them with care—because the system will use the predefined constants for *its* needs. If your constants don't fit in properly, the components may not work as you intended.

To visualize how the different layers fit in, see Figure 8-3.




Figure 8-3. *JLayeredPane* layers

Working with Component Layers and Positions

Components in a `JLayeredPane` have both a layer and a position. When a single component is on a layer, it's at position 0. When multiple components are on the same layer, components added later have higher position numbers. The lower the position setting, the closer to the top the component will appear. (This is the reverse of the layering behavior.) Figure 8-4 shows the positions for four components on the same layer.

To rearrange components on a single layer, you can use either the public `void moveToBack(Component component)` or public `void moveToFront(Component component)` method. When you move a component to the front, it goes to position 0 for the layer. When you move a component to the back, it goes to the highest position number for the layer. You can also manually set the position with public `void setPosition(Component component, int position)`. A position of -1 is automatically the bottom layer with the highest position (see Figure 8-4).




Figure 8-4. *JLayeredPane* positions

JLayeredPane Properties

Table 8-4 shows the two properties of `JLayeredPane`. The `optimizedDrawingEnabled` property determines whether components within the `JLayeredPane` can overlap. By default, this setting is true because in the standard usage with `JRootPane` the `JMenuBar` and content pane can't overlap. However, the `JLayeredPane` automatically validates the property setting to reflect the current state of the contents of the pane.

Table 8-4. *JLayeredPane* Properties

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>optimizedDrawingEnabled</code>	<code>boolean</code>	Read-only

JFrame Class

The `JFrame` class is the Swing high-level container that uses a `JRootPane` and implements the `RootPaneContainer` interface. In addition, it uses the `WindowConstants` interface to help manage closing operations.

Creating a JFrame

The `JFrame` class provides two primary constructors: one for creating a frame without a title and one for creating a frame with a title. There are two additional constructors for creating frames with a specialized `GraphicsConfiguration`.

```
public JFrame()
```

```
JFrame frame = new JFrame();
```

```
public JFrame(String title)
```

```
JFrame frame = new JFrame("Title Bar");
```

```
public JFrame(GraphicsConfiguration config)
```

```
GraphicsEnvironment ge = GraphicsEnvironment.getLocalGraphicsEnvironment();
```

```
GraphicsDevice gsd[] = ge.getScreenDevices();
```

```
GraphicsConfiguration gc[] = gsd[0].getConfigurations();
```

```
JFrame frame = new JFrame(gc[0]);
```

```
public JFrame(String title, GraphicsConfiguration config)
```

```
GraphicsConfiguration gc = ...;
```

```
JFrame frame = new JFrame("Title Bar", gc);
```

JFrame Properties

Table 8-5 shows the nine properties of the `JFrame`.

Table 8-5. *JFrame Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>contentPane</code>	<code>Container</code>	Read-write
<code>defaultCloseOperation</code>	<code>int</code>	Read-write
<code>glassPane</code>	<code>Component</code>	Read-write
<code>iconImage</code>	<code>Image</code>	Write-only
<code>jMenuBar</code>	<code>JMenuBar</code>	Read-write
<code>layeredPane</code>	<code>JLayeredPane</code>	Read-write
<code>layout</code>	<code>LayoutManager</code>	Write-only
<code>rootPane</code>	<code>JRootPane</code>	Read-only

Although most properties are the result of implementing the `RootPaneContainer` interface, two properties are special: `defaultCloseOperation` and `layout`. (You first looked at the `defaultCloseOperation` property in Chapter 2.) By default, a `JFrame` hides itself when the user closes the window. To change the setting, you can use one of the constants listed in Table 8-6 as arguments when setting the default close operation. The first comes from `JFrame` directly; the others are part of the `WindowConstants` interface.

```
aFrame.setDefaultCloseOperation(JFrame.DISPOSE_ON_CLOSE);
```

Table 8-6. *Close Operation Constants*

Constant	Description
<code>EXIT_ON_CLOSE</code>	Call <code>System.exit(0)</code> .
<code>DISPOSE_ON_CLOSE</code>	Call <code>dispose()</code> on the frame.
<code>DO_NOTHING_ON_CLOSE</code>	Ignore the request.
<code>HIDE_ON_CLOSE</code>	Call <code>setVisible(false)</code> on the frame; this is the default.

The `layout` property is odd. By default, setting the layout manager of the `JFrame` passes the call along to the content pane. You can't change the default layout manager of the `JFrame`.

Tip You can use the `state` property (inherited from `Frame`) to say whether the `JFrame` is currently iconified. When using the property, be sure to use one of the additional `Frame` constants of `NORMAL` or `ICONIFIED` to set its state.

There is an additional static property of `JFrame`: `defaultLookAndFeelDecorated`. This works with the `windowDecorationStyle` property of `JRootPane`. When set to `true`, newly created frames will be adorned with decorations from the look and feel instead of the window manager. Of course, this happens only if the current look and feel supports window decorations. Listing 8-2 shows an alternate way to generate the same screen (with the window adornments provided by the Metal look and feel) as the one shown earlier in Figure 8-2.

Listing 8-2. *Alternative Way of Setting the Window Decoration Style*

```
import java.awt.*;
import javax.swing.*;

public class AdornSample2 {
```

```

public static void main(final String args[]) {
    Runnable runner = new Runnable() {
        public void run() {
            JFrame.setDefaultLookAndFeelDecorated(true);
            JFrame frame = new JFrame("Adornment Example");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
            frame.setSize(300, 100);
            frame.setVisible(true);
        }
    };
    EventQueue.invokeLater(runner);
}
}

```

Adding Components to a JFrame

Because `JFrame` implements the `RootPaneContainer` interface and uses a `JRootPane`, you don't add components directly to the `JFrame`. Instead, you add them to the `JRootPane` contained within the `JFrame`. Prior to J2SE 5.0, you needed to add components like this:

```

JRootPane rootPane = aJFrame.getRootPane();
Container contentPane = rootPane.getContentPane();
contentPane.add(...);

```

This can be shortened to the following form:

```
aJFrame.getContentPane().add(...);
```

If you tried to add components directly to the `JFrame`, it resulted in a runtime error being thrown.

Due to many suggestions (complaints?), Sun finally decided to change the `add()` method into a proxy:

```

// J2SE 5.0
aJFrame.add(...);

```

With J2SE 5.0, when you add components to the `JFrame`, they actually are added to the content pane of the `RootPaneContainer`.

Handling JFrame Events

The `JFrame` class supports the registration of eleven different listeners:

- `ComponentListener`: To find out when the frame moves or is resized.
- `ContainerListener`: Normally not added to a `JFrame` because you add components to the content pane of its `JRootPane`.
- `FocusListener`: To find out when the frame gets or loses input focus.

- **HierarchyBoundsListener:** To find out when the frame moves or is resized. This works similarly to **ComponentListener**, since the frame is the top-level container of component.
- **HierarchyListener:** To find out when the frame is shown or hidden.
- **InputMethodListener:** To work with input methods for internationalization.
- **KeyListener:** Normally not added to a **JFrame**. Instead, you register a keyboard action for its content pane, like this:

```
JPanel content = (JPanel)frame.getContentPane();
KeyStroke stroke = KeyStroke.getKeyStroke(KeyEvent.VK_ESCAPE, 0);
content.registerKeyboardAction(actionListener, stroke,
    JComponent.WHEN_IN_FOCUSED_WINDOW);
```

- **MouseListener** and **MouseMotionListener:** To listen for mouse and mouse motion events.
- **PropertyChangeListener:** To listen for changes to bound properties.
- **WindowListener:** To find out when a window is iconified or deiconified or a user is trying to open or close the window.

With the help of the **defaultCloseOperation** property, you typically don't need to add a **WindowListener** to help with closing the frame or stopping the application.

Extending JFrame

If you need to extend **JFrame**, this class has two important protected methods:

```
protected void frameInit()
protected JRootPane createRootPane()
```

By overriding either of these methods in a subclass, you can customize the initial appearance and behavior of the frame or that of its **JRootPane**. For example, in the **ExitableJFrame** class shown in Listing 8-3, the default close operation is initialized to the **EXIT_ON_CLOSE** state. Instead of calling **setDefaultCloseOperation()** for every frame created, you can use this class instead. Because **JFrame** was subclassed, you don't need to add a call to the **frameInit()** method in either of the constructors. The parent class automatically calls the method.

Listing 8-3. Closing Frames by Default

```
import javax.swing.JFrame;
public class ExitableJFrame extends JFrame {
    public ExitableJFrame () {
    }
    public ExitableJFrame (String title) {
        super (title);
    }
}
```

```
protected void frameInit() {  
    super.frameInit();  
    setDefaultCloseOperation(EXIT_ON_CLOSE);  
}  
}
```

Caution If you do override the `frameInit()` method of `JFrame`, remember to call `super.frameInit()` first, to initialize the default behaviors. If you forget and don't reimplement all the default behaviors yourself, your new frame will look and act differently.

JWindow Class

The `JWindow` class is similar to the `JFrame` class. It uses a `JRootPane` for component management and implements the `RootPaneContainer` interface. Basically, it is a top-level window with no adornments.

Creating a JWindow

The `JWindow` class has five constructors:

```
public JWindow()  
JWindow window = new JWindow();  
  
public JWindow(Frame owner)  
JWindow window = new JWindow(aFrame);  
  
public JWindow(GraphicsConfiguration config)  
GraphicsConfiguration gc = ...;  
JWindow window = new JWindow(gc);  
  
public JWindow(Window owner)  
JWindow window = new JWindow(anotherWindow);  
  
public JWindow(Window owner, GraphicsConfiguration config)  
GraphicsConfiguration gc = ...;  
JWindow window = new JWindow(anotherWindow, gc);
```

You can create a window without specifying a parent or by specifying the parent as a `Frame` or `Window`. If no parent is specified, an invisible one is used.

JWindow Properties

Table 8-7 lists the six properties of JWindow. These are similar in nature to the JFrame properties, except that JWindow has no property for a default close operation or a menu bar.

Table 8-7. *JWindow Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
contentPane	Container	Read-write
glassPane	Component	Read-write
layeredPane	JLayeredPane	Read-write
layout	LayoutManager	Write-only
rootPane	JRootPane	Read-only

Handling JWindow Events

The JWindow class adds no additional event-handling capabilities beyond those of the JFrame and Window classes. See the “Handling JFrame Events” section earlier in this chapter for a list of listeners you can attach to a JWindow.

Extending JWindow

If you need to extend JWindow, the class has two protected methods of importance:

```
protected void windowInit()
protected JRootPane createRootPane()
```

JDialog Class

The JDialog class represents the standard pop-up window for displaying information related to a Frame. It acts like a JFrame, whereby its JRootPane contains a content pane and an optional JMenuBar, and it implements the RootPaneContainer and WindowConstants interfaces.

Creating a JDialog

There are 11 constructors for creating JDialog windows:

```
public JDialog()
JDialog dialog = new JDialog();

public JDialog(Dialog owner)
JDialog dialog = new JDialog(anotherDialog);
```

```
public JDialog(Dialog owner, boolean modal)
JDialog dialog = new JDialog(anotherDialog, true);

public JDialog(Dialog owner, String title)
JDialog dialog = new JDialog(anotherDialog, "Hello");

public JDialog(Dialog owner, String title, boolean modal)
JDialog dialog = new JDialog(anotherDialog, "Hello", true);

public JDialog(Dialog owner, String title, boolean modal, GraphicsConfiguration gc)
GraphicsConfiguration gc = ...;
JDialog dialog = new JDialog(anotherDialog, "Hello", true, gc);

public JDialog(Frame owner)
JDialog dialog = new JDialog(aFrame);

public JDialog(Frame owner, String windowTitle)
JDialog dialog = new JDialog(aFrame, "Hello");

public JDialog(Frame owner, boolean modal)
JDialog dialog = new JDialog(aFrame, false);

public JDialog(Frame owner, String title, boolean modal)
JDialog dialog = new JDialog(aFrame, "Hello", true);

public JDialog(Frame owner, String title, boolean modal, GraphicsConfiguration gc)
GraphicsConfiguration gc = ...;
JDialog dialog = new JDialog(aFrame, "Hello", true, gc);
```

■ **Note** Instead of manually creating a `JDialog` and populating it, you may find yourself having `JOptionPane` automatically create and fill the `JDialog` for you. You'll explore the `JOptionPane` component in Chapter 9.

Each constructor allows you to customize the dialog owner, the window title, and the modality of the pop-up. When a `JDialog` is modal, it blocks input to the owner and the rest of the application. When a `JDialog` is nonmodal, it allows a user to interact with the `JDialog` as well as the rest of your application.

■ **Caution** For modality to work properly among the different Java versions, avoid mixing heavyweight AWT components with lightweight Swing components in a `JDialog`.

JDialog Properties

Other than the settable icon image, the `JDialog` class has the same properties as `JFrame`. These eight properties are listed in Table 8-8.

Table 8-8. *JDialog Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>contentPane</code>	<code>Container</code>	Read-write
<code>defaultCloseOperation</code>	<code>int</code>	Read-write
<code>glassPane</code>	<code>Component</code>	Read-write
<code>jMenuBar</code>	<code>JMenuBar</code>	Read-write
<code>layeredPane</code>	<code>JLayeredPane</code>	Read-write
<code>layout</code>	<code>LayoutManager</code>	Write-only
<code>rootPane</code>	<code>JRootPane</code>	Read-only

The constants to use for specifying the default close operation are the `WindowConstants` shown earlier in Table 8-6 (basically all but `EXIT_ON_CLOSE`). By default, the `defaultCloseOperation` property is set to `HIDE_ON_CLOSE`, which is the desirable default behavior for a dialog pop-up.

Like `JFrame`, `JDialog` also has a static `defaultLookAndFeelDecorated` property. This controls whether or not dialogs are decorated by the look and feel, by default.

Handling JDialog Events

There are no special `JDialog` events for you to deal with; it has the same events as those for the `JFrame` class.

One thing that you may want to do with a `JDialog` is specify that pressing the Escape key cancels the dialog. The easiest way to do this is to register an Escape keystroke to a keyboard action within the `JRootPane` of the dialog, causing the `JDialog` to become hidden when Escape is pressed. Listing 8-4 demonstrates this behavior. Most of the source duplicates the constructors of `JDialog`. The `createRootPane()` method maps the Escape key to the custom `Action`.

Listing 8-4. *A JDialog That Closes When Escape Is Pressed*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class EscapeDialog extends JDialog {
    public EscapeDialog() {
        this((Frame)null, false);
    }
}
```

```

public EscapeDialog(Frame owner) {
    this(owner, false);
}
public EscapeDialog(Frame owner, boolean modal) {
    this(owner, null, modal);
}
public EscapeDialog(Frame owner, String title) {
    this(owner, title, false);
}
public EscapeDialog(Frame owner, String title, boolean modal) {
    super(owner, title, modal);
}
public EscapeDialog(Frame owner, String title, boolean modal,
    GraphicsConfiguration gc) {
    super(owner, title, modal, gc);
}
public EscapeDialog(Dialog owner) {
    this(owner, false);
}
public EscapeDialog(Dialog owner, boolean modal) {
    this(owner, null, modal);
}
public EscapeDialog(Dialog owner, String title) {
    this(owner, title, false);
}
public EscapeDialog(Dialog owner, String title, boolean modal) {
    super(owner, title, modal);
}
public EscapeDialog(Dialog owner, String title, boolean modal,
    GraphicsConfiguration gc) {
    super(owner, title, modal, gc);
}
protected JRootPane createRootPane() {
    JRootPane rootPane = new JRootPane();
    KeyStroke stroke = KeyStroke.getKeyStroke("ESCAPE");
    Action actionListener = new AbstractAction() {
        public void actionPerformed(ActionEvent actionEvent) {
            setVisible(false);
        }
    };
    InputMap inputMap = rootPane.getInputMap(JComponent.WHEN_IN_FOCUSED_WINDOW);
    inputMap.put(stroke, "ESCAPE");
    rootPane.getActionMap().put("ESCAPE", actionListener);

    return rootPane;
}
}

```

Note If you use the static creation methods of `JOptionPane`, the `JDialog` windows it creates automatically have the Escape key registered to close the dialog.

Extending JDialog

If you need to extend `JDialog`, the class has two protected methods of importance:

```
protected void dialogInit()  
protected JRootPane createRootPane()
```

The latter method is demonstrated in the previous example in Listing 8-4.

JApplet Class

The `JApplet` class is an extension to the AWT `Applet` class. For event handling to work properly within applets that use Swing components, your applets must subclass `JApplet` instead of `Applet`.

The `JApplet` works the same as the other high-level containers by implementing the `RootPaneContainer` interface. One important difference between `JApplet` and `Applet` is the default layout manager. Because you add components to the content pane of a `JApplet`, its default layout manager is `BorderLayout`. This is unlike the default layout manager of `Applet`, which is `FlowLayout`. In addition, Swing applets can also have a menu bar, or more specifically a `JMenuBar`, which is just another attribute of the `JRootPane` of the applet.

If you plan to deploy an applet that uses the Swing components, it is best to use the Java Plug-in from Sun Microsystems, because that will install the Swing libraries with the runtime.

Tip To make sure you are running the Java Plug-in under Internet Explorer, select Internet Options from the Tools menu, and then choose the Advanced tab. Scroll down to the Java section immediately above Microsoft VM and make sure Use JRE [VERSION] for <applet> (requires restart) is selected. If [VERSION] isn't recent enough, you'll need to get a newer version from Sun at <http://www.java.com>.

If you need to extend the `JApplet` class, it has only one protected method of importance:

```
protected JRootPane createRootPane()
```

Working with a Desktop

Swing provides for the management of a set of frames within a common window or desktop. As discussed in Chapter 1, this management is commonly called MDI. The frames can be layered on top of one another or dragged around, and their appearance is specific to the current look and feel. The frames are instances of the `JInternalFrame` class, whereas the desktop is a specialized `JLayeredPane` called `JDesktopPane`. The management of the frames within a desktop is the responsibility of a `DesktopManager`, in which the default implementation that's provided is `DefaultDesktopManager`. The iconified form of a `JInternalFrame` on the desktop is represented

by the `JDesktopIcon` inner class of `JInternalFrame`. There are also an `InternalFrameListener`, `InternalFrameAdapter`, and `InternalFrameEvent` for event handling.

First, let's look at the parts that make up the desktop, and then you'll see a complete example that uses all the parts.

Note The Swing libraries provide only those tools necessary to build an application using MDI. You use these tools in whatever manner you see fit.

JInternalFrame Class

The `JInternalFrame` class is similar to the `JFrame` class. It acts as a high-level container, using the `RootPaneContainer` interface, but it isn't a top-level window. You must place internal frames within another top-level window. When dragged around, internal frames stay within the bounds of their container, which is usually a `JDesktopPane`. In addition, internal frames are lightweight and therefore offer a UI-delegate to make internal frames appear as the currently configured look and feel.

Note As with the creation of a `JFrame`, the `JInternalFrame` is hidden when first created.

Creating a JInternalFrame

There are six constructors for `JInternalFrame`:

```
public JInternalFrame()
JInternalFrame frame = new JInternalFrame();

public JInternalFrame(String title)
JInternalFrame frame = new JInternalFrame("The Title");

public JInternalFrame(String title, boolean resizable)
JInternalFrame frame = new JInternalFrame("The Title", true);

public JInternalFrame(String title, boolean resizable, boolean closable)
JInternalFrame frame = new JInternalFrame("The Title", false, true);

public JInternalFrame(String title, boolean resizable, boolean
    closable, boolean maximizable)
JInternalFrame frame = new JInternalFrame("The Title", true, false, true);

public JInternalFrame(String title, boolean resizable, boolean
    closable, boolean maximizable, boolean iconifiable)
JInternalFrame frame = new JInternalFrame("The Title", false, true, false, true);
```

These constructors cascade in such a way that each adds a parameter to another constructor. With no arguments, the created `JInternalFrame` has no title and can't be resized, closed, maximized, or iconified. Internal frames can always be dragged, however.

Note In addition to your creating a `JInternalFrame` directly, you can rely on the `JOptionPane` to create an internal frame for common pop-up dialog boxes hosted by a `JInternalFrame` instead of being hosted by the standard `JDialog`.

JInternalFrame Properties

The 30 different properties for the `JInternalFrame` class are listed in Table 8-9. The `layer` property is listed twice as it has two setter methods, one for an `int` and another for an `Integer`.

Table 8-9. *JInternalFrame Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>closable</code>	<code>boolean</code>	Read-write bound
<code>closed</code>	<code>boolean</code>	Read-write bound constrained
<code>contentPane</code>	<code>Container</code>	Read-write bound
<code>defaultCloseOperation</code>	<code>int</code>	Read-write
<code>desktopIcon</code>	<code>JInternalFrame.JDesktopIcon</code>	Read-write bound
<code>desktopPane</code>	<code>JDesktopPane</code>	Read-only
<code>focusCycleRoot</code>	<code>boolean</code>	Read-write
<code>focusCycleRootAncestor</code>	<code>Container</code>	Read-only
<code>focusOwner</code>	<code>Component</code>	Read-only
<code>frameIcon</code>	<code>Icon</code>	Read-write bound
<code>glassPane</code>	<code>Component</code>	Read-write bound
<code>icon</code>	<code>boolean</code>	Read-write bound constrained
<code>iconifiable</code>	<code>boolean</code>	Read-write
<code>internalFrameListeners</code>	<code>InternalFrameListener[]</code>	Read-only
<code>jMenuBar</code>	<code>JMenuBar</code>	Read-write bound
<code>layer</code>	<code>int</code>	Read-write
<code>layer</code>	<code>Integer</code>	Write-only
<code>layeredPane</code>	<code>JLayeredPane</code>	Read-write bound

Table 8-9. *JInternalFrame Properties (Continued)*

Property Name	Data Type	Access
layout	LayoutManager	Write-only
maximizable	boolean	Read-write bound
maximum	boolean	Read-write bound constrained
mostRecentFocusOwner	Component	Read-only
normalBounds	Rectangle	Read-write
resizable	boolean	Read-write bound
rootPane	JRootPane	Read-only bound
selected	boolean	Read-write bound constrained
title	String	Read-write bound
UI	InternalFrameUI	Read-write
UIClassID	String	Read-only
warningString	String	Read-only

The initial defaultCloseOperation property setting for a JInternalFrame is DISPOSE_ON_CLOSE for Java 1.3 releases and later. Earlier releases had a default setting of HIDE_ON_CLOSE. You can set this property to any of the WindowConstants settings shown earlier in Table 8-6.

The normalBounds property describes where an iconified internal frame would appear when deiconified. The focusOwner property provides the actual Component with the input focus when the specific JInternalFrame is active.

The JInternalFrame contains the only four constrained properties within the Swing classes: closed, icon, maximum, and selected. They're directly related to the four boolean constructor parameters. Each allows you to check on the current state of the property as well as change its setting. However, because the properties are constrained, whenever you try to set one, the attempt must be in a try-catch block, catching PropertyVetoException:

```
try {
    // Try to iconify internal frame
    internalFrame.setIcon(false);
} catch (PropertyVetoException propertyVetoException) {
    System.out.println("Rejected");
}
```

To help you work with some of the bound properties, the JInternalFrame class defines 11 constants, as listed in Table 8-10. They represent the string that should be returned by getPropertyName() for a PropertyChangeEvent within a PropertyChangeListener.

Table 8-10. *JInternalFrame Property Constants*

Property Name Constant	Associated Property
CONTENT_PANE_PROPERTY	contentPane
FRAME_ICON_PROPERTY	frameIcon
GLASS_PANE_PROPERTY	glassPane
IS_CLOSED_PROPERTY	closed
IS_ICON_PROPERTY	icon
IS_MAXIMUM_PROPERTY	maximum
IS_SELECTED_PROPERTY	selected
LAYERED_PANE_PROPERTY	layeredPane
MENU_BAR_PROPERTY	jMenuBar
ROOT_PANE_PROPERTY	rootPane
TITLE_PROPERTY	title

The following class example demonstrates the use of the constants within a `PropertyChangeListener`.

```
import java.beans.*;
import javax.swing.*;

public class InternalFramePropertyChangeHandler implements PropertyChangeListener {
    public void propertyChange(PropertyChangeEvent propertyChangeEvent) {
        String propertyName = propertyChangeEvent.getPropertyName();
        if (propertyName.equals(JInternalFrame.IS_ICON_PROPERTY)) {
            System.out.println("Icon property changed. React.");
        }
    }
}
```

Handling `JInternalFrame` Events

To help you use a `JInternalFrame` as you would use a `JFrame`, there's an additional event listener for responding to internal frame opening- and closing-related events. The interface is called `InternalFrameListener`, and its definition follows. It works similarly to the AWT `WindowListener` interface, but with a `JInternalFrame` instead of an AWT `Window` class.

```
public interface InternalFrameListener extends EventListener {
    public void internalFrameActivated(InternalFrameEvent internalFrameEvent);
    public void internalFrameClosed(InternalFrameEvent internalFrameEvent);
    public void internalFrameClosing(InternalFrameEvent internalFrameEvent);
    public void internalFrameDeactivated(InternalFrameEvent internalFrameEvent);
    public void internalFrameDeiconified(InternalFrameEvent internalFrameEvent);
    public void internalFrameIconified(InternalFrameEvent internalFrameEvent);
    public void internalFrameOpened(InternalFrameEvent internalFrameEvent);
}
```

In addition, like the `WindowAdapter` class that has all the `WindowListener` methods stubbed out, there is an `InternalFrameAdapter` class with all the `InternalFrameListener` methods stubbed out. If you're not interested in all the event happenings of a `JInternalFrame`, you can subclass `InternalFrameAdapter` and override only those methods you're interested in. For instance, the listener shown in Listing 8-5 is interested in only the iconification methods. Instead of providing stubs for the other five methods of `InternalFrameListener`, you would need to subclass only `InternalFrameAdapter` and override the two relevant methods.

Listing 8-5. *Custom InternalFrameListener*

```
import javax.swing.*;
import javax.swing.event.*;

public class InternalFrameIconifyListener extends InternalFrameAdapter {
    public void internalFrameIconified(InternalFrameEvent internalFrameEvent) {
        JInternalFrame source = (JInternalFrame)internalFrameEvent.getSource();
        System.out.println ("Iconified: " + source.getTitle());
    }
    public void internalFrameDeiconified(InternalFrameEvent internalFrameEvent) {
        JInternalFrame source = (JInternalFrame)internalFrameEvent.getSource();
        System.out.println ("Deiconified: " + source.getTitle());
    }
}
```

The `InternalFrameEvent` class is a subclass of `AWTEvent`. To define the values returned by the public `int getID()` method of `AWTEvent`, the `InternalFrameEvent` class defines a constant for each of the specific event subtypes that can be used. In addition, two other constants designate the range of valid values. Table 8-11 lists the nine constants. You can also get the actual `JInternalFrame` from the event with `getInternalFrame()`.


Table 8-11. *InternalFrameEvent Event Subtypes*

Event Subtype ID	Associated Interface Method
<code>INTERNAL_FRAME_ACTIVATED</code>	<code>internalFrameActivated</code>
<code>INTERNAL_FRAME_CLOSED</code>	<code>internalFrameClosed</code>
<code>INTERNAL_FRAME_CLOSING</code>	<code>internalFrameClosing</code>
<code>INTERNAL_FRAME_DEACTIVATED</code>	<code>internalFrameDeactivated</code>
<code>INTERNAL_FRAME_DEICONIFIED</code>	<code>internalFrameDeiconified</code>
<code>INTERNAL_FRAME_FIRST</code>	N/A
<code>INTERNAL_FRAME_ICONIFIED</code>	<code>internalFrameIconified</code>
<code>INTERNAL_FRAME_LAST</code>	N/A
<code>INTERNAL_FRAME_OPENED</code>	<code>internalFrameOpened</code>


Customizing a `JInternalFrame` Look and Feel

Because the `JInternalFrame` is a lightweight component, it has an installable look and feel. Each installable Swing look and feel provides a different `JInternalFrame` appearance and set of


default UIResource values. Figure 8-5 shows the appearance of the JWindow container for the preinstalled set of look and feel types.



Motif



Windows



Ocean

Figure 8-5. *JInternalFrame* under different look and feel types

The available set of UIResource-related properties for a `JInternalFrame` is shown in Table 8-12. For the `JInternalFrame` component, there are 60 different properties, including those for the internal frame's title pane.

Table 8-12. *JInternalFrame* UIResource Elements

Property String	Object Type
<code>InternalFrame.actionMap</code>	ActionMap
<code>InternalFrame.activeBorderColor</code>	Color
<code>InternalFrame.activeTitleBackground</code>	Color
<code>InternalFrame.activeTitleForeground</code>	Color
<code>InternalFrame.activeTitleGradient</code>	List
<code>InternalFrame.border</code>	Border
<code>InternalFrame.borderColor</code>	Color
<code>InternalFrame.borderDarkShadow</code>	Color
<code>InternalFrame.borderHighlight</code>	Color
<code>InternalFrame.borderLight</code>	Color
<code>InternalFrame.borderShadow</code>	Color
<code>InternalFrame.borderWidth</code>	Integer
<code>InternalFrame.closeButtonToolTip</code>	String
<code>InternalFrame.closeIcon</code>	Icon
<code>InternalFrame.closeSound</code>	String
<code>InternalFrame.icon</code>	Icon
<code>InternalFrame.iconButtonToolTip</code>	String
<code>InternalFrame.iconifyIcon</code>	Icon
<code>InternalFrame.inactiveBorderColor</code>	Color
<code>InternalFrame.inactiveTitleBackground</code>	Color
<code>InternalFrame.inactiveTitleForeground</code>	Color
<code>InternalFrame.inactiveTitleGradient</code>	List
<code>InternalFrame.layoutTitlePaneAtOrigin</code>	Boolean
<code>InternalFrame.maxButtonToolTip</code>	String
<code>InternalFrame.maximizeIcon</code>	Icon
<code>InternalFrame.maximizeSound</code>	String
<code>InternalFrame.minimizeIcon</code>	Icon
<code>InternalFrame.minimizeIconBackground</code>	Color
<code>InternalFrame.minimizeSound</code>	String

Table 8-12. *JInternalFrame UIResource Elements (Continued)*

Property String	Object Type
<code>InternalFrame.optionDialogBorder</code>	<code>Border</code>
<code>InternalFrame.paletteBorder</code>	<code>Border</code>
<code>InternalFrame.paletteCloseIcon</code>	<code>Icon</code>
<code>InternalFrame.paletteTitleHeight</code>	<code>Integer</code>
<code>InternalFrame.resizeIconHighlight</code>	<code>Color</code>
<code>InternalFrame.resizeIconShadow</code>	<code>Color</code>
<code>InternalFrame.restoreButtonToolTip</code>	<code>String</code>
<code>InternalFrame.restoreDownSound</code>	<code>String</code>
<code>InternalFrame.restoreUpSound</code>	<code>String</code>
<code>InternalFrame.titleButtonHeight</code>	<code>Integer</code>
<code>InternalFrame.titleButtonWidth</code>	<code>Integer</code>
<code>InternalFrame.titleFont</code>	<code>Font</code>
<code>InternalFrame.titlePaneHeight</code>	<code>Integer</code>
<code>InternalFrame.useTaskBar</code>	<code>Boolean</code>
<code>InternalFrame.windowBindings</code>	<code>Object[]</code>
<code>InternalFrameTitlePane.closeButtonAccessibleName</code>	<code>String</code>
<code>InternalFrameTitlePane.closeButtonText</code>	<code>String</code>
<code>InternalFrameTitlePane.closeIcon</code>	<code>Icon</code>
<code>InternalFrameTitlePane.iconifyButtonAccessibleName</code>	<code>String</code>
<code>InternalFrameTitlePane.iconifyIcon</code>	<code>Icon</code>
<code>InternalFrameTitlePane.maximizeButtonAccessibleName</code>	<code>String</code>
<code>InternalFrameTitlePane.maximizeButtonText</code>	<code>String</code>
<code>InternalFrameTitlePane.maximizeIcon</code>	<code>Icon</code>
<code>InternalFrameTitlePane.minimizeButtonText</code>	<code>String</code>
<code>InternalFrameTitlePane.minimizeIcon</code>	<code>Icon</code>
<code>InternalFrameTitlePane.moveButtonText</code>	<code>String</code>
<code>InternalFrameTitlePane.restoreButtonText</code>	<code>String</code>
<code>InternalFrameTitlePane.sizeButtonText</code>	<code>String</code>
<code>InternalFrameTitlePane.titlePaneLayout</code>	<code>LayoutManager</code>
<code>InternalFrameTitlePaneUI</code>	<code>String</code>
<code>InternalFrameUI</code>	<code>String</code>

In addition to the many configurable properties in Table 8-12, with the Metal look and feel, you can designate an internal frame to be a “palette” by using a special client property, `JInternalFrame.isPalette`. When set to `Boolean.TRUE`, this internal frame will have a slightly different appearance from the others and a shorter title bar, as shown in Figure 8-6.




Figure 8-6. A *JInternalFrame* palette with other frames

If you also add an internal frame to the `PALETTE_LAYER` of the desktop, the frame will always appear on top of all the other frames (as noted in Figure 8-6):

```
JInternalFrame palette = new JInternalFrame("Palette", true, false, true, false);
palette.setBounds(150, 0, 100, 100);
palette.putClientProperty("JInternalFrame.isPalette", Boolean.TRUE);
desktop.add(palette, JDesktopPane.PALETTE_LAYER);
```

The complete source for creating the program in Figure 8-6 appears in Listing 8-6 later in this chapter.

Note If the current look and feel is something other than Metal, the palette layer will still be honored, but its appearance won't be quite as distinctive.

Changing the JDesktopIcon

The `JInternalFrame` relies on an inner class, `JDesktopIcon`, to provide a UI delegate for the iconified view of the `JInternalFrame`. The class is merely a specialized `JComponent` for providing this capability, not a specialized `Icon` implementation, as the name might imply. In fact, the `JDesktopIcon` class comments say that the class is temporary, so you shouldn't try to customize it directly. (Of course, the class has been around for some time now.)

If you do want to customize the `JDesktopIcon`, you can change some of the `UIResource`-related properties. Table 8-13 lists the eight `UIResource`-related properties for the `JDesktopIcon` component.

Table 8-13. *JInternalFrame.DesktopIcon UIResource Elements*

Property String	Object Type
DesktopIcon.background	Color
DesktopIcon.border	Border
DesktopIcon.font	Font
DesktopIcon.foreground	Color
DesktopIcon.icon	Icon
DesktopIcon.width	Integer
DesktopIcon.windowBindings	Object[]
DesktopIconUI	String

JDesktopPane Class

Another class for working with groups of internal frames is the `JDesktopPane` class. The sole purpose of the desktop pane is to contain a set of internal frames. When internal frames are contained within a desktop pane, they delegate most of their behavior to the desktop manager of the desktop pane. You'll also learn about the `DesktopManager` interface in greater detail later in this chapter.

Creating a JDesktopPane

The `JDesktopPane` has a single no-argument constructor. Once it's created, you'd typically place the desktop in the center of a container managed by a `BorderLayout`. This ensures that the desktop takes up all the room in the container.

Adding Internal Frames to a JDesktopPane

The `JDesktopPane` doesn't implement `RootPaneContainer`. Instead of adding components to the different panes within a `JRootPane`, you add them directly to the `JDesktopPane`:

```
desktop.add(anInternalFrame);
```

JDesktopPane Properties

As Table 8-14 shows, there are eight properties of `JDesktopPane`. The `JInternalFrame` at index 0 of the `allFrames` property array is the internal frame in front of the desktop (`JInternalFrame f = desktop.getAllFrames()[0]`). Besides getting all the frames within the `JDesktopPane`, you can get only those within a specific layer: `public JInternalFrame[] getAllFramesInLayer(int layer)`. (Remember `JLayeredPane`, covered earlier in this chapter in the "Working with Component Layers and Positions" section, the parent class of `JDesktopPane`?)

Valid `dragMode` property settings are the `LIVE_DRAG_MODE` and `OUTLINE_DRAG_MODE` constants of the class.

Table 8-14. *JDesktopPane Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
allFrames	JInternalFrame[]	Read-only
desktopManager	DesktopManager	Read-write
dragMode	int	Read-write bound
opaque	boolean	Read-only
selectedFrame	JInternalFrame	Read-write
UI	DesktopPaneUI	Read-write
UIClassID	String	Read-only

Note There is also a special client property (`JDesktopPane.dragMode`) for configuring the drawing mode when dragging an internal frame around. The client property has been replaced by the speedier versions available with the standard property.

Customizing a JDesktopPane Look and Feel

Back in Figure 8-5 you can see `JInternalFrame` objects within a `JDesktopPane`. The basic appearance of `JDesktopPane` is the same in each look and feel. As Table 8-15 shows, there aren't many `UIResource`-related properties for a `JDesktopPane` to configure.

Table 8-15. *JDesktopPane UIResource Elements*

Property String	Object Type
desktop	Color
Desktop.ancestorInputMap	InputMap
Desktop.background	Color
Desktop.windowBindings	Object[]
DesktopPane.actionMap	ActionMap
DesktopPaneUI	String

Complete Desktop Example

Now that you have the major desktop-related classes under your belt, let's look at a complete desktop example. The basic process involves creating a group of `JInternalFrame` objects and putting them in a single `JDesktopPane`. Event handling can be done for individual components on each of the internal frames, if desired, or for individual frames. In this example, simply use

the `InternalFrameIconifyListener` class, presented earlier in Listing 8-5, to listen for internal frames being iconified and deiconified.

Figure 8-6 shows how the program looks when it first starts. One particular internal frame has been designated a palette, and the outline drag mode is enabled.

The complete source for the example is shown in Listing 8-6.

Listing 8-6. *Mixing JInternalFrames and the JDesktopPane*

```
import javax.swing.*;
import javax.swing.event.*;
import java.awt.*;
import java.awt.event.*;

public class DesktopSample {

    public static void main(final String[] args) {
        Runnable runner = new Runnable() {
            public void run() {
                String title = (args.length==0 ? "Desktop Sample" : args[0]);
                JFrame frame = new JFrame(title);
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JDesktopPane desktop = new JDesktopPane();
                JInternalFrame internalFrames[] = {
                    new JInternalFrame("Can Do All", true, true, true, true),
                    new JInternalFrame("Not Resizable", false, true, true, true),
                    new JInternalFrame("Not Closable", true, false, true, true),
                    new JInternalFrame("Not Maximizable", true, true, false, true),
                    new JInternalFrame("Not Iconifiable", true, true, true, false)
                };

                InternalFrameListener internalFrameListener =
                    new InternalFrameIconifyListener();

                int pos = 0;
                for(JInternalFrame internalFrame: internalFrames) {
                    // Add to desktop
                    desktop.add(internalFrame);

                    // Position and size
                    internalFrame.setBounds(pos*25, pos*25, 200, 100);
                    pos++;

                    // Add listener for iconification events
                    internalFrame.addInternalFrameListener(internalFrameListener);

                    JLabel label = new JLabel(internalFrame.getTitle(), JLabel.CENTER);
                    internalFrame.add(label, BorderLayout.CENTER);
```

```

        // Make visible
        internalFrame.setVisible(true);
    }

    JInternalFrame palette =
        new JInternalFrame("Palette", true, false, true, false);
    palette.setBounds(350, 150, 100, 100);
    palette.putClientProperty("JInternalFrame.isPalette", Boolean.TRUE);
    desktop.add(palette, JDesktopPane.PALETTE_LAYER);
    palette.setVisible(true);

    desktop.setDragMode(JDesktopPane.OUTLINE_DRAG_MODE);

    frame.add(desktop, BorderLayout.CENTER);
    frame.setSize(500, 300);
    frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}
}

```

DesktopManager Interface

One remaining piece of the puzzle for working on a desktop is the desktop manager, which is an implementation of the DesktopManager interface, shown here:

```

public interface DesktopManager {
    public void activateFrame(JInternalFrame frame);
    public void beginDraggingFrame(JComponent frame);
    public void beginResizingFrame(JComponent frame, int direction);
    public void closeFrame(JInternalFrame frame);
    public void deactivateFrame(JInternalFrame frame);
    public void deiconifyFrame(JInternalFrame frame);
    public void dragFrame(JComponent frame, int newX, int newY);
    public void endDraggingFrame(JComponent frame);
    public void endResizingFrame(JComponent frame);
    public void iconifyFrame(JInternalFrame frame);
    public void maximizeFrame(JInternalFrame frame);
    public void minimizeFrame(JInternalFrame frame);
    public void openFrame(JInternalFrame frame);
    public void resizeFrame(JComponent frame, int newX, int newY, int newWidth,
        int newHeight);
    public void setBoundsForFrame(JComponent frame, int newX, int newY, int newWidth,
        int newHeight);
}

```

Note For the `DesktopManager` methods that accept a `JComponent` argument, the arguments are usually a `JInternalFrame` or another lightweight Swing component.

When `JInternalFrame` objects are in a `JDesktopPane`, they shouldn't attempt operations such as iconifying or maximizing themselves. Instead, they should ask the desktop manager of the desktop pane in which they're installed to perform the operation:

```
getDesktopPane().getDesktopManager().iconifyFrame(anInternalFrame);
```

The `DefaultDesktopManager` class provides one such implementation of a `DesktopManager`. If the default isn't sufficient, a look and feel might provide its own `DesktopManager` implementation class, as the Windows look and feel does with the `WindowsDesktopManager`. You can also define your own manager, but this usually isn't necessary.

Summary

In this chapter, you explored the `JRootPane` class and how implementers of the `RootPaneContainer` interface rely on a `JRootPane` for internal component management. You also learned how in Swing you work with the `JRootPane` of a `JFrame`, `JDialog`, `JWindow`, `JApplet`, or `JInternalFrame` class. The root pane can then layer components with the help of a `JLayeredPane` in such a way that tooltip text and pop-up menus will always appear above their associated components.

The `JInternalFrame` can also reside within a desktop environment, in which a `JDesktopPane` and `DesktopManager` manage how and where the internal frames act and appear. You can also respond to internal frame events by associating `InternalFrameListener` implementations with a `JInternalFrame`.

In Chapter 9, you'll examine the specialized pop-up components within the Swing libraries: `JColorChooser`, `JFileChooser`, `JOptionPane`, and `ProgressMonitor`.



Pop-Ups and Choosers

In Chapter 8, you looked at the top-level containers such as `JFrame` and `JApplet`. In addition, you explored the `JDialog` class used to create pop-up windows to display messages or get user input. Although the `JDialog` class works perfectly well, the Swing component set also offers several simpler approaches to get user input from pop-up windows, which you will explore in this chapter.

The `JOptionPane` class is useful for displaying messages, obtaining textual user input, or getting the answer to a question. The `ProgressMonitor` and `ProgressMonitorInputStream` classes enable you to monitor the progress of lengthy tasks. In addition, the `JColorChooser` and `JFileChooser` classes come equipped with feature-filled pop-up windows for getting a color choice from a user or getting a file or directory name. By using these additional classes, your user interface development tasks can be accomplished much more quickly and easily.

JOptionPane Class

`JOptionPane` is a special class for creating a panel to be placed in a pop-up window. The purpose of the panel is to display a message to a user and get a response from that user. To accomplish its task, the panel presents content in four areas (see Figure 9-1):

- **Icon:** The icon area is for the display of an `Icon` to indicate the type of message being displayed to the user. It's the responsibility of the installed look and feel to provide default icons for certain types of messages, but you can provide your own if you need to display another icon type.
- **Message:** The primary purpose of this area is to display a text message. In addition, the area can contain any optional set of objects to make the message more informational.
- **Input:** The input area allows a user to provide a response to a message. The response can be free form, in a text field, or from a pick list in a combo box or list control. For yes or no type questions, the button area should be used instead.
- **Button:** The button area is also for getting user input. Selection of a button in this area signals the end of the usage of the `JOptionPane`. Default sets of button labels are available, or you can display any number of buttons, including none, with any labels you desire.




Figure 9-1. *JOptionPane* parts

All the areas are optional (although having a panel without at least a message and a button makes the option pane virtually useless).

Besides being a panel with four sections within a pop-up window, the `JOptionPane` is capable of automatically placing itself in a pop-up window and managing the acquisition of the user's response. It can place itself in either a `JDialog` or a `JInternalFrame`, depending on the type of GUI you're providing to the user. With the help of an `Icon` and set of `JButton` components, the `JOptionPane` can easily be configured to show a variety of messages and input dialogs.

Note Because the `JOptionPane` can automatically place itself in a `JDialog`, you might never need to create a `JDialog` directly.

Creating a `JOptionPane`

You can either manually create a `JOptionPane` through one of its 7 constructors or go through one of the 25 factory methods discussed later in the chapter, in the “Automatically Creating a `JOptionPane` in a Pop-Up Window” section. You have the most control when manually creating the `JOptionPane`. However, you then must place it in a pop-up window, show the window, and finally manage getting the response.

Because of the ease of use provided by the methods that do everything automatically, you might think you would *only* use the factory methods when working with `JOptionPane`. However, throughout this chapter, you'll discover several other reasons why you might want to do things manually. In addition, when you use a visual-programming environment, the environment treats the `JOptionPane` as a JavaBean component and will ignore the factory methods.

For the seven constructors, you can have different permutations of six different arguments. The arguments allow you to configure something in one of the four different areas shown in Figure 9-1. The six arguments are the message, the message type, an option type, an icon, an array of options, and an initial option setting. The use of these arguments is shared with the factory methods.

Let's first look at the seven constructors, and then explore the different arguments. Notice that the constructor arguments are cascading and only add additional arguments to the previous constructor.

```

public JOptionPane()
JOptionPane optionPane = new JOptionPane();

public JOptionPane(Object message)
JOptionPane optionPane = new JOptionPane("Printing complete");

public JOptionPane(Object message, int messageType)
JOptionPane optionPane = new JOptionPane("Printer out of paper",
    JOptionPane.WARNING_MESSAGE);

public JOptionPane(Object message, int messageType, int optionType)
JOptionPane optionPane = new JOptionPane("Continue printing?",
    JOptionPane.QUESTION_MESSAGE, JOptionPane.YES_NO_OPTION);

public JOptionPane(Object message, int messageType, int optionType,
    Icon icon)
Icon printerIcon = new ImageIcon("printer.jpg");
JOptionPane optionPane = new JOptionPane("Continue printing?",
    JOptionPane.QUESTION_MESSAGE, JOptionPane.YES_NO_OPTION, printerIcon);

public JOptionPane(Object message, int messageType, int optionType, Icon icon,
    Object options[ ])
Icon greenIcon = new ImageIcon(Color.GREEN);
Icon redIcon = new ImageIcon(Color.RED);
Object optionArray[] = new Object[] { greenIcon, redIcon } ;
JOptionPane optionPane = new JOptionPane("Continue printing?",
    JOptionPane.QUESTION_MESSAGE, JOptionPane.YES_NO_OPTION, printerIcon,
    optionArray);

public JOptionPane(Object message, int messageType, int optionType, Icon icon,
    Object options[], Object initialValue)
JOptionPane optionPane = new JOptionPane("Continue printing?",
    JOptionPane.QUESTION_MESSAGE, JOptionPane.YES_NO_OPTION, printerIcon,
    optionArray, redIcon);

```

The JOptionPane Message Argument

The message argument is an `Object`, not a `String`. While you normally pass only a quoted string as this argument, with an `Object` argument, you can basically display anything you want in the message area. In the “Understanding the Message Property,” section later in this chapter, you’ll look at the more advanced uses of this argument. Briefly, though, there are four basic rules to interpret the meaning of an `Object`-typed message argument. For elements within the `Object`, recursively follow these rules:

- If the message is an array of objects (`Object[]`), make the `JOptionPane` place each entry onto a separate row.
- If the message is a `Component`, place the component in the message area.
- If the message is an `Icon`, place the `Icon` within a `JLabel` and display the label in the message area.
- If the message is an `Object`, convert it to a `String` with `toString()`, place the `String` in a `JLabel`, and display the label in the message area.

The `JOptionPane` Message Type and Icon Arguments

The `messageType` constructor argument is used to represent the type of message being displayed within the `JOptionPane`. If you don't provide a custom icon for the `JOptionPane`, the installed look and feel will use the `messageType` argument setting to determine which icon to display within the icon area. Five different message types are available as `JOptionPane` constants:

- `ERROR_MESSAGE` for displaying an error message
- `INFORMATION_MESSAGE` for displaying an informational message
- `QUESTION_MESSAGE` for displaying a query message
- `WARNING_MESSAGE` for displaying a warning message
- `PLAIN_MESSAGE` for displaying any other type of message

If you're using a constructor with both `messageType` and `icon` arguments and want the `JOptionPane` to use the default icon for the `messageType`, just specify `null` as the value for the `icon` argument. If the `icon` argument is non-`null`, the specified icon will be used, no matter what the message type is.

If the `messageType` constructor argument isn't specified, the default message type is `PLAIN_MESSAGE`.

The `JOptionPane` Option Type Argument

The `optionType` constructor argument is used to determine the configuration for the set of buttons in the button area. If one of the options argument described next is provided, then the `optionType` argument is ignored and configuration for the set of buttons is acquired from the `options` argument. Four different option types are available as `JOptionPane` constants:

- `DEFAULT_OPTION` for a single OK button
- `OK_CANCEL_OPTION` for OK and Cancel buttons
- `YES_NO_CANCEL_OPTION` for Yes, No, and Cancel buttons
- `YES_NO_OPTION` for Yes and No buttons

If the `optionType` constructor argument isn't specified, the default option type is `DEFAULT_OPTION`.

The JOptionPane Options and Initial Value Arguments

The options argument is an `Object` array used to construct a set of `JButton` objects for the button area of the `JOptionPane`. If this argument is `null` (or a constructor without this argument is used), the button labels will be determined by the `optionType` argument. Otherwise, the array works similarly to the message argument, but without supporting recursive arrays:

- If an options array element is a `Component`, place the component in the button area.
- If an options array element is an `Icon`, place the `Icon` within a `JButton` and place the button in the button area.
- If an options array element is an `Object`, convert it to a `String` with `toString()`, place the `String` in a `JButton`, and place the button in the button area.

Normally, the options argument will be an array of `String` objects. You may want to have an `Icon` on the `JButton`, although the resulting button won't have a label. If you want to have both an icon and a text label on the button, you can manually create a `JButton` and place it in the array. Alternatively, you can directly include any other `Component` within the array. There's one minor problem with these latter two approaches, however. It's *your* responsibility to handle responding to component selection and tell the `JOptionPane` when the user selects this component. The "Adding Components to the Button Area" section later in this chapter shows how to properly handle this behavior.

When the options argument is non-`null`, the `initialValue` argument specifies which of the buttons will be the default button when the pane is initially displayed. If it's `null`, the first component in the button area will be the default button. In either case, the first button will have the input focus, unless there is an input component in the message area, in which case, the input component will have the initial input focus.

■ **Tip** To have no buttons on the option pane, pass an empty array as the options setting: `new Object[] { }`.

Displaying a JOptionPane

After you've created the `JOptionPane` with one of the constructors, what you have is a panel filled with components. In other words, the obtained `JOptionPane` is not yet in a pop-up window. You need to create a `JDialog`, a `JInternalFrame`, or another pop-up window, and then place the `JOptionPane` within that. In addition, if you pick this manual style of `JOptionPane` construction, you need to handle the closing of the pop-up window. You must listen for selection of a component in the button area, and then hide the pop-up window after selection.

Because there is so much to do here, the `JOptionPane` includes two helper methods to place a `JOptionPane` within either a modal `JDialog` or a `JInternalFrame` and take care of all the previously described behavior:

```
public JDialog createDialog(Component parentComponent, String title)

public JInternalFrame createInternalFrame(Component parentComponent, String title)
```

Note When using the `createDialog()` and `createInternalFrame()` methods to create a pop-up window, selection of an automatically created button results in the closing of the created pop-up. You would then need to ask the `JOptionPane` which option the user selected with `getValue()` and, if appropriate, get the input value with `getInputValue()`.

The first argument to the methods is a component over which the pop-up window will be centered. The second argument is the title for the pop-up window. Once you create the pop-up window, whether it's a `JDialog` or `JInternalFrame`, you show it. The pop-up is then closed after one of the components in the button area is selected, at which point, your program continues. The following lines of source code show the creation of one such `JOptionPane` shown within a `JDialog`. The resulting pop-up window is shown in Figure 9-2.

```
JOptionPane optionPane = new JOptionPane("Continue printing?",
    JOptionPane.QUESTION_MESSAGE, JOptionPane.YES_NO_OPTION);
JDialog dialog = optionPane.createDialog(source, "Manual Creation");
dialog.setVisible(true);
```




Figure 9-2. Sample *JOptionPane* in a *JDialog*

After you create the `JOptionPane`, place it in a pop-up window, and show it, and the user has responded, you need to find out what the user selected. The selection is provided via the public `Object getValue()` method of `JOptionPane`. The value returned by `getValue()` is determined by whether an options array was provided to the `JOptionPane` constructor. If you provide the array, the argument selected will be returned. If you don't provide the array, an `Integer` object is returned, and its value represents the position of the button selected within the button area. In another case, `getValue()` could return `null` if nothing was selected, such as when the `JDialog` is closed by selecting the appropriate window decoration from the title bar of the pop-up window.

To make this multifaceted response easier to grasp, Listing 9-1 shows an `OptionPaneUtils` class that defines the method `public static int getSelection(JOptionPane optionPane)`. Given an option pane, this method returns the position of the selected value as an `int`, whether or not an options array was provided. To indicate that nothing was selected, `JOptionPane.CLOSED_OPTION (-1)` is returned.

Listing 9-1. *JOptionPane Utility Class*

```
import javax.swing.*;

public final class OptionPaneUtils {

    private OptionPaneUtils() {
    }

    public static int getSelection(JOptionPane optionPane) {
        // Default return value, signals nothing selected
        int returnValue = JOptionPane.CLOSED_OPTION;

        // Get selected value
        Object selectedValue = optionPane.getValue();
        // If none, then nothing selected
        if (selectedValue != null) {
            Object options[] = optionPane.getOptions();
            if (options == null) {
                // Default buttons, no array specified
                if (selectedValue instanceof Integer) {
                    returnValue = ((Integer)selectedValue).intValue();
                }
            } else {
                // Array of option buttons specified
                for (int i=0, n = options.length; i < n; i++) {
                    if (options[i].equals(selectedValue)) {
                        returnValue = i;
                        break; // out of for loop
                    }
                }
            }
        }
        return returnValue;
    }
}
```

With the help of this new `OptionPaneUtils.getSelection(JOptionPane)` helper method, you can now find out the option pane selection with one line of code, and then act accordingly based on the response.

```
int selection = OptionPaneUtils.getSelection(optionPane);
switch (selection) {
    case ...: ...
        break;
    case ...: ...
        break;
    default: ...
}
```

If you create a `JOptionPane` with a null options array, you can use the constants within the `JOptionPane` class to indicate the position of the default button labels and their return values from the `OptionPaneUtils.getSelection(JOptionPane)` method. These constants are listed in Table 9-1. Using these constants enables you to avoid hard-coding constants such as 0, 1, 2, or -1.

Table 9-1. *JOptionPane Option Position Constants*

Position	Description
<code>CANCEL_OPTION</code>	Used when the Cancel button is pressed
<code>CLOSED_OPTION</code>	Used when the pop-up window closed without the user pressing a button
<code>NO_OPTION</code>	Used when the No button is pressed
<code>OK_OPTION</code>	Used when the OK button is pressed
<code>YES_OPTION</code>	Used when the Yes button is pressed

Automatically Creating a JOptionPane in a Pop-Up Window

You can manually create a `JOptionPane`, place it in a `JDialog` or `JInternalFrame` (or any other container), and fetch the response. Alternatively, you could use the `JOptionPane` factory methods for creating `JOptionPane` components directly within either a `JDialog` or a `JInternalFrame`. Using the many factory methods, you can create the option pane, place it in a pop-up window, and get the response with a single line of source code.

There are 25 methods, which are first broken down into two sets: those that create the `JOptionPane` and show it within a `JDialog` and those that show the pane within a `JInternalFrame`. Methods that show the `JOptionPane` within a `JInternalFrame` are named `showInternalXXXDialog()`, and methods that create the pane within a `JDialog` are named `showXXXDialog()`.

The second grouping of factory methods for `JOptionPane` is what fills in the `XXX` part of the method names. This represents the various message types of option panes that you can create and display. In addition, the message type defines what is returned after the user selects something in the option pane. The four different message types are as follows:

- **Message:** With a message pop-up, there's no return value. Therefore, the method is defined `void show[Internal]MessageDialog(...)`.
- **Input:** With an input pop-up, the return value is either what the user typed in a text field (a `String`) or what the user picked from a list of options (an `Object`). Therefore, the `show[Internal]InputDialog(...)` methods return either a `String` or `Object`, depending on which version you use.
- **Confirm:** With the confirm pop-up, the return value signifies which, if any, button the user picked within the option pane. After a button is picked, the pop-up window is dismissed, and the returned value is one of the integer constants shown in Table 9-1. Therefore, the method here is defined as `int show[Internal]ConfirmDialog(...)`.
- **Option:** With the option pop-up, the return value is an `int`, the same type as the confirm pop-up, so the methods are defined `int show[Internal]OptionDialog(...)`. If the button labels are manually specified with a non-null argument, the integer represents the selected button position.

The information in Table 9-2 should help you understand the 25 methods and their arguments. The method names (and return types) are found on the left side of the table, and their argument lists (and data types) are on the right. The numbers that repeat across the columns for each method name indicate a specific set of arguments for that method. For instance, the `showInputDialog` row shows a 3 in the Parent Component column, Message column, Title column, and Message Type column. Therefore, the `showInputDialog` method has one version defined like this:

```
public static String showInputDialog(Component parentComponent, Object message,
    String title, int messageType)
```

Note With the exception of two of the `showInputDialog()` methods, the parent component argument is required for all method varieties. The message argument is the only one required for all without exception. What good is a pop-up dialog without a message?

With the way the different `showXXXDialog()` methods are defined, you don't need to bother with discovering the selected button yourself, or even the user input. The return value for the various methods is one of the following: nothing (`void` return type), an `int` from Table 9-1, a `String`, or an `Object`, depending on the type of dialog box shown.

Caution There is a significant difference between the `JOptionPane` constructors and the factory methods: The option type and message type arguments are reversed.

Table 9-2. *JOptionPane Static create and show Methods*

Method Name/Return Type	Parent Component	Message Object	Title String	Option Type int	Message Type int
showMessageDialog Return type: void[123]	123	123	23		23
showInternalMessageDialog Return type: void[123]	123	123	23		23
showConfirmDialog Return type: int[1234]	1234	1234	234	234	34
showInternalConfirmDialog Return type: int	1234	1234	234	234	34
showInputDialog Return type: String[12356]/Object[4]	2345	123456	34		34
showInternalInputDialog Return type: String[12]/Object[3]	123	123	23		23
showOptionDialog Return type: int[1]	1	1	1	1	1
showInternalOptionDialog Return type: int[1]	1	1	1	1	1

JOptionPane Arguments for Factory Methods

Almost all the arguments for the factory methods match the `JOptionPane` constructor arguments. Two lists in the “Creating a `JOptionPane`” section earlier in this chapter describe the acceptable values for the message type and option type arguments. In addition, the usage of the message, options, and initial value arguments are also described. The parent component and title argument are passed along to one of the `createDialog()` or `createInternalFrame()` methods, depending on the type of pop-up in which the `JOptionPane` is embedded.

You next need to consider the selection values argument and the initial selection value argument of the `showInputDialog()` method. With an input dialog box, you can ask the user for text input and allow the user to type in anything, or you can present the user with a list of predefined choices. The selection values argument to `showInputDialog()` determines how you provide that set of choices. The initial selection value represents the specific option to be chosen when the `JOptionPane` first appears. The look and feel will determine the appropriate Swing component to be used based on the number of choices presented. For small lists, a `JComboBox` is used. For larger lists, starting at 20 with the Motif, Metal/Ocean, and Windows look and feel types, a `JList` is used.

Table 9-2. *JOptionPane Static create and show Methods (Continued)*

Icon	Icon	Options Object[]	Initial Value Object	Selection Values Object[]	Initial Selection Object
	3				
	3				
	4				
	4				
	4			4	456
	3	3	3		
	1	1	1		
	1	1	1		

Note When the parent component argument is null, a hidden frame is used and the pop-up is centered on the screen. See the `getSharedOwnerFrame()` method of `SwingUtilities` for more details on the hidden frame. There are other focus-related usability issues that you might run into when specifying null as a parent component, if the hidden frame and dialog box are swapped to the background.

Message Pop-Ups

The `showMessageDialog()` and `showInternalMessageDialog()` methods create an `INFORMATION_MESSAGE` pop-up with the pop-up title “Message,” unless different argument settings are specified for the message type and window title. Because the sole purpose of the message dialog box is to display a message, these dialog boxes provide only an OK button and return no value. Figure 9-3 shows sample message pop-ups created from the following lines of source:

```
JOptionPane.showMessageDialog(parent, "Printing complete");
JOptionPane.showInternalMessageDialog(desktop, "Printing complete");
```



Figure 9-3. Sample *JOptionPane* message pop-ups

Confirm Pop-Ups

The `showConfirmDialog()` and `showInternalConfirmDialog()` methods, by default, create a pop-up with a `QUESTION_MESSAGE` type and the pop-up title “Select an Option.” Because confirm dialog boxes ask a question, their default option type is `YES_NO_CANCEL_OPTION`, giving them Yes, No, and Cancel buttons. The return value from a call to any of these methods is one of the *JOptionPane* class constants `YES_OPTION`, `NO_OPTION`, or `CANCEL_OPTION`. No prizes for guessing which constant maps to which option pane button! Figure 9-4 shows sample confirm pop-ups created from the following lines of source:

```
JOptionPane.showConfirmDialog(parent, "Continue printing?");
JOptionPane.showInternalConfirmDialog(desktop, "Continue printing?");
```




Figure 9-4. Sample *JOptionPane* confirm pop-ups

Input Pop-Ups

By default, the `showInputDialog()` and `showInternalInputDialog()` methods create a `QUESTION_MESSAGE` pop-up with an “Input” pop-up title. The option type for input dialogs is `OK_CANCEL_OPTION`, giving them an OK and a Cancel button, and the option type isn’t changeable. The return data type for these methods is either a `String` or an `Object`. If you don’t specify selection values, the pop-up prompts the user with a text field and returns the input as a `String`. If you do specify selection values, you get back an `Object` from the selection values array. Figure 9-5 shows some input pop-ups created from the following lines of source:

```
JOptionPane.showInputDialog(parent, "Enter printer name:");

// Moons of Neptune
String smallList[] = {
    "Naiad", "Thalassa", "Despina", "Galatea", "Larissa", "Proteus",
    "Triton", "Nereid"} ;
```

```

JOptionPane.showInternalInputDialog(desktop, "Pick a printer", "Input",
    JOptionPane.QUESTION_MESSAGE, null, smallList, "Triton");

// Twenty of the moons of Saturn
String bigList[] = {"Pan", "Atlas", "Prometheus", "Pandora", "Epimetheus",
    "Janus", "Mimas", "Enceladus", "Telesto", "Tethys", "Calypso", "Dione",
    "Helene", "Rhea", "Titan", "Hyperion", "Iapetus", "Phoebe", "Skadi",
    "Mundilfari"};
JOptionPane.showInputDialog(parent, "Pick a printer", "Input",
    JOptionPane.QUESTION_MESSAGE, null, bigList, "Titan");

```




Figure 9-5. Sample *JOptionPane* input pop-ups

Note It is the responsibility of the look and feel to determine the type of input component. A look and feel can use something other than a *JTextField*, *JComboBox*, or *JList*. It's just that all the system-provided look and feel types (from Sun) use these three components.

Option Pop-Ups

The `showOptionDialog()` and `showInternalOptionDialog()` methods provide the most flexibility because they allow you to configure all the arguments. There are no default arguments, and the return value is an `int`. If an options argument is not specified, the return value will be one of the constants listed in Table 9-1. Otherwise, the value returned represents the component position of the selected option from the options argument. Figure 9-6 shows a couple of input pop-ups created from the following lines of source, in which icons (instead of text) are provided on the buttons:

```
Icon greenIcon = new DiamondIcon(Color.GREEN);
Icon redIcon = new DiamondIcon(Color.RED);
Object iconArray[] = { greenIcon, redIcon };
JOptionPane.showOptionDialog(source, "Continue printing?", "Select an Option",
    JOptionPane.YES_NO_OPTION, JOptionPane.QUESTION_MESSAGE, null, iconArray,
    iconArray[1]);
```

```
Icon blueIcon = new DiamondIcon(Color.BLUE);
Object stringArray[] = { "Do It", "No Way" };
JOptionPane.showInternalOptionDialog(desktop, "Continue printing?",
    "Select an Option", JOptionPane.YES_NO_OPTION, JOptionPane.QUESTION_MESSAGE,
    blueIcon, stringArray, stringArray[0]);
```




Figure 9-6. Sample `JOptionPane` option pop-ups

Caution When using a factory method to show a `JOptionPane` within a `JDialog`, the dialog box is automatically modal, preventing another window from getting the input focus. When showing the `JOptionPane` within a `JInternalFrame`, the internal frame might be modal, but other windows might not be. Therefore, a user could do something within one of the other windows of the application, including an action on the `JDesktopPane`.

JOptionPane Properties

Table 9-3 shows the 15 properties of `JOptionPane`. These properties are accessible only if you don't use one of the factory methods of `JOptionPane`. For most of the arguments, their meaning maps directly to one of the constructor arguments.

Table 9-3. *JOptionPane Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
icon	Icon	Read-write bound
initialSelectionValue	Object	Read-write bound
initialValue	Object	Read-write bound
inputValue	Object	Read-write bound
maxCharactersPerLineCount	int	Read-only
message	Object	Read-write bound
messageType	int	Read-write bound
options	Object[]	Read-write bound
optionType	int	Read-write bound
selectionValues	Object[]	Read-write bound
UI	OptionPaneUI	Read-write bound
UIClassID	String	Read-only
value	Object	Read-write bound
wantsInput	boolean	Read-write bound

The `wantsInput` property is automatically set to `true` for the input dialog boxes or when the `selectionValues` property is non-null. The `inputValue` property is the item picked from an input dialog box. The `value` property indicates the option selected from the button area.

Displaying Multiline Messages

The `maxCharactersPerLineCount` property is set to an extremely large value, `Integer.MAX_VALUE`, by default. For some strange reason, the Swing developers chose not to provide a setter method for this property. If you want to change the setting, you must subclass `JOptionPane` and override the `public int getMaxCharactersPerLineCount()` method. This causes a long text message to be broken up into multiple lines within an option pane. In addition, you cannot use any of the factory methods because they don't know about your subclass.

To help you create narrow `JOptionPane` components, you can add the source shown in Listing 9-2 to the `OptionPaneUtils` class definition shown earlier in Listing 9-1. The new method provides a way of specifying the desired option pane character width.

Listing 9-2. *Helper Method to Create a Narrow JOptionPane*

```

public static JOptionPane getNarrowOptionPane(int maxCharactersPerLineCount) {
    // Our inner class definition
    class NarrowOptionPane extends JOptionPane {
        int maxCharactersPerLineCount;
        NarrowOptionPane(int maxCharactersPerLineCount) {
            this.maxCharactersPerLineCount = maxCharactersPerLineCount;
        }
        public int getMaxCharactersPerLineCount() {
            return maxCharactersPerLineCount;
        }
    }
    return new NarrowOptionPane(maxCharactersPerLineCount);
}

```

Once the method and new class are defined, you can create an option pane of a specified character width, manually configure all the properties, place it in a pop-up window, show it, and then determine the user's response. The following source demonstrates using these new capabilities, with the long message trimmed a bit.

```

String msg = "this is a really long message ... this is a really long message";
JOptionPane optionPane = JOptionPaneUtils.getNarrowOptionPane(72);
optionPane.setMessage(msg);
optionPane.setMessageType(JOptionPane.INFORMATION_MESSAGE);
JDialog dialog = optionPane.createDialog(source, "Width 72");
dialog.setVisible(true);

```

Figure 9-7 demonstrates what would happen if you didn't change the `maxCharactersPerLineCount` property. Figure 9-7 also shows the new narrow `JOptionPane`.



Default



Narrow

Figure 9-7. *Default JOptionPane and a narrow JOptionPane*

Although this seems like a lot of work, it's the best way to create multiline option panes, unless you want to manually parse the message into separate lines.

Note Including the characters `\n` in the message text will force the message to be displayed on multiple lines. Then it's your responsibility to count the number of characters in each message line. The message text in a `JOptionPane` can be formatted with HTML tags, as it can in other Swing components.

Understanding the Message Property

In all the previous examples in this chapter of using the message argument to the `JOptionPane` constructors and using the factory methods, the message was a single string. As described earlier in the “The `JOptionPane` Message Argument” section, this argument doesn't need to be a single string. For instance, if the argument were an array of strings, each string would be on a separate line. This eliminates the need to use the narrow `JOptionPane`, but requires you to count the characters yourself. However, because you're splitting apart the message, you can use one of the 25 factory methods. For instance, the following source creates the pop-up window shown in Figure 9-8.

```
String multiLineMsg[] = { "Hello,", "World"} ;
JOptionPane.showMessageDialog(source, multiLineMsg);
```



Figure 9-8. Using `JOptionPane` with a string array

Caution If you manually count the characters within a long message to split it into a multiline message, the output may not be the best. For instance, when using a proportional font in which character widths vary, a line of 20 *w* characters would be much wider than a line of 20 *i* or *l* characters.

The message argument not only supports displaying an array of strings, but it also can support an array of any type of object. If an element in the array is a `Component`, it's placed directly into the message area. If the element is an `Icon`, the icon is placed within a `JLabel`, and the `JLabel` is placed into the message area. All other objects are converted to a `String`, placed into a `JLabel`, and displayed in the message area, unless the object is itself an array; in that case, these rules are applied recursively.

To demonstrate the possibilities, Figure 9-9 shows off the true capabilities of the `JOptionPane`. The actual content isn't meant to show anything in particular—just that you can display a lot of different stuff. The message argument is made up of the following array:

```
Object complexMsg[] = {
    "Above Message", new DiamondIcon(Color.RED), new JButton("Hello"),
    new JSlider(), new DiamondIcon(Color.BLUE), "Below Message"} ;
```




Figure 9-9. Using *JOptionPane* with a complex message property

Adding Components to the Message Area

If you were to display the pop-up in Figure 9-9, you would notice a slight problem. The option pane doesn't know about the embedded *JSlider* setting, unlike the way it automatically knows about input to the automatic *JTextField*, *JComboBox*, or *JList* components. If you want the *JOptionPane* (or for that matter, any input component) to get the *JSlider* value, you need to have your input component change the *inputValue* property of the *JOptionPane*. When this value is changed, the option pane tells the pop-up window to close because the *JOptionPane* has acquired its input value.

Attaching a *ChangeListener* to the *JSlider* component enables you to find out when its value has changed. Adding yet another method to the *OptionPaneUtils* class shown earlier in Listing 9-1 allows you to reuse this specialized *JSlider* with multiple *JOptionPane* objects more easily. The important method call is shown in boldface in Listing 9-3. A similar line would need to be added for any input component that you wanted to place within a *JOptionPane*. The line notifies the option pane when the user has changed the value of the input component.

Listing 9-3. *Helper Method for Creating a JSlider for Use in a JOptionPane*

```
public static JSlider getSlider(final JOptionPane optionPane) {
    JSlider slider = new JSlider();
    slider.setMajorTickSpacing (10);
    slider.setPaintTicks(true);
    slider.setPaintLabels(true);
    ChangeListener changeListener = new ChangeListener() {
        public void stateChanged(ChangeEvent changeEvent) {
            JSlider theSlider = (JSlider)changeEvent.getSource();
            if (!theSlider.getValueIsAdjusting()) {
                optionPane.setInputValue(new Integer(theSlider.getValue()));
            }
        }
    };
    slider.addChangeListener(changeListener);
    return slider;
}
```

Now that the specialized *JSlider* is created, you need to place it on a *JOptionPane*. This requires the manual creation of a *JOptionPane* component and, surprisingly, doesn't require

the setting of the `wantsInput` property. The `wantsInput` property is set to `true` only when you want the `JOptionPane` to provide its own input component. Because you're providing one, this isn't necessary. The resulting pop-up window is shown in Figure 9-10. (The `JSlider` component will be more fully described in Chapter 12.)

```
JOptionPane optionPane = new JOptionPane();
JSlider slider = OptionPaneUtils.getSlider(optionPane);
optionPane.setMessage(new Object[] { "Select a value: " , slider } );
optionPane.setMessageType(JOptionPane.QUESTION_MESSAGE);
optionPane.setOptionType(JOptionPane.OK_CANCEL_OPTION);
JDialog dialog = optionPane.createDialog(source, "My Slider");
dialog.setVisible(true);
System.out.println ("Input: " + optionPane.getInputValue());
```




Figure 9-10. Using `JOptionPane` with a `JSlider`

Note If the user doesn't move the slider, `JOptionPane.getInputValue()` correctly returns `JOptionPane.UNINITIALIZED_VALUE`.

Adding Components to the Button Area

In “The `JOptionPane` Options and Initial Value Arguments” section earlier in this chapter, you saw that if you have a `Component` in the array of options for the `JOptionPane`, you must configure the component yourself to handle selection. The same holds true for any components you add via the `options` property. When a component is configured to handle selection, the pop-up window that a `JOptionPane` is embedded in will disappear when the component is selected. The default set of buttons works this way. When installing your own components, you must notify the option pane when one of the components has been selected by setting the `value` property of the option pane.

To demonstrate this mechanism, create a `JButton` with both an icon and a text label that can be placed in an option pane. Without defining this component yourself, the option pane supports only the display of a label or an icon on the button. When the button is selected, the button tells the option pane it was selected by setting the option pane's `value` property to the current text label of the button. Adding yet another method to `OptionPaneUtils` shown earlier in Listing 9-1 allows you to create such a button. The boldfaced line in the source shown in Listing 9-4 is the important method call to add to any other such component that you want to combine with the component array for the `options` property of a `JOptionPane`. The line would be called after selection of such a component.

Listing 9-4. *A JButton for Use on a JOptionPane*

```

public static JButton getButton(
    final JOptionPane optionPane, String text, Icon icon) {
    final JButton button = new JButton (text, icon);
    ActionListener actionListener = new ActionListener() {
        public void actionPerformed(ActionEvent actionEvent) {
            // Return current text label, instead of argument to method
            optionPane.setValue(button.getText());
        }
    };
    button.addActionListener(actionListener);
    return button;
}

```

After the specialized JButton is created, you need to place it in a JOptionPane. Unfortunately, this, too, requires the long form of the JOptionPane usage. The resulting pop-up window is shown in Figure 9-11.

```

JOptionPane optionPane = new JOptionPane();
optionPane.setMessage("I got an icon and a text label");
optionPane.setMessageType(JOptionPane.INFORMATION_MESSAGE);
Icon icon = new DiamondIcon (Color.BLUE);
JButton jButton = OptionPaneUtils.getButton(optionPane, "OK", icon);
optionPane.setOptions(new Object[] {jButton} );
JDialog dialog = optionPane.createDialog(source, "Icon/Text Button");
dialog.setVisible(true);

```



Figure 9-11. Using JOptionPane with a JButton containing a text label and an icon

Tip Setting the value of the JOptionPane with setValue() will hide the option pane when a user selects the button. If you want to prevent users from closing the window without selecting a button, you can set the default close operation of the dialog containing the JOptionPane to JDialog.DO_NOTHING_ON_CLOSE. Then users won't be able to select the close icon from the window adornments. Well, they can select it; it just won't do anything.

Listening for Property Changes

The JOptionPane class defines the following 11 constants to assist with listening for bound property changes:

- ICON_PROPERTY
- INITIAL_SELECTION_VALUE_PROPERTY
- INITIAL_VALUE_PROPERTY
- INPUT_VALUE_PROPERTY
- MESSAGE_PROPERTY
- MESSAGE_TYPE_PROPERTY
- OPTION_TYPE_PROPERTY
- OPTIONS_PROPERTY
- SELECTION_VALUES_PROPERTY
- VALUE_PROPERTY
- WANTS_INPUT_PROPERTY

If you don't use the factory methods of `JOptionPane`, you can instead use a `PropertyChangeListener` to listen for changes to the bound properties. This would allow you to passively listen for changes to bound properties, instead of actively getting them after the change.

Customizing a `JOptionPane` Look and Feel

Each installable Swing look and feel provides a different `JOptionPane` appearance and set of default `UIResource` values. Figure 9-12 shows the appearance of the `JOptionPane` container for the preinstalled set of look and feel types: Motif, Windows, and Ocean.




















Figure 9-12. *`JOptionPane` under different look and feel types*

The message type of the `JOptionPane` helps determine the default icon to display in the icon area of the option pane. For plain messages, there are no icons. The remaining four default icons—for informational, question, warning, and error messages—are shown in Table 9-4 for the different look and feel types.

Table 9-4. *JOptionPane Icons for the Different Look and Feel Types*

Look and Feel	Informational	Question	Warning	Error
Motif				
Windows				
Metal				
Ocean				

The available set of `UIResource`-related properties for a `JOptionPane` is shown in Table 9-5. For the `JOptionPane` component, there are 56 different properties.

Table 9-5. *JOptionPane UIResource Elements*

Property String	Object Type
<code>OptionPane.actionMap</code>	<code>ActionMap</code>
<code>OptionPane.background</code>	<code>Color</code>
<code>OptionPane.border</code>	<code>Border</code>
<code>OptionPane.buttonAreaBorder</code>	<code>Border</code>
<code>OptionPane.buttonClickThreshold</code>	<code>Integer</code>
<code>OptionPane.buttonFont</code>	<code>Font</code>
<code>OptionPane.buttonOrientation</code>	<code>Integer</code>
<code>OptionPane.buttonPadding</code>	<code>Integer</code>
<code>OptionPane.cancelButtonMnemonic</code>	<code>String</code>
<code>OptionPane.cancelButtonText</code>	<code>String</code>
<code>OptionPane.cancelIcon</code>	<code>Icon</code>
<code>OptionPane.errorDialog.border.background</code>	<code>Color</code>
<code>OptionPane.errorDialog.titlePane.background</code>	<code>Color</code>
<code>OptionPane.errorDialog.titlePane.foreground</code>	<code>Color</code>
<code>OptionPane.errorDialog.titlePane.shadow</code>	<code>Color</code>

Table 9-5. *JOptionPane UIResource Elements (Continued)*

Property String	Object Type
<code>OptionPane.errorIcon</code>	Icon
<code>OptionPane.errorSound</code>	String
<code>OptionPane.font</code>	Font
<code>OptionPane.foreground</code>	Color
<code>OptionPane.informationIcon</code>	Icon
<code>OptionPane.informationSound</code>	String
<code>OptionPane.inputDialogTitle</code>	String
<code>OptionPane.isYesLast</code>	Boolean
<code>OptionPane.messageAnchor</code>	Integer
<code>OptionPane.messageAreaBorder</code>	Border
<code>OptionPane.messageFont</code>	Font
<code>OptionPane.messageForeground</code>	Color
<code>OptionPane.messageDialogTitle</code>	String
<code>OptionPane.minimumSize</code>	Dimension
<code>OptionPane.noButtonMnemonic</code>	String
<code>OptionPane.noButtonText</code>	String
<code>OptionPane.noIcon</code>	Icon
<code>OptionPane.okButtonMnemonic</code>	String
<code>OptionPane.okButtonText</code>	String
<code>OptionPane.okIcon</code>	Icon
<code>OptionPane.questionDialog.border.background</code>	Color
<code>OptionPane.questionDialog.titlePane.background</code>	Color
<code>OptionPane.questionDialog.titlePane.foreground</code>	Color
<code>OptionPane.questionDialog.titlePane.shadow</code>	Color
<code>OptionPane.questionIcon</code>	Icon
<code>OptionPane.questionSound</code>	String
<code>OptionPane.sameSizeButtons</code>	Boolean
<code>OptionPane.separatorPadding</code>	Integer
<code>OptionPane.setButtonMargin</code>	Boolean
<code>OptionPane.titleText</code>	String
<code>OptionPane.warningDialog.border.background</code>	Color
<code>OptionPane.warningDialog.titlePane.background</code>	Color

Table 9-5. *JOptionPane UIResource Elements (Continued)*

Property String	Object Type
OptionPane.warningDialog.titlePane.foreground	Color
OptionPane.warningDialog.titlePane.shadow	Color
OptionPane.warningIcon	Icon
OptionPane.warningSound	String
OptionPane.windowBindings	Object[]
OptionPane.yesButtonMnemonic	String
OptionPane.yesButtonText	String
OptionPane.yesIcon	Icon
OptionPaneUI	String

One good use of the resources in Table 9-5 is for customizing default button labels to match the locale or language of the user. For instance, to change the four labels for the Cancel, No, OK, and Yes buttons into French, add the following code to your program. (You may be able to get the translated text from a `java.util.ResourceBundle`.)

```
// Set JOptionPane button labels to French
UIManager.put("OptionPane.cancelButtonText", "Annuler");
UIManager.put("OptionPane.noButtonText", "Non");
UIManager.put("OptionPane.okButtonText", "D'accord");
UIManager.put("OptionPane.yesButtonText", "Oui");
```

Now when you display the option pane, the buttons will have localized button labels. Of course, this would require translating the messages for the option pane, too. Figure 9-13 shows how a pop-up would look for the following line of source that asks if the user is 18 or older. Because the pop-up window title isn't a property, you must pass the title to every created dialog box.

```
int result = JOptionPane.showConfirmDialog(
    aFrame, "Est-ce que vous avez 18 ans ou plus?", "Choisissez une option",
    JOptionPane.YES_NO_CANCEL_OPTION);
```




Figure 9-13. *A JOptionPane in French*

The `JOptionPane` component supports localized `JOptionPane` button labels. Out of the box, the `JOptionPane` displays Chinese or Japanese button labels for the standard Yes, No, Cancel, and OK buttons for the appropriate locale. For instance, the left side of Figure 9-14 shows buttons with Japanese labels for Yes, No, and Cancel, and the right side of Figure 9-14 shows buttons with Japanese labels for OK and Cancel. Obviously, you would need to change the message in the option pane, but the buttons are set for you (assuming you have the fonts to support it).




Figure 9-14. A `JOptionPane` with Japanese-language buttons

Thankfully, the 5.0 release of the JDK includes translations for the standard `JOptionPane` (as well as the `JFileChooser` and `JColorChooser`) labels. These are available for German (de), Spanish (es), French (fr), Italian (it), Japanese (ja), Korean (ko), English, Swedish (sv), and Chinese (Simplified/zh_CN and Traditional/zh_TW).

Tip To start the Java runtime with a different language, just set the `user.language` property, as in `java -Duser.language=FR ClassName`. Then, whenever you create a `JOptionPane`, you would get the French labels for Yes, No, OK, and Cancel. The button labels would be like those shown in Figure 9-14, but without you needing to manually do the `UIManager.put()` calls. (Instead of *D'accord*, Sun chose to leave OK as OK.)

ProgressMonitor Class

The `ProgressMonitor` class is used to report on the status of a time-consuming task. The class is a special Swing class that's not a GUI component, an option pane, or a JavaBean component. Instead, you tell the `ProgressMonitor` when each part of the task is done. If the task is taking an extended length of time to complete, the `ProgressMonitor` displays a pop-up window like the one shown in Figure 9-15.




Figure 9-15. `ProgressMonitor` sample

After the `ProgressMonitor` displays the pop-up window, the user can do one of two things. The user can watch the `ProgressMonitor` display to see how much of the task has been completed; when the task is done, the `ProgressMonitor`'s display automatically disappears. Or, if the user selects the Cancel button, this tells the `ProgressMonitor` that the task needs to be canceled. To detect the cancellation, the task needs to check the `ProgressMonitor` periodically to see if the user canceled the task's operation. Otherwise, the task will continue.

The pop-up window that the `ProgressMonitor` class displays is a `JOptionPane` with a `maxCharactersPerLineCount` property setting of 60, allowing the option pane to automatically word wrap any displayed messages. The option pane is embedded within a nonmodal `JDialog` whose title is "Progress . . .". Because the `JDialog` isn't modal, a user can still interact with the main program. The `JOptionPane` for a `ProgressMonitor` will always get an informational icon within its icon area.

In addition, the message area of the option pane consists of three objects:

- At the top of the message area is a fixed message that stays the same throughout the life of the `JOptionPane`. The message can be a text string or an array of objects just like the message property of `JOptionPane`.
- In the middle of the message area is a note or variable message that can change as the task progresses.
- At the bottom of the message area is a progress bar (`JProgressBar` component) that fills as an increasing percentage of the task is completed.

The button area of the option pane shows a Cancel button.

Creating a ProgressMonitor

When you create a `ProgressMonitor`, there are five arguments to the single constructor:

```
public ProgressMonitor(Component parentComponent, Object message, String note,  
    int minimum, int maximum)
```

The first argument represents the parent component for the `JOptionPane` for when the `ProgressMonitor` needs to appear. The parent component is the component over which the pop-up window appears, and acts like the `parentComponent` argument for the `createDialog()` method of `JOptionPane`. You then provide the static and variable message parts for the message area of the `JOptionPane`. Either of these message parts could be `null`, although `null` means that this part of the message area will never appear. Lastly, you provide `minimum` and `maximum` values as the range for the progress bar. The difference between these two values represents the expected number of operations to be performed, such as the number of files to load or the size of a file to read. Normally, the `minimum` setting is zero, but that isn't required. The number of completed operations determines how far the progress bar moves.

Initially, the pop-up window isn't displayed. By default, the progress monitor checks every half second (500 milliseconds) to see if the task at hand will complete in two seconds. If the task has shown some progress and it still won't complete in two seconds, then the pop-up window appears. The time to completion is configurable by changing the `millisToDecideToPopup` and `millisToPopup` properties of the `ProgressMonitor`.

The following line of source demonstrates the creation of a `ProgressMonitor` with 200 steps in the operation. A reference to the `ProgressMonitor` would need to be saved so that it can be notified as the task progresses.

```
ProgressMonitor monitor = new ProgressMonitor(
    parent, "Loading Progress", "Getting Started...", 0, 200);
```

Using a ProgressMonitor

Once you've created the `ProgressMonitor`, you need to begin the task whose progress is being monitored. As the task completes one or many steps, the `ProgressMonitor` needs to be notified of the task's progress. Notification is done with a call to the public void `setProgress(int newValue)` method, where the argument represents the progress completed thus far and the `newValue` needs to be in the `minimum...maximum` range initially specified. This progress value needs to be maintained outside the `ProgressMonitor`, because you can't ask the monitor how much progress has been made (no public `int getProgress()` method of `ProgressMonitor` exists). If the progress value were maintained in a variable named `progress`, the following two lines would update the progress value and notify the `ProgressMonitor`.

```
progress += 5;
monitor.setProgress(progress);
```

Note It's possible that multiple calls to `setProgress()` may not advance the progress bar in the option pane. The changes to the progress setting must be enough to make the progress bar advance at least one pixel in length. For instance, if the minimum and maximum settings were zero and 2 billion, increasing the progress setting 1,000 times by 5 would have no visible effect on the progress bar, because the fractional amount would be negligible.

The progress setting could represent the number of files loaded thus far, or the number of bytes read in from a file. In addition to updating the count, you should update the note to reflect the progress. If the difference between the minimum and maximum arguments used in the `ProgressMonitor` constructor were 100, then the current progress could be viewed as a percentage of the task. Otherwise, the progress property merely represents the progress completed so far.

```
monitor.setNote("Loaded " + progress + " files");
```

It's the responsibility of the executing task to check whether the user pressed the Cancel button in the `ProgressMonitor` dialog box. If the task is canceled, the `ProgressMonitor` automatically closes the dialog box, but the task must actively check for the change by adding a simple check at the appropriate place or places in the source:

```
if (monitor.isCanceled()) {
    // Task canceled - cleanup
    ...
} else {
    // Continue doing task
    ...
}
```

Most tasks requiring a `ProgressMonitor` will be implemented using separate threads to avoid blocking the responsiveness of the main program.

Listing 9-5 shows a program that creates a `ProgressMonitor` and allows you to either manually or automatically increase its progress property (see the following section for a description of this property). These tasks are handled by on-screen buttons (see Figure 9-16). Selecting the Start button creates the `ProgressMonitor`. Selecting the Manual Increase button causes the progress to increase by 5. Selecting the Automatic Increase button causes the progress to increase by 3 every 250 milliseconds (1/4 second). Pressing the Cancel button in the pop-up window during the automatic increase demonstrates what should happen when the operation is canceled; the timer stops sending updates.




Figure 9-16. *Main ProgressMonitor sample frame*

Note The pop-up window won't appear until some progress is shown.

The `ProgressMonitorHandler` inner class at the start of Listing 9-5 is necessary to ensure that the `ProgressMonitor` is accessed only from the event thread. Otherwise, the access wouldn't be thread-safe in some random thread.

Listing 9-5. *Sample ProgressMonitor Usage*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class SampleProgress {
    static ProgressMonitor monitor;
    static int progress;
    static Timer timer;

    static class ProgressMonitorHandler implements ActionListener {
        // Called by Timer
        public void actionPerformed(ActionEvent actionEvent) {
            if (monitor == null)
                return;
        }
    }
}
```

```

        if (monitor.isCanceled()) {
            System.out.println("Monitor canceled");
            timer.stop();
        } else {
            progress += 3;
            monitor.setProgress(progress);
            monitor.setNote("Loaded " + progress + " files");
        }
    }
}

public static void main(String args[]) {

    Runnable runner = new Runnable() {
        public void run() {
            JFrame frame = new JFrame("ProgressMonitor Sample");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
            frame.setLayout(new GridLayout (0, 1));

            // Define Start Button
            JButton startButton = new JButton ("Start");
            ActionListener startActionListener = new ActionListener() {
                public void actionPerformed(ActionEvent actionEvent) {
                    Component parent = (Component)actionEvent.getSource();
                    monitor = new ProgressMonitor(parent, "Loading Progress",
                        "Getting Started...", 0, 200);
                    progress = 0;
                }
            };
            startButton.addActionListener(startActionListener);
            frame.add(startButton);

            // Define Manual Increase Button
            // Pressing this button increases progress by 5
            JButton increaseButton = new JButton ("Manual Increase");
            ActionListener increaseActionListener = new ActionListener() {
                public void actionPerformed(ActionEvent actionEvent) {
                    if (monitor == null)
                        return;
                    if (monitor.isCanceled()) {
                        System.out.println("Monitor canceled");
                    } else {
                        progress += 5;
                        monitor.setProgress(progress);
                        monitor.setNote("Loaded " + progress + " files");
                    }
                }
            };
        }
    };
}

```

```

        increaseButton.addActionListener(increaseActionListener);
        frame.add(increaseButton);

        // Define Automatic Increase Button
        // Start Timer to increase progress by 3 every 250 ms
        JButton autoIncreaseButton = new JButton ("Automatic Increase");
        ActionListener autoIncreaseActionListener = new ActionListener() {
            public void actionPerformed(ActionEvent actionEvent) {
                if (monitor != null) {
                    if (timer == null) {
                        timer = new Timer(250, new ProgressMonitorHandler());
                    }
                    timer.start();
                }
            }
        };
        autoIncreaseButton.addActionListener(autoIncreaseActionListener);
        frame.add(autoIncreaseButton);

        frame.setSize(300, 200);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

ProgressMonitor Properties

Table 9-6 shows the eight properties of ProgressMonitor.

Table 9-6. *ProgressMonitor Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
canceled	boolean	Read-only
maximum	int	Read-write
millisToDecideToPopup	int	Read-write
millisToPopup	int	Read-write
minimum	int	Read-write
note	String	Read-write
progress	int	Write-only

The `millisToDecideToPopup` property represents the number of milliseconds that the monitor waits before deciding if it needs to display the pop-up window. If the `progress` property hasn't changed yet, the monitor waits for another increment of this time period before checking again. When the `ProgressMonitor` checks and the `progress` property has changed, it estimates whether the task will be completed in the number of milliseconds in the `millisToPopup` property. If the `ProgressMonitor` thinks the monitored task will complete on time, the pop-up window is never displayed. Otherwise, the pop-up will display after `millisToPopup` milliseconds have passed from the time the task started.

Caution Although technically possible, it isn't a good practice to move the minimum and maximum properties after the pop-up has appeared. This could result in the progress bar increasing and decreasing in an erratic manner. The same behavior happens if you move the progress setting in a nonlinear fashion.

Customizing a ProgressMonitor Look and Feel

Changing the look and feel of `ProgressMonitor` requires changing the appearance of both the `JProgressBar` and the `JLabel`, as well as the `JOptionPane` the `ProgressMonitor` uses.

The `ProgressMonitor` has one `UIResource`-related property:

- `ProgressMonitor.progressText` of type `String`

ProgressMonitorInputStream Class

The `ProgressMonitorInputStream` class represents an input stream filter that uses a `ProgressMonitor` to check the progress of the reading of an input stream. If the reading is taking too long to complete, a `ProgressMonitor` appears, and the user can select the `Cancel` button in the pop-up window, causing the reading to be interrupted and the input stream to throw an `InterruptedException`.

Creating a ProgressMonitorInputStream

Like other filtering streams, the `ProgressMonitorInputStream` is created with a reference to the stream it needs to filter. Besides a reference to this filter, the single constructor for `ProgressMonitorInputStream` requires two arguments for its `ProgressMonitor`: a parent component and a message. As seen here, the constructor takes the `ProgressMonitor` arguments first:

```
public ProgressMonitorInputStream(  
    Component parentComponent, Object message, InputStream inputStream)
```

As with the `JOptionPane` and `ProgressMonitor`, the message argument is an `Object`, not a `String`, so you can display an array of components or strings on multiple lines. The following code creates one `ProgressMonitorInputStream`.

```
FileInputStream fis = new FileInputStream(filename);
ProgressMonitorInputStream pmis =
    new ProgressMonitorInputStream(parent, "Reading " + filename, fis);
```

Note The minimum...maximum range for the `ProgressMonitorInputStream` `ProgressMonitor` is `[0...size of stream]`.

Using a `ProgressMonitorInputStream`

As with all input streams, once you've created a `ProgressMonitorInputStream`, you need to read from it. If the input stream isn't read quickly enough, the underlying `ProgressMonitor` causes the progress pop-up window to appear. Once that window appears, a user can monitor the progress or cancel the reading by selecting the Cancel button. If the Cancel button is selected, an `InterruptedException` is thrown, and the `bytesTransferred` field of the exception is set to the number of bytes successfully read.

Figure 9-17 shows what one `ProgressMonitorInputStream` pop-up might look like. For a little variety, the pop-up uses two `JLabel` components in the message, instead of just one.




Figure 9-17. *ProgressMonitorInputStream* pop-up

Listing 9-6 shows a complete source example. The boldfaced lines are the keys to using the `ProgressMonitorInputStream`. They set up the dialog box's message and create the input stream. The program uses a file name specified from the command line, reads the file, and copies the file to standard output (the console). If the file is large enough, the progress monitor will appear. If you press the Cancel button, the reading stops and `Canceled` is printed to standard error.

Listing 9-6. *ProgressMonitorInputStream Demonstration*

```
import java.io.*;
import java.awt.*;
import javax.swing.*;

public class ProgressInputSample {
    public static final int NORMAL    = 0;
    public static final int BAD_FILE  = 1;
    public static final int CANCELED  = NORMAL;
    public static final int PROBLEM   = 2;
```

```

public static void main(String args[]) {
    int returnValue = NORMAL;
    if (args.length != 1) {
        System.err.println("Usage:");
        System.err.println("java ProgressInputSample filename");
    } else {
        try {
            FileInputStream fis = new FileInputStream(args[0]);
            JLabel filenameLabel = new JLabel(args[0], JLabel.RIGHT);
            Object message[] = { "Reading:", filenameLabel } ;
            ProgressMonitorInputStream pmis =
                new ProgressMonitorInputStream(null, message, fis);
            InputStreamReader isr = new InputStreamReader(pmis);
            BufferedReader br = new BufferedReader(isr);
            String line;
            while ((line = br.readLine()) != null) {
                System.out.println(line);
            }
            br.close();
        } catch (FileNotFoundException exception) {
            System.err.println("Bad File " + exception);
            returnValue = BAD_FILE;
        } catch (InterruptedIOException exception) {
            System.err.println("Canceled");
            returnValue = CANCELED;
        } catch (IOException exception) {
            System.err.println("I/O Exception " + exception);
            returnValue = PROBLEM;
        }
    }
    // AWT Thread created - must exit
    System.exit(returnValue);
}
}

```

■ **Note** Having a null argument for the parent component to the `ProgressMonitorInputStream` constructor causes the pop-up window to appear centered on the screen.

ProgressMonitorInputStream Properties

Table 9-7 shows the single property of `ProgressMonitorInputStream`. The `ProgressMonitor` is created when the input stream is created. You shouldn't need to modify the `ProgressMonitor`.

However, you might want to provide a longer or shorter delay (the `millisToDecideToPopup` property of `ProgressMonitor`) before the pop-up window is displayed.

Table 9-7. *ProgressMonitorInputStream* Property

Property Name	Data Type	Access
<code>progressMonitor</code>	<code>ProgressMonitor</code>	Read-only

JColorChooser Class

You can think of a `JColorChooser` as an input-only `JOptionPane` whose input field asks you to choose a color. Like a `JOptionPane`, the `JColorChooser` is just a bunch of components in a container, not a ready-to-use pop-up window. Figure 9-18 shows how a `JColorChooser` might appear in your own application window. At the top are three selectable color chooser panels; at the bottom is a preview panel. The “I Love Swing” bit is not part of the chooser, but of the application that contains the chooser.




Figure 9-18. *JColorChooser* sample

In addition to appearing within your application windows, the `JColorChooser` class also provides support methods for automatically placing the group of components in a `JDialog`. Figure 9-19 shows one such automatically created pop-up.




Figure 9-19. *JColorChooser pop-up sample*

In support of this behavior, the `JColorChooser` class requires the help of several support classes found in the `javax.swing.colorchooser` package. The data model for the `JColorChooser` is an implementation of the `ColorSelectionModel` interface. The `javax.swing.colorchooser` package provides the `DefaultColorSelectionModel` class as an implementation of the `ColorSelectionModel` interface. For the user interface, the `JColorChooser` class relies on the `ColorChooserComponentFactory` to create the default panels from which to choose a color. These panels are specific subclasses of the `AbstractColorChooserPanel` class, and if you don't like the default set, you can create your own.

By default, when multiple chooser panels are in a `JColorChooser`, each panel is shown on a tab of a `JTabbedPane`. However, the `ColorChooserUI` can deal with multiple panels in any way it desires.

Creating a `JColorChooser`

If you want to create a `JColorChooser` and place it in your own window, you use one of the following three constructors for the `JColorChooser` class:

```
public JColorChooser()
JColorChooser colorChooser = new JColorChooser();

public JColorChooser(Color initialColor)
JColorChooser colorChooser =
    new JColorChooser(aComponent.getBackground());

public JColorChooser(ColorSelectionModel model)
JColorChooser colorChooser = new JColorChooser(aColorSelectionModel);
```

By default, the initial color for the chooser is white. If you don't want white as the default, you can provide the initial color as a `Color` object or `ColorSelectionModel`.

Using JColorChooser

Once you've created a `JColorChooser` from a constructor, you can place it in any `Container`, just like any other `Component`. For instance, the source shown in Listing 9-7 created the GUI shown earlier in Figure 9-18.

Listing 9-7. *Using a `JColorChooser` in Your `JFrame`*

```
import java.awt.*;
import javax.swing.*;
import javax.swing.event.*;
import javax.swing.colorchooser.*;

public class ColorSample {

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("JColorChooser Popup");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                final JLabel label = new JLabel("I Love Swing", JLabel.CENTER);
                label.setFont(new Font("Serif", Font.BOLD | Font.ITALIC, 48));
                frame.add(label, BorderLayout.SOUTH);

                final JColorChooser colorChooser =
                    new JColorChooser(label.getBackground());
                colorChooser.setBorder(
                    BorderFactory.createTitledBorder("Pick Foreground Color"));

                // More source to come
                frame.add(colorChooser, BorderLayout.CENTER);

                frame.pack();
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

Although this source code creates the GUI, selecting a different color within the `JColorChooser` doesn't do anything yet. Let's now look at the code that causes color changes.

Listening for Color Selection Changes

The `JColorChooser` uses a `ColorSelectionModel` as its data model. As the following interface definition shows, the data model includes a single property, `selectedColor`, for managing the state of the color chooser.

```
public interface ColorSelectionModel {
    // Listeners
    public void addChangeListener(ChangeListener listener);
    public void removeChangeListener(ChangeListener listener);
    // Properties
    public Color getSelectedColor();
    public void setSelectedColor(Color newValue);
}
```

When a user changes the color within the `JColorChooser`, the `selectedColor` property changes, and the `JColorChooser` generates a `ChangeEvent` to notify any registered `ChangeListener` objects.

Therefore, to complete the earlier `ColorSample` example in the previous section, and have the foreground color of the label change when the user changes the color selection within the `JColorChooser`, you need to register a `ChangeListener` with the color chooser. This involves creating a `ChangeListener` and adding it to the `ColorSelectionModel`. Placing the source code shown in Listing 9-8 where the `//More source to come` comment appears in the Listing 9-7 is necessary for this example to work properly.

Listing 9-8. Activating the `JColorChooser` Example

```
ColorSelectionModel model = colorChooser.getSelectionModel();
ChangeListener changeListener = new ChangeListener() {
    public void stateChanged(ChangeEvent changeEvent) {
        Color newForegroundColor = colorChooser.getColor();
        label.setForeground(newForegroundColor);
    }
};
model.addChangeListener(changeListener);
```

Once this source is added, the example is complete. Running the program brings up Figure 9-18, and selecting a new color alters the foreground of the label.

Creating and Showing a `JColorChooser` Pop-Up Window

Although the previous example is sufficient if you want to include a `JColorChooser` within your own window, more often than not, you want the `JColorChooser` to appear in a separate pop-up window. This window might appear as the result of selecting a button on the screen, or possibly even selecting a menu item. To support this behavior, the `JColorChooser` includes the following factory method:

```
public static Color showDialog(Component parentComponent,
    String title, Color initialColor)
```

When called, `showDialog()` creates a modal dialog box with the given parent component and title. Within the dialog box is a `JColorChooser` whose initial color is the one provided. As you can see in Figure 9-18 (shown earlier in the chapter), along the bottom are three buttons: OK, Cancel, and Reset. When OK is pressed, the pop-up window disappears and the `showDialog()` method returns the currently selected color. When Cancel is pressed, `null` is returned instead of the selected color or the initial color. Selection of the Reset button causes the `JColorChooser` to change its selected color to the initial color provided at startup.

What normally happens with the `showDialog()` method is that the initial color argument is some color property of an object. The returned value of the method call then becomes the new setting for the same color property. This usage pattern is shown in the following lines of code, where the changing color property is the background for a button. As with `JOptionPane`, the `null` parent-component argument causes the pop-up window to be centered on the screen instead of over any particular component.

```
Color initialBackground = button.getBackground();
Color background = JColorChooser.showDialog(
    null, "Change Button Background", initialBackground);
if (background != null) {
    button.setBackground(background);
}
```

To place this code in the context of a complete example, Listing 9-9 shows source code that offers a button that, when selected, displays a `JColorChooser`. The color selected within the chooser becomes the background color of the button after the OK button is selected.

Listing 9-9. *Using `showDialog` with the `JColorChooser`*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;

public class ColorSamplePopup {

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("JColorChooser Sample Popup");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                final JButton button = new JButton("Pick to Change Background");

                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        Color initialBackground = button.getBackground();
                        Color background = JColorChooser.showDialog(
                            null, "Change Button Background", initialBackground);
```

```

        if (background != null) {
            button.setBackground(background);
        }
    }
};
button.addActionListener(actionListener);
frame.add(button, BorderLayout.CENTER);

frame.setSize(300, 100);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Providing Your Own OK/Cancel Event Listeners

If the `showDialog()` method provides too much automatic behavior, you may prefer another `JColorChooser` method that allows you to customize the chooser before displaying it and define what happens when the OK and Cancel buttons are selected:

```

public static JDialog createDialog(Component parentComponent, String title,
    boolean modal, JColorChooser chooserPane, ActionListener okListener,
    ActionListener cancelListener)

```

In `createDialog()`, the parent component and title arguments are the same as `showDialog()`. The modal argument allows the pop-up window to be nonmodal, unlike `showDialog()` in which the pop-up is always modal. When the pop-up is not modal, the user can still interact with the rest of the application. The OK and Cancel buttons in the pop-up window automatically have one associated `ActionListener` that hides the pop-up window after selection. It's your responsibility to add your own listeners if you need any additional response from selection.

To demonstrate proper usage of `createDialog()`, the program shown in Listing 9-10 duplicates the functionality of the program shown in Listing 9-9. However, instead of automatically accepting the new color, the color change is rejected if the new background is the same color as the foreground. In addition, if the user selects the Cancel button, the button background color is set to red.

Listing 9-10. Custom Action Listeners on `JColorChooser` Buttons

```

import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import javax.swing.event.*;
import javax.swing.colorchooser.*;

public class CreateColorSamplePopup {

```

```

public static void main(String args[]) {
    Runnable runner = new Runnable() {
        public void run() {
            JFrame frame = new JFrame("JColorChooser Create Popup Sample");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

            final JButton button = new JButton("Pick to Change Background");

            ActionListener actionListener = new ActionListener() {
                public void actionPerformed(ActionEvent actionEvent) {
                    Color initialBackground = button.getBackground();

                    final JColorChooser colorChooser =
                        new JColorChooser(initialBackground);

                    // For okay selection, change button background to selected color
                    ActionListener okActionListener = new ActionListener() {
                        public void actionPerformed(ActionEvent actionEvent) {
                            Color newColor = colorChooser.getColor();
                            if (newColor.equals(button.getForeground())) {
                                System.out.println("Color change rejected");
                            } else {
                                button.setBackground(colorChooser.getColor());
                            }
                        }
                    };

                    // For cancel selection, change button background to red
                    ActionListener cancelActionListener = new ActionListener() {
                        public void actionPerformed(ActionEvent actionEvent) {
                            button.setBackground(Color.RED);
                        }
                    };

                    final JDialog dialog = JColorChooser.createDialog(null,
                        "Change Button Background", true, colorChooser,
                        okActionListener, cancelActionListener);

                    // Wait for current event dispatching to complete before showing
                    Runnable showDialog = new Runnable() {
                        public void run() {
                            dialog.setVisible(true);
                        }
                    };
                }
            };
        }
    };
}

```

```

        EventQueue.invokeLater(showDialog);
    }
};
button.addActionListener(actionListener);
frame.add(button, BorderLayout.CENTER);

frame.setSize(300, 100);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Note Notice that the `actionPerformed()` method that shows the color chooser uses the `EventQueue.invokeLater()` method to show the chooser. The current event handler needs to finish before showing the chooser. Otherwise, the previous action event processing won't complete before the chooser is shown.

JColorChooser Properties

Table 9-8 lists information on the eight properties of the `JColorChooser`, including the three data types of the single property `color`.

Table 9-8. *JColorChooser Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>chooserPanels</code>	<code>AbstractColorChooserPanel[]</code>	Read-write bound
<code>color</code>	<code>Color</code>	Read-write
<code>color</code>	<code>int rgb</code>	Write-only
<code>color</code>	<code>int red, int green, int blue</code>	Write-only
<code>dragEnabled</code>	<code>boolean</code>	Read-write
<code>previewPanel</code>	<code>JComponent</code>	Read-write bound
<code>selectionModel</code>	<code>ColorSelectionModel</code>	Read-write bound
<code>UI</code>	<code>ColorChooserUI</code>	Read-write bound
<code>UIClassID</code>	<code>String</code>	Read-only

The color property is special in that it has three ways of setting itself:

- Directly from a `Color`
- From one integer representing its red-green-blue values combined into one `int` variable using the nibble allocation `0xAARRGGBB`, where *A* is for alpha value (and is ignored, using 255 instead)
- From three integers, separating the red, green, and blue color components into three separate `int` variables

If you don't use `showDialog()`, you can customize the `JColorChooser` before displaying it. Besides customizing the color property, which is settable in the `JColorChooser` constructor, you can customize the component to be displayed in the preview area and the color chooser panels.

Changing the Preview Panel

It's the responsibility of the `ColorChooserComponentFactory` class to provide the default component for the preview area of the `JColorChooser`. For the standard look and feel types, the preview panel is in the bottom portion of the color chooser.

If you don't want a preview panel in the color chooser, you must change the `previewPanel` property to a component value that isn't null. When the property is set to null, the default preview panel for the look and feel is shown. Setting the property to an empty `JPanel` serves the purpose of not showing the preview panel.

```
colorChooser.setPreviewPanel(new JPanel());
```

Figure 9-20 shows what one such color chooser might look like without the preview panel. Because the `JPanel` has no size when nothing is in it, this effectively removes the panel.




Figure 9-20. *JColorChooser without a preview panel*

If you want the preview panel present, but just don't like the default appearance, you can add your own `JComponent` to the area. Configuration entails placing your new preview panel in

a title-bordered container, and having the foreground of the preview panel change when the user selects a new color.

Caution A bug in the `ColorChooserUI` implementation class (`BasicColorChooserUI`) requires an extra step to properly install the preview panel. Besides calling `setPreviewPanel(newPanel)`, you must set the panel's size and border to enable the user interface to properly configure the new preview panel. The exact steps seem to vary with which JDK release you are using. See http://bugs.sun.com/bugdatabase/view_bug.do?bug_id=5029286 for more details. There are some other related bugs (search the Bug Parade for `setPreviewPanel`).

The following source demonstrates the use of a `JLabel` as the custom preview panel with the necessary work-around. Figure 9-21 demonstrates what the `JColorChooser` that uses this preview panel would look like.

```
final JLabel previewLabel = new JLabel("I Love Swing", JLabel.CENTER);
previewLabel.setFont(new Font("Serif", Font.BOLD | Font.ITALIC, 48));
previewLabel.setSize(previewLabel.getPreferredSize());
previewLabel.setBorder(BorderFactory.createEmptyBorder(0,0,1,0));
colorChooser.setPreviewPanel(previewLabel);
```





Figure 9-21. *JColorChooser with custom preview panel*

Note Because the initial setting for the foreground of the preview panel is its background color, the panel will appear to be empty. This is one reason why the default preview panel shows text with contrasting background colors.


Changing the Color Chooser Panels

The various tabs in the upper part of the `JColorChooser` represent the `AbstractColorChooserPanel` implementations. Each allows the user to pick a color in a different manner. By default, the `ColorChooserComponentFactory` provides the `JColorChooser` with three panels (see Figure 9-22):


- The Swatches panel lets a user pick a color from a set of predefined color swatches, as if at a paint store.
- The HSB panel allows a user to pick a color using the Hue-Saturation-Brightness color model.
- The RGB panel is for picking colors using the Red-Green-Blue color model.



Swatches



HSB



RGB

Figure 9-22. *The default `JColorChooser` panels*

If you don't like the default chooser panels, or you just want to add other color chooser panels that work differently, you can create your own by subclassing the `AbstractColorChooserPanel` class. To add a new panel to the existing set, call the following method:

```
public void addChooserPanel(AbstractColorChooserPanel panel)
```

If you later decide that you no longer want the new panel, you can remove it with this method:

```
public AbstractColorChooserPanel removeChooserPanel(AbstractColorChooserPanel panel)
```

To replace the existing set of panels, call this method:

```
setChooserPanels(AbstractColorChooserPanel panels[ ])
```

Creating a new panel entails subclassing `AbstractColorChooserPanel` and filling in the details of choosing a color for the new panel. The class definition, shown in the following code lines, includes five abstract methods. These five methods are what must be overridden.

```
public abstract class AbstractColorChooserPanel extends JPanel {
    public AbstractColorChooserPanel();
    protected abstract void buildChooser();
    protected Color getColorFromModel();
    public ColorSelectionModel getColorSelectionModel();
    public int getDisplayMnemonicIndex();
    public abstract String getDisplayName();
    public abstract Icon getLargeDisplayIcon();
    public int getMnemonic();
    public abstract Icon getSmallDisplayIcon();
    public void installChooserPanel(JColorChooser);
    public void paint(Graphics);
    public void uninstallChooserPanel(JColorChooser);
    public abstract void updateChooser();
}
```

To demonstrate how to work with color chooser panels, let's look at how to create a new one that displays a list of colors from the `Color` and `SystemColor` class. From this list, the user must pick one. The panel will use a `JComboBox` to represent the list of colors. (The details of using a `JComboBox` are explained in Chapter 13.) Figure 9-23 shows the finished panel. The panel is created and added with the following source:

```
SystemColorChooserPanel newChooser = new SystemColorChooserPanel();
AbstractColorChooserPanel chooserPanels[] = {newChooser};
colorChooser.setChooserPanels(chooserPanels);
```




Figure 9-23. *Replacing all panels with the new SystemColor chooser panel*

The first method to define is `public String getDisplayName()`. This method returns a text label to display on the tab when multiple chooser panels are available. If there's only one chooser panel, this name isn't shown.

```
public String getDisplayName() {
    return "SystemColor";
}
```

The return values for the two `Icon` methods do nothing with the system look and feel types. You can return null from them or return an `Icon` to check that nothing has been done with them. A custom `ColorChooserUI` could use the two `Icon` methods somewhere, possibly for the icon on a chooser panel tab.

```
public Icon getSmallDisplayIcon() {
    return new DiamondIcon(Color.BLUE);
}

public Icon getLargeDisplayIcon() {
    return new DiamondIcon(Color.GREEN);
}
```

The protected `void buildChooser()` method is called by the `installChooserPanel()` method of `AbstractColorChooserPanel` when the panel is added to the chooser. You use this method to add the necessary components to the container. In the sample `SystemColorChooserPanel` chooser, this involves creating the `JComboBox` and adding it to the panel. Because `AbstractColorChooserPanel` is a `JPanel` subclass, you can just `add()` the combo box. The combo box must be filled with options and an event handler installed for when the user selects the component. The specifics of the event handling are described after the following block of source code.

```
protected void buildChooser() {
    comboBox = new JComboBox(labels);
    comboBox.addItemListener(this);
    add(comboBox);
}
```

Note In addition, if you choose to override `uninstallChooserPanel` (`JColorChooser` enclosing `Chooser`), you need to call `super.uninstallChooserPanel` (`JColorChooser` enclosing `Chooser`) *last*, instead of first.

When a user changes the color value in an `AbstractColorChooserPanel`, the panel must notify the `ColorSelectionModel` of the change in color. In the `SystemColorChooserPanel` panel, this equates to the user selecting a new choice in the `JComboBox`. Therefore, when the combo box value changes, find the `Color` that equates to the choice and tell the model about the change.

```
public void itemStateChanged(ItemEvent itemEvent) {
    int state = itemEvent.getStateChange();
    if (state == ItemEvent.SELECTED) {
        int position = findColorLabel(itemEvent.getItem());
        // Last position is bad (not selectable)
        if ((position != NOT_FOUND) && (position != labels.length-1)) {
            ColorSelectionModel selectionModel = getColorSelectionModel();
            selectionModel.setSelectedColor(colors[position]);
        }
    }
}
```

The final `AbstractColorChooserPanel` method to implement is `public void updateChooser()`. It, too, is called by `installChooserPanel()` at setup time. In addition, it's also called whenever the `ColorSelectionModel` of the `JColorChooser` changes. When `updateChooser()` is called, the chooser panel should update its display to show that the current color of the model is selected. Not all panels show which color is currently selected, so a call may do nothing. (The system-provided `Swatches` panel is one that doesn't display the current color.) In addition, it's possible that the current color isn't displayable on the panel. For instance, on the `SystemColorChooserPanel`, if the current selection isn't a `SystemColor` or `Color` constant, you can either do nothing or display something to signify a custom color. Therefore, in the `updateChooser()` implementation, you need to get the current color from the `ColorSelectionModel` and change the color for the panel. The actual setting is done in a helper method called `setColor(Color newValue)`.

```
public void updateChooser() {
    Color color = getColorFromModel();
    setColor(color);
}
```

The `setColor(Color newColor)` method simply looks up the color in a lookup table using the position returned from `findColorPosition(Color newColor)`.

```
// Change combo box to match color, if possible
private void setColor(Color newColor) {
    int position = findColorPosition(newColor);
    comboBox.setSelectedIndex(position);
}
```

The specifics of the `findColorLabel(Object label)` and `findColorPosition(Color newColor)` methods are shown in the complete source in Listing 9-11, coming up shortly.

If you don't use the `showDialog()` means of showing the chooser pop-up window, once the chooser panel has been defined, and you've created a chooser panel, it can be placed within a `JColorChooser` with `addChooserPanel()`.

```
AbstractColorChooserPanel newChooser = new SystemColorChooserPanel();
colorChooser.addChooserPanel(newChooser);
```

After showing the `JColorChooser` and picking the appropriate tab, your new chooser will be available for use, as shown in Figure 9-24.




Figure 9-24. After adding the new `SystemColor` chooser panel

The complete source for the `SystemColorChooserPanel` is shown in Listing 9-11. The program should use the `ComboBoxModel` to store the labels and colors arrays of the example in one data model. However, the complexities of using the MVC capabilities of the `JComboBox` will be saved for Chapter 13. Feel free to change the example in order to use the appropriate data model for the `JComboBox` or some of the other `Collections` API classes available.

Listing 9-11. Custom `AbstractColorChooserPanel`

```
import javax.swing.*;
import javax.swing.colorchooser.*;
import java.awt.*;
import java.awt.event.*;

public class SystemColorChooserPanel
    extends AbstractColorChooserPanel
    implements ItemListener {
```

```
private static int NOT_FOUND = -1;
```

```
JComboBox comboBox;  
String labels[] = {  
    "BLACK",  
    "BLUE",  
    "CYAN",  
    "DARK_GRAY",  
    "GRAY",  
    "GREEN",  
    "LIGHT_GRAY",  
    "MAGENTA",  
    "ORANGE",  
    "PINK",  
    "RED",  
    "WHITE",  
    "YELLOW",  
    "activeCaption",  
    "activeCaptionBorder",  
    "activeCaptionText",  
    "control",  
    "controlDkShadow",  
    "controlHighlight",  
    "controlLtHighlight",  
    "controlShadow",  
    "controlText",  
    "desktop",  
    "inactiveCaption",  
    "inactiveCaptionBorder",  
    "inactiveCaptionText",  
    "info",  
    "infoText",  
    "menu",  
    "menuText",  
    "scrollbar",  
    "text",  
    "textHighlight",  
    "textHighlightText",  
    "textInactiveText",  
    "textText",  
    "window",  
    "windowBorder",  
    "windowText",  
    "<Custom>"};
```

```
Color colors[] = {
    Color.BLACK,
    Color.BLUE,
    Color.CYAN,
    Color.DARK_GRAY,
    Color.GRAY,
    Color.GREEN,
    Color.LIGHT_GRAY,
    Color.MAGENTA,
    Color.ORANGE,
    Color.PINK,
    Color.RED,
    Color.WHITE,
    Color.YELLOW,
    SystemColor.activeCaption,
    SystemColor.activeCaptionBorder,
    SystemColor.activeCaptionText,
    SystemColor.control,
    SystemColor.controlDkShadow,
    SystemColor.controlHighlight,
    SystemColor.controlLtHighlight,
    SystemColor.controlShadow,
    SystemColor.controlText,
    SystemColor.desktop,
    SystemColor.inactiveCaption,
    SystemColor.inactiveCaptionBorder,
    SystemColor.inactiveCaptionText,
    SystemColor.info,
    SystemColor.infoText,
    SystemColor.menu,
    SystemColor.menuText,
    SystemColor.scrollbar,
    SystemColor.text,
    SystemColor.textHighlight,
    SystemColor.textHighlightText,
    SystemColor.textInactiveText,
    SystemColor.textText,
    SystemColor.window,
    SystemColor.windowBorder,
    SystemColor.windowText,
    null};

// Change combo box to match color, if possible
private void setColor(Color newColor) {
    int position = findColorPosition(newColor);
    comboBox.setSelectedIndex(position);
}
```

```

// Given a label, find the position of the label in the list
private int findColorLabel(Object label) {
    String stringLabel = label.toString();
    int position = NOT_FOUND;
    for (int i=0,n=labels.length; i<n; i++) {
        if (stringLabel.equals(labels[i])) {
            position=i;
            break;
        }
    }
    return position;
}

// Given a color, find the position whose color matches
// This could result in a position different from original if two are equal
// Since actual color is same, this is considered to be okay
private int findColorPosition(Color color) {
    int position = colors.length-1;
    // Cannot use equals() to compare Color and SystemColor
    int colorRGB = color.getRGB();
    for (int i=0,n=colors.length; i<n; i++) {
        if ((colors[i] != null) && (colorRGB == colors[i].getRGB())) {
            position=i;
            break;
        }
    }
    return position;
}

public void itemStateChanged(ItemEvent itemEvent) {
    int state = itemEvent.getStateChange();
    if (state == ItemEvent.SELECTED) {
        int position = findColorLabel(itemEvent.getItem());
        // last position is bad (not selectable)
        if ((position != NOT_FOUND) && (position != labels.length-1)) {
            ColorSelectionModel selectionModel = getColorSelectionModel();
            selectionModel.setSelectedColor(colors[position]);
        }
    }
}

public String getDisplayName() {
    return "SystemColor";
}

```

```

public Icon getSmallDisplayIcon() {
    return new DiamondIcon(Color.BLUE);
}

public Icon getLargeDisplayIcon() {
    return new DiamondIcon(Color.GREEN);
}

protected void buildChooser() {
    comboBox = new JComboBox(labels);
    comboBox.addItemListener(this);
    add(comboBox);
}

public void updateChooser() {
    Color color = getColorFromModel();
    setColor(color);
}
}

```

Listing 9-12 demonstrates the use of the new chooser panel. It's a slightly modified version of the `CreateColorSamplePopup` program shown earlier in Listing 9-10. You can uncomment the `setChooserPanels()` statement and comment out the `addChooserPanel()` call to go from adding one panel (as in Figure 9-23) to replacing all of them (as in Figure 9-24).

Listing 9-12. *Having Custom Panels in a JColorChooser*

```

import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import javax.swing.event.*;
import javax.swing.colorchooser.*;

public class CustomPanelPopup {

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("JColorChooser Custom Panel Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                final JButton button = new JButton("Pick to Change Background");

                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        Color initialBackground = button.getBackground();

```

```

final JColorChooser colorChooser =
    new JColorChooser(initialBackground);
SystemColorChooserPanel newChooser =
    new SystemColorChooserPanel();
// AbstractColorChooserPanel chooserPanels[] = {newChooser};
// colorChooser.setChooserPanels(chooserPanels);
colorChooser.addChooserPanel(newChooser);

// For okay button, change button background to selected color
ActionListener okActionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        Color newColor = colorChooser.getColor();
        if (newColor.equals(button.getForeground())) {
            System.out.println("Color change rejected");
        } else {
            button.setBackground(colorChooser.getColor());
        }
    }
};

// For cancel button, change button background to red
ActionListener cancelActionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        button.setBackground(Color.RED);
    }
};

final JDialog dialog =
    JColorChooser.createDialog(
        null, "Change Button Background", true, colorChooser,
        okActionListener, cancelActionListener);

// Wait for current event dispatching to complete before showing
Runnable showDialog = new Runnable() {
    public void run() {
        dialog.setVisible(true);
    }
};
EventQueue.invokeLater(showDialog);
};
button.addActionListener(actionListener);
frame.add(button, BorderLayout.CENTER);

```

```

        frame.setSize(300, 100);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Using the ColorChooserComponentFactory Class

One class worthy of some special attention is `ColorChooserComponentFactory`. Normally, this class does its work behind the scenes, and you never need to deal with it.

However, if you want to remove one of the default color choosers, you cannot use the public `AbstractColorChooserPanel removeChooserPanel(AbstractColorChooserPanel panel)` method of `JColorChooser`. Initially, the `chooserPanels` property of `JColorChooser` is null. When this property is null, the default `ColorChooserUI` asks the `ColorChooserComponentFactory` for the default panels with the public static `AbstractColorChooserPanel[] getDefaultChooserPanels()` method. So, until you modify the property, no panels will appear. If you want to remove a default panel, you must get the default array, place the panels you want to keep in a new array, and then change the `chooserPanels` property of the chooser to the new array. This is a little extra work, but it gets the job done.

The other method in the `ColorChooserComponentFactory` class is public static `JComponent getPreviewPanel()`, which gets the default preview panel when the `previewPanel` property of a `JColorChooser` is null. This is the reason that providing a null argument to the `setPreviewPanel()` method of `JColorChooser` doesn't remove the preview panel. For the panel to be empty, you must provide a `JComponent` with no size.

```
colorChooser.setPreviewPanel(new JPanel());
```

Customizing a JColorChooser Look and Feel

The `JColorChooser` appearance is nearly the same for all the preinstalled look and feel types. The only differences are related to how each look and feel displays the internal components, such as a `JTabbedPane`, `JLabel`, `JButton`, or `JSlider`. Changing the `UIResource`-related properties of those components affects the appearance of a newly created `JColorChooser`. In addition, the `JColorChooser` class has its own 39 `UIResource`-related properties available for customization, as listed in Table 9-9. Most of these resources are related to text labels appearing on the various default color chooser panels.

Table 9-9. *JColorChooser UIResource Elements*

Property String	Object Type
<code>ColorChooser.background</code>	Color
<code>ColorChooser.cancelText</code>	String
<code>ColorChooser.font</code>	Font
<code>ColorChooser.foreground</code>	Color

Table 9-9. *JColorChooser UIResource Elements (Continued)*

Property String	Object Type
ColorChooser.hsbBlueText	String
ColorChooser.hsbBrightnessText	String
ColorChooser.hsbDisplayedMnemonicIndex	Integer
ColorChooser.hsbGreenText	String
ColorChooser.hsbHueText	String
ColorChooser.hsbMnemonic	Integer
ColorChooser.hsbNameText	String
ColorChooser.hsbRedText	String
ColorChooser.hsbSaturationText	String
ColorChooser.okText	String
ColorChooser.panels	AbstractColorChooserPanel[]
ColorChooser.previewText	String
ColorChooser.resetMnemonic	Integer
ColorChooser.resetText	String
ColorChooser.rgbBlueDisplayedMnemonicIndex	Integer
ColorChooser.rgbBlueMnemonic	Integer
ColorChooser.rgbBlueText	String
ColorChooser.rgbGreenDisplayedMnemonicIndex	Integer
ColorChooser.rgbGreenMnemonic	Integer
ColorChooser.rgbGreenText	String
ColorChooser.rgbMnemonic	Integer
ColorChooser.rgbNameText	String
ColorChooser.rgbRedDisplayedMnemonicIndex	Integer
ColorChooser.rgbRedMnemonic	Integer
ColorChooser.rgbRedText	String
ColorChooser.sampleText	String
ColorChooser.showPreviewPanelText	Boolean
ColorChooser.swatchesDefaultRecentColor	Color
ColorChooser.swatchesDisplayedMnemonicIndex	Integer
ColorChooser.swatchesMnemonic	Integer
ColorChooser.swatchesNameText	String
ColorChooser.swatchesRecentSwatchSize	Dimension

Table 9-9. *JColorChooser UIResource Elements (Continued)*

Property String	Object Type
ColorChooser.swatchesRecentText	String
ColorChooser.swatchesSwatchSize	Dimension
ColorChooserUI	String

JFileChooser Class

The Swing component set also provides a chooser for the selection of file names and/or directories: the `JFileChooser` class. This chooser replaces the need for using the `FileDialog` from the original AWT component set. Like the other Swing chooser components, `JFileChooser` isn't automatically placed in a pop-up window, but it can be placed anywhere within the user interface of your program. Figure 9-25 shows a `JFileChooser` with the Metal look and feel, Ocean theme, that has been automatically placed in a modal `JDialog`.




Figure 9-25. *JFileChooser sample*

In support of the `JFileChooser` class are a handful of classes in the `javax.swing.filechooser` package. The support classes include a `FileFilter` class for restricting files and directories to be listed in the `FileView` of the `JFileChooser`. The `FileView` controls how the directories and files are listed within the `JFileChooser`. The `FileSystemView` is an abstract class that tries to hide file system-related operating system specifics from the file chooser. Java 2 platform vendors will provide operating system-specific versions so that tasks such as listing root partitions can be done (with 100% Pure Java code).

Caution Don't confuse the abstract `javax.swing.filechooser.FileFilter` class with the `java.io.FileFilter` interface. Although functionally similar, they're different. The two coexist because the `java.io.FileFilter` interface didn't exist in a Java 1.1 runtime. Because the original Swing `JFileChooser` needed to run in both Java 1.1 and Java 2 environments, the chooser needed to define a replacement. Unless otherwise specified, all `FileFilter` references in this text are to the class in the `javax.swing.filechooser` package.

Creating a JFileChooser

There are six constructors for `JFileChooser`:

```
public JFileChooser()  
JFileChooser fileChooser = new JFileChooser();  
  
public JFileChooser(File currentDirectory)  
File currentDirectory = new File("."); // starting directory of program  
JFileChooser fileChooser = new JFileChooser(currentDirectory);  
  
public JFileChooser(File currentDirectory, FileSystemView fileSystemView)  
FileSystemView fileSystemView = new SomeFileSystemView(...);  
JFileChooser fileChooser = new JFileChooser(currentDirectory, fileSystemView);  
  
public JFileChooser(FileSystemView fileSystemView)  
JFileChooser fileChooser = new JFileChooser(fileSystemView);  
  
public JFileChooser(String currentDirectoryPath)  
String currentDirectoryPath = "."; // starting directory of program  
JFileChooser fileChooser = new JFileChooser(currentDirectoryPath);  
  
public JFileChooser(String currentDirectoryPath, FileSystemView fileSystemView)  
JFileChooser fileChooser = new JFileChooser(currentDirectoryPath, fileSystemView);
```

By default, the starting directory displayed is the user's home directory (system property `user.home`). If you want to start the `JFileChooser` pointing at another directory, the directory can be specified as either a `String` or a `File` object.

You can also specify a `FileSystemView` to specify a custom representation to the operating system's top-level directory structure. When the `FileSystemView` argument is not specified, the `JFileChooser` uses a `FileSystemView` appropriate for the user's operating system.

Using JFileChooser

After creating a `JFileChooser` from a constructor, you can place it in any `Container`, because it's a `JComponent`. The `JFileChooser` object looks a little strange in an object that's not a pop-up window, but this may allow you to do a task without needing to constantly bring up a new file chooser.

Listing 9-13 demonstrates a simple window with two labels and a `JFileChooser`. Notice that there are no Open or Cancel buttons, but the buttons in the `FileSystemView` area are selectable.

Listing 9-13. *Using a `JFileChooser` in Your `JFrame`*

```
import java.io.File;
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;

public class FileSamplePanel {

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("JFileChooser Popup");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                final JLabel directoryLabel = new JLabel(" ");
                directoryLabel.setFont(new Font("Serif", Font.BOLD | Font.ITALIC, 36));
                frame.add(directoryLabel, BorderLayout.NORTH);

                final JLabel filenameLabel = new JLabel(" ");
                filenameLabel.setFont(new Font("Serif", Font.BOLD | Font.ITALIC, 36));
                frame.add(filenameLabel, BorderLayout.SOUTH);

                JFileChooser fileChooser = new JFileChooser(".");
                fileChooser.setControlButtonsAreShown(false);
                frame.add(fileChooser, BorderLayout.CENTER);

                frame.pack();
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

Adding an `ActionListener` to a `JFileChooser`

The `JFileChooser` allows you to add `ActionListener` objects to listen for selection of the approval or cancel actions. Approval is double-clicking a file; cancel is pressing the Escape key. To detect which action was triggered, check the action command for the `ActionEvent` received by your `ActionListener`. Its action command setting will be either `JFileChooser.APPROVE_SELECTION` for file selection or `JFileChooser.CANCEL_SELECTION` for pressing the Escape key.

To complete the previous example in Listing 9-13, adding an `ActionListener` allows you to set the text for the two labels when the user selects a file. On selection, the text becomes the

current directory and file name. On pressing of the Escape key, text is cleared. Listing 9-14 shows the new ActionListener.

Listing 9-14. *ActionListener for JFileChooser in Your JFrame*

```
// Create ActionListener
ActionListener actionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        JFileChooser theFileChooser = (JFileChooser)actionEvent.getSource();
        String command = actionEvent.getActionCommand();
        if (command.equals(JFileChooser.APPROVE_SELECTION)) {
            File selectedFile = theFileChooser.getSelectedFile();
            directoryLabel.setText(selectedFile.getParent());
            filenameLabel.setText(selectedFile.getName());
        } else if (command.equals(JFileChooser.CANCEL_SELECTION)) {
            directoryLabel.setText(" ");
            filenameLabel.setText(" ");
        }
    }
};
fileChooser.addActionListener(actionListener);
```

With the addition of the ActionListener, the program is now complete in the sense that selection is now active. Figure 9-26 shows what this window would look like after selection of the COPYRIGHT file within the c:\jdk1.5.0 directory.




Figure 9-26. *JFileChooser within a custom window*

Showing a JFileChooser within a Pop-Up Window

Instead of placing a JFileChooser panel within your own window, you will more typically place it in a modal JDialog. There are three ways to do this, depending on the text you want to appear on the approval button:

- `public int showDialog(Component parentComponent, String approvalButtonText)`
- `public int showOpenDialog(Component parentComponent)`
- `public int showSaveDialog(Component parentComponent)`

Calling one of these methods will place the configured JFileChooser into a modal JDialog and show the dialog box centered over the parent component. Providing a null parent component centers the pop-up window on the screen. The call doesn't return until the user selects the approval or cancel button. After selection of one of the two buttons, the call returns a status value, depending on which button was selected. This status would be one of three JFileChooser constants: `APPROVE_OPTION`, `CANCEL_OPTION`, or `ERROR_OPTION`.

Caution If the user clicks the approval button without selecting anything, `CANCEL_OPTION` is returned.

To perform the same task as the previous example, in which an ActionListener was attached to the JFileChooser (Listing 9-14), you can just show the dialog box and change the labels based on the return status, instead of relying on the action command, as follows:

```
JFileChooser fileChooser = new JFileChooser(".");
int status = fileChooser.showOpenDialog(null);
if (status == JFileChooser.APPROVE_OPTION) {
    File selectedFile = fileChooser.getSelectedFile();
    directoryLabel.setText(selectedFile.getParent());
    filenameLabel.setText(selectedFile.getName());
} else if (status == JFileChooser.CANCEL_OPTION) {
    directoryLabel.setText(" ");
    filenameLabel.setText(" ");
}
```

With this technique, the file chooser will be shown in another window, instead of within the window with the two labels. Notice that this version switches from checking the String return values of the earlier example to checking int return values: [if (command.equals(JFileChooser.APPROVE_SELECTION)) versus if (status == JFileChooser.APPROVE_OPTION)].

JFileChooser Properties

Once you understand the basic JFileChooser usage, you can customize the component's behavior and appearance by modifying its many properties. Table 9-10 shows the 26 properties of JFileChooser.

Table 9-10. *JFileChooser Properties*

Property Name	Data Type	Access
acceptAllFileFilter	FileFilter	Read-only
acceptAllFileFilterUsed	boolean	Read-write bound
accessibleContext	AccessibleContext	Read-only
accessory	JComponent	Read-write bound
actionListeners	ActionListener[]	Read-only
approveButtonMnemonic	char	Read-write bound
approveButtonText	String	Read-write bound
approveButtonToolTipText	String	Read-write bound
choosableFileFilters	FileFilter[]	Read-only
controlButtonsAreShown	boolean	Read-write bound
currentDirectory	File	Read-write bound
dialogTitle	String	Read-write bound
dialogType	int	Read-write bound
directorySelectionEnabled	boolean	Read-only
dragEnabled	boolean	Read-write
fileFilter	FileFilter	Read-write bound
fileHidingEnabled	boolean	Read-write bound
fileSelectionEnabled	boolean	Read-only
fileSelectionMode	int	Read-write bound
fileSystemView	FileSystemView	Read-write bound
fileView	FileView	Read-write bound
multiSelectionEnabled	boolean	Read-write bound
selectedFile	File	Read-write bound
selectedFiles	File[]	Read-write bound
UI	FileChooserUI	Read-only
UIClassID	String	Read-only

When the different `showDialog()` methods are used, the `dialogType` property is automatically set to one of three `JOptionPane` constants: `OPEN_DIALOG`, `SAVE_DIALOG`, `CUSTOM_DIALOG`. If you're not using `showDialog()`, you should set this property according to the type of dialog box you plan to work with. The `controlButtonsAreShown` property allows you to hide the Open, Save, and Cancel buttons.

Working with File Filters

The `JFileChooser` supports three ways of filtering its file and directory list. The first two involve working with the `FileFilter` class, and the last involves hidden files. First, let's look at the `FileFilter` class.

`FileFilter` is an abstract class that works something like `FilenameFilter` in AWT. However, instead of working with strings for directory and file names, it works with a `File` object. For every `File` object that is to be displayed (both files and directories), the filter decides whether the `File` can appear within the `JFileChooser`. In addition to providing an acceptance mechanism, the filter also provides a description, or name, for when the description is displayed to a user. These two capabilities are reflected in the following two methods of the class definition:

```
public abstract class FileFilter {
    public FileFilter();
    public abstract String getDescription();
    public abstract boolean accept(File file);
}
```

Note Given the abstract nature of this class, it should be an interface, but it isn't.

To demonstrate a file filter, Listing 9-15 creates one that accepts an array of file extensions. If the file sent to `accept()` is a directory, it's automatically accepted. Otherwise, the file extension must match one of the extensions in the array provided, and the character preceding the extension must be a period. For this particular filter, the comparisons are case-insensitive.

Listing 9-15. *A Custom FileFilter for Use with a JFileChooser*

```
import javax.swing.filechooser.*;
import java.io.File; // avoid FileFilter name conflict

public class ExtensionFileFilter extends FileFilter {
    String description;
    String extensions[];

    public ExtensionFileFilter(String description, String extension) {
        this(description, new String[] { extension} );
    }
}
```

```

public ExtensionFileFilter(String description, String extensions[]) {
    if (description == null) {
// Since no description, use first extension and # of extensions as description
        this.description = extensions[0]+"{ "+extensions.length+"} ";
    } else {
        this.description = description;
    }
    // Convert array to lowercase
    // Don't alter original entries
    this.extensions = (String[])extensions.clone();
    toLower(this.extensions);
}
private void toLower(String array[]) {
    for (int i=0, n=array.length; i<n; i++) {
        array[i] = array[i].toLowerCase();
    }
}

public String getDescription() {
    return description;
}

// Ignore case, always accept directories
// Character before extension must be a period
public boolean accept(File file) {
    if (file.isDirectory()) {
        return true;
    } else {
        String path = file.getAbsolutePath().toLowerCase();
        for (int i=0, n=extensions.length; i<n; i++) {
            String extension = extensions[i];
            if ((path.endsWith(extension) &&
                (path.charAt(path.length()-extension.length()-1)) == '.')) {
                return true;
            }
        }
    }
    return false;
}
}

```

Using the file filter entails creating it and associating it with the `JFileChooser`. If you just want to make the filter selectable by the user, but not the default initial selection, call `public void addChoosableFileFilter(FileFilter filter)`. This will keep the default accept-all-files filter selected. If, instead, you want the filter to be set when the chooser first appears, call `public void setFileFilter(FileFilter filter)`, and the file chooser will filter the initial set of files shown.

For example, the following source will add two filters to a file chooser:

```
FileFilter jpegFilter =
    new ExtensionFileFilter(null, new String[]{ "JPG", "JPEG" } );
fileChooser.addChoosableFileFilter(jpegFilter);
FileFilter gifFilter = new ExtensionFileFilter("gif", new String[]{ "gif" } );
fileChooser.addChoosableFileFilter(gifFilter);
```

When no file filters have been associated with the `JFileChooser`, the filter from `JFileChooser.getAcceptAllFileFilter()` is used to provide a filter that accepts all files and that is also appropriate for the underlying operating system.

Figure 9-27 shows an open filter selection combo box in a Motif file chooser.




Figure 9-27. Using custom `FileFilter` with a `JFileChooser`

■ **Tip** Setting the `FileFilter` with `setFileFilter()` before adding filters with `addChoosableFileFilter()` causes the accept-all-file filter to be unavailable. To put it back, call `setAcceptAllFileFilterUsed(true)`. In addition, you can reset the filter list with a call to `resetChoosableFileFilters()`.

One built-in filter isn't a `FileFilter`. It concerns hidden files, such as those that begin with a period (.) on UNIX file systems. By default, hidden files aren't shown within the `JFileChooser`. To enable the display of hidden files, you must set the `fileHidingEnabled` property to `false`:

```
aFileChooser.setFileHidingEnabled(false);
```

■ **Tip** When creating `javax.swing.filechooser.FileFilter` subclasses, you may want to have the new class also implement the `java.io.FileFilter` interface. To do this, simply add `implements java.io.FileFilter` to the class definition. This works because the method signature for the `accept()` method in the `javax.swing.filechooser` class matches the interface definition: `public boolean accept(File file)`.

Choosing Directories Instead of Files

The `JFileChooser` supports three selection modes: files only, directories only, and files and directories. The `fileSelectionMode` property setting determines the mode of the chooser. The available settings are specified by the three `JFileChooser` constants: `FILES_ONLY`, `DIRECTORIES_ONLY`, and `FILES_AND_DIRECTORIES`. Initially, the file chooser is in `JFileChooser.FILES_ONLY` mode. To change the mode, just call `public void setFileSelectionMode(int newMode)`.

In addition to the `fileSelectionMode` property, you can use the read-only `fileSelectionEnabled` and `directorySelectionEnabled` properties to determine the type of input currently supported by the file chooser.

Adding Accessory Panels

The `JFileChooser` supports the addition of an accessory component. This component can enhance the functionality of the chooser, including previewing an image or document, or playing an audio file. To respond to file selection changes, the accessory component should attach itself as a `PropertyChangeListener` to the `JFileChooser`. When the `JFileChooser.SELECTED_FILE_CHANGED_PROPERTY` property changes, the accessory then changes to reflect the file selection. Figure 9-28 shows how an image previewer accessory component might appear. Configuring the accessory for a chooser is just like setting any other property.

```
fileChooser.setAccessory(new LabelAccessory(fileChooser));
```




Figure 9-28. A *JFileChooser* with an accessory panel

Listing 9-16 shows source for an *Image* component that displays an accessory icon. The selected image file becomes the icon for a *JLabel* component. The component does two scaling operations to make sure the dimensions of the image are sized to fit within the accessory.

Listing 9-16. Custom Accessory for Use with *JFileChooser*

```
import javax.swing.*;
import java.beans.*;
import java.awt.*;
import java.io.*;

public class LabelAccessory extends JLabel implements PropertyChangeListener {
    private static final int PREFERRED_WIDTH = 125;
    private static final int PREFERRED_HEIGHT = 100;

    public LabelAccessory(JFileChooser chooser) {
        setVerticalAlignment(JLabel.CENTER);
        setHorizontalAlignment(JLabel.CENTER);
        chooser.addPropertyChangeListener(this);
        setPreferredSize(new Dimension(PREFERRED_WIDTH, PREFERRED_HEIGHT));
    }

    public void propertyChange(PropertyChangeEvent changeEvent) {
        String changeName = changeEvent.getPropertyName();
        if (changeName.equals(JFileChooser.SELECTED_FILE_CHANGED_PROPERTY)) {
            File file = (File)changeEvent.getNewValue();
            if (file != null) {
                ImageIcon icon = new ImageIcon(file.getPath());
                if (icon.getIconWidth() > PREFERRED_WIDTH) {
                    icon = new ImageIcon(icon.getImage().getScaledInstance(
                        PREFERRED_WIDTH, -1, Image.SCALE_DEFAULT));
                }
            }
        }
    }
}
```

```

        if (icon.getIconHeight() > PREFERRED_HEIGHT) {
            icon = new ImageIcon(icon.getImage().getScaledInstance(
                -1, PREFERRED_HEIGHT, Image.SCALE_DEFAULT));
        }
    }
    setIcon(icon);
}
}
}
}
}

```

Using the FileSystemView Class

The `FileSystemView` class localizes access to platform-specific file system information. Where the JDK 1.1 version of `java.io.File` was fairly crippled in this respect, `FileSystemView` fills in to make it easier to design `FileChooserUI` objects. The Swing `FileSystemView` class provides three custom views as package-private subclasses of `FileSystemView`. They include support for UNIX and Windows, plus a generic handler.

Although it isn't necessary to define your own `FileSystemView`, the class provides some features that can be useful outside the context of a `JFileChooser`. To get the view specific to the user's runtime environment, call public static `FileSystemView getFileSystemView()`. The class definition follows.

```

public abstract class FileSystemView {
    // Constructors
    public FileSystemView(); // Properties
    // Properties
    public File getDefaultDirectory();
    public File getHomeDirectory();
    public File[] getRoots();
    // Class Methods
    public static FileSystemView getFileSystemView();
    // Other Methods
    public File createFileObject(File directory, String filename);
    public File createFileObject(String path);
    protected File createFileSystemRoot(File file);
    public abstract File createNewFolder(File containingDir) throws IOException;
    public File getChild(File parent, String filename);
    public File[] getFiles(File directory, boolean useFileHiding);
    public File getParentDirectory(File file);
    public String getSystemDisplayName(File file);
    public Icon getSystemIcon(File file);
    public String getSystemTypeDescription(File file);
    public boolean isComputerNode(File file);
    public boolean isDrive(File file);
    public boolean isFileSystem(File file);
    public boolean isFileSystemRoot(File file);
    public boolean isFloppyDrive(File file);
}

```

```

    public boolean isHiddenFile(File file);
    public boolean isParent(File folder, File file);
    public boolean isRoot(File file);
    public Boolean isTraversable(File file);
}

```

Note Notice that the `isTraversable()` method returns a `Boolean`, not a `boolean`. (I haven't a clue why the difference—perhaps somewhere an object is needed, and the primitive `boolean` wasn't sufficient.)

FileView Class

The final part of the `JFileChooser` class to examine is the `FileView` area where all the file names are listed. Each of the custom look and feel types has its own `FileView` area class. In addition, some of the predefined look and feel types, such as `Motif`, aren't changeable. Nevertheless, at least in the `Metal` and `Windows` file choosers, you can customize the icons for different file types or change the display name for a file.

The five methods of the `FileView` class allow you to change the name, icon, or description (two forms) of each `File` in the view. In addition, the `FileView` actually controls whether a directory is traversable, allowing you to program in a weak level of access control. Nontraversable directories have a different default icon, because those directories cannot be browsed for file selection.

Here's the definition of the abstract `FileView` class:

```

public abstract class FileView {
    public FileView();
    public String getDescription(File file);
    public Icon getIcon(File file);
    public String getName(File file);
    public String getTypeDescription(File file);
    public Boolean isTraversable(File file);
}

```

Note Like `FileSystemView`, the `isTraversable()` method returns a `Boolean` value, not a `boolean` one.

Customizing the `FileView` requires creating a subclass and overriding the appropriate methods. By default, all the methods return `null`, indicating that you don't want to define custom behavior for a specific method.

Once you've defined the file view, simply change the `fileView` property of your `JFileChooser`:

```
fileChooser.setFileView(new JavaFileView());
```

Figure 9-29 shows the changed appearance of a `Metal` `JFileChooser` after installing a custom `FileView`.




Figure 9-29. *Changing the FileView*

The `JavaFileView` class in Listing 9-17 provides a `FileView` implementation that customizes the appearance of files related to Java development—specifically, `.java`, `.class`, `.jar`, and `.html` or `.htm` files. (This is certainly not meant to be a comprehensive list of Java file types.) For each of these file types, a special icon instead of the default icon is displayed next to the name. In addition, for Java source files, the length of the file is displayed. (Imagine if every file attribute were being displayed!) Unfortunately, you can't modify the font or color from a `FileView`.

Listing 9-17. *Custom FileView for Some Java-Related File Types*

```
import java.io.File;
import java.awt.*;
import javax.swing.*;
import javax.swing.filechooser.*;

public class JavaFileView extends FileView {
    Icon javaIcon = new DiamondIcon(Color.BLUE);
    Icon classIcon = new DiamondIcon(Color.GREEN);
    Icon htmlIcon = new DiamondIcon(Color.RED);
    Icon jarIcon = new DiamondIcon(Color.PINK);

    public String getName(File file) {
        String filename = file.getName();
        if (filename.endsWith(".java")) {
            String name = filename + " : " + file.length();
            return name;
        }
        return null;
    }
}
```

```

public String getTypeDescription(File file) {
    String typeDescription = null;
    String filename = file.getName().toLowerCase();


    if (filename.endsWith(".java")) {
        typeDescription = "Java Source";
    } else if (filename.endsWith(".class")){
        typeDescription = "Java Class File";
    } else if (filename.endsWith(".jar")){
        typeDescription = "Java Archive";
    } else if (filename.endsWith(".html") || filename.endsWith(".htm")) {
        typeDescription = "Applet Loader";
    }
    return typeDescription;
}

public Icon getIcon(File file) {
    if (file.isDirectory()) {
        return null;
    }
    Icon icon = null;
    String filename = file.getName().toLowerCase();
    if (filename.endsWith(".java")) {
        icon = javaIcon;
    } else if (filename.endsWith(".class")){
        icon = classIcon;
    } else if (filename.endsWith(".jar")){
        icon = jarIcon;
    } else if (filename.endsWith(".html") || filename.endsWith(".htm")) {
        icon = htmlIcon;
    }
    return icon;
}
}


```

Customizing a JFileChooser Look and Feel

Each installable Swing look and feel provides a different JFileChooser appearance and set of default UIResource values. Figure 9-30 shows the appearance of the JFileChooser for the preinstalled set of look and feel types: Motif, Windows, and Ocean.



Motif



Windows



Ocean

Figure 9-30. *JFileChooser* under different look and feel types

The available set of UIResource-related properties for a `JFileChooser` is shown in Table 9-11. For the `JFileChooser` component, there are 83 different properties. Nearly all the properties relate to the button labels, mnemonics, icons, and tooltip text.

Table 9-11. *JFileChooser UIResource Elements*

Property String	Object Type
<code>FileChooser.acceptAllFileFilterText</code>	String
<code>FileChooser.ancestorInputMap</code>	InputMap
<code>FileChooser.cancelButtonMnemonic</code>	Integer
<code>FileChooser.cancelButtonText</code>	String
<code>FileChooser.cancelButtonToolTipText</code>	String
<code>FileChooser.deleteFileButtonMnemonic</code>	Integer
<code>FileChooser.deleteFileButtonText</code>	String
<code>FileChooser.deleteFileButtonToolTipText</code>	String
<code>FileChooser.detailsViewButtonAccessibleName</code>	String
<code>FileChooser.detailsViewButtonToolTipText</code>	String
<code>FileChooser.detailsViewIcon</code>	Icon
<code>FileChooser.directoryDescriptionText</code>	String
<code>FileChooser.directoryOpenButtonMnemonic</code>	Integer
<code>FileChooser.directoryOpenButtonText</code>	String
<code>FileChooser.directoryOpenButtonToolTipText</code>	String
<code>FileChooser.enterFilenameLabelMnemonic</code>	String
<code>FileChooser.enterFilenameLabelText</code>	String
<code>FileChooser.fileDescriptionText</code>	String
<code>FileChooser.fileNameLabelMnemonic</code>	Integer
<code>FileChooser.fileNameLabelText</code>	String
<code>FileChooser.filesLabelMnemonic</code>	Integer
<code>FileChooser.filesLabelText</code>	String
<code>FileChooser.filesOfTypeLabelMnemonic</code>	Integer
<code>FileChooser.filesOfTypeLabelText</code>	String
<code>FileChooser.filterLabelMnemonic</code>	Integer
<code>FileChooser.filterLabelText</code>	String
<code>FileChooser.foldersLabelMnemonic</code>	Integer
<code>FileChooser.foldersLabelText</code>	String
<code>FileChooser.helpButtonMnemonic</code>	Integer

Table 9-11. *JFileChooser UIResource Elements (Continued)*

Property String	Object Type
<code>FileChooser.helpButtonText</code>	String
<code>FileChooser.helpButtonToolTipText</code>	String
<code>FileChooser.homeFolderAccessibleName</code>	String
<code>FileChooser.homeFolderIcon</code>	Icon
<code>FileChooser.homeFolderToolTipText</code>	String
<code>FileChooser.listFont</code>	Font
<code>FileChooser.listViewBackground</code>	Color
<code>FileChooser.listViewBorder</code>	Border
<code>FileChooser.listViewButtonAccessibleName</code>	String
<code>FileChooser.listViewButtonToolTipText</code>	String
<code>FileChooser.listViewIcon</code>	Icon
<code>FileChooser.listViewWindowsStyle</code>	Boolean
<code>FileChooser.lookInLabelMnemonic</code>	Integer
<code>FileChooser.lookInLabelText</code>	String
<code>FileChooser.newFolderAccessibleName</code>	String
<code>FileChooser.newFolderButtonMnemonic</code>	Integer
<code>FileChooser.newFolderButtonText</code>	String
<code>FileChooser.newFolderButtonToolTipText</code>	String
<code>FileChooser.newFolderDialogText</code>	String
<code>FileChooser.newFolderErrorSeparator</code>	String
<code>FileChooser.newFolderErrorText</code>	String
<code>FileChooser.newFolderIcon</code>	Icon
<code>FileChooser.newFolderToolTipText</code>	String
<code>FileChooser.openButtonMnemonic</code>	Integer
<code>FileChooser.openButtonText</code>	String
<code>FileChooser.openButtonToolTipText</code>	String
<code>FileChooser.openDialogTitleText</code>	String
<code>FileChooser.other.newFolder</code>	String
<code>FileChooser.other.newFolder.subsequent</code>	String
<code>FileChooser.win32.newFolder</code>	String
<code>FileChooser.win32.newFolder.subsequent</code>	String
<code>FileChooser.pathLabelMnemonic</code>	Integer
<code>FileChooser.pathLabelText</code>	String

Table 9-11. *JFileChooser UIResource Elements (Continued)*

Property String	Object Type
<code>FileChooser.readOnly</code>	Boolean
<code>FileChooser.renameFileButtonMnemonic</code>	Integer
<code>FileChooser.renameFileButtonText</code>	String
<code>FileChooser.renameFileButtonToolTipText</code>	String
<code>FileChooser.renameFileDialogText</code>	String
<code>FileChooser.renameFileErrorText</code>	String
<code>FileChooser.renameFileErrorTitle</code>	String
<code>FileChooser.saveButtonMnemonic</code>	Integer
<code>FileChooser.saveButtonText</code>	String
<code>FileChooser.saveButtonToolTipText</code>	String
<code>FileChooser.saveDialogTitleText</code>	String
<code>FileChooser.saveInLabelText</code>	String
<code>FileChooser.updateButtonMnemonic</code>	Integer
<code>FileChooser.updateButtonText</code>	String
<code>FileChooser.updateButtonToolTipText</code>	String
<code>FileChooser.upFolderAccessibleName</code>	String
<code>FileChooser.upFolderIcon</code>	Icon
<code>FileChooser.upFolderToolTipText</code>	String
<code>FileChooser.usesSingleFilePane</code>	Boolean
<code>FileChooser.useSystemExtensionHiding</code>	Boolean
<code>FileChooserUI</code>	String

In addition to the more than 80 resources for `JFileChooser`, there are 5 additional ones as part of the `FileView`, which are shown in Table 9-12.

Table 9-12. *FileView UIResource Elements*

Property String	Object Type
<code>FileView.computerIcon</code>	Icon
<code>FileView.directoryIcon</code>	Icon
<code>FileView.fileIcon</code>	Icon
<code>FileView.floppyDriveIcon</code>	Icon
<code>FileView.hardDriveIcon</code>	Icon

Summary

In this chapter, you explored the intricacies of Swing's pop-up and chooser classes. Instead of manually creating a `JDialog` and filling it with the necessary pieces, the Swing component set includes support for many different pop-up and chooser classes. Starting with the `JOptionPane`, you learned how to create informational, question, and input pop-ups. In addition, you explored how to monitor the progress of time-consuming tasks by using the `ProgressMonitor` and `ProgressMonitorInputStream` classes.

After looking at the more general pop-up classes, you explored the specifics of Swing's color and file chooser classes: `JColorChooser` and `JFileChooser`. From each of these two classes, you can prompt the user for the requested input and customize the display in more ways than you can imagine.

Now that you have a feel for the predefined pop-ups, it is time to move on to the `LayoutManager` classes in Chapter 10. With the help of the system layout managers, you can create even better user interfaces.



Layout Managers

In Chapter 9, you learned about the various pop-up and chooser classes available from the Swing component set. In this chapter, you'll learn about the AWT and Swing layout managers.

While this book focuses on the Swing component set, you can't use them in a vacuum. You need to understand both the AWT and Swing layout managers. In fact, you're more apt to use four of the five AWT layout managers than three of the five Swing layout managers. The AWT layout managers are `FlowLayout`, `BorderLayout`, `GridLayout`, `CardLayout`, and `GridBagLayout`. The Swing layouts are `BoxLayout`, `OverlayLayout`, `ScrollPaneLayout`, `ViewportLayout`, and `SpringLayout`. Another manager is `JRootPane.RootLayout`, which was described in Chapter 8.

In addition to the layout managers, you'll look at several helper classes: `GridBagLayout`'s constraint class `GridBagConstraints`, the `SizeRequirements` class used by both the `BoxLayout` and `OverlayLayout` managers, and the `SpringLayout` manager's associated `Spring` and `SpringLayout.Constraints` classes.

Layout Manager Responsibilities

Every container, such as a `JPanel` or `Container`, has a layout manager. That layout manager is responsible for positioning components, regardless of the platform or screen size.

Layout managers eliminate the need to compute component placement on your own, which would be a losing proposition, since the size required for any component depends on the platform on which your program is deployed and the current look and feel. Even for a simple layout, the code required to discover component sizes and compute absolute positions could be hundreds of lines, particularly if you concern yourself with what happens when the user resizes a window. A layout manager takes care of this for you. It asks each component in the container how much space it requires, and then arranges the components on the screen as best it can, based on the component sizes on the platform in use, the available space, and the rules of the layout manager.

To find out how much space a component needs, the layout manager calls the component's `getMinimumSize()`, `getPreferredSize()`, and `getMaximumSize()` methods. These methods report the minimum, preferred, and maximum space that a component requires to be displayed correctly. Thus, each component must know its space requirements. The layout manager then uses the component's space requirements to resize components and arrange them on the screen. Your Java program never needs to worry about platform-dependent positioning, beyond layout manager setup.

Note that a layout manager is free to ignore some of its components; there is no requirement that a layout manager display everything. For example, a `Container` using a `BorderLayout` might include 30 or 40 components; however, the `BorderLayout` will display at most 5 of them (the last component placed in each of its five named areas). Likewise, a `CardLayout` may manage many components but displays exactly one at a time.

Besides ignoring components, a layout manager can do anything it wants with the components' minimum, preferred, and maximum size. It is free to ignore any or all of these. It makes sense that a layout manager can ignore a *preferred* size—after all, preferred means, “Give me this size if it’s available.” However, a layout manager can also ignore a minimum size. At times, there is no reasonable alternative because the container may not have enough room to display a component at its minimum size. How to handle this situation is left to the layout manager designer’s discretion.

LayoutManager Interface

The `LayoutManager` interface defines the responsibilities of the manager that lays out the `Component` objects within a `Container`. As explained in the previous section, it is the duty of the layout manager to determine the position and size of each component within the `Container`. You will never call the methods of the `LayoutManager` interface directly; for the most part, layout managers do their work behind the scenes. Once you have created a `LayoutManager` object and told the container to use it (by calling `setLayout(manager)`), you’re finished with it. The system calls the appropriate methods of the layout manager when necessary. Like any interface, `LayoutManager` specifies the methods a layout manager must implement but says nothing about how the `LayoutManager` does its job.

The `LayoutManager` interface itself is most important if you are writing a new layout manager. I’ll describe this interface first because it’s the foundation on which all layout managers are based. I’ll also describe the `LayoutManager2` interface, which is used by some layout managers.

Exploring the LayoutManager Interface

Five methods make up the `LayoutManager` interface:

```
public interface LayoutManager {  
    public void addLayoutComponent(String name, Component comp);  
    public void layoutContainer(Container parent);  
    public Dimension minimumLayoutSize(Container parent);  
    public Dimension preferredLayoutSize(Container parent);  
    public void removeLayoutComponent(Component comp);  
}
```

If you create your own class that implements `LayoutManager`, you must define all five. As you will see, many of the methods do not need to do anything, but you must still include a stub with the appropriate signature.

The `addLayoutComponent()` method is called only when you add components by calling the `add(String, Component)` or `add(Component, Object)` method, not just plain `add(Component)`. For `add(Component, Object)`, the `Object` must be of type `String`, or else that isn't called either.

Exploring the `LayoutManager2` Interface

For layout managers that require each component to carry its layout manager constraints, the `LayoutManager2` interface comes into play. The layout managers that use `LayoutManager2` include `BorderLayout`, `CardLayout`, and `GridBagLayout`, to name a few.

`LayoutManager2` has five additional methods:

```
public interface LayoutManager2 {  
    public void addLayoutComponent(Component comp, Object constraints);  
    public float getLayoutAlignmentX(Container target);  
    public float getLayoutAlignmentY(Container target);  
    public void invalidateLayout(Container target);  
    public Dimension maximumLayoutSize(Container target);  
}
```

The `addLayoutComponent()` method is called when you assign constraints to the component when adding it to the layout. In practice, this means that you added the component to the container by calling the `add(Component component, Object constraints)` or `add(String name, Component component)` methods, rather than the `add(Component component)` method. It is up to the layout manager to decide what, if anything, to do with the constraints. For example, `GridBagLayout` uses constraints to associate a `GridBagConstraints` object to the component added, and `BorderLayout` uses constraints to associate a location (like `BorderLayout.CENTER`) with the component.

FlowLayout Class

`FlowLayout` is the default layout manager for a `JPanel`. A `FlowLayout` adds components to the container in rows, working in the order defined by the `getComponentOrientation()` method of `Component`, typically left to right in the United States and western Europe. When it can't fit more components in a row, it starts a new row, similar to a word processor with word wrap enabled. When the container is resized, the components within it are repositioned based on the container's new size. Components within a `FlowLayout`-managed container are given their preferred size. If there is insufficient space, you do not see all the components, as illustrated in Figure 10-1.




Figure 10-1. The default `FlowLayout` setup, with seven buttons and three different screen sizes. As the third example shows, if the screen is too small, the components will not be shrunk to fit all the components.

There are three constructors for creating the `FlowLayout` layout manager:

```
public FlowLayout()
public FlowLayout(int alignment)
public FlowLayout(int alignment, int hgap, int vgap)
```

If an alignment is not specified, components within a `FlowLayout`-managed container are centered. Otherwise, the setting is controlled by one of the following constants:

- `CENTER`
- `LEADING`
- `LEFT`
- `RIGHT`
- `TRAILING`

For the typical left-to-right orientation, `LEADING` and `LEFT` are the same, as are `TRAILING` and `RIGHT`. For a language like Hebrew, these would be reversed. Figure 10-2 shows the effect of several different alignments.




Figure 10-2. *FlowLayout with three different alignments*

You can specify the gaps, in pixels, for the spacing between components, both horizontal (hgap) and vertical (vgap). Gaps default to five pixels unless specified. It is possible to specify negative gaps if you want components to be placed on top of one another.

BorderLayout Class

BorderLayout is the default layout manager for the content pane of a JFrame, JWindow, JDialog, JInternalFrame, and JApplet. It provides for a more flexible way of positioning components along the edges of the window. Figure 10-3 shows a typical BorderLayout.




Figure 10-3. *Sample BorderLayout*

When using `BorderLayout`, you add components with constraints to identify in which of the five locations to place the component. If you don't specify a constraint, the component is added to the center area. Adding multiple components to the same area shows only the last component, although technically speaking, the other components are still within the container; they are just not shown.

There are two constructors for creating the `BorderLayout` layout manager:

```
public BorderLayout()  
public BorderLayout(int hgap, int vgap)
```

Unlike `FlowLayout`, the default gaps for a `BorderLayout` are zero pixels, meaning the components are positioned right next to one another.

The constraints to use when adding a component to a `BorderLayout`-managed container are constants of the `BorderLayout` class:

- `AFTER_LAST_LINE`
- `AFTER_LINE_ENDS`
- `BEFORE_FIRST_LINE`
- `BEFORE_LINE_BEGINS`
- `CENTER`
- `EAST`
- `LINE_END`
- `LINE_START`
- `NORTH`
- `PAGE_END`
- `PAGE_START`
- `SOUTH`
- `WEST`

With only five regions to add a component to, you would expect only five constants. As with `FlowLayout`, the additional constants deal with proper positioning when the component orientation is reversed, either horizontally or vertically. For the typical left-to-right, top-to-bottom orientation, the common set of values is as follows:

- `AFTER_LAST_LINE`, `PAGE_END`, `SOUTH`
- `AFTER_LINE_ENDS`, `LINE_END`, `EAST`
- `BEFORE_FIRST_LINE`, `PAGE_START`, `NORTH`
- `BEFORE_LINE_BEGINS`, `LINE_START`, `WEST`
- `CENTER`

■ **Tip** Using the BEFORE and AFTER constants, as opposed to the NORTH, SOUTH, EAST, and WEST constants, is recommended, though all are supported.

You do not need specify all five areas of the container. The component in the north region takes up the entire width of the container along its top. South does the same along the bottom. The heights of north and south will be the preferred heights of the component added. The east and west areas are given the widths of the component each contains, where the height is whatever is left in the container after satisfying north's and south's height requirements. Any remaining space is given to the component in the center region.

The way to place multiple components into one of the regions of a BorderLayout-managed container is to add them to a different container first, and then add them to the BorderLayout-managed container. For instance, if you want a label and text field in the north area of a BorderLayout-managed container, place them in the west and center areas of another BorderLayout-managed container first, as shown here:

```
JPanel outerPanel = new JPanel(new BorderLayout());
JPanel topPanel = new JPanel(new BorderLayout());
JLabel label = new JLabel("Name:");
JTextField text = new JTextField();
topPanel.add(label, BorderLayout.BEFORE_LINE_BEGINS);
topPanel.add(text, BorderLayout.CENTER);
outerPanel.add(topPanel, BorderLayout.BEFORE_FIRST_LINE);
```

GridLayout Class

The GridLayout manager is ideal for laying out objects in rows and columns, where each cell in the layout has the same size. Components are added to the layout from left to right, top to bottom. A call to `setLayout(new GridLayout(3, 4))` changes the layout manager of the current container to a GridLayout with three rows and four columns, as shown in Figure 10-4.



Figure 10-4. Sample GridLayout

There are three constructors for creating the `GridLayout` layout manager:

```
public GridLayout()  
public GridLayout(int rows, int columns)  
public GridLayout(int rows, int columns, int hgap, int vgap)
```

Typically, you would explicitly specify the overall grid size for your `GridLayout`-managed container. However, you can set the number of rows or columns to be zero, and the layout will grow without bounds in the direction with a zero setting.

Caution If both rows and columns are specified to be zero to the `GridLayout` constructor, a runtime exception of `IllegalArgumentException` will be thrown.

The actual number of rows and columns drawn is based on the number of components within the container. The `GridLayout` tries to observe the number of rows requested first. If the requested number of rows is nonzero, the number of columns is determined by $(\# \text{ of components} + \text{rows} - 1) / \text{rows}$. If your request is for zero rows, the number of rows to use is determined by a similar formula: $(\# \text{ of components} + \text{columns} - 1) / \text{columns}$. Table 10-1 demonstrates this calculation. The last entry in the table is of special interest: if you request a 3×3 grid but place only four components in the layout, you actually get a 2×2 layout as a result. If you do not want to be surprised, size the `GridLayout` based on the actual number of objects you plan to add to the display.

Table 10-1. *GridLayout Row/Column Calculation*

Rows	Columns	# Components	Display Rows	Display Columns
0	1	10	10	1
0	2	10	5	2
1	0	10	1	10
2	0	10	2	5
2	3	10	2	5
2	3	20	2	10
3	2	10	3	4
3	3	3	3	1
3	3	4	2	2

GridBagLayout Class

`GridBagLayout` is the most complex and most flexible of the layout managers. Although it sounds like it should be a subclass of `GridLayout`, it's a different beast altogether. With `GridLayout`, elements are arranged in a rectangular grid, and each element in the container is sized identically

(where possible). With `GridBagLayout`, elements can have different sizes and can occupy multiple rows or columns.

There is only the no-argument constructor for `GridBagLayout`:

```
public GridBagLayout()
```

The position and behavior of each element is specified by an instance of the `GridBagConstraints` class. By properly constraining the elements, you can specify the number of rows and columns a component occupies, which component grows when additional screen real estate is available, and various other restrictions. The actual grid size is based on the number of components within the `GridBagLayout` and the `GridBagConstraints` of those objects. For example, Figure 10-5 shows a `GridBagLayout` with seven components, arranged in a 3×3 grid.



Figure 10-5. *GridBagLayout with seven components in a 3×3 grid*

Note The maximum capacity of a screen using `GridBagLayout` is 512 rows by 512 columns. This is specified by the protected `MAXGRIDSIZE` constant of the layout manager.

The code used to create Figure 10-5 is shown in Listing 10-1.

Listing 10-1. *Seven-Button GridBagLayout*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import java.text.*;

public class GridBagButtons {
    private static final Insets insets = new Insets(0,0,0,0);
    public static void main(final String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                final JFrame frame = new JFrame("GridBagLayout");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                frame.setLayout(new GridBagLayout());
                JButton button;
```

```

        // Row One - Three Buttons
        button = new JButton("One");
        addComponent(frame, button, 0, 0, 1, 1,
            GridBagConstraints.CENTER, GridBagConstraints.BOTH);
        button = new JButton("Two");
        addComponent(frame, button, 1, 0, 1, 1,
            GridBagConstraints.CENTER, GridBagConstraints.BOTH);
        button = new JButton("Three");
        addComponent(frame, button, 2, 0, 1, 1,
            GridBagConstraints.CENTER, GridBagConstraints.BOTH);
        // Row Two - Two Buttons
        button = new JButton("Four");
        addComponent(frame, button, 0, 1, 2, 1,
            GridBagConstraints.CENTER, GridBagConstraints.BOTH);
        button = new JButton("Five");
        addComponent(frame, button, 2, 1, 1, 2,
            GridBagConstraints.CENTER, GridBagConstraints.BOTH);
        // Row Three - Two Buttons
        button = new JButton("Six");
        addComponent(frame, button, 0, 2, 1, 1,
            GridBagConstraints.CENTER, GridBagConstraints.BOTH);
        button = new JButton("Seven");
        addComponent(frame, button, 1, 2, 1, 1,
            GridBagConstraints.CENTER, GridBagConstraints.BOTH);
        frame.setSize(500, 200);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}

private static void addComponent(Container container, Component component,
    int gridx, int gridy, int gridwidth, int gridheight, int anchor,
    int fill) {
    GridBagConstraints gbc = new GridBagConstraints(gridx, gridy,
        gridwidth, gridheight, 1.0, 1.0, anchor, fill, insets, 0, 0);
    container.add(component, gbc);
}
}

```

Most of the work in Listing 10-1 is done by the helper method `addComponent()`, which creates a set of constraints for the component to be added to the container.

GridBagLayout Rows and Columns

To help you visualize the grid of components in the `GridBagLayout`, Figure 10-6 indicates how the layout manager counts cells. The top-left cell in the layout has location (0, 0). There's nothing surprising about buttons one, two, three, six, and seven. Each of those occupies a 1×1 area of the layout's 3×3 grid. Button four occupies a 2×1 area; it is placed at location (0, 1), and thus occupies this cell plus the cell at (1, 1). Likewise, button five occupies a 1×2 area and takes up the cells at (2, 1) and (2, 2). The total size of the layout is determined entirely by the components that are placed in it and their constraints.




Figure 10-6. How `GridBagLayout` counts rows and columns

GridBagConstraints Class

The magic of the layout manager is strictly controlled by the different `GridBagConstraints` objects passed in for each component added to the container. Each specifies how to display a specific component. Unlike most other layout managers, which have a built-in idea about what to do with their display, the `GridBagLayout` is a blank slate. The constraints attached to the components tell the layout manager how to build its display.

Every component added to a `GridBagLayout` container should have a `GridBagConstraints` object associated with it. When an object is first added to the layout, it is given a default set of constraints (see Table 10-2). Calling `container.add(Component, GridBagConstraints)` or `gridBagLayout.setConstraints(GridBagConstraints)` applies the new set of constraints to the component.

`GridBagConstraints` has two constructors:

```
public GridBagConstraints()
public GridBagConstraints(int gridx, int gridy, int gridwidth, int gridheight,
    double weightx, double weighty, int anchor, int fill, Insets insets, int ipadx,
    int ipady)
```

Using the no-argument constructor for `GridBagConstraints` starts with all the defaults in Table 10-2. You can leave the individual settings alone and just set the individual fields. All are public, without getter methods. While you can just blindly pass in all the constraints to the `GridBagConstraints` constructor, it is better to describe the different fields separately.

Table 10-2. *GridBagConstraints Defaults*

Variable	Value	Description
anchor	CENTER	If the component is smaller than the space available, it will be centered within its region.
fill	NONE	The component should not resize itself if extra space is available within its region.
gridx	RELATIVE	The component associated with this constraint will be positioned relative to the last item added. If all components have <code>gridx</code> and <code>gridy</code> <code>RELATIVE</code> , they will be placed in a single row.
gridy	RELATIVE	The component associated with this constraint will be positioned relative to the last item added.
gridwidth	1	The component will occupy a single cell wide within the layout.
gridheight	1	The component will occupy a single cell high within the layout.
insets	0x0x0x0	No extra space is added around the edges of the component.
ipadx	0	There is no internal horizontal padding for the component.
ipady	0	There is no internal vertical padding for the component.
weightx	0	The component will not get any extra horizontal space, if available.
weighty	0	The component will not get any extra vertical space, if available.


Component Anchoring

The `anchor` variable specifies the direction in which the component will drift in the event it is smaller than the space available for it. `CENTER` is the default. The absolute values are `NORTH`, `SOUTH`, `EAST`, `WEST`, `NORTHEAST`, `NORTHWEST`, `SOUTHEAST`, and `SOUTHWEST`. The relative values are `PAGE_START`, `PAGE_END`, `LINE_START`, `LINE_END`, `FIRST_LINE_START`, `FIRST_LINE_END`, `LAST_LINE_START`, and `LAST_LINE_END`.

Component Resizing

The value of `fill` controls the component's resize policy. If `fill` is `NONE` (the default), the layout manager tries to give the component its preferred size. If `fill` is `VERTICAL`, it resizes in height if additional space is available. If `fill` is `HORIZONTAL`, it resizes in width. If `fill` is `BOTH`, the layout

manager takes advantage of all available space in both directions. Figure 10-7 demonstrates VERTICAL, HORIZONTAL, and NONE values (generated by changing the `GridBagConstraints.BOTH` settings in Listing 10-1).



Vertical



Horizontal



None

Figure 10-7. *GridBagLayout with different fill values*

Grid Positioning

The `gridx` and `gridy` variables specify the grid position where this component would be placed. (0, 0) specifies the cell at the origin of the screen. The `gridwidth` and `gridheight` variables specify the number of rows (`gridwidth`) and columns (`gridheight`) a particular component occupies. Table 10-3 shows the `gridx`, `gridy`, `gridwidth`, and `gridheight` values for the example shown earlier in Figure 10-5.

Table 10-3. *The gridx, gridy, gridwidth, and gridheight Values for Figure 10-5*

Component	gridx	gridy	gridwidth	gridheight
One	0	0	1	1
Two	1	0	1	1
Three	2	0	1	1
Four	0	1	2	1
Five	2	1	0	2
Six	0	2	1	1
Seven	1	2	1	3

It isn't necessary to set `gridx` and `gridy` to a specific location. If you set these fields to `RELATIVE` (the default), the system calculates the location for you. According to the Javadoc comments, if `gridx` is `RELATIVE`, the component appears to the right of the last component added to the layout. If `gridy` is `RELATIVE`, the component appears below the last component added to the layout. However, this is misleadingly simple. `RELATIVE` placement works best if you are adding components along a row or column. In this case, there are four possibilities for placement:

- With `gridx` and `gridy` `RELATIVE`, components are placed in one row.
- With `gridx` `RELATIVE` and `gridy` constant, components are placed in one row, each to the right of the previous component.
- With `gridx` constant and `gridy` `RELATIVE`, components are placed in one column, each below the previous component.
- Varying `gridx` or `gridy` while setting the other field `RELATIVE` appears to start a new row, placing the component as the first element of the new row.

If `gridwidth` or `gridheight` is set to `REMAINDER`, the component will be the last element of the row or column occupying any space that's remaining. For the components in the rightmost column of Table 10-3, for example, the `gridwidth` values could have been `REMAINDER`. Similarly, `gridheight` could be set to `REMAINDER` for the components in the bottom row.

`gridwidth` and `gridheight` may also have the value `RELATIVE`, which forces the component to be the next-to-last component in the row or column. Looking back to Figure 10-5, if button six had a `gridwidth` of `RELATIVE`, button seven wouldn't appear because button five is the last item in the row, and six is already next to last. If button five had a `gridheight` of `RELATIVE`, the layout manager would reserve space below it so the button could be the next-to-last item in the column.

Padding

The `insets` value specifies the external padding in pixels around the component (the space between the component and the edge of the cell or cells allotted to it). An `Insets` object can specify different padding for the top, bottom, left, or right side of the component.

`ipadx` and `ipady` specify the internal padding within the component. `ipadx` specifies the extra space to the right and left of the component (so the minimum width increases by $2 \times \text{ipadx}$ pixels). `ipady` specifies the extra space above and below the component (so the minimum height increases by $2 \times \text{ipady}$ pixels). The difference between insets (external padding) and `ipadx`/`ipady` (internal padding) can be confusing. The insets don't add space to the component itself; they are external to the component. `ipadx` and `ipady` change the component's minimum size, so they do add space to the component itself.

Weight

`weightx` and `weighty` describe how to distribute any additional space within the container. They allow you to control how components grow (or shrink) when the user resizes the container, or the container is just bigger to start.

If `weightx` is 0.0, the component won't get any additional space available in its row. If one or more components in a row have a positive `weightx`, any extra space is distributed proportionally between them. For example, if one component has a `weightx` value of 1.0 and the others are all 0.0, the one component will get all the additional space. If four components in a row each has a `weightx` value of 1.0, and the other components have `weightx` values of 0.0, the four components each get one quarter of the additional space. `weighty` behaves similarly to `weightx`, but in the other direction. Because `weightx` and `weighty` control the distribution of extra space in any row or column, setting either for one component may affect the position of the other components.

CardLayout Class

The `CardLayout` layout manager is significantly different from the other layout managers. Whereas the other layout managers attempt to display all the components within the container at once, a `CardLayout` displays only one component at a time. That component can be a component or container, where the latter lets you see multiple components laid out based on the layout manager of the embedded container.

Now that the `JTabbedPane` component (described in the next chapter) is available, `CardLayout` is rarely used.

BoxLayout Class

Swing's `BoxLayout` manager allows you to position components in either a horizontal row or a vertical column within your own container. In addition to using `BoxLayout` within your own container, the `Box` class (described in the next chapter) offers a container that uses `BoxLayout` as its default layout manager.

The benefit of using `BoxLayout` over something like `FlowLayout` or `GridLayout` is that `BoxLayout` works to honor each component's `x` and `y` alignment properties as well as its maximum size. And `BoxLayout` is much easier to use than `GridBagLayout`. Figure 10-8 demonstrates `BoxLayout` in action. Previously, you would have needed to figure out the necessary layout constraints to get `GridBagLayout` to behave like this.




Figure 10-8. *BoxLayout example, before and after resizing*

Creating a BoxLayout

BoxLayout has a single constructor:

```
public BoxLayout(Container target, int axis)
```

The constructor takes two arguments. The first argument is the container with which this instance of the layout manager is to be associated, and the second is the layout direction. Valid directions are `BoxLayout.X_AXIS` for a left-to-right layout and `BoxLayout.Y_AXIS` for a top-to-bottom layout.

Caution Trying to set the axis to something other than the equivalent value of the two constructor constants will throw an `AWTError`. If the layout manager is associated with a container that isn't the container passed in to the constructor, an `AWTError` will be thrown when the layout manager tries to lay out the other (that is, wrong) container.

Once you create a `BoxLayout` instance, you can associate the layout manager with a container as you would with any other layout manager.

```
JPanel panel = new JPanel();
LayoutManager layout = new BoxLayout (panel, BoxLayout.X_AXIS);
panel.setLayout(layout);
```

Unlike all the other system-provided layout managers, a `BoxLayout` and container are bound together in two directions, from manager to container as well as from container to manager.

Tip The `Box` class, described in Chapter 11, lets you create a container and set its layout manager to `BoxLayout` all in one step.

Laying Out Components

Once you've set the layout manager of a container to `BoxLayout`, that's really all you do directly with the layout manager. Adding components to the container is done with either the `add(Component component)` or `add(Component component, int index)` method. Although `BoxLayout` implements the `LayoutManager2` interface, implying the use of constraints, it currently uses none. Therefore, it isn't necessary to use `add(Component component, Object constraints)`.

When it comes time to lay out the container, `BoxLayout` does its work. The `BoxLayout` manager tries to satisfy the minimum and maximum sizes of the components within the container, as well as their x-axis and y-axis alignments. Alignment values range from 0.0f to 1.0f. (Alignment settings are floating-point constants, not doubles, hence the need for the *f*.)

By default, all `Component` subclasses have an x-axis alignment of `Component.CENTER_ALIGNMENT` and a y-axis alignment of `Component.CENTER_ALIGNMENT`. However, all `AbstractButton` subclasses and `JLabel` have a default x-axis alignment of `Component.LEFT_ALIGNMENT`. Table 10-4 shows the constants available from `Component` for these component properties, settable with either `setAlignmentX(float newValue)` or `setAlignmentY(float newValue)`. The different alignments work identically, except in different directions. In the case of horizontal alignments, this is similar to left-, center-, or right-justifying a paragraph.

Table 10-4. *Component Alignments*

Setting	Value
Vertical Alignment	
<code>Component.TOP_ALIGNMENT</code>	0.0f
<code>Component.CENTER_ALIGNMENT</code>	0.5f
<code>Component.BOTTOM_ALIGNMENT</code>	1.0f
Horizontal Alignment	
<code>Component.LEFT_ALIGNMENT</code>	0.0f
<code>Component.CENTER_ALIGNMENT</code>	0.5f
<code>Component.RIGHT_ALIGNMENT</code>	1.0f

Laying Out Components with the Same Alignments

The `BoxLayout` manager acts differently depending on the alignment of the components within the container being managed. If all the alignments are the same, those components whose maximum size is smaller than the container will be aligned based on the alignment setting. For instance, if you have a wide area with a vertical `BoxLayout` and small buttons within it, the horizontal alignment will serve to left-, center-, or right-justify the buttons. Figure 10-9 shows how this looks.




Figure 10-9. *Three y-axis BorderLayout containers, each with components having the same horizontal alignments*

The key point demonstrated here is that if all the components share the same alignment setting, the actual alignment of all the components within the managed container is the components' alignment setting.

The source used to generate Figure 10-9 is shown in Listing 10-2.

Listing 10-2. *Y-Axis Alignment*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class YAxisAlignX {
    private static Container makeIt(String title, float alignment) {
        String labels[] = {"--", "---", "-----", "-----"};

        JPanel container = new JPanel();
        container.setBorder(BorderFactory.createTitledBorder(title));
        BorderLayout layout = new BorderLayout(container, BorderLayout.Y_AXIS);
        container.setLayout(layout);

        for (int i=0,n=labels.length; i<n; i++) {
            JButton button = new JButton(labels[i]);
            button.setAlignmentX(alignment);
            container.add(button);
        }
        return container;
    }

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Alignment Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                Container panel1 = makeIt("Left", Component.LEFT_ALIGNMENT);
                Container panel2 = makeIt("Center", Component.CENTER_ALIGNMENT);
                Container panel3 = makeIt("Right", Component.RIGHT_ALIGNMENT);
```

```

        frame.setLayout(new FlowLayout());
        frame.add(panel1);
        frame.add(panel2);
        frame.add(panel3);

        frame.pack();
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

An x-axis `BoxLayout` works similarly when all the components have the same vertical alignments. Instead of being left-, center-, and right-justified, the components would appear at the top, center, and bottom of the container. Figure 10-10 demonstrates this appearance.




Figure 10-10. Three x-axis `BoxLayout` containers that each have components with the same vertical alignments

The source for the example shown in Figure 10-10 requires just a few changes from Listing 10-2. The complete source is provided in Listing 10-3.

Listing 10-3. *X-Axis Alignment*

```

import javax.swing.*.*;
import java.awt.*.*;
import java.awt.event.*.*;

public class XAxisAlignY {
    private static Container makeIt(String title, float alignment) {
        String labels[] = {"-", "-", "-"};

        JPanel container = new JPanel();
        container.setBorder(BorderFactory.createTitledBorder(title));
        BoxLayout layout = new BoxLayout(container, BoxLayout.X_AXIS);
        container.setLayout(layout);
    }
}

```

```

        for (int i=0,n=labels.length; i<n; i++) {
            JButton button = new JButton(labels[i]);
            button.setAlignmentY(alignment);
            container.add(button);
        }
        return container;
    }

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Alignment Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                Container panel1 = makeIt("Top",    Component.TOP_ALIGNMENT);
                Container panel2 = makeIt("Center", Component.CENTER_ALIGNMENT);
                Container panel3 = makeIt("Bottom", Component.BOTTOM_ALIGNMENT);

                frame.setLayout(new GridLayout(1, 3));
                frame.add(panel1);
                frame.add(panel2);
                frame.add(panel3);

                frame.setSize(423, 171);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

Laying Out Components with Different Alignments

Working with small components that have the same alignment is relatively simple. However, if the components in a container managed by a `BoxLayout` have different alignments, things become more complex. In addition, the components won't necessarily be displayed the way you might expect. For a vertical box, the components appear as follows:

- If a component has its x alignment set to `Component.LEFT_ALIGNMENT`, the left edge of the component will be aligned with the center of the container.
- If a component has its x alignment set to `Component.RIGHT_ALIGNMENT`, the right edge of the component will be aligned with the center of the container.
- If a component has its x alignment set to `Component.CENTER_ALIGNMENT`, the component will be centered within the container.
- Other alignment values cause components to be placed in varying positions (depending on the value) relative to the center of the container.

To help you visualize this mixed alignment behavior, Figure 10-11 shows two `BoxLayout` containers. The left container has two components, one with a left alignment (the button labeled 0.0) and another with a right alignment (the button labeled 1.0). Here, you can see that the left edge of the right component is aligned to the right edge of the left component, with the common edge being the centerline of the container. The right container shows additional components placed between the 0.0 and 1.0 alignment settings. The label of each button represents its alignment setting.




Figure 10-11. Two y-axis `BoxLayout` containers with mixed horizontal alignments

For a horizontal box, the y alignment works the same relative to the top and bottom of the components on an x-axis, as illustrated in Figure 10-12.




Figure 10-12. Two x-axis `BoxLayout` containers with mixed vertical alignments

Laying Out Larger Components

In the examples so far, the size of the components is always smaller than the space available. Those examples demonstrate a subtle difference between Swing and the original AWT components. The default maximum size of Swing components is the preferred size of the component. With AWT components, the default maximum size is a dimension with a width and height of `Short.MAX_VALUE`. If the previous examples had used AWT `Button` components instead of Swing `JButton` components, you would see surprisingly different results. You would also see different results if you manually set the maximum size property of the components to some value wider or higher than the screen for the appropriate `BoxLayout`. Using AWT `Button` components makes things a little easier to demonstrate.

Figure 10-9 showed three y-axis `BoxLayout` containers in which the components inside the container share the same horizontal alignment setting and the maximum size of each button is constrained. If the component's maximum size is unconstrained, or just larger than the container, you see something like Figure 10-13, in which the y-axis `BoxLayout` container has four `Button`

components with the same horizontal alignment. Notice that instead of aligning to the left, center, or right, the components grow to fill all available space.




Figure 10-13. *Y-axis BorderLayout containers with the same vertical alignments and unconstrained size*

If the components had different alignments and an unconstrained maximum size, you would get yet another behavior. Any component with an alignment not at the minimum (0.0f) or maximum (1.0f) setting will grow to fill the entire space. If components with both the minimum and maximum alignment settings are present, the middle edges of those two components will align in the middle, as Figure 10-14 demonstrates.




Figure 10-14. *Y-axis BorderLayout containers with different vertical alignments, unconstrained size, and both minimum/maximum alignment present*

If, however, only one component has an edge case (0.0 or 1.0) and is in a container with components having other alignments, that edge-case component will grow toward somewhere other than the middle of the container. This behavior is shown in Figure 10-15. The x-axis BorderLayout containers work similarly with different horizontal alignments.




Figure 10-15. *Y-axis BoxLayout containers with different vertical alignments, unconstrained size, and only one alignment at minimum/maximum*

OverlayLayout Class

As its name implies, the `OverlayLayout` class is for layout management of components that lie on top of one another. When using `add(Component component)`, the order in which you add components to a container with an `OverlayLayout` manager determines the component layering. If you use `add(Component component, int index)` instead, you can add components in any order. Although `OverlayLayout` implements the `LayoutManager2` interface, like `BoxLayout` it currently doesn't use any constraints.

Determining the two-dimensional position of the components requires the layout manager to examine the `x` and `y` alignment properties of the contained components. Each component will be positioned such that its `x` and `y` alignment properties define a point shared by all the components, called the *axis point* of the layout manager. If you multiply the alignment value by the component's size in each appropriate direction, you'll get each part of the axis point for that component.

After the axis point is determined for each component, the `OverlayLayout` manager calculates the position of this shared point within the container. To calculate this position, the layout manager averages the different alignment properties of the components, and then multiplies each setting by the width or height of the container. This position is where the layout manager places the axis point, and the components are then positioned over this shared point.

For example, suppose you have three buttons: a 25×25 white button on top of a 50×50 gray button on top of a 100×100 black button. If the `x` and `y` alignment of each button is 0.0f, the shared axis point for the three components is their upper-left corner, and the components are all in the upper-left corner of the container. Figure 10-16 shows how this might appear.

If the `x` and `y` alignment of each button is 1.0f, the axis point for the three components is their bottom-right corner, and the components are in the bottom-right corner of the container. Figure 10-17 shows this appearance.




Figure 10-16. *Sample OverlayLayout with 0.0 x and y alignments*




Figure 10-17. *Sample OverlayLayout with 1.0 x and y alignments*

If the x and y alignment of each button is 0.5f, the axis point for the three components is their center, and the components are in the center of the container. Figure 10-18 shows this appearance.




Figure 10-18. *Sample OverlayLayout with 0.5 x and y alignments*

Having all components with the same alignment is relatively easy to visualize, but what would happen if the components had different alignments? For instance, if the small button had x and y alignments of 0.0f, the medium button had alignments of 0.5f, and the large button had alignments of 1.0f, where would everything appear? Well, the first thing the layout manager calculates is the axis point. Based on the specific alignment of each button, the axis point would be the upper-left corner of the small button, the middle of the medium button, and the bottom-right corner of the large button. The position of the axis point within the container would then be the average of the alignment values multiplied by the dimensions of the container. The average of 0, 0.5, and 1 for both directions places the axis point at the center of the container. The components are then placed and layered from this position, as Figure 10-19 shows.




Figure 10-19. Three buttons managed by an *OverlayLayout* with 0.0, 0.5, and 1.0 x and y alignments

When you set up overlaid components, make sure that the `optimizedDrawingEnabled` property of the container of the components is set to `false`. This ensures proper repainting and event propagation.

To try out the *OverlayLayout* manager, use the source that follows in Listing 10-4. It provides selectable buttons to demonstrate interactively the effect of varying the alignment values. Initially, the program has everything centered.

Listing 10-4. *OverLayout Example*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class OverlaySample {
    public static final String SET_MINIMUM = "Minimum";
    public static final String SET_MAXIMUM = "Maximum";
    public static final String SET_CENTRAL = "Central";
    public static final String SET_MIXED = "Mixed";
```

```
static JButton smallButton = new JButton();
static JButton mediumButton = new JButton();
static JButton largeButton = new JButton();

public static void setupButtons(String command) {
    if (SET_MINIMUM.equals(command)) {
        smallButton.setAlignmentX(0.0f);
        smallButton.setAlignmentY(0.0f);
        mediumButton.setAlignmentX(0.0f);
        mediumButton.setAlignmentY(0.0f);
        largeButton.setAlignmentX(0.0f);
        largeButton.setAlignmentY(0.0f);
    } else if (SET_MAXIMUM.equals(command)) {
        smallButton.setAlignmentX(1.0f);
        smallButton.setAlignmentY(1.0f);
        mediumButton.setAlignmentX(1.0f);
        mediumButton.setAlignmentY(1.0f);
        largeButton.setAlignmentX(1.0f);
        largeButton.setAlignmentY(1.0f);
    } else if (SET_CENTRAL.equals(command)) {
        smallButton.setAlignmentX(0.5f);
        smallButton.setAlignmentY(0.5f);
        mediumButton.setAlignmentX(0.5f);
        mediumButton.setAlignmentY(0.5f);
        largeButton.setAlignmentX(0.5f);
        largeButton.setAlignmentY(0.5f);
    } else if (SET_MIXED.equals(command)) {
        smallButton.setAlignmentX(0.0f);
        smallButton.setAlignmentY(0.0f);
        mediumButton.setAlignmentX(0.5f);
        mediumButton.setAlignmentY(0.5f);
        largeButton.setAlignmentX(1.0f);
        largeButton.setAlignmentY(1.0f);
    } else {
        throw new IllegalArgumentException("Illegal Command: " + command);
    }
    // Redraw panel
    ((JPanel)largeButton.getParent()).revalidate();
}

public static void main(String args[]) {
```

```

final ActionListener generalActionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        JComponent comp = (JComponent)actionEvent.getSource();
        System.out.println (
            actionEvent.getActionCommand() + ": " + comp.getBounds());
    }
};

final ActionListener sizingActionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        setupButtons(actionEvent.getActionCommand());
    }
};

Runnable runner = new Runnable() {
    public void run() {
        JFrame frame = new JFrame("Overlay Example");
        frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

        JPanel panel = new JPanel() {
            public boolean isOptimizedDrawingEnabled() {
                return false;
            }
        };
        LayoutManager overlay = new OverlayLayout(panel);
        panel.setLayout(overlay);

        Object settings[][] = {
            {"Small", new Dimension(25, 25), Color.white},
            {"Medium", new Dimension(50, 50), Color.gray},
            {"Large", new Dimension(100, 100), Color.black}
        };
        JButton buttons[] = {smallButton, mediumButton, largeButton};

        for (int i=0, n=settings.length; i<n; i++) {
            JButton button = buttons[i];
            button.addActionListener(generalActionListener);
            button.setActionCommand((String)settings[i][0]);
            button.setMaximumSize((Dimension)settings[i][1]);
            button.setBackground((Color)settings[i][2]);
            panel.add(button);
        }
    }
};

```

```

        setupButtons(SET_CENTRAL);

        JPanel actionPanel = new JPanel();
        actionPanel.setBorder(BorderFactory.createTitledBorder("Change Alignment"));
        String actionSettings[] = {SET_MINIMUM, SET_MAXIMUM, SET_CENTRAL,
            SET_MIXED};
        for (int i=0, n=actionSettings.length; i<n; i++) {
            JButton button = new JButton(actionSettings[i]);
            button.addActionListener(sizingActionListener);
            actionPanel.add(button);
        }

        frame.add(panel, BorderLayout.CENTER);
        frame.add(actionPanel, BorderLayout.SOUTH);

        frame.setSize(400, 300);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

SizeRequirements Class

The `BoxLayout` and `OverlayLayout` managers rely on the `SizeRequirements` class to determine the exact positions of the contained components. The `SizeRequirements` class contains various static methods to assist in the calculations necessary to position components in either an aligned or a tiled manner. The layout managers use this class to calculate their components' x coordinates and width and y coordinates and height. Each pair is calculated separately. If the associated layout manager needs both sets of attributes for positioning, the layout manager asks the `SizeRequirements` class separately for each.

ScrollPaneLayout Class

The `JScrollPane` class, a container class that will be described in Chapter 11, uses the `ScrollPaneLayout` manager. Trying to use the layout manager outside a `JScrollPane` isn't possible because the layout manager checks to see if the container object associated with the layout manager is an instance of `JScrollPane`. See Chapter 11 for a complete description of this layout manager (and its associated `ScrollPaneConstants` interface) in the context of the `JScrollPane`.

ViewportLayout Class

The ViewportLayout manager is used by the JViewport class, a container class (to be described in Chapter 11). The JViewport is also used within the ScrollPaneLayout/JScrollPane combination. Like ScrollPaneLayout, the ViewportLayout manager is closely tied to its component, JViewport in this case, and isn't usable outside the component, except in a subclass. In addition, the JViewport class is rarely used outside a JScrollPane. The ViewportLayout manager will be discussed in the context of its container, JViewport, in Chapter 11.

SpringLayout Class

The newest addition to the Java layout manager front is the SpringLayout manager, added with the J2SE 1.4 release. This allows you to attach “springs” to components so that they are laid out relative to other components. For instance, with SpringLayout, you can say that a button appears attached to the right border, no matter what size a user makes the screen.

The SpringLayout manager relies on SpringLayout.Constraints for the component constraints. This works similarly to the GridBagConstraints class that complements the GridBagLayout manager. Each component added to the container can have an attached SpringLayout.Constraints. Therein lies the end to the similarities between these two types of constraints.

You usually don't need to add the component with the constraints. Instead, you can add the component, and then typically attach the constraints separately. There is nothing stopping you from adding the constraints with the component, but SpringLayout.Constraints is not a simple class. It is a collection of Spring objects, each a different constraint on the component. You need to add each Spring constraint separately to SpringLayout.Constraints. You do this by setting specific constraints on an edge of the component. Using the four SpringLayout constants of EAST, WEST, NORTH, and SOUTH, you call the setConstraints(String edge, Spring spring) method of SpringLayout.Constraints, where the String is one of the constants.

For instance, if you want to add a component in the top left of a container, you can set up two springs of a constant size, combine them together, and add the component to the container with the combined set, as shown here:

```
Component left = ...;
SpringLayout layout = new SpringLayout();
JPanel panel = new JPanel(layout);
Spring xPad = Spring.constant(5);
Spring yPad = Spring.constant(25);
SpringLayout.Constraints constraint = new SpringLayout.Constraints();
constraint.setConstraint(SpringLayout.WEST, xPad);
constraint.setConstraint(SpringLayout.NORTH, yPad);
frame.add(left, constraint);
```

That doesn't look too complicated, but it gets more difficult when you need to add the next component, either to the right of the first or below it. You can't just say to add the component *n* pixels over. You must actually add the padding to the edge of the earlier component. To find the edge of the earlier component, you ask the layout manager with `getConstraint()`, passing in the edge you want and the component, as in `layout.getConstraint(SpringLayout.EAST, left)`, to get the location of the right edge of the first component. From that location, you can add in the necessary padding and attach it to the edge of the other component, as shown here:

```
Component right = ...;
Spring rightSideOfLeft = layout.getConstraint(SpringLayout.EAST, left);
Spring pad = Spring.constant(20);
Spring leftEdgeOfRight = Spring.sum(rightSideOfLeft, pad);
constraint = new SpringLayout.Constraints();
constraint.setConstraint(SpringLayout.WEST, leftEdgeOfRight);
constraint.setConstraint(SpringLayout.NORTH, yPad);
frame.add(right, constraint);
```

This works perfectly well, but it gets tedious as the number of components increases. To eliminate the in-between steps, you can add the components without the constraints, and then add each separately, connecting the components via the `putConstraint()` method of `SpringLayout`.

```
public void putConstraint(String e1, Component c1, int pad, String e2,
    Component c2)
public void putConstraint(String e1, Component c1, Spring s, String e2,
    Component c2)
```

Here, instead of asking for the edge and adding in the padding yourself, the `putConstraint()` call combines the tasks for you. To demonstrate, the following snippet adds the same component constraints to the right component as the previous one, but using `putConstraint()` instead of using `SpringLayout.Constraints` directly:

```
Component left = ...;
Component right = ...;
SpringLayout layout = new SpringLayout();
JPanel panel = new JPanel(layout);
panel.add(left);
panel.add(right);
layout.putConstraint(SpringLayout.WEST, left, 5, SpringLayout.WEST, panel);
layout.putConstraint(SpringLayout.NORTH, left, 25, SpringLayout.NORTH, panel);
layout.putConstraint(SpringLayout.NORTH, right, 25, SpringLayout.NORTH, panel);
layout.putConstraint(SpringLayout.WEST, right, 20, SpringLayout.EAST, left);
```

To help you visualize the use of `SpringLayout`, Sun has a tool available from <https://bean-builder.dev.java.net/> called The Bean Builder. The tool is primarily intended to be used when working with JavaBean components, but it works well to see `SpringLayout` in action. Figure 10-20 shows what the tool looks like on startup through Java WebStart.




Figure 10-20. *The Bean Builder startup*

Around the edges of each component lies a set of four boxes, one each for north, south, east, and west. You can drag an arrow out of a box and connect it to any other box. Had the tool been a little more sophisticated, it would permit you to specify gap sizes for springs, too, but, as it is, the screen will look something like Figure 10-21 during screen design. Each arrow created is mapped to a specific call to the `putConstraint()` method.




Figure 10-21. *Bean Builder and SpringLayout*

Listing 10-5 offers source similar to what would be used to generate a screen like Figure 10-21. Notice that you must use the content pane of the JFrame directly, as `putConstraint()` wants that container, not the frame itself.

Listing 10-5. *SpringLayout Example*

```
import java.awt.*;
import javax.swing.*;

public class SpringSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("SpringLayout");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                Container contentPane = frame.getContentPane();

                SpringLayout layout = new SpringLayout();
                contentPane.setLayout(layout);

                Component left = new JLabel("Left");
                Component right = new JTextField(15);

                contentPane.add(left);
                contentPane.add(right);
            }
        };
        SwingUtilities.invokeLater(runner);
    }
}
```

```
        layout.putConstraint(SpringLayout.WEST, left, 10, SpringLayout.WEST,
                             contentPane);
        layout.putConstraint(SpringLayout.NORTH, left, 25, SpringLayout.NORTH,
                             contentPane);
        layout.putConstraint(SpringLayout.NORTH, right, 25, SpringLayout.NORTH,
                             contentPane);
        layout.putConstraint(SpringLayout.WEST, right, 20, SpringLayout.EAST, left);

        frame.setSize(300, 100);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}
```

Summary

This chapter introduced AWT's predefined layout managers `FlowLayout`, `BorderLayout`, `GridLayout`, `GridBagLayout`, and `CardLayout`, as well as Swing's predefined layout managers `BoxLayout`, `OverlayLayout`, `ScrollPaneLayout`, `ViewportLayout`, and `SpringLayout`. You saw how the various alignment settings affect the components within a container whenever you use a layout manager such as `BoxLayout` or `OverlayLayout`. In addition, you were introduced to the `SizeRequirements` class, which is used internally by `BoxLayout` and `OverlayLayout`.

In Chapter 11, you'll look at the `JScrollPane` and `JViewport` containers, which use the `ScrollPaneLayout` and `ViewportLayout` managers, plus several other sophisticated Swing container classes.



Advanced Swing Containers

Chapter 10 explored the layout managers available within AWT and Swing. In this chapter, you'll look at some of the containers that rely on these layout managers, as well as some others that work without a layout manager.

Starting with the `Box` class, you'll discover the best way to use the `BoxLayout` manager to create a single row or column of components. Next, you'll learn about the `JSplitPane` container, which is a bit like a specialized `Box` with just two components inside. The `JSplitPane` provides a splitter bar that acts as a divider users can drag to resize the components to suit their needs.

Then you'll explore the `JTabbedPane` container, which works something like a container whose layout manager is a `CardLayout`, except with tabs built into the container that allow you to move from card to card. You'll be able to create multiple-screen, property-sheet dialog boxes for user input with `JTabbedPane`.

The last two advanced Swing containers covered are the `JScrollPane` and `JViewport`. Both of these components offer the ability to display a section of a large component within a limited amount of screen real estate. The `JScrollPane` adds scrollbars to a display area so that you can move around a large component that sits within a small area. In fact, the `JScrollPane` uses the `JViewport` to "clip away" the part of the larger component that shouldn't be seen.

So, let's get started and look at the first container, the `Box` class.

Box Class

As a subclass of `JComponent`, the `Box` class is a special Java Container for creating a single row or column of components with the help of the `BoxLayout` manager. The `Box` container works like a `JPanel` (or `Panel`), but has a different default layout manager, `BoxLayout`. Using `BoxLayout` can be a little cumbersome without a `Box`, which simplifies working with `BoxLayout`. You can associate the `BoxLayout` manager with a container in just three steps: manually creating the container, creating the layout manager, and associating the manager with the container. When you create an instance of `Box`, you perform these three steps at once. In addition, you can use an inner class of `Box` called `Box.Filler` to better position components within the container.

Creating a Box

You have three ways to create a Box, offered by one constructor and two static factory methods:

```
public Box(int direction)
Box horizontalBox = new Box(BoxLayout.X_AXIS);
Box verticalBox   = new Box(BoxLayout.Y_AXIS);

public static Box createHorizontalBox()
Box horizontalBox = Box.createHorizontalBox();

public static Box createVerticalBox()
Box verticalBox   = Box.createVerticalBox();
```

Note The Box class is not designed to be used as a JavaBean component. Use of this container within an IDE can be awkward.

The less frequently used constructor requires a direction for the main axis of the layout manager. The direction is specified by either of two BoxLayout constants, X_AXIS or Y_AXIS, to create a horizontal or vertical box, respectively. Instead of manually specifying the direction, simply create a Box with the desired orientation by using one of the provided factory methods: createHorizontalBox() or createVerticalBox().

Filling a horizontal and vertical Box with a JLabel, a JTextField, and a JButton demonstrates the flexibility of BoxLayout, as shown in Figure 11-1.




Figure 11-1. A horizontal and a vertical box

For the horizontal container, the label and button are at their preferred widths because their maximum size is the same as their preferred size. The text field uses up the remaining space.

In the vertical container, the label and button sizes are their preferred size, too, because their maximum size is still the same as their preferred size. The text field's height fills the height that the label and button don't use, and its width is as wide as the container.

The source code for creating the screens shown in Figure 11-1 follows in Listing 11-1.

Listing 11-1. Working with the Box

```

import javax.swing.*;
import java.awt.*;

public class BoxSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame verticalFrame = new JFrame("Vertical");
                verticalFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                Box verticalBox = Box.createVerticalBox();
                verticalBox.add(new JLabel("Top"));
                verticalBox.add(new JTextField("Middle"));
                verticalBox.add(new JButton("Bottom"));
                verticalFrame.add(verticalBox, BorderLayout.CENTER);
                verticalFrame.setSize(150, 150);
                verticalFrame.setVisible(true);

                JFrame horizontalFrame = new JFrame("Horizontal");
                horizontalFrame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                Box horizontalBox = Box.createHorizontalBox();
                horizontalBox.add(new JLabel("Left"));
                horizontalBox.add(new JTextField("Middle"));
                horizontalBox.add(new JButton("Right"));
                horizontalFrame.add(horizontalBox, BorderLayout.CENTER);
                horizontalFrame.setSize(150, 150);
                horizontalFrame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

Box Properties

As Table 11-1 shows, there are only two Box properties. Although the layout property inherits a `setLayout(LayoutManager)` method from its parent `Container` class, if called on a Box object, the class throws an `AWTError`. Once the `BoxLayout` manager is set during its construction, it can't be changed, nor can its direction.

Table 11-1. Box Properties

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>layout</code>	<code>LayoutManager</code>	Write-only

Working with Box.Filler

The `Box` class has an inner class `Box.Filler` to help you create invisible components for better component positioning within a container whose layout manager is `BoxLayout`. By directly manipulating the minimum, maximum, and preferred size of the created component, you can create components that grow to fill unused space or remain a fixed size, making screens more aesthetically pleasing to your users.

Note Technically speaking, the use of `Box.Filler` is not limited to containers whose layout manager is `BoxLayout`. You can use them anywhere you can use any other `Component`. The components are just invisible.

Instead of directly using the `Box.Filler` class, several static methods of the `Box` class can help you create the appropriate filler components. The factory methods allow you to categorize these components by type, instead of by minimum, maximum, or preferred size. You'll look at these methods in the next two sections.

If you're interested in the class definition, it's shown next. Like the `Box` class, `Box.Filler` isn't meant to be used as a `JavaBean` component.

```
public class Box.Filler extends Component implements Accessible {
    // Constructors
    public Filler(Dimension minSize, Dimension prefSize, Dimension maxSize);
    // Properties
    public AccessibleContext getAccessibleContext();
    public Dimension getMaximumSize();
    public Dimension getMinimumSize();
    public Dimension getPreferredSize();
    // Others
    protected AccessibleContext accessibleContext;
    public void changeShape(Dimension minSize, Dimension prefSize, Dimension maxSize);
}
```

Creating Areas That Grow

If a component has a dimensionless minimum and preferred size, and a maximum size bigger than the screen, the component will grow to take up unused space between components in the container along one or both axes. In the case of a `Box`, or more precisely, a container whose layout manager is `BoxLayout`, the growth occurs along the layout manager's initially chosen direction (either `BoxLayout.X_AXIS` or `BoxLayout.Y_AXIS`). For a horizontal box, the growth affects the component's width. For a vertical box, the growth is reflected in the component's height.

The name commonly given to this type of growing component is *glue*. The two flavors of glue are direction-independent glue and direction-dependent glue. The following factory methods of `Box` are used to create the glue components:

```

public static Component createGlue()
// Direction independent
Component glue = Box.createGlue();
aBox.add(glue);

public static Component createHorizontalGlue();
// Direction dependent: horizontal
Component horizontalGlue = Box.createHorizontalGlue();
aBox.add(horizontalGlue);

public static Component createVerticalGlue()
// Direction dependent: vertical
Component verticalGlue = Box.createVerticalGlue();
aBox.add(verticalGlue);

```

Once you create glue, you add it to a container in the same way as any other component, by using `Container.add(Component)` or one of the other `add()` varieties. Glue allows you to align components within a container, as Figure 11-2 shows.



Figure 11-2. *Using glue in a Box*

You can add glue components to any container whose layout manager honors minimum, maximum, and preferred size properties of a component, such as `BoxLayout`. For instance, Figure 11-3 demonstrates what happens when you add a glue component to a `JMenuBar` just before adding the last `JMenu`. Because the layout manager for a `JMenuBar` is `BoxLayout` (actually the subclass `javax.swing.plaf.basic.DefaultMenuLayout`), this action pushes the last menu to the right edge of the menu bar, similar to the Motif/CDE style of help menus.

Caution I recommend that you avoid using the glue capability described here to set up help menus on menu bars. Eventually, the public void `setHelpMenu(JMenu menu)` of `JMenuBar` will be implemented and won't throw an `Error`. Of course, many of us are still waiting for this to happen.




Figure 11-3. Using glue in a JMenuBar

Creating Rigid Areas

Because a glue component grows to fill the available space, if you want to have a fixed distance between components, you need to create a rigid component, or *strut*. When doing so, you specify the strut's size. Struts can be two-dimensional, requiring you to specify the width and height of the component; or, they can be one-dimensional, requiring you to specify either the width or height.


```
public static Component createRigidArea(Dimension dimension)
// Two-dimensional
Component rigidArea = Box. createRigidArea(new Dimension(10, 10));
aBox.add(rigidArea);
```

```
public static Component createHorizontalStrut(int width)
// One-dimensional: horizontal
Component horizontalStrut = Box. createHorizontalStrut(10);
aBox.add(horizontalStrut);
```

```
public static Component createVerticalStrut(int height)
// One-dimensional: vertical
Component verticalStrut = Box. createVerticalStrut(10);
aBox.add(verticalStrut);
```

Caution Although direction-independent glue created with `createGlue()` shows no side effects if you change container direction, creating a rigid area may cause layout problems if the axis is later changed. (Imagine dragging a menu bar and dropping it along the right side from the top.) That's because the component has a dimensionless minimum size. Using `createRigidArea()` isn't recommended, unless you truly want a two-dimensional empty component.

Figure 11-4 demonstrates several struts in action. Notice that you can have varying strut distances between different components, and struts at the end of a container may have no effect. After a user resizes a screen, the strut distance between components remains fixed, as you can see in Figure 11-4.



Before Resizing



After Resizing

Figure 11-4. *Using struts in a Box*

JSplitPane Class

Similar to the Box container, the JSplitPane container allows you to display components in a single row or column. Whereas a Box can contain any number of components, a JSplitPane is meant to display two—and only two—components. The components are of variable size and separated by a movable divider. The divider is specially constructed in that the end user can grab it and drag the divider to adjust the size of the contained components. Figure 11-5 demonstrates both vertical and horizontal split panes, shown before and after moving the divider.




Figure 11-5. Examples of `JSplitPane` containers

Creating a `JSplitPane`

There are five constructors for `JSplitPane`. With them, you can initialize the orientation of the contained component pair, set the `continuousLayout` property, or initialize the pair of components for the container.

```
public JSplitPane()
```

```
JSplitPane splitPane = new JSplitPane();
```

```
public JSplitPane(int newOrientation)
```

```
JSplitPane splitPane = new JSplitPane(JSplitPane.VERTICAL_SPLIT);
```

```
public JSplitPane(int newOrientation, boolean newContinuousLayout)
```

```
JSplitPane splitPane = new JSplitPane(JSplitPane.VERTICAL_SPLIT, true);
```

```
public JSplitPane(int newOrientation, Component newLeftComponent,  
    Component newRightComponent)
```

```
JComponent topComponent = new JButton("Top Button");
```

```
JComponent bottomComponent = new JButton("Bottom Button");
```

```
JSplitPane splitPane = new JSplitPane(JSplitPane.VERTICAL_SPLIT,  
    topComponent, bottomComponent);
```

```
public JSplitPane(int newOrientation, boolean newContinuousLayout,
    Component newLeftComponent, Component newRightComponent)
JSplitPane splitPane = new JSplitPane(JSplitPane.VERTICAL_SPLIT, true,
    topComponent, bottomComponent);
```

Unless otherwise specified, the orientation is horizontal. Orientation can be specified by either of the `JSplitPane` constants `VERTICAL_SPLIT` or `HORIZONTAL_SPLIT`. The `continuousLayout` property setting determines how the split pane reacts when the user drags the divider. When the setting is false (the default), only the divider is redrawn when dragged. When the setting is true, the `JSplitPane` resizes and redraws the components on each side of the divider as the user drags the divider.

Note If the orientation is `JSplitPane.VERTICAL_SPLIT`, you can think of the top component as the left component and the bottom component as the right component.

If you're using the no-argument constructor, the initial set of components within the split pane is made up of buttons (two `JButton` components). Two other constructors explicitly set the initial two components. Surprisingly, the remaining two constructors provide no components within the container by default. To add or change the components within the `JSplitPane`, see the “Changing `JSplitPane` Components” section that’s coming up shortly.

JSplitPane Properties

Table 11-2 shows the 17 properties of `JSplitPane`.

Table 11-2. *JSplitPane Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>bottomComponent</code>	<code>Component</code>	Read-write
<code>continuousLayout</code>	<code>boolean</code>	Read-write bound
<code>dividerLocation</code>	<code>double</code>	Write-only
<code>dividerLocation</code>	<code>int</code>	Read-write bound
<code>dividerSize</code>	<code>int</code>	Read-write bound
<code>lastDividerLocation</code>	<code>int</code>	Read-write bound
<code>leftComponent</code>	<code>Component</code>	Read-write
<code>maximumDividerLocation</code>	<code>int</code>	Read-only
<code>minimumDividerLocation</code>	<code>int</code>	Read-only

Table 11-2. *JSplitPane Properties (Continued)*

Property Name	Data Type	Access
oneTouchExpandable	boolean	Read-write bound
orientation	int	Read-write bound
resizeWeight	double	Read-write bound
rightComponent	Component	Read-write
topComponent	Component	Read-write
validateRoot	boolean	Read-only
UI	JSplitPaneUI	Read-write bound
UIClassID	String	Read-only

Setting Orientation

Besides initializing the orientation within the constructor, you can change the `JSplitPane` orientation by changing the orientation property setting to either `JSplitPane.VERTICAL_SPLIT` or `JSplitPane.HORIZONTAL_SPLIT`. If you try to change the property to a nonequivalent setting, an `IllegalArgumentException` is thrown.

Dynamically changing the orientation at runtime is not recommended because it can confuse a user. However, if you're using a visual development tool, you can explicitly set the orientation for this property after creating the `JSplitPane`. When not programming visually, you would normally initialize the orientation when you create the `JSplitPane`.

Changing JSplitPane Components

There are four read-write properties for the different positions of a component within a `JSplitPane`: `bottomComponent`, `leftComponent`, `rightComponent`, and `topComponent`. In reality, these four properties represent two components internally: The left and top components are one; the right and bottom components represent the other.

You should use the properties that are appropriate for the orientation of your `JSplitPane`. Using the inappropriate property methods can make life difficult for the maintenance programmer. Imagine, after creating a user interface, seeing something like the following code six months later:

```
JComponent leftButton = new JButton("Left");
JComponent rightButton = new JButton("Right");
JSplitPane splitPane = new JSplitPane(JSplitPane.VERTICAL_SPLIT);
splitPane.setLeftComponent(leftButton);
splitPane.setRightComponent(rightButton);
```

If you glance at the source, you might think that the screen will contain a button to the left and one to the right based on the variable names and the `setXXXComponent()` methods used. But because the instantiated `JSplitPane` has a vertical orientation, the interface that's created looks like Figure 11-6. The variable names are used because of the button labels, not their position.



Figure 11-6. Adding left/right buttons to a vertical *JSplitPane*

The code is more understandable if the `setTopComponent()` and `setBottomComponent()` methods are used with better variable names:

```
JComponent topButton = new JButton("Left");
JComponent bottomButton = new JButton("Right");
JSplitPane splitPane = new JSplitPane(JSplitPane.VERTICAL_SPLIT);
splitPane.setTopComponent(topButton);
splitPane.setBottomComponent(bottomButton);
```

Moving the JSplitPane Divider

Initially, the divider is shown below or to the right of the preferred size of the top or left component. At any time, you can reset the divider position to that position by calling the `resetToPreferredSizes()` method of `JSplitPane`. If you want to programmatically position the divider, you can change the `dividerLocation` property with `setDividerLocation(newLocation)`. This property can be changed to an `int` position, representing an absolute distance from the top or left side, or it can be set to a `double` value between 0.0 and 1.0, representing a percentage of the `JSplitPane` container width.

Caution Changing the property setting to a `double` value outside the range of 0.0 and 1.0 results in an `IllegalArgumentException` being thrown.

If you want to set the divider location, you must wait for the component to be realized. Essentially, that means it must be visible. While there are roundabout ways of doing this, the most direct way is to attach a `HierarchyListener` to the `JSplitPane` and watch for when the `HierarchyEvent` is of type `SHOWING_CHANGED`. This is demonstrated in the following code fragment, changing the divider location to 75%.

```
HierarchyListener hierarchyListener = new HierarchyListener() {
    public void hierarchyChanged(HierarchyEvent e) {
        long flags = e.getChangeFlags();
        if ((flags & HierarchyEvent.SHOWING_CHANGED) ==
            HierarchyEvent.SHOWING_CHANGED) {
            splitPane.setDividerLocation(.75);
        }
    }
};
splitPane.addHierarchyListener(hierarchyListener);
```

Although you can set the `dividerLocation` property with a double value, you can get only an `int`, indicating its absolute position.

Tip With the system-provided look and feel classes, pressing the F8 key allows you to move the divider with the keyboard keys such as Home, End, or the arrows. F8 isn't a modifier like Shift or Alt. Instead, pressing F8 moves the focus to the divider so that it can be moved with keystrokes.

Resizing Components and Working with a One-Touch Expandable Divider

Limitations exist on the resizing of components within the `JSplitPane`. The `JSplitPane` honors the minimum size of each contained component. If grabbing and moving the divider line will cause a component to shrink to less than its minimum size, the scroll pane won't let the user drag the divider past that minimum size.

Note You can always programmatically position the divider to be anywhere, even if it makes a component smaller than its minimum size. However, this isn't a good idea because the component has a minimum size for a good reason.

If the minimum dimensions of a component are too large for a `JSplitPane`, you need to change the component's minimum size so that the divider can use some of that component's space. For AWT components, changing the minimum size of a standard component requires subclassing. With Swing components, you can simply call the `setMinimumSize()` method of `JComponent` with a new `Dimension`. Nevertheless, minimum sizes are set for a reason. The component probably won't look right if you explicitly shrink its minimum size.

A better approach is available for allowing one component to take up more space than another: Set the `oneTouchExpandable` property of the `JSplitPane` to `true`. When this property is `true`, an icon is added to the divider, allowing a user to completely collapse one of the two components to give the other component the entire area. In the example in Figure 11-7, the icon is a combination up-and-down arrow.

Figure 11-7 shows how this icon might appear (as rendered by the Ocean look and feel) and illustrates what happens after selecting the up arrow on the divider to expand the lower component to its fullest size. Clicking again on the icon on the divider returns the components to their previous positions. Clicking on the divider somewhere other than on the icon will position the divider in such a way that the collapsed component is at its preferred size.




Figure 11-7. *Setting and using the oneTouchExpandable property*


Note There's no easy way to alter the one-touch expandable icon or change how the divider is rendered. Both are defined by the `BasicSplitPaneDivider` subclass and created in the `createDefaultDivider()` method of the `BasicSplitPaneUI` subclass for the specific look and feel. One thing you can easily change is the border around the divider, which is a custom border.

The `lastDividerLocation` property allows you or the system to inquire about the previous divider location. The `JSplitPane` uses this property when the user selects the maximizer icon to undo the minimization of one of the components in the `JSplitPane`.

Caution Beware of components that base their minimum size on the container size or their initial size! Placing them in a `JSplitPane` may require you to manually set the minimum and/or preferred size of the components. The components that most frequently cause problems when used within a `JSplitPane` are `JTextArea` and `JScrollPane`.

Resizing the `JSplitPane`

If additional space is available within the `JSplitPane` that is not required by the preferred size of the components it contains, this space is allocated based on the `resizeWeight` property setting. The initial setting of this property is 0.0, meaning the right or bottom component gets any additional space. Changing the setting to 1.0 would give all the space to the left or top component. A value of 0.5 would split the space evenly between the two components. Figure 11-8 shows the effect of these changes.



Default Resize Weight (0.0)



Resize Weight 1.0



Resize Weight 0.5

Figure 11-8. *Changing the resize weight*

Listening for JSplitPane Property Changes

The `JSplitPane` class defines the following constants to help with listening for bound property changes:

- `CONTINUOUS_LAYOUT_PROPERTY`
- `DIVIDER_LOCATION_PROPERTY`
- `DIVIDER_SIZE_PROPERTY`
- `LAST_DIVIDER_LOCATION_PROPERTY`
- `ONE_TOUCH_EXPANDABLE_PROPERTY`
- `ORIENTATION_PROPERTY`
- `RESIZE_WEIGHT_PROPERTY`

One way of listening for when the user moves the divider is to watch for changes to the `lastDividerLocation` property. The example in Listing 11-2 attaches a `PropertyChangeListener` to a `JSplitPane` displaying the current divider location, the current last location, and the previous last location. The component above and below the divider is the `OvalPanel` class (discussed in


```

        // Attach listener
        splitPane.addPropertyChangeListener(propertyChangeListener);

        frame.add(splitPane, BorderLayout.CENTER);
        frame.setSize(300, 150);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

As the following sample output demonstrates, when you run the previous program, you'll notice that the `lastDividerLocation` property changes to reflect the divider's being dragged. When the user stops dragging the divider, the last setting is set to the prior setting for the `dividerLocation` property, not to the initial last value (prior current value) when the drag started. As the divider is being dragged, the current value travels first to the last value and then to the prior last value. When the dragging stops, the final last setting (29 in this case) is set to the initial last setting to reflect the current value when the dragging started. The last three sets of output reflect the changes after pressing the one-touch expandable button.

```

Current: 11
Last: -1
Prior last: 0
Current: 12
Last: 11
Prior last: -1
Current: 12
Last: 12
Prior last: 11
Current: 12
Last: 11
Prior last: 12
Current: 15
Last: 12
Prior last: 11
Current: 15
Last: 15
Prior last: 12
Current: 15
Last: 12
Prior last: 15
Current: 112
Last: 15
Prior last: 12
Current: 112
Last: 112

```

Prior last: 15
Current: 112
Last: 15
Prior last: 112


Note The BOTTOM, DIVIDER, LEFT, RIGHT, and TOP constants of the `JSplitPane` class aren't for `PropertyChangeListener` support. Instead, they're internal constraints used by the `add(Component, Object constraints)` method.

Customizing a `JSplitPane` Look and Feel

Each installable Swing look and feel provides a different `JSplitPane` appearance and set of default `UIResource` values for this component. Figure 11-9 shows the appearance of the `JSplitPane` container for the preinstalled set of look and feel types: Motif, Windows, and Ocean.



Motif



Windows



Ocean

Figure 11-9. *`JSplitPane` under the different look and feel types*

The available set of `UIResource`-related properties for a `JSplitPane` is shown in Table 11-3. For the `JSplitPane` component, there are 25 different properties, including 3 specific to the divider.

Table 11-3. *JSplitPane UIResource Elements*

Property String	Object Type
<code>SplitPane.actionMap</code>	<code>ActionMap</code>
<code>SplitPane.activeThumb</code>	<code>Color</code>
<code>SplitPane.ancestorInputMap</code>	<code>InputMap</code>
<code>SplitPane.background</code>	<code>Color</code>
<code>SplitPane.border</code>	<code>Border</code>
<code>SplitPane.centerOneTouchButtons</code>	<code>Boolean</code>
<code>SplitPane.darkShadow</code>	<code>Color</code>
<code>SplitPane.dividerFocusColor</code>	<code>Color</code>
<code>SplitPane.dividerSize</code>	<code>Integer</code>
<code>SplitPane.foreground</code>	<code>Color</code>
<code>SplitPane.highlight</code>	<code>Color</code>
<code>SplitPane.leftButtonText</code>	<code>String</code>
<code>SplitPane.oneTouchButtonOffset</code>	<code>Integer</code>
<code>SplitPane.oneTouchButtonSize</code>	<code>Integer</code>
<code>SplitPane.oneTouchButtonsOpaque</code>	<code>Boolean</code>
<code>SplitPane.oneTouchExpandable</code>	<code>Boolean</code>
<code>SplitPane.oneTouchOffset</code>	<code>Integer</code>
<code>SplitPane.rightButtonText</code>	<code>String</code>
<code>SplitPane.shadow</code>	<code>Color</code>
<code>SplitPane.size</code>	<code>Integer</code>
<code>SplitPane.supportsOneTouchButtons</code>	<code>Boolean</code>
<code>SplitPaneDivider.border</code>	<code>Border</code>
<code>SplitPaneDivider.draggingColor</code>	<code>Color</code>
<code>SplitPaneDivider.oneTouchButtonSize</code>	<code>Integer</code>
<code>SplitPaneUI</code>	<code>String</code>

JTabbedPane Class

The `JTabbedPane` class represents the ever-popular property sheet to support input or output from multiple panels within a single window in which only one panel is shown at a time. Using `JTabbedPane` is like using the `CardLayout` manager, except with added support for changing cards built in. While `CardLayout` is a `LayoutManager`, `JTabbedPane` is a full-fledged `Container`. In case you're not familiar with property sheets, tabbed dialog boxes, or tabbed panes (all alternate names for the same thing), Figure 11-10 shows a set of tabs from the original `SwingSet` demo

that comes with the JDK 1.2 version of the Swing classes. (This version is more appropriate than the current one for demonstrating the features of `JTabbedPane` described in this section.)




Figure 11-10. Sample `JTabbedPane` screen

To help the `JTabbedPane` manage which Component (tab) is selected, the model for the container is an implementation of the `SingleSelectionModel` interface or, more precisely, a `DefaultSingleSelectionModel` instance. (`SingleSelectionModel` and `DefaultSingleSelectionModel` were described with the menuing classes in Chapter 6.)

Creating a `JTabbedPane`

There are only three constructors for the `JTabbedPane`:

```
public JTabbedPane()
JTabbedPane tabbedPane = new JTabbedPane();

public JTabbedPane(int tabPlacement)
JTabbedPane tabbedPane = new JTabbedPane(JTabbedPane.RIGHT);

public JTabbedPane(int tabPlacement, int tabLayoutPolicy)
JTabbedPane tabbedPane =
    new JTabbedPane(JTabbedPane.RIGHT, JTabbedPane.SCROLL_TAB_LAYOUT);
```




Figure 11-12. *JTabbedPane with the scroll tab layout*

Adding and Removing Tabs

Once you've created the basic `JTabbedPane` container, you need to add panels that make up the sheets or pages of the `JTabbedPane`. You can add panels in either one of two basic ways.

If you're visually creating your interface with a tool like `JBuilder` or `Eclipse`, the user interface builder will use the familiar `add()` methods of `Container` to add a `Component` as a panel. The panel added uses `component.getName()` as the default title. However, you shouldn't use the various `add()` methods if you're programming by hand.

The more appropriate way to add components or panels to create tabs is with any of the `addTab()` or `insertTab()` methods listed next. Any or all of the arguments other than the component and the position index of `insertTab()` can be null. (Passing null as the `Component` argument causes a `NullPointerException` to be thrown at runtime.) The displayed icon and tooltip settings have no default values.

- `public void addTab(String title, Component component)`
- `public void addTab(String title, Icon icon, Component component)`
- `public void addTab(String title, Icon icon, Component component, String tip)`
- `public void insertTab(String title, Icon icon, Component component, String tip, int index)`

When using `addTab()`, the tab is added to the end, which is the farthest right position for a set of top or bottom tabs, or at the very bottom for tabs positioned on the left or right side, potentially reversing sides, depending on component orientation.

After creating a panel, you can change its title, icon, mnemonic, tooltip, or component on a particular tab with one of the `setXXXAt()` methods:

- `public void setTitleAt(int index, String title)`
- `public void setIconAt(int index, Icon icon)`
- `public void setMnemonicAt(int index, int mnemonic)`
- `public void setDisplayedMnemonicIndexAt(int index, int mnemonicIndex)`
- `public void setToolTipTextAt(int index, String text)`
- `public void setComponentAt(int index, Component component)`

Tip The displayed mnemonic index refers to which time a particular character in the title should be highlighted. For instance, if you wanted the second *t* in *title* to be the highlighted mnemonic, you would set the mnemonic character to `KeyEvent.VK_T`, with `setMnemonicAt()`, and the mnemonic index to be 2, with `setDisplayedMnemonicIndexAt()`.

In addition, you can change the background or foreground of a specific tab, enable or disable a specific tab, or have a different disabled icon with additional `setXXXAt()` methods:

- `public void setBackgroundAt(int index, Color background)`
- `public void setForegroundAt(int index, Color foreground)`
- `public void setEnabledAt(int index, boolean enabled)`
- `public void setDisabledIconAt(int index, Icon disabledIcon)`

To remove a tab, you can remove a specific tab with `removeTabAt(int index)`, `remove(int index)`, or `remove(Component component)`. In addition, you can remove all tabs with `removeAll()`.

JTabbedPane Properties

Table 11-4 shows the 11 properties of `JTabbedPane`. Because many of the setter/getter methods of `JTabbedPane` specify an index parameter, they aren't true properties in the literal sense.

Table 11-4. *JTabbedPane Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>changeListeners</code>	<code>ChangeListener[]</code>	Read-only
<code>model</code>	<code>SingleSelectionModel</code>	Read-write bound
<code>selectedComponent</code>	<code>Component</code>	Read-write
<code>selectedIndex</code>	<code>int</code>	Read-write
<code>tabCount</code>	<code>int</code>	Read-only
<code>tabLayoutPolicy</code>	<code>int</code>	Read-write-bound
<code>tabPlacement</code>	<code>int</code>	Read-write bound
<code>tabRunCount</code>	<code>int</code>	Read-only
<code>UI</code>	<code>TabbedPaneUI</code>	Read-write bound
<code>UIClassID</code>	<code>String</code>	Read-only

You can programmatically change the displayed tab by setting either the `selectedComponent` or the `selectedIndex` property.

The `tabRunCount` property represents the number of rows (for top or bottom tab placement) or columns (for right or left placement) necessary to display all the tabs.

Caution Changing the `LayoutManager` for the `JTabbedPane` will throw an exception when it comes time to displaying the container. In other words, don't do it.

Listening for Changing Tab Selection

If you're interested in finding out when the selected tab changes, you need to listen for changes to the selection model. This is done by your attaching a `ChangeListener` to the `JTabbedPane` (or directly to the `SingleSelectionModel`). The registered `ChangeListener` reports when the selection model changes, as the model changes when the selected panel changes.

The program shown in Listing 11-3 demonstrates listening for changes to the selected tab and displays the title of the newly selected tab.

Listing 11-3. *Listening for Selected Tab Changes*

```

import javax.swing.*;
import javax.swing.event.*;
import java.awt.*;
import java.awt.event.*;

public class TabSample {
    static Color colors[] = {Color.RED, Color.ORANGE, Color.YELLOW,
        Color.GREEN, Color.BLUE, Color.MAGENTA};
    static void add(JTabbedPane tabbedPane, String label, int mnemonic) {
        int count = tabbedPane.getTabCount();
        JButton button = new JButton(label);
        button.setBackground(colors[count]);
        tabbedPane.addTab(label, new DiamondIcon(colors[count]), button, label);
        tabbedPane.setMnemonicAt(count, mnemonic);
    }

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Tabbed Pane Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JTabbedPane tabbedPane = new JTabbedPane();
                tabbedPane.setTabLayoutPolicy(JTabbedPane.SCROLL_TAB_LAYOUT);
                String titles[] = {"General", "Security", "Content", "Connection",
                    "Programs", "Advanced"};
                int mnemonic[] = {KeyEvent.VK_G, KeyEvent.VK_S, KeyEvent.VK_C,
                    KeyEvent.VK_O, KeyEvent.VK_P, KeyEvent.VK_A};
                for (int i=0, n=titles.length; i<n; i++) {
                    add(tabbedPane, titles[i], mnemonic[i]);
                }

                ChangeListener changeListener = new ChangeListener() {
                    public void stateChanged(ChangeEvent changeEvent) {
                        JTabbedPane sourceTabbedPane = (JTabbedPane)changeEvent.getSource();
                        int index = sourceTabbedPane.getSelectedIndex();
                        System.out.println ("Tab changed to: " +
                            sourceTabbedPane.getTitleAt(index));
                    }
                };
                tabbedPane.addChangeListener(changeListener);
            }
        };
        runner.run();
    }
}

```

```

        frame.add(tabbedPane, BorderLayout.CENTER);
        frame.setSize(400, 150);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}



```

Customizing a JTabbedPane Look and Feel

Each installable Swing look and feel provides a different JTabbedPane appearance and set of default UIResource values for the JTabbedPane component. Figure 11-13 shows the appearance of the JTabbedPane container for the preinstalled set of look and feel types: Motif, Windows, and Ocean. Several items are specific to the look and feel: how the JTabbedPane appears when the set of available tabs is too wide for the display, how it responds when a user selects a tab in a back row, how it displays the tooltip, and how it displays the scroll tab layout.



Motif



Windows



Ocean



Figure 11-13. *JTabbedPane* under the different look and feel types

The available set of `UIResource`-related properties for a `JTabbedPane` is shown in Table 11-5. For the `JTabbedPane` component, there are 34 different properties.

Table 11-5. *JTabbedPane UIResource Elements*

Property String	Object Type
<code>TabbedPane.actionMap</code>	<code>ActionMap</code>
<code>TabbedPane.ancestorInputMap</code>	<code>InputMap</code>
<code>TabbedPane.background</code>	<code>Color</code>
<code>TabbedPane.borderHighlightColor</code>	<code>Color</code>
<code>TabbedPane.contentAreaColor</code>	<code>Color</code>
<code>TabbedPane.contentBorderInsets</code>	<code>Insets</code>
<code>TabbedPane.contentOpaque</code>	<code>Boolean</code>
<code>TabbedPane.darkShadow</code>	<code>Color</code>
<code>TabbedPane.focus</code>	<code>Color</code>
<code>TabbedPane.focusInputMap</code>	<code>InputMap</code>
<code>TabbedPane.font</code>	<code>Font</code>
<code>TabbedPane.foreground</code>	<code>Color</code>
<code>TabbedPane.highlight</code>	<code>Color</code>
<code>TabbedPane.light</code>	<code>Color</code>
<code>TabbedPane.opaque</code>	<code>Boolean</code>
<code>TabbedPane.selected</code>	<code>Color</code>
<code>TabbedPane.selectedForeground</code>	<code>Color</code>
<code>TabbedPane.selectedTabPadInsets</code>	<code>Insets</code>
<code>TabbedPane.selectHighlight</code>	<code>Color</code>
<code>TabbedPane.selectionFollowsFocus</code>	<code>Boolean</code>
<code>TabbedPane.shadow</code>	<code>Color</code>
<code>TabbedPane.tabAreaBackground</code>	<code>Color</code>
<code>TabbedPane.tabAreaInsets</code>	<code>Insets</code>
<code>TabbedPane.tabInsets</code>	<code>Insets</code>
<code>TabbedPane.tabRunOverlay</code>	<code>Integer</code>
<code>TabbedPane.tabsOpaque</code>	<code>Boolean</code>
<code>TabbedPane.tabsOverlapBorder</code>	<code>Boolean</code>
<code>TabbedPane.textIconGap</code>	<code>Integer</code>
<code>TabbedPane.unselectedBackground</code>	<code>Color</code>

Table 11-5. *JTabbedPane UIResource Elements (Continued)*

Property String	Object Type
TabbedPane.unselectedTabBackground	Color
TabbedPane.unselectedTabForeground	Color
TabbedPane.unselectedTabHighlight	Color
TabbedPane.unselectedTabShadow	Color
TabbedPaneUI	String

JScrollPane Class

Swing's `JScrollPane` container provides for the display of a large component within a smaller display area, with scrolling support (if necessary) to get to the parts currently invisible. Figure 11-14 shows one such implementation, in which the large component is a `JLabel` with an `ImageIcon` on it.

**Figure 11-14.** *JScrollPane example*

Identifying the component to be scrolled can be done in one of two ways. Instead of adding the component to be scrolled directly to the `JScrollPane` container, you add the component to another component, a `JViewport`, already contained within the scroll pane. Alternatively, you can identify the component at construction time, by passing it into the constructor.

```
Icon icon = new ImageIcon("dog.jpg");
JLabel label = new JLabel(icon);
JScrollPane jScrollPane = new JScrollPane();
jScrollPane.setViewportView(label);
// or
JScrollPane jScrollPane2 = new JScrollPane(label);
```

Once you've added the component into the `JScrollPane`, users can use the scrollbars to see the parts of the large component that aren't visible within the inner area of the `JScrollPane`.

In addition to giving you the means to set the scrollable component for the `JScrollPane`, a display policy determines if and when scrollbars are shown around the `JScrollPane`. Swing's `JScrollPane` maintains separate display policies for the horizontal and vertical scrollbars.

Besides enabling you to add the `JViewport` and two `JScrollBar` components for scrolling, the `JScrollPane` allows you to provide two more `JViewport` objects for row and column headers and four `Component` objects to display in the scroll pane corners. The placement of all these components is managed by the `ScrollPaneLayout` manager, introduced in Chapter 10 and described more fully here. The actual `JScrollBar` components used by `JScrollPane` are a subclass of `JScrollBar` called `JScrollPane.ScrollBar`. They are used instead of the regular `JScrollBar` to properly handle scrolling the component inside the inner `JViewport`, when that component implements the `Scrollable` interface.

To help you see how all the components fit within the `JScrollPane`, Figure 11-15 demonstrates how the `ScrollPaneLayout` positions the various pieces.

UPPER_ LEFT_ CORNER	COLUMN_HEADER	UPPER_ RIGHT_ CORNER
ROW_HEADER	VIEWPORT	HORIZONTAL_SCROLLBAR
LOWER_ LEFT_ CORNER	VERTICAL_SCROLLBAR	LOWER_ RIGHT_ CORNER

Figure 11-15. *ScrollPaneLayout regions*

Caution The `JScrollPane` component supports scrolling only lightweight components. You should not add regular, heavyweight AWT components to the container.

Creating a JScrollPane

There are four `JScrollPane` constructors:

```

public JScrollPane()
JScrollPane scrollPane = new JScrollPane();

public JScrollPane(Component view)
Icon icon = new ImageIcon("largeImage.jpg");
JLabel imageLabel = new JLabel(icon);
JScrollPane scrollPane = new JScrollPane(imageLabel);

public JScrollPane(int verticalScrollBarPolicy, int horizontalScrollBarPolicy)
JScrollPane scrollPane = new
    JScrollPane(JScrollPane.VERTICAL_SCROLLBAR_ALWAYS,
        JScrollPane.HORIZONTAL_SCROLLBAR_ALWAYS);

public JScrollPane(Component view, int verticalScrollBarPolicy,
    int horizontalScrollBarPolicy)
JScrollPane scrollPane = new JScrollPane(imageLabel,
    JScrollPane.VERTICAL_SCROLLBAR_ALWAYS,
    JScrollPane.HORIZONTAL_SCROLLBAR_ALWAYS);

```

These offer the options of preinstalling a component to scroll and configuring the scrolling policies of the individual scrollbars. By default, the scrollbars are shown only when needed. Table 11-6 shows the `JScrollPane` constants used to explicitly set the policies for each scrollbar. Using any other nonequivalent setting results in an `IllegalArgumentException` being thrown.

Table 11-6. *JScrollPane Scrollbar Policies*

Policy Type	Description
<code>VERTICAL_SCROLLBAR_AS_NEEDED</code>	Displays designated scrollbar if viewport is too small to display its entire contents
<code>HORIZONTAL_SCROLLBAR_AS_NEEDED</code>	Displays designated scrollbar if viewport is too small to display its entire contents
<code>VERTICAL_SCROLLBAR_ALWAYS</code>	Always displays designated scrollbar
<code>HORIZONTAL_SCROLLBAR_ALWAYS</code>	Always displays designated scrollbar
<code>VERTICAL_SCROLLBAR_NEVER</code>	Never displays designated scrollbar
<code>HORIZONTAL_SCROLLBAR_NEVER</code>	Never displays designated scrollbar

The next section explains how to add or change the component after creating a `JScrollPane`.

Changing the Viewport View

If you've created a `JScrollPane` with an associated component to scroll, you just need to add the `JScrollPane` to the display, and it's ready to go. If, however, you didn't associate a component at creation time, or just want to change it later, there are two ways to associate a new component to scroll. First, you can directly change the component to scroll by setting the `viewportView` property:

```
scrollPane.setViewportView(dogLabel);
```

The other way of changing the component to scroll involves centering the `JViewport` within the `JScrollPane` and changing its `view` property:

```
scrollPane.getViewport().setView(dogLabel);
```

You'll learn more about `JViewport` components in the "JViewport Class" section later in this chapter.

Scrollable Interface

Unlike the AWT components such as `List`, which automatically provide a scrollable area when the choices are too numerous to display at once, Swing components `JList`, `JTable`, `JTextComponent`, and `JTree` don't automatically provide scrolling support. You must create the component, add it to a `JScrollPane`, and then add the scroll pane to the screen.

```
JList list = new JList(...);
JScrollPane scrollPane = new JScrollPane(list);
aFrame.add(scrollPane, BorderLayout.CENTER);
```

The reason that adding a component to a `JScrollPane` works is that each of the Swing components that might be too large for the screen (and require scrolling support) implements the `Scrollable` interface. With this interface implemented, when you move the scrollbars associated with the `JScrollPane`, the `JScrollPane` asks the `Scrollable` component within the container for its sizing information to properly position the component based on the current scrollbar positions.

The only time you need to worry about the `Scrollable` interface is when you're creating a new custom component that requires scrolling support. The following is the `Scrollable` interface definition.

```
public interface Scrollable {
    public Dimension getPreferredScrollableViewportSize();
    public boolean getScrollableTracksViewportHeight();
    public boolean getScrollableTracksViewportWidth();
    public int getScrollableBlockIncrement(Rectangle visibleRect, int orientation,
        int direction);
    public int getScrollableUnitIncrement(Rectangle visibleRect, int orientation,
        int direction);
}
```

If you create a custom `Scrollable` component and then place that component in a `JScrollPane`, it will respond appropriately when the scrollbars for the `JScrollPane` or the mouse wheel are moved.

JScrollPane Properties

Table 11-7 shows the 19 properties of `JScrollPane`.

Table 11-7. *JScrollPane Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>columnHeader*</code>	<code>JViewport</code>	Read-write bound
<code>columnHeaderView</code>	<code>Component</code>	Write-only
<code>componentOrientation</code>	<code>ComponentOrientation</code>	Write-only bound
<code>horizontalScrollBar*</code>	<code>JScrollBar</code>	Read-write bound
<code>horizontalScrollBarPolicy*</code>	<code>int</code>	Read-write bound
<code>layout</code>	<code>LayoutManager</code>	Write-only
<code>rowHeader*</code>	<code>JViewport</code>	Read-write bound
<code>rowHeaderView</code>	<code>Component</code>	Write-only
<code>UI</code>	<code>ScrollPaneUI</code>	Read-write bound
<code>UIClassID</code>	<code>String</code>	Read-only
<code>validateRoot</code>	<code>boolean</code>	Read-only
<code>verticalScrollBar*</code>	<code>JScrollBar</code>	Read-write bound
<code>verticalScrollBarPolicy*</code>	<code>int</code>	Read-write bound
<code>viewport*</code>	<code>JViewport</code>	Read-write bound
<code>viewportBorder</code>	<code>Border</code>	Read-write bound
<code>viewportBorderBounds</code>	<code>Rectangle</code>	Read-only
<code>viewportView</code>	<code>Component</code>	Write-only
<code>wheelScrollingEnabled</code>	<code>boolean</code>	Read-write bound

* These properties directly map to properties of the `ScrollPaneLayout` manager used by the `JScrollPane`. Changing one of these properties for a `JScrollPane` causes its layout manager to change accordingly.

Caution An attempt to change the layout property of `JScrollPane` to something other than a `ScrollPaneLayout` instance or `null` will throw a `ClassCastException` at runtime, because the layout manager used by a `JScrollPane` must be a `ScrollPaneLayout`.

Working with ScrollPaneLayout

The `JScrollPane` relies on the `ScrollPaneLayout` manager for the positioning of components within the container. Whereas most layout managers are designed to lay out any type of component, all but four regions of `ScrollPaneLayout` accept a component of a specific type. Table 11-8 shows the type of component that can go into each of the regions shown in Figure 11-15.

Table 11-8. *ScrollPaneLayout Locations*

Location	Data Type	Description
COLUMN_HEADER	JViewport	Usually empty. If main content is a table, serves as column headers that won't scroll as vertical scrollbar is moved.
HORIZONTAL_SCROLLBAR	JScrollBar	A scrollbar for the main content region placed below that region.
LOWER_LEFT_CORNER	Component	Usually empty. For a graphic in the lower-left corner.
LOWER_RIGHT_CORNER	Component	Usually empty. For a graphic in the lower-right corner.
ROW_HEADER	JViewport	Usually empty. If main content is a table, serves as row labels that won't scroll when horizontal scrollbar is moved.
UPPER_LEFT_CORNER	Component	Usually empty. For a graphic in the upper-left corner.
UPPER_RIGHT_CORNER	Component	Usually empty. For a graphic in the upper-right corner.
VERTICAL_SCROLLBAR	JScrollBar	A scrollbar for the main content region, placed to the right of the content area.
VIEWPORT	JViewport	The main content area.

Note The corners have two sets of constants. For internationalization support, you can use `LOWER_LEADING_CORNER`, `LOWER_TRAILING_CORNER`, `UPPER_LEADING_CORNER`, and `UPPER_TRAILING_CORNER`, which deal with component orientation for you. For left-to-right component orientation (United States locale), leading is left, and trailing is right.

As designed, the layout manager describes the screen layout necessary to support a main content area (`VIEWPORT`) that's too large for the available space. Scrollbars for navigating through the area can be placed to the right of the content area (`VERTICAL_SCROLLBAR`) or below it (`HORIZONTAL_SCROLLBAR`). Fixed headers that don't scroll can be placed above the content area (`COLUMN_HEADER`) or to its left (`ROW_HEADER`). The four corners (`*_CORNER`) are configurable to display any type of component, which are typically labels with images on them; however, any component can be placed there.

Note Some developers think of `ScrollPaneLayout` as a `GridBagLayout` with customized constraints (and restricted contents). Under normal circumstances, most developers won't use `ScrollPaneLayout` outside a `JScrollPane`.

Working with JScrollPane Headers and Corners

As Figure 11-15 and Table 11-8 demonstrate, many different regions exist within the `JScrollPane`. Normally, you work with only the central view, and let the two scrollbars do their thing. In addition, when working with the `JTable` component (described in Chapter 18), the table automatically places the column labels within the column header region when placed within a `JScrollPane`.

You can also manually add or change the column header or row header for a `JScrollPane`. Although you can completely replace the `JViewport` in these areas, it's easier to just set the `columnHeaderView` or `rowHeaderView` property to the `Component` for the area. This action will place the component within a `JViewport` for you.

To place a component in one of the corners of the `JScrollPane`, you need to call the `setCorner(String key, Component corner)` method, where `key` is one of the following constants from `JScrollPane`: `LOWER_LEFT_CORNER`, `LOWER_RIGHT_CORNER`, `UPPER_LEFT_CORNER`, or `UPPER_RIGHT_CORNER`.

Working with corners can be tricky. A corner component is displayed only if the two components at a right angle from the corner are currently shown. For instance, suppose you place a company logo within a label in the lower-right corner, and the scrollbar policy for both scrollbars is to show only when necessary. In that case, if one scrollbar were not needed, the logo in the corner wouldn't be shown. As another example, if a `JScrollPane` had a column header showing but didn't have a row header, any component in the upper-left corner would not be shown.

Therefore, just because you've set a corner to a component (as with `scrollPane.setCorner(JScrollPane.UPPER_LEFT_CORNER, logoLabel)`), don't expect it to be always or automatically shown. Moreover, as Figure 11-16 shows, the neighboring areas control the size of the corner. Don't assume a corner component can be as large as necessary. That's because its minimum, preferred, and maximum sizes are completely ignored. In Figure 11-16, the actual image used to create the corner component is larger than the space used.



Figure 11-16. A `JScrollPane` with a corner component and row and column headers

Note Changing a corner of a `JScrollPane` acts like a bound property where the property name is one of the corner keys shown in Table 11-8.

Resetting the Viewport Position

At times, you may want to move the contents of the inner view to the upper-left corner of the `JScrollPane`. This change may be needed because the view changed, or because some event happened that requires the viewport component to return to the origin of the `JScrollPane`. The simplest way of moving the view is to adjust the position of the scrollbar thumbs of the `JScrollPane`. Setting each scrollbar to its minimum value effectively moves the view of the component to the component's upper-left corner. The `ActionListener` shown in Listing 11-4 can be associated with a button on the screen or in the corner of the `JScrollPane`, causing the contents of the `JScrollPane` to return to their origin.

Listing 11-4. Action to Move JScrollPane to Top

```
import java.awt.event.*;
import javax.swing.*;

public class JScrollPaneToTopAction implements ActionListener {
    JScrollPane scrollPane;

    public JScrollPaneToTopAction(JScrollPane scrollPane) {
        if (scrollPane == null) {
            throw new IllegalArgumentException(
                "JScrollPaneToTopAction: null JScrollPane");
        }
        this.scrollPane = scrollPane;
    }

    public void actionPerformed(ActionEvent actionEvent) {
        JScrollBar verticalScrollBar = scrollPane.getVerticalScrollBar();
        JScrollBar horizontalScrollBar = scrollPane.getHorizontalScrollBar();
        verticalScrollBar.setValue(verticalScrollBar.getMinimum());
        horizontalScrollBar.setValue(horizontalScrollBar.getMinimum());
    }
}
```

Customizing a JScrollPane Look and Feel

Each installable Swing look and feel provides a different `JScrollPane` appearance and set of default `UIResource` values for the component. Figure 11-17 shows the appearance of the `JScrollPane` component for the preinstalled set of look and feel types. With a `JScrollPane`, the primary differences between the look and feel types are related to the scrollbar's appearance and border around the viewport.

The available set of `UIResource`-related properties for a `JScrollPane` is shown in Table 11-9. For the `JScrollPane` component, there are ten different properties. Changing the properties related to the `JScrollBar` will also affect appearance when a scrollbar in a `JScrollPane` is visible.



Motif



Windows



Ocean

Figure 11-17. *JScrollPane under the different look and feel types***Table 11-9.** *JScrollPane UIResource Elements*

Property String	Object Type
<code>ScrollPane.actionMap</code>	ActionMap
<code>ScrollPane.ancestorInputMap</code>	InputMap
<code>ScrollPane.ancestorInputMap.RightToLeft</code>	InputMap
<code>ScrollPane.background</code>	Color
<code>ScrollPane.border</code>	Border
<code>ScrollPane.font</code>	Font
<code>ScrollPane.foreground</code>	Color
<code>ScrollPane.viewportBorder</code>	Border
<code>ScrollPane.viewportBorderInsets</code>	Insets
<code>ScrollPaneUI</code>	String

JViewport Class

The JViewport component is rarely used on its own outside a JScrollPane. It normally lives within the center of a JScrollPane and uses the ViewportLayout manager to respond to positioning requests to display a part of a large Component within a smaller space. In addition to residing in the center of a JScrollPane, JViewport is also used for the row and column headers of a JScrollPane.

Creating a JViewport

There’s only one constructor for creating a JViewport: the no-argument version: `public JViewport()`. Once you’ve created the JViewport, you place a component within it by using `setView(Component)`.

JViewport Properties

Table 11-10 shows the 13 properties of JViewport. Setting the layout manager to something other than ViewportLayout is possible but not recommended because the layout manager makes the JViewport do its work properly.

Table 11-10. *JViewport Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>border</code>	<code>Border</code>	Write-only
<code>changeListeners</code>	<code>ChangeListener[]</code>	Read-only
<code>extentSize</code>	<code>Dimension</code>	Read-write
<code>insets</code>	<code>Insets</code>	Read-only
<code>optimizedDrawingEnabled</code>	<code>boolean</code>	Read-only
<code>scrollMode</code>	<code>int</code>	Read-write
<code>UI</code>	<code>ViewportUI</code>	Read-write bound
<code>UIClassID</code>	<code>String</code>	Read-only
<code>view</code>	<code>Component</code>	Read-write
<code>viewPosition</code>	<code>Point</code>	Read-write
<code>viewRect</code>	<code>Rectangle</code>	Read-only
<code>viewSize</code>	<code>Dimension</code>	Read-write

Because of scrolling complexity and for performance reasons, the JViewport doesn’t support a border. Trying to change the border to a non-null value with `setBorder(Border)` throws an

`IllegalArgumentException`. Because there can't be a border, the `insets` property setting is always (0, 0, 0, 0). Instead of displaying a border around the `JViewport`, you can display a border around the component within the view. Simply place a border around the component, or place the component inside a `JPanel` with a border before adding it to the `JViewport`. If you do place a border around the component, the border would be seen only if that part of the component is visible. If you don't want the border to scroll, you must place the `JViewport` within a component such as a `JScrollPane` that has its own border.

Tip To set the background color of what appears in the `JScrollPane`, you need to set the background color of the viewport: `aScrollPane.getViewport().setBackground(newColor)`.

The size of the view (`viewSize` property) is based on the size of the component (`view` property) within the `JViewport`. The view position (`viewPosition` property) is the upper-left corner of the view rectangle (`viewRect` property), where the rectangle's size is the extent size (`extentSize` property) of the viewport. If that's confusing, Figure 11-18 should help you see where all these properties lie within the `JViewport`.




Figure 11-18. Visualizing `JViewport` properties

The `scrollMode` property can be set to one of the class constants shown in Table 11-11. In most cases, you can rely on the fastest and default `BLIT_SCROLL_MODE` mode.

Table 11-11. *JViewport Scroll Modes*

Scroll Mode	Description
<code>BACKINGSTORE_SCROLL_MODE</code>	A deprecated but supported mode that relies on a buffer for scrolling
<code>BLIT_SCROLL_MODE</code>	The default mode, which relies on <code>Graphics.copyArea()</code>
<code>SIMPLE_SCROLL_MODE</code>	Redraws entire area

To move the visible part of the view around, just change the `viewPosition` property. This moves the `viewRect`, allowing you to see a different part of the view. To demonstrate this, the program shown in Listing 11-5 attaches keyboard accelerators to the `JViewport` so that you can use the arrow keys to move around the view. (Normally, the `JScrollPane` would get these keyboard actions.) The majority of the code is necessary to set up the appropriate input/action maps. The boldfaced line of code is the one necessary to move the view.

Listing 11-5. *Keyboard Movement Control in a JViewport*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class MoveViewSample {

    public static final int INCREASE = 0; // direction
    public static final int DECREASE = 1; // direction
    public static final int X_AXIS   = 0; // axis
    public static final int Y_AXIS   = 1; // axis
    public static final int UNIT     = 0; // type
    public static final int BLOCK    = 1; // type

    static class MoveAction extends AbstractAction {
        JViewport viewport;
        int direction;
        int axis;
        int type;
        public MoveAction(JViewport viewport, int direction, int axis, int type) {
            if (viewport == null) {
                throw new IllegalArgumentException ("null viewport not permitted");
            }
        }
    }
}
```

```

        this.viewport = viewport;
        this.direction = direction;
        this.axis = axis;
        this.type = type;
    }
    public void actionPerformed(ActionEvent actionEvent) {
        Dimension extentSize = viewport.getExtentSize();
        int horizontalMoveSize = 0;
        int verticalMoveSize = 0;
        if (axis == X_AXIS) {
            if (type == UNIT) {
                horizontalMoveSize = 1;
            } else { // type == BLOCK
                horizontalMoveSize = extentSize.width;
            }
        } else { // axis == Y_AXIS
            if (type == UNIT) {
                verticalMoveSize = 1;
            } else { // type == BLOCK
                verticalMoveSize = extentSize.height;
            }
        }
        if (direction == DECREASE) {
            horizontalMoveSize = -horizontalMoveSize;
            verticalMoveSize = -verticalMoveSize;
        }
        // Translate origin by some amount
        Point origin = viewport.getViewPosition();
        origin.x += horizontalMoveSize;
        origin.y += verticalMoveSize;
        // Set new viewing origin
        viewport.setViewPosition(origin);
    }
}

public static void main(String args[]) {
    Runnable runner = new Runnable() {
        public void run() {
            JFrame frame = new JFrame("JViewport Sample");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
            Icon icon = new ImageIcon("dog.jpg");
            JLabel dogLabel = new JLabel(icon);
            JViewport viewport = new JViewport();
            viewport.setView(dogLabel);
        }
    };
    new Thread(runner).start();
}

```

```

InputMap inputMap = viewport.getInputMap(JComponent.WHEN_IN_FOCUSED_WINDOW);
ActionMap actionMap = viewport.getActionMap();

// Up key moves view up unit
Action upKeyAction =
    new MoveAction(viewport, DECREASE, Y_AXIS, UNIT);
KeyStroke upKey = KeyStroke.getKeyStroke("UP");
inputMap.put(upKey, "up");
actionMap.put("up", upKeyAction);

// Down key moves view down unit
Action downKeyAction =
    new MoveAction(viewport, INCREASE, Y_AXIS, UNIT);
KeyStroke downKey = KeyStroke.getKeyStroke("DOWN");
inputMap.put(downKey, "down");
actionMap.put("down", downKeyAction);

// Left key moves view left unit
Action leftKeyAction =
    new MoveAction(viewport, DECREASE, X_AXIS, UNIT);
KeyStroke leftKey = KeyStroke.getKeyStroke("LEFT");
inputMap.put(leftKey, "left");
actionMap.put("left", leftKeyAction);

// Right key moves view right unit
Action rightKeyAction =
    new MoveAction(viewport, INCREASE, X_AXIS, UNIT);
KeyStroke rightKey = KeyStroke.getKeyStroke("RIGHT");
inputMap.put(rightKey, "right");
actionMap.put("right", rightKeyAction);

// PgUp key moves view up block
Action pgUpKeyAction =
    new MoveAction(viewport, DECREASE, Y_AXIS, BLOCK);
KeyStroke pgUpKey = KeyStroke.getKeyStroke("PAGE_UP");
inputMap.put(pgUpKey, "pgUp");
actionMap.put("pgUp", pgUpKeyAction);

// PgDn key moves view down block
Action pgDnKeyAction =
    new MoveAction(viewport, INCREASE, Y_AXIS, BLOCK);
KeyStroke pgDnKey = KeyStroke.getKeyStroke("PAGE_DOWN");
inputMap.put(pgDnKey, "pgDn");
actionMap.put("pgDn", pgDnKeyAction);

```

```

// Shift-PgUp key moves view left block
Action shiftPgUpKeyAction =
    new MoveAction(viewport, DECREASE, X_AXIS, BLOCK);
KeyStroke shiftPgUpKey = KeyStroke.getKeyStroke("shift PAGE_UP");
inputMap.put(shiftPgUpKey, "shiftPgUp");
actionMap.put("shiftPgUp", shiftPgUpKeyAction);

// Shift-PgDn key moves view right block
Action shiftPgDnKeyAction =
    new MoveAction(viewport, INCREASE, X_AXIS, BLOCK);
KeyStroke shiftPgDnKey = KeyStroke.getKeyStroke("shift PAGE_DOWN");
inputMap.put(shiftPgDnKey, "shiftPgDn");
actionMap.put("shiftPgDn", shiftPgDnKeyAction);

frame.add(viewport, BorderLayout.CENTER);
frame.setSize(300, 200);
frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Customizing a JViewport Look and Feel

Each installable Swing look and feel shares the same JViewport appearance with the BasicViewportUI. There are no actual appearance differences. However, there still exists a set of UIResource-related properties for the JViewport, as shown in Table 11-12. For the JViewport component, there are four such properties.

Table 11-12. *JViewport UIResource Elements*

Property String	Object Type
Viewport.background	Color
Viewport.font	Font
Viewport.foreground	Color
ViewportUI	String

Summary

In this chapter, you explored several high-level Swing containers. With the Box class, you can more easily utilize the BoxLayout manager to create a single row or column of components, honoring the minimum, preferred, and maximum size of the components the best way possible.

With the `JSplitPane` component, you can create a row or column consisting of two components with a divider in between them to allow an end user to alter the components' sizes manually by moving the divider.

The `JTabbedPane` container displays only one component from a set of contained components at a time. The displayed component is picked by the user selecting a tab, which can contain a title with or without mnemonic, an icon, and a tooltip. This is the popular property sheet metaphor commonly seen within applications.

The `JScrollPane` and `JViewport` containers allow you to display a large component within a small area. The `JScrollPane` adds scrollbars to enable an end user to move the visible part around, whereas the `JViewport` doesn't add these scrollbars.

In Chapter 12, we'll once again examine the individual components within the Swing library, including the `JProgressBar`, `JScrollBar`, and `JSlider` that share the `BoundedRangeModel` as their data model.



Bounded Range Components

In the previous chapter, you saw how `JScrollPane` provides a scrollable region for those situations when there isn't sufficient space to display an entire component on screen. Swing also offers several components that support some type of scrolling or the display of a bounded range of values. The available components are `JScrollBar`, `JSlider`, `JProgressBar`, and, in a more limited sense, `JTextField`. These components share a `BoundedRangeModel` as their data model. The default implementation of this data model provided with the Swing classes is the `DefaultBoundedRangeModel` class.

In this chapter, you'll look at the similarities and differences between these Swing components. Let's start with their shared data model, the `BoundedRangeModel`.

BoundedRangeModel Interface

The `BoundedRangeModel` interface is the Model-View-Controller (MVC) data model shared by the components described in this chapter. The interface contains four interrelated properties that are necessary to describe a range of values: minimum, maximum, value, and extent.

The minimum and maximum properties define the limits of the value of the model. The value property defines what you might think of as the current setting of the model, where the maximum setting of the value property is not necessarily the value of the maximum property of the model. Instead, the maximum setting that the value property can take is the maximum property less the extent property. To help you visualize these properties, Figure 12-1 shows these settings in relation to a `JScrollBar`. Any other purpose of the extent property depends on the component acting as the model's view.




Figure 12-1. *BoundedRange* properties on a `JScrollBar`

The settings for the four properties must abide by the following ordering:

```
minimum <= value <= value+extent <= maximum
```

When one of the settings changes, the change may trigger changes to other settings to keep the ordering valid. For instance, changing the minimum to a setting between the current value plus extent setting and the maximum will decrease the extent and increase the value to keep the ordering valid. In addition, the original property change may result in a change to a new setting other than the requested setting. For instance, attempting to set the value below the minimum or maximum will set the value to the nearest limit of the range.

The `BoundedRangeModel` interface definition follows:

```
public interface BoundedRangeModel {
    // Properties
    public int getExtent();
    public void setExtent(int newValue);
    public int getMaximum();
    public void setMaximum(int newValue);
    public int getMinimum();
    public void setMinimum(int newValue);
    public int getValue();
    public void setValue(int newValue);
    public boolean getValueIsAdjusting();
    public void setValueIsAdjusting(boolean newValue);
    // Listeners
    public void addChangeListener(ChangeListener listener);
    public void removeChangeListener(ChangeListener listener);
    // Other Methods
    public void setRangeProperties(int value, int extent, int minimum,
        int maximum, boolean adjusting);
}
```

Although the different settings available for the model are JavaBean properties, when a property setting changes, the interface uses Swing's `ChangeListener` approach instead of a `java.beans.PropertyChangeListener`.

The model's `valueIsAdjusting` property comes into play when the user is performing a series of rapid changes to the model, probably as a result of dragging the slider on the screen. For someone interested in knowing only when the final value is set for a model, a listener would ignore any changes until `getValueIsAdjusting()` returns false.

DefaultBoundedRangeModel Class

The Swing class actually implementing the `BoundedRangeModel` interface is `DefaultBoundedRangeModel`. This class takes care of the adjustments necessary to ensure the appropriate ordering of the different property values. It also manages a `ChangeListener` list to notify listeners when a model change happens.

DefaultBoundedRangeModel has two constructors:

```
public DefaultBoundedRangeModel()
```

```
public DefaultBoundedRangeModel(int value, int extent, int minimum, int maximum)
```

The no-argument version sets up the minimum, value, and extent properties of the model to have a setting of 0. The remaining maximum property gets a setting of 100.

The second constructor version takes four integer parameters, explicitly setting four properties. For both constructors, the initial value of the `valueIsAdjusting` property is false because the value of the model isn't yet changing beyond the initial value.

Note Unless you're sharing a model across multiple components, it generally isn't necessary to create a `BoundedRangeModel`. Even if you're sharing a model across multiple components, you can create just the first component and get its `BoundedRangeModel` model to share.

As with practically all of the classes that manage their own listener lists, you can ask `DefaultBoundedRangeModel` for the listeners assigned to it. Here, you ask the model for its `ChangeListener` list with `getListeners(ClassListener.class)`. This returns an array of `EventListener` objects.

JScrollBar Class

The simplest of the bounded range components is the `JScrollBar`. The `JScrollBar` component is used within the `JScrollPane` container, described in Chapter 11, to control the scrollable region. You can also use this component within your own containers, although with the flexibility of `JScrollPane` this typically isn't necessary. The one point to remember about `JScrollBar`, however, is that it isn't used for the entry of a value, but solely for the scrolling of a region of screen real estate. For the entry of a value, you use the `JSlider` component discussed in the next section.

Note The `JScrollBar` within a `JScrollPane` is actually a specialized subclass of `JScrollBar` that properly deals with scrollable components that implement the `Scrollable` interface. Although you can change the scrollbars of a `JScrollPane`, it's usually unnecessary—and more work than you might think.

As Figure 12-2 shows, the horizontal `JScrollBar` is composed of several parts. Starting from the middle and working outward, you find the scrollbar's *thumb*—also called a *knob* or *slider*. The width of the thumb is the `extent` property from the `BoundedRangeModel`. The current value of the scrollbar is at the left edge of the thumb. To the immediate left and right of the thumb are the block paging areas. Clicking to the left of the thumb will decrement the scrollbar's value, while clicking to the right increments it. The increased or decreased amount of the scrollbar's value is the scrollbar's `blockIncrement` property.




Figure 12-2. *Horizontal JScrollBar anatomy*

On the left and right edges of the scrollbar are arrow buttons. When the left arrow is pressed, the scrollbar decrements down a unit. The scrollbar's `unitIncrement` property specifies this unit. Typically, this value is one, though it doesn't have to be. To the immediate right of the left arrow is the minimum value of the scrollbar and the model. In addition to decreasing the value with the left arrow, clicking the right arrow causes the scrollbar to increment a unit. To the immediate left of the right arrow is the scrollbar's maximum range. The maximum value is actually a little farther to the left, where this "little farther" is specified by the model's `extent` property. When the thumb is next to the right arrow, this places the scrollbar value of the scrollbar at the left edge of the thumb, which is the case with all other positions, no matter where the thumb is.

A vertical `JScrollBar` is composed of the same parts as a horizontal `JScrollBar`, with the minimum and decrement parts at the top, and the value designated by the top edge of the scrollbar's thumb. The maximum and increment parts are at the bottom.

As previously mentioned, the model for the `JScrollBar` is the `BoundedRangeModel`. The delegate for the user interface is the `ScrollbarUI`.

Now that you've seen the different pieces of a `JScrollBar`, let's see how to use them.

Creating JScrollBar Components

There are three constructors for `JScrollBar`:

```
public JScrollBar()
JScrollBar aJScrollBar = new JScrollBar();

public JScrollBar(int orientation)
// Vertical
JScrollBar aJScrollBar = new JScrollBar(JScrollBar.VERTICAL);
// Horizontal
JScrollBar bJScrollBar = new JScrollBar(JScrollBar.HORIZONTAL);

public JScrollBar(int orientation, int value, int extent, int minimum, int maximum)
// Horizontal, initial value 500, range 0-1000, and extent of 25
JScrollBar aJScrollBar = new JScrollBar(JScrollBar.HORIZONTAL, 500, 25, 0, 1025);
```

Creating a `JScrollBar` with no arguments creates a vertical scrollbar with a default data model. The model has an initial value of 0, a minimum of 0, a maximum of 100, and an extent

of 10. This default model offers a range of only 0 through 90. You can also explicitly set the orientation to `JScrollBar.HORIZONTAL` or `JScrollBar.VERTICAL`. If you don't like the initial model settings provided by the other two constructors, you need to explicitly set everything yourself. If the data elements aren't properly constrained, as described in the previous section about `BoundedRangeModel`, an `IllegalArgumentException` will be thrown, causing the `JScrollBar` construction to be aborted.

Surprisingly missing from the list of constructors is one that accepts a `BoundedRangeModel` argument. If you have a model instance, you can either call `setModel(BoundedRangeModel newModel)` after creating the scrollbar or get the individual properties from the model when creating the scrollbar, as follows:

```
JScrollBar aJScrollBar =
    new JScrollBar (JScrollBar.HORIZONTAL, aModel.getValue(), aModel.getExtent(),
        aModel.getMinimum(), aModel.getMaximum())
```

Tip Starting with the 1.3 release of the J2SE platform, scrollbars do not participate in focus traversal.

Handling Scrolling Events

Once you've created your `JScrollBar`, it's necessary to listen for changes if you're interested in when the value changes. There are two ways of listening: the AWT 1.1 event model way and the Swing MVC way. The AWT way involves attaching an `AdjustmentListener` to the `JScrollBar`. The MVC way involves attaching a `ChangeListener` to the data model. Each works equally well, and both are notified if the model changes programmatically or by the user dragging the scrollbar thumb. The latter offers more flexibility and is a good choice, unless you're sharing a data model across components and need to know which component altered the model.

Listening to Scrolling Events with an `AdjustmentListener`

Attaching an `AdjustmentListener` to a `JScrollBar` allows you to listen for the user to change the setting of the scrollbar. The following code fragments, used for the example shown later in Figure 12-3, show how to attach an `AdjustmentListener` to a `JScrollBar` to listen for the user adjusting the value of the `JScrollBar`.

First, define the appropriate `AdjustmentListener` that simply prints out the current value of the scrollbar:

```
AdjustmentListener adjustmentListener = new AdjustmentListener() {
    public void adjustmentValueChanged (AdjustmentEvent adjustmentEvent) {
        System.out.println ("Adjusted: " + adjustmentEvent.getValue());
    }
};
```

After you've created the listener, you can create the component and attach the listener:

```
JScrollBar oneJScrollBar = new JScrollBar (JScrollBar.HORIZONTAL);
oneJScrollBar.addAdjustmentListener(adjustmentListener);
```

This manner of listening for adjustment events works perfectly well. However, you may prefer to attach a `ChangeListener` to the data model, as described next.

Listening to Scrolling Events with a `ChangeListener`

Attaching a `ChangeListener` to a `JScrollBar` data model provides more flexibility in your program designs. With an `AWT AdjustmentListener`, listeners are notified only when the value of the scrollbar changes. On the other hand, an attached `ChangeListener` is notified when there's any change in the minimum value, maximum value, current value, or extent. In addition, because the model has a `valueIsAdjusting` property, you can choose to ignore intermediate change events—something you can also do with an `AdjustmentListener`, via the property of the same name in the `AdjustmentEvent`.

To demonstrate, define a `ChangeListener` that prints out the current value of the scrollbar when the model has finished adjusting, as shown in Listing 12-1. You'll enhance this `BoundedChangeListener` class throughout the chapter.

Listing 12-1. *ChangeListener for BoundedRangeModel*

```
import javax.swing.*;
import javax.swing.event.*;

public class BoundedChangeListener implements ChangeListener {
    public void stateChanged(ChangeEvent changeEvent) {
        Object source = changeEvent.getSource();
        if (source instanceof BoundedRangeModel) {
            BoundedRangeModel aModel = (BoundedRangeModel)source;
            if (!aModel.getValueIsAdjusting()) {
                System.out.println ("Changed: " + aModel.getValue());
            }
        } else {
            System.out.println ("Something changed: " + source);
        }
    }
}
```

Once you create the listener, you can create the component and attach the listener. In this particular case, you need to attach the listener to the data model of the component, instead of directly to the component.

```
ChangeListener changeListener = new BoundedChangeListener();
JScrollBar anotherJScrollBar = new JScrollBar (JScrollBar.HORIZONTAL);
BoundedRangeModel model = anotherJScrollBar.getModel();
model.addChangeListener(changeListener);
```

The source for the testing program is shown in Listing 12-2.

Listing 12-2. *JScrollBar Usage Sample*

```

import javax.swing.*;
import javax.swing.event.*;
import java.awt.*;
import java.awt.event.*;

public class ScrollBarSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                AdjustmentListener adjustmentListener = new AdjustmentListener() {
                    public void adjustmentValueChanged(AdjustmentEvent adjustmentEvent) {
                        System.out.println("Adjusted: " + adjustmentEvent.getValue());
                    }
                };
                JScrollBar oneJScrollBar = new JScrollBar(JScrollBar.HORIZONTAL);
                oneJScrollBar.addAdjustmentListener(adjustmentListener);

                ChangeListener changeListener = new BoundedChangeListener();
                JScrollBar anotherJScrollBar = new JScrollBar(JScrollBar.HORIZONTAL);
                BoundedRangeModel model = anotherJScrollBar.getModel();
                model.addChangeListener(changeListener);

                JFrame frame = new JFrame("ScrollBars R Us");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                frame.add(oneJScrollBar, BorderLayout.NORTH);
                frame.add(anotherJScrollBar, BorderLayout.SOUTH);
                frame.setSize(300, 200);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

When you run this program, it shows the two horizontal scrollbars seen in Figure 12-3. The output of moving the scrollbars is sent to the console window.




Figure 12-3. *Dual JScrollBar listening*

JScrollBar Properties

After you’ve created a `JScrollBar`, it may become necessary to modify its underlying data model. You can get the model with the public `BoundedRangeModel getModel()` method, and then modify the model directly. More likely, you would just call the appropriate methods of the component:

- `setValue(int newValue), setExtent(int newValue), setMinimum(int newValue)`
- `setMaximum(int newValue)`

These methods act as proxies and redirect any calls to the equivalent model method.

Caution Although supported, it’s not recommended that you modify a `JScrollBar`’s orientation after displaying the component. This could seriously diminish the user’s satisfaction and encourage the user to find a solution from another vendor!

In addition to the data model properties, Table 12-1 shows the 16 properties of `JScrollBar`.

Table 12-1. *JScrollBar Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>adjustmentListeners</code>	<code>AdjustmentListener[]</code>	Read-only
<code>blockIncrement</code>	<code>int</code>	Read-write bound
<code>enabled</code>	<code>boolean</code>	Write-only
<code>maximum</code>	<code>int</code>	Read-write
<code>maximumSize</code>	<code>Dimension</code>	Read-only
<code>minimum</code>	<code>int</code>	Read-write
<code>minimumSize</code>	<code>Dimension</code>	Read-only
<code>model</code>	<code>BoundedRangeModel</code>	Read-write bound
<code>orientation</code>	<code>int</code>	Read-write bound
<code>UI</code>	<code>ScrollBarUI</code>	Read-write bound
<code>UIClassID</code>	<code>String</code>	Read-only
<code>unitIncrement</code>	<code>int</code>	Read-write bound
<code>value</code>	<code>int</code>	Read-write bound
<code>valueIsAdjusting</code>	<code>boolean</code>	Read-write bound
<code>visibleAmount</code>	<code>int</code>	Read-write

Customizing a JScrollBar Look and Feel

Each installable Swing look and feel provides a different JScrollBar appearance and set of default UIResource values. Figure 12-4 shows the appearance of the JScrollBar component for the preinstalled set of look and feel types: Motif, Windows, and Ocean.



Figure 12-4. *JScrollBar under different look and feel types*

The available set of UIResource-related properties for a JScrollBar is shown in Table 12-2. There are 28 different properties.

Table 12-2. *JScrollBar UIResource Elements*

Property String	Object Type
scrollbar	Color
ScrollBar.actionMap	ActionMap
ScrollBar.allowsAbsolutePositioning	Boolean
ScrollBar.ancestorInputMap	InputMap
ScrollBar.ancestorInputMap.RightToLeft	InputMap
ScrollBar.background	Color
ScrollBar.border	Border
ScrollBar.darkShadow	Color
ScrollBar.focusInputMap	Object[]
ScrollBar.focusInputMap.RightToLeft	InputMap
ScrollBar.foreground	Color
ScrollBar.gradient	List
ScrollBar.highlight	Color
ScrollBar.maximumThumbSize	Dimension
ScrollBar.minimumThumbSize	Dimension
ScrollBar.shadow	Color
ScrollBar.squareButtons	Boolean
ScrollBar.thumb	Color
ScrollBar.thumbDarkShadow	Color
ScrollBar.thumbHeight	Integer
ScrollBar.thumbHighlight	Color

Table 12-2. *JScrollBar UIResource Elements (Continued)*

Property String	Object Type
ScrollBar.thumbShadow	Color
ScrollBar.track	Color
ScrollBar.trackForeground	Color
ScrollBar.trackHighlight	Color
ScrollBar.trackHighlightForeground	Color
ScrollBar.width	Integer
ScrollBarUI	String

JSlider Class

Although the `JScrollBar` component is useful for scrolling regions of the screen, it's *not* a good component for getting user input for a range of values. For that purpose, Swing offers the `JSlider` component. In addition to a draggable thumb like the one provided by the `JScrollBar` component, the `JSlider` component offers visible tick marks and labels to assist in showing the current setting and selecting a new one. Figure 12-5 shows several sample `JSlider` components.




Figure 12-5. *Sample JSlider components*

The `JSlider` is made up of several pieces. The familiar `BoundedRangeModel` stores the data model for the component, and a `Dictionary` stores any labels for the tick marks. The user interface delegate is the `SliderUI`.

Now that you’ve seen the different pieces of a `JSlider`, let’s find out how to use them.

Creating JSlider Components

There are six different constructors for `JSlider`:

```

public JSlider()
JSlider aJSlider = new JSlider();

public JSlider(int orientation)
// Vertical
JSlider aJSlider = new JSlider(JSlider.VERTICAL);
// Horizontal
JSlider bJSlider = new JSlider(JSlider.HORIZONTAL);

public JSlider(int minimum, int maximum)
// Initial value midpoint / 0
JSlider aJSlider = new JSlider(-100, 100);

public JSlider(int minimum, int maximum, int value)
JSlider aJSlider = new JSlider(-100, 100, 0);

public JSlider(int orientation, int minimum, int maximum, int value)
// Vertical, initial value 6, range 1-12 (months of year)
JSlider aJSlider = new JSlider(JSlider.VERTICAL, 6, 1, 12);

public JSlider(BoundedRangeModel model)
// Data model, initial value 3, range 1-31, and extent of 0
// JSlider direction changed to vertical prior to display on screen
DefaultBoundedRangeModel model = new DefaultBoundedRangeModel(3, 0, 1, 31);
JSlider aJSlider = new JSlider(model);
aJSlider.setOrientation(JSlider.VERTICAL);

```

Creating a `JSlider` with no arguments creates a horizontal slider with a default data model. The model has an initial value of 50, a minimum of 0, a maximum of 100, and an extent of 0. You can also explicitly set the orientation with `JSlider.HORIZONTAL` or `JSlider.VERTICAL`, and any of the specific model properties, with the various constructors. In addition, you can explicitly set the data model for the component.

If you're using a preconfigured `BoundedRangeModel`, remember to set the extent to 0 when creating the model. If the extent property is greater than 0, then the maximum setting of the value property is decreased by that amount, and the value setting will never reach the setting of the maximum property.

Caution Initializing the orientation to something not equivalent to `VERTICAL` or `HORIZONTAL` throws an `IllegalArgumentException`. All constructors that initialize the data model could throw an `IllegalArgumentException` if the range and initial value fail to abide by the rules of the `BoundedRangeModel` described earlier in the section “`BoundedRangeModel` Interface.”

Handling JSlider Events

You track changes to a JSlider with a `ChangeListener`. There's no `AdjustmentListener`, as there is with `JScrollBar` (and `Scrollbar`). The same `BoundedChangeListener` from the earlier `JScrollBar` example could be added to a data model of the JSlider, and you'll then be notified when the model changes.

```
ChangeListener aChangeListener = new BoundedChangeListener();
JSlider aJSlider = new JSlider ();
BoundedRangeModel model = aJSlider.getModel();
model.addChangeListener(aChangeListener);
```

In addition to attaching a `ChangeListener` to the model, you can associate the `ChangeListener` directly with the JSlider itself. This allows you to share the data model between views and listen independently for changes. This requires you to modify the preceding listener a bit, because the change event source will now be a JSlider instead of a `BoundedRangeModel`. The updated `BoundedChangeListener`, shown in Listing 12-3, will work for both associations, however. The changes are boldfaced in the following listing.

Listing 12-3. *ChangeListener for BoundedRangeModel and JSlider*

```
import javax.swing.*;
import javax.swing.event.*;

public class BoundedChangeListener implements ChangeListener {
    public void stateChanged(ChangeEvent changeEvent) {
        Object source = changeEvent.getSource();
        if (source instanceof BoundedRangeModel) {
            BoundedRangeModel aModel = (BoundedRangeModel)source;
            if (!aModel.getValueIsAdjusting()) {
                System.out.println ("Changed: " + aModel.getValue());
            }
        } else if (source instanceof JSlider) {
            JSlider theJSlider = (JSlider)source;
            if (!theJSlider.getValueIsAdjusting()) {
                System.out.println ("Slider changed: " + theJSlider.getValue());
            }
        } else {
            System.out.println ("Something changed: " + source);
        }
    }
}
```

The association with the slider can now be direct, instead of indirect through the model.

```
aJSlider.addChangeListener(aChangeListener);
```

JSlider Properties

After you've created a `JSlider`, you may want to modify its underlying data model. As is the case with `JScrollBar`, you can get the model with the public `BoundedRangeModel getModel()` method, and then modify the model directly. You can also directly call the methods of the component:

- `setValue(int newValue), setExtent(int newValue), setMinimum(int newValue)`
- `setMaximum(int newValue)`

As with `JScrollBar`, these methods act as proxies and redirect any calls to the equivalent model method.

Table 12-3 shows the 19 properties of `JSlider`.

Table 12-3. *JSlider Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>changeListeners</code>	<code>ChangeListener[]</code>	Read-only
<code>extent</code>	<code>int</code>	Read-write
<code>inverted</code>	<code>boolean</code>	Read-write bound
<code>labelTable</code>	<code>Dictionary</code>	Read-write bound
<code>majorTickSpacing</code>	<code>int</code>	Read-write bound
<code>maximum</code>	<code>int</code>	Read-write bound
<code>minimum</code>	<code>int</code>	Read-write bound
<code>minorTickSpacing</code>	<code>int</code>	Read-write bound
<code>model</code>	<code>BoundedRangeModel</code>	Read-write bound
<code>orientation</code>	<code>int</code>	Read-write bound
<code>paintLabels</code>	<code>boolean</code>	Read-write bound
<code>paintTicks</code>	<code>boolean</code>	Read-write bound
<code>paintTrack</code>	<code>boolean</code>	Read-write bound
<code>snapToTicks</code>	<code>boolean</code>	Read-write bound
<code>UI</code>	<code>SliderUI</code>	Read-write bound
<code>UIClassID</code>	<code>String</code>	Read-only
<code>value</code>	<code>int</code>	Read-write
<code>valueIsAdjusting</code>	<code>boolean</code>	Read-write bound

Displaying Tick Marks Within a JSlider

The `JSlider` component allows you to add tick marks either below a horizontal slider or to the right of a vertical slider. These tick marks allow a user to get a rough estimate of the slider's value and scale. There can be both major and minor tick marks; the major ones are simply drawn to be a little longer. Either or both can be displayed, as well as neither of them, which is the default.

Note Technically, a custom look and feel could place the tick marks anywhere. However, the system-provided look and feel types place the ticks below or to the right.

To display the tick marks, you need to enable their painting with the public `void setPaintTicks(boolean newValue)` method. When called with a setting of `true`, this method enables the painting of minor and major tick marks. By default, the tick spacing for both types of tick marks is set to zero. When either is set to zero, that particular tick type isn't displayed. Because both are initially zero, you must change the value of either tick spacing to see any ticks. The public `void setMajorTickSpacing(int newValue)` and `public void setMinorTickSpacing(int newValue)` methods both support this change.

To demonstrate, Figure 12-6 shows four sliders: one with no ticks, one with aesthetically pleasing tick spacing, and two with unconventional tick spacing. It helps if the major tick spacing is a multiple of the minor tick spacing (just as a ruler shows inches, half inches, quarter inches, and so on with different tick lengths). In addition, the tick spacing shouldn't be so narrow that the ticks look like a solid block.




Figure 12-6. *Four JSlider controls demonstrating tick marks*

The source for the example in Figure 12-6 is shown in Listing 12-4. The top slider has no ticks. The bottom slider has the aesthetically pleasing major/minor spacing, with minor ticks at 5 units and major ones at 25 units. The left slider displays poor spacing with minor ticks at 6 and major ticks at 25. The right slider has minor ticks at each individual unit, resulting in spacing that's much too tight.

Listing 12-4. *JSlider with Tick Marks*

```
import javax.swing.*;
import java.awt.*;

public class TickSliders {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Tick Slider");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                // No Ticks
                JSlider jSliderOne = new JSlider();
                // Major Tick 25 - Minor 5
                JSlider jSliderTwo = new JSlider();
                jSliderTwo.setMinorTickSpacing(5);
                jSliderTwo.setMajorTickSpacing(25);
                jSliderTwo.setPaintTicks(true);
                jSliderTwo.setSnapToTicks(true);
                // Major Tick 25 - Minor 6
                JSlider jSliderThree = new JSlider(JSlider.VERTICAL);
                jSliderThree.setMinorTickSpacing(6);
                jSliderThree.setMajorTickSpacing(25);
                jSliderThree.setPaintTicks(true);
                JSlider jSliderFour = new JSlider(JSlider.VERTICAL);
                // Major Tick 25 - Minor 1
                jSliderFour.setMinorTickSpacing(1);
                jSliderFour.setMajorTickSpacing(25);
                jSliderFour.setPaintTicks(true);

                frame.add(jSliderOne, BorderLayout.NORTH);
                frame.add(jSliderTwo, BorderLayout.SOUTH);
                frame.add(jSliderThree, BorderLayout.WEST);
                frame.add(jSliderFour, BorderLayout.EAST);
                frame.setSize(300, 200);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

Snapping the JSlider Thumb into Position

One additional property of `JSlider` is related to tick marks: the `snapToTicks` property, set with `public void setSnapToTicks(boolean newValue)`. When this property is `true` and tick marks are displayed, after you move the slider's thumb, the thumb will rest only on a tick. For instance, if a slider has a range of 0–100 with tick marks at every tenth unit, and you drop the thumb at the 33 mark, the thumb will snap to the position of the tick at 30. If tick marks aren't displayed, the property setting has no effect, including when labels are displayed without tick marks.

Labeling JSlider Positions

As Figure 12-5 (shown earlier in the chapter) demonstrates, you can label any position within the `JSlider` with a `Component`. When a position is labeled, the component will be displayed next to it. The labels are stored within a lookup table that subclasses the `Dictionary` class, where the key is the `Integer` position and the value is the `Component`. Any AWT `Component` can be the label; however, the `JLabel` is best suited to the role. Figure 12-7 shows how the dictionary for the right slider of Figure 12-5 might look.




Figure 12-7. A `JSlider` dictionary

Normally, the Dictionary used to store the labels is a Hashtable. However, any class that extends the Dictionary class and that can use Integer keys will do. After you've created your dictionary of labels, you associate the dictionary with the slider with the public void `setLabelTable(Dictionary newValue)` method. The following source creates the label lookup table associated with Figure 12-7.

```
Hashtable<Integer, JLabel> table = new Hashtable<Integer, JLabel>();
table.put (0, new JLabel(new ImageIcon(Color.RED)));
table.put (10, new JLabel("Ten"));
table.put (25, new JLabel("Twenty-Five"));
table.put (34, new JLabel("Thirty-Four"));
table.put (52, new JLabel("Fifty-Two"));
table.put (70, new JLabel("Seventy"));
table.put (82, new JLabel("Eighty-Two"));
table.put (100, new JLabel(new ImageIcon(Color.BLACK)));
aJSlider.setLabelTable (table);
```

Note Keep in mind that with J2SE 5.0, the compiler will auto-box an `int` parameter into an `Integer`.

Simply associating the label table with the slider won't display the labels. To enable their painting, you need to call the public void `setPaintLabels(boolean newValue)` method with a parameter of `true`. If you haven't manually created a table of labels, the system will create one with an interval of values reflecting the major tick spacing. For example, the left slider of Figure 12-5 has a slider range of 0–100 and major tick spacing of 10. When `setPaintLabels(true)` is called on that slider, labels are created for 0, 10, 20, and so on, all the way up to 100. The minor tick spacing is irrelevant as far as automatic generation of labels goes. And the ticks don't need to be painted for the labels to appear; the `getPaintTicks()` method can return `false`.

The automatic creation of labels is done through the public Hashtable `createStandardLabels(int increment)` method, where the increment is the major tick spacing. You don't need to call this method directly. If you want to create the labels from other than the minimum value, you can call the overloaded public Hashtable `createStandardLabels(int increment, int start)` variety, and associate the hash table with the slider yourself.

Customizing a JSlider Look and Feel

Each installable Swing look and feel provides a different JSlider appearance and set of default UIResource values. Figure 12-8 shows the appearance of the JSlider component for the pre-installed set of look and feel types.




Figure 12-8. *JSlider under different look and feel types*

Two look-and-feel-related properties are part of the `JSlider` class definition. By default, the minimum slider value for a horizontal slider is at the left; for a vertical slider, it's at the bottom. To change the direction of a slider, call the public void `setInverted(boolean newValue)` method with an argument of `true`. In addition, the track that the slider moves along is displayed by default. You can turn it off with the public void `setPaintTrack(boolean newValue)` method. A value of `false` turns off the track display. Figure 12-9 identifies the `JSlider` track and points out the minimum and maximum positions of regular and inverted sliders.




Figure 12-9. *Identifying JSlider positions and tracks*

Table 12-4 shows the 30 available UIResource-related properties for a JSlider.

Table 12-4. *JSlider UIResource Elements*

Property String	Object Type
Slider.actionMap	ActionMap
Slider.altTrackColor	Color
Slider.background	Color
Slider.border	Border
Slider.darkShadow	Color
Slider.focus	Color
Slider.focusGradient	List
Slider.focusInputMap	Object[]
Slider.focusInputMap.RightToLeft	InputMap
Slider.focusInsets	Insets
Slider.foreground	Color
Slider.gradient	List
Slider.highlight	Color
Slider.horizontalSize	Dimension
Slider.horizontalThumbIcon	Icon
Slider.majorTickLength	Integer
Slider.minimumHorizontalSize	Dimension
Slider.minimumVerticalSize	Dimension
Slider.paintThumbArrowShape	Boolean
Slider.paintValue	Boolean
Slider.shadow	Color
Slider.thumb	Color
Slider.thumbHeight	Integer
Slider.thumbWidth	Integer
Slider.tickColor	Color
Slider.trackBorder	Border
Slider.trackWidth	Integer
Slider.verticalSize	Dimension
Slider.verticalThumbIcon	Icon
SliderUI	String

The JSlider resources allow customization of elements that aren't accessible through JSlider or SliderUI methods. For instance, to customize the JSlider appearance of your application, you may want to alter the icon used for the draggable thumb. With just a few lines of code, you can take any icon and make it the slider's icon for every slider in your application.

```
Icon icon = new ImageIcon("logo.jpg");
UIDefaults defaults = UIManager.getDefaults();
defaults.put("Slider.horizontalThumbIcon", icon);
```

Figure 12-10 shows the results. As with all UIResource properties, this change will affect all JSlider components created after setting the property.



Figure 12-10. *A JSlider with a custom icon*

Note The height and width of the icon are limited to the dimensions of the slider. Changing the icon property doesn't affect the slider size.

JSlider Client Properties

By default, with the Metal look and feel, when the track is visible, the track on which the slider moves does not change as the slider is moved over it. Nevertheless, you can enable a client property that will signal the slider to fill this track up to the point of the current value that the thumb has crossed. The name of this property is JSlider.isFilled, and a Boolean object represents the current setting. By default, this setting is Boolean.FALSE. Figure 12-11 demonstrates both a Boolean.TRUE and a Boolean.FALSE setting; the code fragment follows:

```
JSlider oneJSlider = new JSlider();
oneJSlider.putClientProperty("JSlider.isFilled", Boolean.TRUE);
JSlider anotherJSlider = new JSlider();
// Set to default setting
anotherJSlider.putClientProperty("JSlider.isFilled", Boolean.FALSE);
```



Figure 12-11. *Filled and unfilled JSlider*

This setting works only in the Metal look and feel. The Ocean theme of the Metal look and feel ignores this setting, always drawing the track filled. To get this behavior, you need to set the system property swing.metalTheme to steel, as in `java -Dswing.metalTheme=steel ClassName`.

JProgressBar Class

Swing's `JProgressBar` is different from the other `BoundedRangeModel` components. Its main purpose is not to get input from the user, but rather to present output. This output is in the form of a process completion percentage. As the percentage increases, a bar progresses across the component until the job is completed and the bar is filled. The movement of the bar is usually part of some multithreaded task, to avoid affecting the rest of the application.

Figure 12-12 shows several sample `JProgressBar` components. The top bar uses all the display defaults. The bottom bar adds a border around the component and displays the completion percentage. The right bar removes the border, and the left bar has a fixed string present instead of a completion percentage.




Figure 12-12. *Sample `JProgressBar` components*

From an object-oriented perspective, there are two primary parts to a `JProgressBar`: The familiar `BoundedRangeModel` stores the data model for the component, and the `ProgressUI` is the user interface delegate.

Note To display a progress bar in a dialog box, use the `ProgressMonitor` class discussed in Chapter 9.

Creating `JProgressBar` Components

There are five different constructors for `JProgressBar`:

```
public JProgressBar()
JProgressBar aJProgressBar = new JProgressBar();

public JProgressBar(int orientation)
// Vertical
JProgressBar aJProgressBar = new JProgressBar(JProgressBar.VERTICAL);
// Horizontal
JProgressBar bJProgressBar = new JProgressBar(JProgressBar.HORIZONTAL);

public JProgressBar(int minimum, int maximum)
JProgressBar aJProgressBar = new JProgressBar(0, 500);
```

```
public JProgressBar(int orientation, int minimum, int maximum)
JProgressBar aJProgressBar = new JProgressBar(JProgressBar.VERTICAL, 0, 1000);

public JProgressBar(BoundedRangeModel model)
// Data model, initial value 0, range 0-250, and extent of 0
DefaultBoundedRangeModel model = new DefaultBoundedRangeModel(0, 0, 0, 250);
JProgressBar aJProgressBar = new JProgressBar(model);
```

Creating a `JProgressBar` with no arguments results in a horizontal progress bar with a default data model. The model has an initial value of 0, a minimum value of 0, a maximum value of 100, and an extent of 0. The progress bar has an extent, but it doesn't use it, even though it's part of the data model.

You can explicitly set the orientation with `JProgressBar.HORIZONTAL` or `JProgressBar.VERTICAL`, as well as any of the specific model properties, with the different constructors. In addition, you can explicitly set the data model for the component.

Caution Initializing the orientation to a value not equivalent to `VERTICAL` or `HORIZONTAL` throws an `IllegalArgumentException`.

Creating a `JProgressBar` from a `BoundedRangeModel` is a little awkward in the sense that the progress bar virtually ignores one setting and the initial value is normally initialized to the minimum. Assuming you want the `JProgressBar` to start as a user might expect it to, you need to remember to set the extent to 0 and the value to the minimum when creating the model. If you increase the extent property, the maximum setting of the value property is decreased by that amount, and the value setting will never reach the setting of the maximum property.

JProgressBar Properties

After you've created a `JProgressBar`, you may want to modify it. Table 12-5 shows the 14 properties of `JProgressBar`.

Table 12-5. *JProgressBar Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>borderPainted</code>	<code>boolean</code>	Read-write bound
<code>changelisteners</code>	<code>ChangeListener[]</code>	Read-only
<code>indeterminate</code>	<code>boolean</code>	Read-write bound
<code>maximum</code>	<code>int</code>	Read-write
<code>minimum</code>	<code>int</code>	Read-write
<code>model</code>	<code>BoundedRangeModel</code>	Read-write
<code>orientation</code>	<code>int</code>	Read-write bound

Table 12-5. *JProgressBar Properties (Continued)*

Property Name	Data Type	Access
percentComplete	double	Read-only
string	String	Read-write bound
stringPainted	boolean	Read-write bound
UI	ProgressBarUI	Read-write
UIClassID	String	Read-only
value	int	Read-write

Painting JProgressBar Borders

All JComponent subclasses feature a border property by default, and the JProgressBar has a special borderPainted property to easily enable or disable the painting of the border. Calling the public void setBorderPainted(boolean newValue) method with a parameter of false turns off the painting of the progress bar's border. The right-hand progress bar in Figure 12-12 (shown earlier) has its border turned off. The source for its initialization follows:

```
JProgressBar cJProgressBar = new JProgressBar(JProgressBar.VERTICAL);
cJProgressBar.setBorderPainted(false);
```

Labeling a JProgressBar

The JProgressBar supports the display of text within the center of the component. There are three forms of this labeling:

- By default, no label exists.
- To display the percentage completed $[100 \times (\text{value} - \text{minimum}) / (\text{maximum} - \text{minimum})]$, call the public void setStringPainted(boolean newValue) method with a parameter of true. This will result in a range from 0% to 100% displayed.
- To change the label to a fixed string, call the public void setString(String newValue) method and setStringPainted(true). On a vertical progress bar, the string is drawn rotated, so a longer string will fit better.

The left and bottom progress bars in Figure 12-12 demonstrate the fixed label and percentage label, respectively. The source code to create both progress bars follows:

```
JProgressBar bJProgressBar = new JProgressBar();
bJProgressBar.setStringPainted(true);
Border border = BorderFactory.createTitledBorder("Reading File");
bJProgressBar.setBorder(border);

JProgressBar dJProgressBar = new JProgressBar(JProgressBar.VERTICAL);
dJProgressBar.setString("Ack");
dJProgressBar.setStringPainted(true);
```

Using an Indeterminate JProgressBar

Some tasks don't have a fixed number of steps, or they do have a fixed number of steps, but you don't know what that number is until after all the steps are done. For this type of operation, the `JProgressBar` offers an indeterminate mode where the bar within the `JProgressBar` bounces back and forth from side to side, or top to bottom, depending on the direction of the progress bar. To enable this mode, just call the public `void setIndeterminate(boolean newValue)` method with a value of `true`. Figure 12-13 shows what an indeterminate progress bar looks like at different times. The length of the sliding box is one-sixth the available space and seems to not be settable.



Figure 12-13. *Sample indeterminate JProgressBar*

Stepping Along a JProgressBar

The main usage of the `JProgressBar` is to show progress as you step through a series of operations. Normally, you set the minimum value of the progress bar to zero and the maximum value to the number of steps to perform. Starting with a value property of zero, you increase the value to the maximum as you perform each step. All these operations imply multithreading, which is, in fact, absolutely necessary. In addition, when updating the progress bar's value, you need to remember to update it only from within the event dispatching thread (with the help of `EventQueue.invokeLater()`, if appropriate, as described in Chapter 2).

The process of having a progress bar step through its range is as follows:

1. Initialize it. This is the basic process of creating a `JProgressBar` with the desired orientation and range. In addition, perform any bordering and labeling here.

```
JProgressBar aJProgressBar = new JProgressBar(0, 50);
aJProgressBar.setStringPainted(true);
```

2. Start up the thread to perform the desired steps. Probably as the result of performing some action on the screen, you'll need to start the thread to do the work the progress bar is reporting. You need to start a new thread so that the user interface remains responsive.

```
Thread stepper = new BarThread (aJProgressBar);
stepper.start();
```

3. Perform the steps. Ignore updating the progress bar, and instead write the appropriate code to perform each step.

```
static class BarThread extends Thread {
    private static int DELAY = 500;
    JProgressBar progressBar;
```

```

public BarThread (JProgressBar bar) {
    progressBar = bar;
}

public void run() {
    int minimum = progressBar.getMinimum();
    int maximum = progressBar.getMaximum();
    for (int i=minimum; i<maximum; i++) {
        try {
            // Our job for each step is to just sleep
            Thread.sleep(DELAY);
        } catch (InterruptedException ignoredException) {}
        // The EventQueue.invokeLater() call
        // we'll add will throw this
    }
}
}
}

```

4. For each step, have the thread update the progress bar in the event thread. Create the Runnable class just once outside the for loop. It isn't necessary to create one for each step.

```

Runnable runner = new Runnable() {
    public void run() {
        int value = progressBar.getValue();
        progressBar.setValue(value+1);
    }
};

```

Within the loop, tell the runner to update the progress bar. This update must be done in the event thread using the special EventQueue method `invokeLater()` or `invokeAndWait()`, because you're updating a property of the JProgressBar.

```
EventQueue.invokeLater (runner);
```

The complete working example is shown in Listing 12-5.

Listing 12-5. *JProgressBar Sample*

```

import javax.swing.*.*;
import java.awt.*.*;
import java.awt.event.*;
import java.lang.reflect.InvocationTargetException;

public class ProgressBarStep {
    static class BarThread extends Thread {
        private static int DELAY = 500;
        JProgressBar progressBar;
    }
}

```

```

public BarThread(JProgressBar bar) {
    progressBar = bar;
}

public void run() {
    int minimum = progressBar.getMinimum();
    int maximum = progressBar.getMaximum();
    Runnable runner = new Runnable() {
        public void run() {
            int value = progressBar.getValue();
            progressBar.setValue(value+1);
        }
    };
    for (int i=minimum; i<maximum; i++) {
        try {
            EventQueue.invokeAndWait(runner);
            // Our job for each step is to just sleep
            Thread.sleep(DELAY);
        } catch (InterruptedException ignoredException) {}
        } catch (InvocationTargetException ignoredException) {}
    }
}

public static void main(String args[]) {
    Runnable runner = new Runnable() {
        public void run() {
            JFrame frame = new JFrame("Stepping Progress");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
            final JProgressBar aJProgressBar = new JProgressBar(0, 50);
            aJProgressBar.setStringPainted(true);

            final JButton aJButton = new JButton("Start");

            ActionListener actionListener = new ActionListener() {
                public void actionPerformed(ActionEvent e) {
                    aJButton.setEnabled(false);
                    Thread stepper = new BarThread(aJProgressBar);
                    stepper.start();
                }
            };
};

```

```
        aJButton.addActionListener(actionListener);
        frame.add(aJProgressBar, BorderLayout.NORTH);
        frame.add(aJButton, BorderLayout.SOUTH);
        frame.setSize(300, 200);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}
```

Figure 12-14 shows the demonstration program after selecting the button and at 22% completion.




Figure 12-14. *JProgressBar in action*

By simply changing the sleep action in Listing 12-5 to the desired operation, this example should provide a suitable framework for reuse.

Note To have the progress bar fill in the opposite direction, have the value start at the maximum and decrease it with each step. You probably don't want to display the percentage-completed string, as it will start at 100% and decrease to 0%.

Handling JProgressBar Events

Technically, the `JProgressBar` class supports notification of data model changes through a `ChangeListener`. In addition, you can attach a `ChangeListener` to its data model. Because the progress bar is meant more for visualization of output than for providing input, you typically won't use a `ChangeListener` with it. However, there may be times when this is appropriate. To reuse the `BoundedChangeListener` from Listing 12-3 earlier in this chapter, make one final change (as shown in boldface in Listing 12-6), because the source of these change events is the `JProgressBar`.

Listing 12-6. *ChangeListener for BoundedRangeModel, JSlider, and JProgressBar*

```
import javax.swing.*;
import javax.swing.event.*;

public class BoundedChangeListener implements ChangeListener {
    public void stateChanged(ChangeEvent changeEvent) {
        Object source = changeEvent.getSource();
        if (source instanceof BoundedRangeModel) {
            BoundedRangeModel aModel = (BoundedRangeModel)source;
            if (!aModel.getValueIsAdjusting()) {
                System.out.println ("Changed: " + aModel.getValue());
            }
        } else if (source instanceof JSlider) {
            JSlider theJSlider = (JSlider)source;
            if (!theJSlider.getValueIsAdjusting()) {
                System.out.println ("Slider changed: " + theJSlider.getValue());
            }
        } else if (source instanceof JProgressBar) {
            JProgressBar theJProgressBar = (JProgressBar)source;
            System.out.println ("ProgressBar changed: " + theJProgressBar.getValue());
        } else {
            System.out.println ("Something changed: " + source);
        }
    }
}
```

Customizing a JProgressBar Look and Feel

Each installable Swing look and feel provides a different JProgressBar appearance and set of default UIResource values. Figure 12-15 shows the appearance of the JProgressBar component for the preinstalled set of look and feel types.

Table 12-6 shows the set of available UIResource-related properties for a JProgressBar. It has 15 different properties.

Table 12-6. *JProgressBar UIResource Elements*

Property String	Object Type
ProgressBar.background	Color
ProgressBar.border	Border
ProgressBar.cellLength	Integer
ProgressBar.cellSpacing	Integer
ProgressBar.cycleTime	Integer
ProgressBar.font	Font
ProgressBar.foreground	Color

Table 12-6. *JProgressBar UIResource Elements (Continued)*

Property String	Object Type
ProgressBar.highlight	Color
ProgressBar.horizontalSize	Dimension
ProgressBar.repaintInterval	Integer
ProgressBar.selectionBackground	Color
ProgressBar.selectionForeground	Color
ProgressBar.shadow	Color
ProgressBar.verticalSize	Dimension
ProgressBarUI	String

**Figure 12-15.** *JProgressBar under different look and feel types*

JTextField Class and BoundedRangeModel Interface

The `JTextField` component is not technically a bounded-range component, but nevertheless, it uses `BoundedRangeModel`. Built inside the `JTextField` is a scrollable area used when the width of the component's contents exceeds its visible horizontal space. A `BoundedRangeModel` controls this scrolling area. You'll look at `JTextField` in more depth in Chapter 15. Here, you can see

how a `JScrollBar` can track the scrolling area of the `JTextField`. Figure 12-16 shows the example in action, and Listing 12-7 shows the source.




Figure 12-16. *Tracking a `JTextField` width with a `JScrollBar`*

Listing 12-7. *`JTextField` with a `JScrollBar` for Scrolling*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class TextSlider extends JPanel {
    private JTextField textField;
    private JScrollBar scrollBar;

    public TextSlider() {
        setLayout(new BorderLayout(this, BoxLayout.Y_AXIS));
        textField = new JTextField();
        scrollBar = new JScrollBar(JScrollBar.HORIZONTAL);
        BoundedRangeModel brm = textField.getHorizontalVisibility();
        scrollBar.setModel(brm);
        add(textField);
        add(scrollBar);
    }

    public JTextField getTextField() {
        return textField;
    }

    public String getText() {
        return textField.getText();
    }

    public void addActionListener(ActionListener l) {
        textField.addActionListener(l);
    }

    public void removeActionListener(ActionListener l) {
        textField.removeActionListener(l);
    }

    public JScrollBar getScrollBar() {
        return scrollBar;
    }
}
```

```

public static void main(String args[]) {
    Runnable runner = new Runnable() {
        public void run() {
            JFrame frame = new JFrame("Text Slider");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
            final TextSlider ts = new TextSlider();
            ts.addActionListener(new ActionListener() {
                public void actionPerformed(ActionEvent e) {
                    System.out.println("Text: " + ts.getText());
                }
            });
            frame.add(ts, BorderLayout.NORTH);
            frame.setSize(300, 100);
            frame.setVisible(true);
        }
    };
    EventQueue.invokeLater(runner);
}
}

```

Normally, the `JTextField` has no associated scrollbar. In fact, most look and feel types don't offer it as an alternative. However, if this component is something you want to incorporate, you can reuse it in your own applications. Plenty of accessor methods should make reuse simpler, and you can avoid needing to access the internal pieces directly.

Summary

In this chapter, you've learned how to use Swing's `JScrollBar`, `JSlider`, and `JProgressBar` components. You saw how each uses the `BoundedRangeModel` interface to control the internal data necessary to operate the component, and how the `DefaultBoundedRangeModel` class offers a default implementation of this data model.

Now that you know how to use the various bounded range components, you can move on to Chapter 13, which looks at the controls that offer data selection: `JList` and `JComboBox`.



List Model Controls

Chapter 12 explored the bounded range controls that support scrolling and the input or display of some bounded range of values. In this chapter, you'll examine two data-selection controls that present a list of choices: `JList` and `JComboBox`. The primary difference between these controls is that the `JList` component supports multiple selections, whereas the `JComboBox` does not. Also, the `JComboBox` lets a user provide a choice that isn't among the available options.

ListModel Interface

Figure 13-1 shows the two controls you'll be examining in this chapter.




Figure 13-1. *Sample JComboBox and JList controls*

The data model shared by the two components is `ListModel`, which originates with the `ListModel` interface. The `AbstractListModel` class provides an implementation basis by supporting the management and notification of a set of `ListDataListener` objects.

In the case of a `JList` component, the data model implementation is the `DefaultListModel` class. This class adds an actual data repository, which follows the API of a `Vector`, for the different elements to be displayed within the `JList` component.

In the `JComboBox` component, an extension of the `ListModel` interface called `ComboBoxModel` supports the notion of a selected item within the model. The `DefaultComboBoxModel` class implements the `ComboBoxModel` interface through yet another interface, the `MutableComboBoxModel`, which supplies supporting methods for adding and removing elements from the model.

Note The `BasicDirectoryModel` class is another `ListModel` implementation. This implementation is used by the file chooser component, `JFileChooser`, as described in Chapter 9.

The actual `ListModel` interface is rather simple. It provides for management of a `ListDataListener`, and it accesses the size of a particular element of the model.

```
public interface ListModel {
    // Properties
    public int getSize();
    // Listeners
    public void addListDataListener(ListDataListener l);
    public void removeListDataListener(ListDataListener l);
    // Other methods
    public Object getElementAt(int index);
}
```

AbstractListModel Class

The `AbstractListModel` class provides a partial implementation of the `ListModel` interface. You need to provide only the data structure and the data. The class provides for the list management of `ListDataListener` objects and the framework for notification of those listeners when the data changes. You can also get the list of listeners by using the public `ListDataListener[]` `getListDataListeners()` method. When you modify the data model, you must then call the appropriate method of `AbstractListModel` to notify the listening `ListDataListener` objects:

- `protected void fireIntervalAdded(Object source, int index0, int index1):` To be called after adding a contiguous range of values to the list.
- `protected void fireIntervalRemoved(Object source, int index0, int index1):` To be called after removing a contiguous range of values from the list.
- `protected void fireContentsChanged(Object source, int index0, int index1):` To be called if the modified range wasn't contiguous for insertion, removal, or both.

Note The ranges specified by the `fireXXX()` methods of `AbstractListModel` are closed intervals. This simply means that the indices are the endpoints of the range modified. There's no implied order for the indices; `index0`, for example, doesn't need to be less than `index1`. The only requirement is that the methods be called after the data model has changed.

If you have your data in an existing data structure, you need to convert it into a form that one of the Swing components understands or implement the `ListModel` interface yourself. As you'll see, an array or `Vector` is directly supported by `JList` and `JComboBox`. You can also wrap your data structure into an `AbstractListModel`. For instance, if your initial data structure is an

ArrayList from the Collections framework, you can convert the data structure to a ListModel with the following code:

```
final List arrayList = ...;
ListModel model = new AbstractListModel() {
    public int getSize() {
        return arrayList.size();
    }
    public Object getElementAt(int index) {
        return arrayList.get(index);
    }
}
```

The other option is to just pass the List into the Vector constructor, and then pass that Vector into the JList constructor. Effectively, you've then done the same thing.

DefaultListModel Class

The DefaultListModel class provides a data structure for you to store the data internally in the form of a Vector. You just need to add the data, because the class manages the ListDataListener list for you.

First, you create the data structure with the no-argument constructor: DefaultListModel model = new DefaultListModel(). Then you manipulate it. As shown in Table 13-1, the DefaultListModel class has only two properties.

Table 13-1. *DefaultListModel Properties*

Property Name	Data Type	Access
empty	boolean	Read-only
size	int	Read-write

The DefaultListModel class provides all its operational methods through a series of public methods. To add elements, use the following methods:

```
public void add(int index, Object element)
public void addElement(Object element)
public void insertElementAt(Object element, int index)
```

The addElement() method of DefaultListModel adds the element to the end of the data model.

To change elements, use these methods:

```
public Object set(int index, Object element)
public void setElementAt(Object element, int index)
```

And to remove elements, these methods are provided:

```

public void clear()
public Object remove(int index)
public void removeAllElements()
public boolean removeElement(Object element)
public void removeElementAt(int index)
public void removeRange(int fromIndex, int toIndex)

```

The `removeElement()` method returns a status: true if it found the object and removed it, and false otherwise.

The `DefaultListModel` class is useful when you don't have your data in an existing data structure. For example, the results of a database query come back as a `JDBC ResultSet`. If you wish to use those results as the basis for what to display in a `JList`, you must store them somewhere. That somewhere can be a `DefaultListModel`, as demonstrated by the following:

```

ResultSet results = aJDBCStatement.executeQuery(
    "SELECT columnName FROM tableName");
DefaultListModel model = new DefaultListModel();
while (results.next()) {
    model.addElement(result.getString(1));
}

```

Listening for ListModel Events with a ListDataListener

If you're interested in finding out when the contents of the list model change, you can register a `ListDataListener` with the model. Three separate methods of the interface tell you when contents are added, removed, or altered. Altering the data model means adding and/or removing contents from one or more regions of the data model or changing the existing contents without adding or removing anything. The following is the interface definition:

```

public interface ListDataListener extends EventListener {
    public void contentsChanged(ListDataEvent e);
    public void intervalAdded(ListDataEvent e);
    public void intervalRemoved(ListDataEvent e);
}

```

Upon notification of the list-altering event, you're passed a `ListDataEvent` instance, which contains three properties, as shown in Table 13-2.

Table 13-2. *ListDataEvent Properties*

Property Name	Data Type	Access
index0	int	Read-only
index1	int	Read-only
type	int	Read-only

The indices aren't necessarily ordered, and neither are the bounds of the altered region. In the case of the list model contents changing, not everything within the region may have been altered. The area whose contents *did* change is the bounded region specified by the indices. The type property setting is one of three constants, as shown in Table 13-3, that map directly to the specific interface method called.

Table 13-3. *ListDataEvent Type Constants*

Type Constant	Method
CONTENTS_CHANGED	contentsChanged()
INTERVAL_ADDED	intervalAdded()
INTERVAL_REMOVED	intervalRemoved()

If any `ListDataListener` objects are attached to the data model when any one of the operational methods of the `DefaultListModel` class are called, each of the listeners will be notified of the data model change. To demonstrate the use of `ListDataListener` and the dynamic updating of the data model, the `ModifyModelSample` program shown in Listing 13-1 uses all the `DefaultListModel` class modifying methods, sending the output in the form of the event and list contents to a `JTextArea`.

Listing 13-1. *Modifying the Data Model*

```
import javax.swing.*;
import javax.swing.event.*;
import java.awt.*;
import java.awt.event.*;
import java.io.*;
import java.util.Enumuration;

public class ModifyModelSample {
    static String labels[] = {"Chardonnay", "Sauvignon", "Riesling", "Cabernet",
        "Zinfandel", "Merlot", "Pinot Noir", "Sauvignon Blanc", "Syrah",
        "Gewürztraminer"};

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Modifying Model");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                // Fill model
                final DefaultListModel model = new DefaultListModel();
                for (int i=0, n=labels.length; i<n; i++) {
                    model.addElement(labels[i]);
                }
            }
        };
    }
}
```

```

JList jlist = new JList(model);
JScrollPane scrollPane1 = new JScrollPane(jlist);
frame.add(scrollPane1, BorderLayout.WEST);

final JTextArea textArea = new JTextArea();
textArea.setEditable(false);
JScrollPane scrollPane2 = new JScrollPane(textArea);
frame.add(scrollPane2, BorderLayout.CENTER);

ListDataListener listDataListener = new ListDataListener() {
    public void contentsChanged(ListDataEvent listDataEvent) {
        appendEvent(listDataEvent);
    }
    public void intervalAdded(ListDataEvent listDataEvent) {
        appendEvent(listDataEvent);
    }
    public void intervalRemoved(ListDataEvent listDataEvent) {
        appendEvent(listDataEvent);
    }
    private void appendEvent(ListDataEvent listDataEvent) {
        StringWriter sw = new StringWriter();
        PrintWriter pw = new PrintWriter(sw);
        switch (listDataEvent.getType()) {
            case ListDataEvent.CONTENTS_CHANGED:
                pw.print("Type: Contents Changed");
                break;
            case ListDataEvent.INTERVAL_ADDED:
                pw.print("Type: Interval Added");
                break;
            case ListDataEvent.INTERVAL_REMOVED:
                pw.print("Type: Interval Removed");
                break;
        }
        pw.print(", Index0: " + listDataEvent.getIndex0());
        pw.print(", Index1: " + listDataEvent.getIndex1());
        DefaultListModel theModel =
            (DefaultListModel)listDataEvent.getSource();
        pw.println(theModel);
        textArea.append(sw.toString());
    }
};

model.addListDataListener(listDataListener);

```

```

// Set up buttons
JPanel jp = new JPanel(new GridLayout(2, 1));
JPanel jp1 = new JPanel(new FlowLayout(FlowLayout.CENTER, 1, 1));
JPanel jp2 = new JPanel(new FlowLayout(FlowLayout.CENTER, 1, 1));
jp.add(jp1);
jp.add(jp2);
JButton jb = new JButton("add F");
jp1.add(jb);
jb.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        model.add(0, "First");
    }
});
jb = new JButton("addElement L");
jp1.add(jb);
jb.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        model.addElement("Last");
    }
});
jb = new JButton("insertElementAt M");
jp1.add(jb);
jb.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        int size = model.getSize();
        model.insertElementAt("Middle", size/2);
    }
});
jb = new JButton("set F");
jp1.add(jb);
jb.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        int size = model.getSize();
        if (size != 0)
            model.set(0, "New First");
    }
});
jb = new JButton("setElementAt L");
jp1.add(jb);
jb.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        int size = model.getSize();
        if (size != 0)
            model.setElementAt("New Last", size-1);
    }
});

```

```

jb = new JButton("load 10");
jp1.add(jb);
jb.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        for (int i=0, n=labels.length; i<n ;i++) {
            model.addElement(labels[i]);
        }
    }
});
jb = new JButton("clear");
jp2.add(jb);
jb.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        model.clear();
    }
});
jb = new JButton("remove F");
jp2.add(jb);
jb.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        int size = model.getSize();
        if (size != 0)
            model.remove(0);
    }
});
jb = new JButton("removeAllElements");
jp2.add(jb);
jb.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        model.removeAllElements();
    }
});
jb = new JButton("removeElement 'Last'");
jp2.add(jb);
jb.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        model.removeElement("Last");
    }
});
jb = new JButton("removeElementAt M");
jp2.add(jb);
jb.addActionListener(new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        int size = model.getSize();
        if (size != 0)
            model.removeElementAt(size/2);
    }
});

```

```

        jb = new JButton("removeRange FM");
        jp2.add(jb);
        jb.addActionListener(new ActionListener() {
            public void actionPerformed(ActionEvent actionEvent) {
                int size = model.getSize();
                if (size != 0)
                    model.removeRange(0,size/2);
            }
        });
        frame.add(jp, BorderLayout.SOUTH);
        frame.setSize(640, 300);
        frame.setVisible(true);
    }
}
EventQueue.invokeLater(runner);
}
}

```

Figure 13-2 shows the output for one such run, after several buttons were selected.



Figure 13-2. A listing for data model changes

Note To help you decode the button labels in Figure 13-2, an *F* means the method affects the first cell, an *M* means it affects the middle cell, and an *L* means it affects the last cell. The removeElement “Last” button will remove the first element in the data model whose content is Last.

The retrieving methods of the `DefaultListModel` class are quite varied in their capabilities. The class has the basic accessor methods `public Object get(int index)`, `public Object getElementAt(int index)`, and `public Object elementAt(int index)`, which all do the same thing. The `DefaultListModel` class also has more specific methods. For instance, to work with all elements, you can obtain an instance of `Enumeration` using `public Enumeration elements()`.

Or, if you want to work with all elements as an array, use either `public Object[] toArray()` or `public void copyInto(Object anArray[])`. You can also check for the existence of an element within a model with methods such as `public boolean contains(Object element)`, `public int indexOf(Object element)`, `public int indexOf(Object element, int index)`, `public int lastIndexOf(Object element)`, and `public int lastIndexOf(Object element, int index)`.

Tip Once you're finished adding elements to the data model, it's a good idea to trim its length with `public void trimToSize()`. This removes any extra preallocated space within the internal data structure. In addition, if you know the size of the data model in advance, you can call `public void ensureCapacity(int minCapacity)` to preallocate space. Both of these methods work only with `DefaultListModel`.

ComboBoxModel Interface

The `ComboBoxModel` interface extends the `ListModel` interface. The key reason for this extension is that the classes that implement the `ComboBoxModel` interface need to manage the selected item internally through a `selectedItem` property, as shown by the interface definition.

```
public interface ComboBoxModel extends ListModel {
    // Properties
    public Object getSelectedItem();
    public void setSelectedItem(Object anItem);
}
```

MutableComboBoxModel Interface

In addition to the `ComboBoxModel` interface, another data model interface, `MutableComboBoxModel`, extends `ComboBoxModel` to make methods available to modify the data model.

```
public interface MutableComboBoxModel extends ComboBoxModel {
    // Other methods
    public void addElement(Object obj);
    public void insertElementAt(Object obj, int index);
    public void removeElement(Object obj);
    public void removeElementAt(int index);
}
```

The `JComboBox` component uses an implementation of this interface by default.

DefaultComboBoxModel Class

The `DefaultComboBoxModel` class extends the `AbstractListModel` class to provide an appropriate data model for the `JComboBox`. Because of this extension, it inherits the managing of the `ListDataListener` list.

Like `DefaultListModel`, `DefaultComboBoxModel` adds the necessary data structure for you to collect elements to show within a component. Also, because the model is modifiable, implementing `MutableComboBoxModel` causes the data model to call the various `fileXXX()` methods of the `AbstractListModel` class when the data elements within the model change.

Note If you create a `DefaultComboBoxModel` from an array, the elements of the array are copied into an internal data structure. If you use a `Vector`, they're not copied; instead, the actual `Vector` is used internally.

To use the data model, you must first create the model with one of the three constructors:

```
public DefaultComboBoxModel()  
DefaultComboBoxModel model = new DefaultComboBoxModel();  
  
public DefaultComboBoxModel(Object listData[])  
String labels[] = { "Chardonnay", "Sauvignon", "Riesling", "Cabernet", "Zinfandel",  
    "Merlot", "Pinot Noir", "Sauvignon Blanc", "Syrah", "Gewürztraminer"};  
DefaultComboBoxModel model = new DefaultComboBoxModel(labels);  
  
public DefaultComboBoxModel(Vector listData)  
Vector vector = aBufferedImage.getSources();  
DefaultComboBoxModel model = new DefaultComboBoxModel(vector);
```

Next, you manipulate the model. Two new properties are introduced in the `DefaultComboBoxModel` class, as shown in Table 13-4.

Table 13-4. *DefaultComboBoxModel Properties*

Property Name	Data Type	Access
selectedItem	Object	Read-write
size	int	Read-only

The data model modification methods for the `DefaultComboBoxModel` are different from those for `DefaultListModel`. They all come from the `MutableComboBoxModel` interface:

```
public void addElement(Object element)  
public void insertElementAt(Object element, int index)  
public boolean removeElement(Object element)  
public void removeElementAt(int index)
```

Due to the flexibility (and functionality) of the `DefaultComboBoxModel`, it's usually unnecessary to create your own `ComboBoxModel` implementation. Just create an instance of `DefaultComboBoxModel`, and then simply fill it from the appropriate data source.

Note One case in which you may wish to provide your own model is when you need to support the presence of the same item within the model multiple times. With the `DefaultComboBoxModel`, if you have two items in the list whose `equals()` methods will return `true`, the model won't work properly.

If you really want to define your own model implementation, perhaps because you already have the data in your own data structure, it works best to subclass the `AbstractListModel` and implement the `ComboBoxModel` or `MutableComboBoxModel` interface methods. When subclassing the `AbstractListModel`, you merely need to provide the data structure and the access into it. Because the “selected item” part of the data model is maintained outside the primary data structure, you need a place to store that, as well. The program source in Listing 13-2 demonstrates one such implementation using an `ArrayList` as the data structure. The program includes a `main()` method to demonstrate the use of the model within a `JComboBox`.

Listing 13-2. *Using a Custom Data Model*

```
import java.awt.*;
import javax.swing.*;
import java.util.Collection;
import java.util.ArrayList;

public class ArrayListComboBoxModel
    extends AbstractListModel implements ComboBoxModel {
    private Object selectedItem;
    private ArrayList anArrayList;
    public ArrayListComboBoxModel(ArrayList arrayList) {
        anArrayList = arrayList;
    }
    public Object getSelectedItem() {
        return selectedItem;
    }
    public void setSelectedItem(Object newValue) {
        selectedItem = newValue;
    }
    public int getSize() {
        return anArrayList.size();
    }
    public Object getElementAt(int i) {
        return anArrayList.get(i);
    }

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("ArrayListComboBoxModel");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
```

```

Collection<Object> col = System.getProperties().values();
ArrayList<Object> arrayList = new ArrayList<Object>(col);
ArrayListComboBoxModel model = new ArrayListComboBoxModel(arrayList);

JComboBox comboBox = new JComboBox (model);

frame.add(comboBox, BorderLayout.NORTH);
frame.setSize(300, 225);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Figure 13-3 shows the model in action using the current system properties as the source for the data model elements.




Figure 13-3. *Using an ArrayListComboBoxModel*

JList Class

The `JList` component is the basic Swing component for selecting one or more items from a set of choices. You present the list of choices to the user, and the user can pick one or several, depending on the selection mode of the component.

Three key elements and their implementations define the `JList` structure:

- A data model for holding the `JList` data, as defined by the `ListModel` interface
- A cell renderer for drawing the elements of the `JList`, as described by the `ListCellRenderer` interface
- A selection model for selecting elements of the `JList`, as described by the `ListSelectionModel` interface

Creating JList Components

The `JList` component has four constructors, which allow you to create a `JList` instance based on your initial data structure:

```
public JList()
JList jlist = new JList();

public JList(Object listData[])
String labels[] = { "Chardonnay", "Sauvignon", "Riesling", "Cabernet", "Zinfandel",
    "Merlot", "Pinot Noir", "Sauvignon Blanc", "Syrah", "Gewürztraminer"};
JList jlist = new JList(labels);

public JList(Vector listData)
Vector vector = aBufferedImage.getSources();
JList jlist = new JList(vector);

public JList(ListModel model)
ResultSet results = aJDBCStatement.executeQuery("SELECT colName FROM tableName");
DefaultListModel model = new DefaultListModel();
while (result.next())
    model.addElement(result.getString(1));
JList jlist = new JList(model);
```

If you use the no-argument constructor, you can fill in the data later. However, if you use the array or Vector constructor, you can't alter the contents without changing the whole model.

Note If you want to display something other than the toString() results of each array element, see the section “Rendering JList Elements” later in this chapter for details on how to do that.

JList Properties

After creating a JList component, you can modify each of its many properties. Table 13-5 shows the 32 properties of JList.

Table 13-5. *JList Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
anchorSelectionIndex	int	Read-only
cellRenderer	ListCellRenderer	Read-write bound
dragEnabled	boolean	Read-write
firstVisibleIndex	int	Read-only
fixedCellHeight	int	Read-write bound
fixedCellWidth	int	Read-write bound

Table 13-5. *JList Properties (Continued)*

Property Name	Data Type	Access
lastVisibleIndex	int	Read-only
layoutOrientation	int	Read-write bound
leadSelectionIndex	int	Read-only
listData	Vector	Write-only
listSelectionListeners	ListSelectionListener[]	Read-only
maxSelectionIndex	int	Read-only
minSelectionIndex	int	Read-only
model	ListModel	Read-write bound
preferredScrollableViewportSize	Dimension	Read-only
prototypeCellValue	Object	Read-write bound
scrollableTracksViewportHeight	boolean	Read-only
scrollableTracksViewportWidth	boolean	Read-only
selectedIndex	int	Read-write
selectedIndices	int[]	Read-write
selectedValue	Object	Read-only
selectedValues	Object[]	Read-only
selectionBackground	Color	Read-write bound
selectionEmpty	boolean	Read-only
selectionForeground	Color	Read-write bound
selectionMode	int	Read-write
selectionModel	ListSelectionModel	Read-write bound
UI	ListUI	Read-write
UIClassID	String	Read-only
valueIsAdjusting	boolean	Read-write
visibleRowCount	int	Read-write bound

Many of the `JList` properties are related to the process of selection. For instance, `anchorSelectionIndex`, `leadSelectionIndex`, `maxSelectionIndex`, `minSelectionIndex`, `selectedIndex`, and `selectedIndices` deal with the indices of the selected rows, while `selectedValue` and `selectedValues` relate to the contents of the selected elements. The `anchorSelectionIndex` is the most recent `index0` of a `ListDataEvent`, whereas the `leadSelectionIndex` is the most recent `index1`.

To control the preferred number of visible rows shown, set the `visibleRowCount` property of `JList`. The default setting for this property is 8.

Scrolling JList Components


When you're working with a `JList` component, you must place the component within a `JScrollPane` if you want to allow the user to pick from all available choices. If it's not placed within a `JScrollPane` and the default number of rows displayed is smaller than the size of the data model, or if there isn't sufficient space to display the rows, the other choices aren't shown. When placed within a `JScrollPane`, the `JList` offers a vertical scrollbar to move through all the available choices.

If you don't place a `JList` in a `JScrollPane` and the number of choices exceeds the available space, only the top group of choices will be visible, as you can see in Figure 13-4.



Figure 13-4. A ten-element `JList`, in and out of a `JScrollPane`

Tip Whenever you see that a class implements the `Scrollable` interface, it should serve as a reminder to place that component within a `JScrollPane` before adding it to the application.

The `JScrollPane` relies on the dimensions provided by the `preferredScrollable`  `ViewportSize` property setting to determine the preferred size of the pane contents. When the data model of a `JList` is empty, a default size of 16 pixels high by 256 pixels wide per visible row is used. Otherwise, the width is determined by looping through all the cells to find the widest one, and the height is determined by the height of the first cell.

To speed the sizing of the viewport for the `JScrollPane`, you can define a prototype cell by setting the `prototypeCellValue` property. You must be sure the `prototypeToString()` value is sufficiently wide and tall to accommodate all the contents of the `JList`. Then the `JScrollPane` bases the sizing of its viewport on the prototype, and it won't be necessary for the `JList` to ask each cell for its size; instead, it will ask only for the prototype.

You can also improve performance by assigning a size to the `fixedCellHeight` and `fixedCellWidth` properties. Setting these properties is another way to avoid having the `JList` ask each cell for its rendered size. Setting both properties is the fastest way to have a `JList` sized within a viewport. Of course, this is also the least flexible because it ensures that the `JList` choices aren't widened (or shortened) when the contents change. However, if you have a large number of entries in the data model, this loss of flexibility may be worthwhile to improve performance. Figure 13-5 helps you to visualize some of the sizing capabilities of a `JList`.




Figure 13-5. *Sizing entries within a JList*

The source used to generate the output in Figure 13-5 follows in Listing 13-3. The center list in the figure contains more than 1,000 fixed-size cells. The top list shows that you can set the number of visible rows with `setVisibleRowCount()`. Notice that the bottom list in the figure also uses `setVisibleRowCount()`. However, because the list isn't in a `JScrollPane`, the request to limit the number of rows is ignored.

Listing 13-3. *Sizing the List Cells*

```
import javax.swing.*;
import java.awt.*;

public class SizingSamples {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                String labels[] = {"Chardonnay", "Sauvignon", "Riesling", "Cabernet",
                                   "Zinfandel", "Merlot", "Pinot Noir", "Sauvignon Blanc", "Syrah",
                                   "Gewürztraminer"};

                JFrame frame = new JFrame("Sizing Samples");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JList jlist1 = new JList(labels);
                jlist1.setVisibleRowCount(4);
                DefaultListModel model = new DefaultListModel();
                model.ensureCapacity(1000);
                for (int i=0; i<100; i++) {
                    for (int j=0; j<10; j++) {
                        model.addElement(labels[j]);
                    }
                }
            }
        }
        runner.run();
    }
}
```

```

JScrollPane scrollPane1 = new JScrollPane(jlist1);
frame.add(scrollPane1, BorderLayout.NORTH);

JList jlist2 = new JList(model);
jlist2.setVisibleRowCount(4);
jlist2.setFixedCellHeight(12);
jlist2.setFixedCellWidth(200);
JScrollPane scrollPane2 = new JScrollPane(jlist2);
frame.add(scrollPane2, BorderLayout.CENTER);

JList jlist3 = new JList(labels);
jlist3.setVisibleRowCount(4);
frame.add(jlist3, BorderLayout.SOUTH);

frame.setSize(300, 350);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

In addition to placing a `JList` within a `JScrollPane`, you can also find out which choices are visible or request that a specific element be made visible. The `firstVisibleIndex` and `lastVisibleIndex` properties allow you to find out which choices are currently visible within the `JScrollPane`. Both methods return `-1` if nothing is visible; this usually happens where the data model is empty. To request that a specific element be made visible, use the public `void ensureIndexIsVisible(int index)` method. For instance, to programmatically move the list to the top, use the following:

```
jlist.ensureIndexIsVisible(0);
```

Rendering JList Elements

Every element within the `JList` is called a *cell*. Every `JList` has an installed cell renderer that draws every cell when the list needs to be drawn. The default renderer, `DefaultListCellRenderer`, is a subclass of `JLabel`, which means you can use either text or an icon as the graphical depiction for the cell. This tends to suit most users' needs, but sometimes the cell's appearance can benefit from some customization. And, because every `JList` can have at most one renderer installed, customization requires that you replace the existing renderer.

ListCellRenderer Interface and DefaultListCellRenderer Class

The `JList` has an installed renderer. A class that implements the `ListCellRenderer` interface provides this renderer.

```

public interface ListCellRenderer {
    public Component getListCellRendererComponent(JList list, Object value,
        int index, boolean isSelected, boolean cellHasFocus);
}

```

When it's time to draw each cell, the interface's sole method is called. The returned renderer provides the specific rendering for that one cell of the `JList`. The `JList` uses the rendering to draw the element, and then gets the next renderer.

A reference to the enclosing `JList` is provided to the `getListCellRendererComponent()` method so that the renderer can share display characteristics. The value of the selection contains the object in the list's data model at position `index`. The index is zero-based from the beginning of the data model. The last two parameters allow you to customize the cell's appearance based on the cell's state—that is, whether it's selected or has the input focus.

Listing 13-4 shows a renderer that demonstrates this technique. The sole difference for this renderer is that the cell with the input focus has a titled border. After the renderer is created, you install it by setting the `cellRenderer` property of the `JList`.

■ Tip For performance reasons, it is best not to create the actual renderer in the `getListCellRendererComponent()` method. Either subclass `Component` and return this or create a class variable to hold one instance of a `Component`, which then may be customized and returned.

Listing 13-4. *Rendering the List Cells*

```
import java.awt.*;
import javax.swing.*;
import javax.swing.border.*;

public class FocusedTitleListCellRenderer implements ListCellRenderer {
    protected static Border noFocusBorder =
        new EmptyBorder(15, 1, 1, 1);
    protected static TitledBorder focusBorder =
        new TitledBorder(LineBorder.createGrayLineBorder(), "Focused");
    protected DefaultListCellRenderer defaultRenderer = new DefaultListCellRenderer();

    public String getTitle() {
        return focusBorder.getTitle();
    }

    public void setTitle(String newValue) {
        focusBorder.setTitle(newValue);
    }

    public Component getListCellRendererComponent(JList list, Object value,
        int index, boolean isSelected, boolean cellHasFocus) {
        JLabel renderer = (JLabel)defaultRenderer.getListCellRendererComponent(
            list, value, index, isSelected, cellHasFocus);
        renderer.setBorder(cellHasFocus ? focusBorder : noFocusBorder);
        return renderer;
    }
}
```

Caution A common mistake when creating your own renderer is forgetting to make the renderer component opaque. This causes the background coloration of the renderer to be ignored and the list container's background to bleed through. With the `DefaultListCellRenderer` class, the renderer component is already opaque.

A sample program that uses the new renderer follows in Listing 13-5. It doesn't do anything special other than install the custom cell renderer that was just created.

Listing 13-5. *Rendering List Cells Sample*

```
import javax.swing.*.*;
import java.awt.*.*;
public class CustomBorderSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                String labels[] = {"Chardonnay", "Sauvignon", "Riesling", "Cabernet",
                    "Zinfandel", "Merlot", "Pinot Noir", "Sauvignon Blanc", "Syrah",
                    "Gewürztraminer"};
                JFrame frame = new JFrame("Custom Border");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                JList jlist = new JList(labels);
                ListCellRenderer renderer = new FocusedTitleListCellRenderer();
                jlist.setCellRenderer(renderer);
                JScrollPane sp = new JScrollPane(jlist);
                frame.add(sp, BorderLayout.CENTER);
                frame.setSize(300, 200);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

Figure 13-6 shows the output of the sample program.




Figure 13-6. *A JList with a custom focus border cell renderer*

Creating a Complex ListCellRenderer

More often than not, custom cell renderers (like the one shown in Figure 13-6) are necessary when the data model consists of more complex data in each element—something not representable by a text string. For instance, Listing 13-6 shows the source for an example where each element of the data model consists of a font, foreground color, icon, and text string. Ensuring the proper usage of these elements within the renderer simply involves a little more work in configuring the renderer component. In this particular example, that data is stored within each element of an array in the data model. You could just as easily define a new class or use a hash table.

Listing 13-6. *Rendering Complex List Cells*

```
import java.awt.*;
import javax.swing.*;
import javax.swing.border.*;

public class ComplexCellRenderer implements ListCellRenderer {
    protected DefaultListCellRenderer defaultRenderer = new DefaultListCellRenderer();

    public Component getListCellRendererComponent(JList list, Object value, int index,
        boolean isSelected, boolean cellHasFocus) {
        Font theFont      = null;
        Color theForeground = null;
        Icon theIcon       = null;
        String theText      = null;

        JLabel renderer = (JLabel)defaultRenderer.getListCellRendererComponent(
            list, value, index, isSelected, cellHasFocus);

        if (value instanceof Object[]) {
            Object values[] = (Object[])value;
            theFont         = (Font)values[0];
            theForeground    = (Color)values[1];
            theIcon          = (Icon)values[2];
            theText          = (String)values[3];
        } else {
            theFont         = list.getFont();
            theForeground    = list.getForeground();
            theText         = "";
        }
        if (!isSelected) {
            renderer.setForeground(theForeground);
        }
        if (theIcon != null) {
            renderer.setIcon(theIcon);
        }
    }
}
```

```

        renderer.setText(theText);
        renderer.setFont(theFont);
        return renderer;
    }
}

```

This renderer merely customizes the renderer component returned by the `DefaultListCellRenderer`. The customization is based on the data model value being passed in as an array to the value argument of the `getListCellRendererComponent()` method.

Listing 13-7 shows the test class. This demonstration program reuses the `DiamondIcon` created in Chapter 4. Most of the code is for initialization of the data model.

Listing 13-7. *Rendering Complex List Cells Sample*

```

import javax.swing.*.*;
import java.awt.*.*;
public class ComplexRenderingSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {

                Object elements[][] = {
                    {new Font("Helvetica", Font.PLAIN, 20), Color.RED,
                     new DiamondIcon(Color.BLUE), "Help"},
                    {new Font("TimesRoman", Font.BOLD, 14), Color.BLUE,
                     new DiamondIcon(Color.GREEN), "Me"},
                    {new Font("Courier", Font.ITALIC, 18), Color.GREEN,
                     new DiamondIcon(Color.BLACK), "I'm"},
                    {new Font("Helvetica", Font.BOLD | Font.ITALIC, 12), Color.GRAY,
                     new DiamondIcon(Color.MAGENTA), "Trapped"},
                    {new Font("TimesRoman", Font.PLAIN, 32), Color.PINK,
                     new DiamondIcon(Color.YELLOW), "Inside"},
                    {new Font("Courier", Font.BOLD, 16), Color.YELLOW,
                     new DiamondIcon(Color.RED), "This"},
                    {new Font("Helvetica", Font.ITALIC, 8), Color.DARK_GRAY,
                     new DiamondIcon(Color.PINK), "Computer"}
                };

                JFrame frame = new JFrame("Complex Renderer");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JList jlist = new JList(elements);
                ListCellRenderer renderer = new ComplexCellRenderer();
                jlist.setCellRenderer(renderer);
                JScrollPane scrollPane = new JScrollPane(jlist);
                frame.add(scrollPane, BorderLayout.CENTER);
            }
        };
        runner.run();
    }
}

```

```

// JComboBox comboBox = new JComboBox(elements);
// comboBox.setRenderer(renderer);
// frame.add(comboBox, BorderLayout.NORTH);

frame.setSize(300, 200);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

The output of this example is shown in Figure 13-7.



Figure 13-7. Using a more complex list cell renderer

Tip When you create your own rendering components, you'll find it's best to start with the default list cell renderer. This allows you to focus on the specific details you're interested in. Otherwise, you'll need to worry about everything, such as the default selection foreground and background colors, and whether you've remembered to make the component opaque. Of course, if you want to configure everything yourself, feel free to do so.

Selecting JList Elements

By default, every `JList` component is in multiple-selection mode. This means that you can select multiple elements within the component. How you select multiple elements depends on the user interface you're employing. For instance, with the Ocean look and feel interface, `Ctrl-select` (Ctrl key and left mouse button on a right-handed mouse) acts as a selection toggle, and `Shift-select` acts as a means of range selection.

ListSelectionModel Interface and DefaultListSelectionModel Class

An implementation of the `ListSelectionModel` interface controls the selection mechanism for a `JList` component. The interface definition, shown here, defines constants for different selection modes and describes how to manage a list of `ListSelectionListener` objects. It also provides the means to describe several selection intervals.

```

public interface ListSelectionModel {
    // Constants
    public final static int MULTIPLE_INTERVAL_SELECTION;
    public final static int SINGLE_INTERVAL_SELECTION;
    public final static int SINGLE_SELECTION;
    // Properties
    public int getAnchorSelectionIndex();
    public void setAnchorSelectionIndex(int index);
    public int getLeadSelectionIndex();
    public void setLeadSelectionIndex(int index);
    public int getMaxSelectionIndex();
    public int getMinSelectionIndex();
    public boolean isSelectionEmpty();
    public int getSelectionMode();
    public void setSelectionMode(int selectionMode);
    public boolean getValueIsAdjusting();
    public void setValueIsAdjusting(boolean valueIsAdjusting);
    // Listeners
    public void addListSelectionListener(ListSelectionListener x);
    public void removeListSelectionListener(ListSelectionListener x);
    // Other methods
    public void addSelectionInterval(int index0, int index1);
    public void clearSelection();
    public void insertIndexInterval(int index, int length, boolean before);
    public boolean isSelectedIndex(int index);
    public void removeIndexInterval(int index0, int index1);
    public void removeSelectionInterval(int index0, int index1);
    public void setSelectionInterval(int index0, int index1);
}

```

Three different selection modes are available. Table 13-6 contains the name of each mode and its description.

Table 13-6. *ListSelectionModel Modes*

Mode	Description
SINGLE_SELECTION	One item at a time can be selected.
SINGLE_INTERVAL_SELECTION	One contiguous range of items can be selected.
MULTIPLE_INTERVAL_SELECTION	Any set of ranges can be selected.

Figure 13-8 shows you the results of each selection mode.




Figure 13-8. Visual representation of selection modes

To change the selection mode of a `JList`, set its `selectionMode` property to one of the `ListSelectionModel` constants shown in Table 13-6. For instance, the following would change a list to single-selection mode:

```
JList list = new JList(...);
list.setSelectionMode(ListSelectionModel.SINGLE_SELECTION);
```

The `DefaultListSelectionModel` class is the default implementation of the `ListSelectionModel` interface. You can examine any of its nine properties, shown in Table 13-7, to learn about the currently selected range.

Table 13-7. *DefaultListSelectionModel Properties*

Property Name	Data Type	Access
<code>anchorSelectionIndex</code>	<code>int</code>	Read-write
<code>leadAnchorNotificationEnabled</code>	<code>boolean</code>	Read-write
<code>leadSelectionIndex</code>	<code>int</code>	Read-write
<code>listSelectionListeners</code>	<code>ListSelectionListener[]</code>	Read-only
<code>maxSelectionIndex</code>	<code>int</code>	Read-only
<code>minSelectionIndex</code>	<code>int</code>	Read-only
<code>selectionEmpty</code>	<code>boolean</code>	Read-only
<code>selectionMode</code>	<code>int</code>	Read-write
<code>valueIsAdjusting</code>	<code>boolean</code>	Read-write

The selection model can show you what is currently being used in the multiple-selection mode when the `selectionEmpty` property is false. Simply ask each index between the minimum and maximum selection indices if it's selected with `public boolean isSelectedIndex(int index)`. Because multiple-selection mode supports noncontiguous areas, this is the only way to find out what's selected. However, the `selectedIndices` property of `JList` provides this information without you needing to check it manually.

Listening to JList Events with a ListSelectionListener

If you want to know when elements of a `JList` have been selected, you need to attach a `ListSelectionListener` to the `JList` or the `ListSelectionModel`. The `addListSelectionListener()` and `removeListSelectionListener()` methods of the `JList` only delegate to the underlying `ListSelectionModel`. When the set of selected elements changes, attached listener objects are notified. The interface definition follows:

```
public interface ListSelectionListener extends EventListener {
    public void valueChanged(ListSelectionEvent e);
}
```

The `ListSelectionEvent` instance received by the listener describes the range of affected elements for *this* selection event, as well as whether or not the selection is still changing, as shown in Table 13-8. When a user is still altering selected elements, with a `valueIsAdjusting` setting of `true`, you might want to delay performing costly operations such as drawing a high-resolution graphics presentation.

Table 13-8. *ListSelectionEvent Properties*

Property Name	Data Type	Access
<code>firstIndex</code>	<code>int</code>	Read-only
<code>lastIndex</code>	<code>int</code>	Read-only
<code>valueIsAdjusting</code>	<code>boolean</code>	Read-only

In order to demonstrate selection with a `JList`, the program shown in Listing 13-8 adds a `JTextArea` to a window to show the output of the selection listener. The listener prints out the currently selected items by item position and value.

Listing 13-8. *Rendering Complex List Cells Sample*

```
import javax.swing.*;
import javax.swing.event.*;
import java.awt.*;
import java.io.*;

public class SelectingJListSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                String labels[] = {"Chardonnay", "Sauvignon", "Riesling", "Cabernet",
                                   "Zinfandel", "Merlot", "Pinot Noir", "Sauvignon Blanc", "Syrah",
                                   "Gewürztraminer"};
                JFrame frame = new JFrame("Selecting JList");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
```

```

JList jlist = new JList(labels);
JScrollPane scrollPane1 = new JScrollPane(jlist);
frame.add(scrollPane1, BorderLayout.WEST);

final JTextArea textArea = new JTextArea();
textArea.setEditable(false);
JScrollPane scrollPane2 = new JScrollPane(textArea);
frame.add(scrollPane2, BorderLayout.CENTER);

ListSelectionListener listSelectionListener =
    new ListSelectionListener() {
    public void valueChanged(ListSelectionEvent listSelectionEvent) {
        StringWriter sw = new StringWriter();
        PrintWriter pw = new PrintWriter(sw);
        pw.print("First index: " + listSelectionEvent.getFirstIndex());
        pw.print(", Last index: " + listSelectionEvent.getLastIndex());
        boolean adjust = listSelectionEvent.getValueIsAdjusting();
        pw.println(", Adjusting? " + adjust);
        if (!adjust) {
            JList list = (JList)listSelectionEvent.getSource();
            int selections[] = list.getSelectedIndices();
            Object selectionValues[] = list.getSelectedValues();
            for (int i=0, n=selections.length; i<n; i++) {
                if (i==0) {
                    pw.print("  Selections: ");
                }
                pw.print(selections[i] + "/" + selectionValues[i] + " ");
            }
            pw.println();
        }
        textArea.append(sw.toString());
    }
};
jlist.addListSelectionListener(listSelectionListener);

frame.setSize(350, 200);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Note If you know that a `JList` is in single-selection mode, you can get the currently selected item with either the `selectedIndex` or `selectedValue` property.

Figure 13-9 shows the appearance of the running program.




Figure 13-9. *Listening for JList selections*

The example in Listing 13-8 prints out only the currently selected items when it is not doing a rapid update (when `isAdjusting` reports false). Otherwise, the program merely reports the starting and ending range of selection changes, as well as the adjusting status. The example examines the `selectedIndices` and `selectedValues` properties of `JList` to get an ordered list of selected items. The `selectedIndices` and `selectedValues` arrays are ordered in the same way, so a particular element of the data model will show up in the same position in both lists.

There's no special selection event for double-clicking an item in the list. If you're interested in double-click events, you need to fall back to the AWT `MouseEvent`/`MouseListener` pair. Adding the following code to the program in Listing 13-8 will add appropriate text to the `JTextArea` for double-click events. The key method here is the public `int locationToIndex(Point location)` method of `JList`, which attempts to map screen coordinates to list elements.

```
import java.awt.event.*;
...
MouseListener mouseListener = new MouseAdapter() {
    public void mouseClicked(MouseEvent mouseEvent) {
        JList theList = (JList)mouseEvent.getSource();
        if (mouseEvent.getClickCount() == 2) {
            int index = theList.locationToIndex(mouseEvent.getPoint());
            if (index >= 0) {
                Object o = theList.getModel().getElementAt(index);
                textArea.append("Double-clicked on: " + o.toString());
                textArea.append(System.getProperty("line.separator"));
            }
        }
    }
};
jlist.addMouseListener(mouseListener);
```

Note The `JList` class also provides the public `Point indexToLocation(int index)` method, which produces the reverse behavior, returning a `Point` as the origin of the provided index.

Manually Selecting JList Events

In addition to detecting when a user selects items in a list, you can also programmatically select or deselect items. If any `ListSelectionListener` objects are attached to the `JList`, they will also be notified when the set of selected items is programmatically altered. The following methods are available:

- For a single item, `public void setSelectedValue(Object element, boolean shouldScroll)` selects the first item that matches the `element`. If the element wasn't previously selected, everything that was selected will be deselected first.
- For a range of items, `public void setSelectedInterval(int index0, int index1)` selects an inclusive range.
- For adding a range of selected items to the already selected set, use `public void addSelectedInterval(int index0, int index1)`.
- You can clear all the selected items with the `public void clearSelection()` method.
- You can clear a range of selected items with the `public void removeSelectedInterval(int index0, int index1)` method.

Displaying Multiple Columns

Typically, whenever you work with a `JList`, you present its choices within a single column. While this is the usual manner of usage, the Swing `JList` control offers support for displaying its choices within multiple columns. Through the help of the `setLayoutOrientation()` method, you can set each `JList` orientation to lay out cells in columns horizontally or vertically. `JList.VERTICAL` is the default setting where everything appears in one column.

To lay out cells horizontally, before going to next row, use the value `JList.HORIZONTAL_WRAP`. For example, a list with nine elements would be displayed as shown here:

0	1	2
3	4	5
6	7	8

To lay out cells vertically, before going to next column, use the value `JList.VERTICAL_WRAP`. For example, a list with nine elements would be displayed as shown here:

0	3	6
1	4	7
2	5	8

Set the `visibleRowCount` property of `JList` to control the number of rows. Otherwise, the list width determines the row count for `HORIZONTAL_WRAP` and the list height for `VERTICAL_WRAP`.

Figure 13-10 shows a sample `JList` with horizontal wrap, presented as a 3×3 grid. Notice that it still supports multiple-selection mode.




Figure 13-10. A `JList` with horizontal wrap

Customizing a `JList` Look and Feel

Each installable Swing look and feel provides a different `JList` appearance and set of default `UIResource` value settings for the component. Figure 13-11 shows the appearance of the `JList` component for the preinstalled set of look and feel types: Motif, Windows, and Ocean.




Figure 13-11. `JList` under different look and feel types

The available set of `UIResource`-related properties for a `JList` is shown in Table 13-9. For the `JList` component, there are 17 different properties.

Table 13-9. *`JList` `UIResource` Elements*

Property String	Object Type
<code>List.actionMap</code>	<code>ActionMap</code>
<code>List.background</code>	<code>Color</code>
<code>List.border</code>	<code>Border</code>
<code>List.cellHeight</code>	<code>Integer</code>
<code>List.cellRenderer</code>	<code>ListCellRenderer</code>
<code>List.focusCellHighlightBorder</code>	<code>Border</code>
<code>List.focusInputMap</code>	<code>InputMap</code>
<code>List.focusInputMap.RightToLeft</code>	<code>InputMap</code>
<code>List.font</code>	<code>Font</code>
<code>List.foreground</code>	<code>Color</code>


Table 13-9. *JList UIResource Elements (Continued)*

Property String	Object Type
List.lockToPositionOnScroll	Boolean
List.rendererUseListColors	Boolean
List.rendererUseUIBorder	Boolean
List.selectionBackground	Color
List.selectionForeground	Color
List.timeFactor	Long
ListUI	String

As with most of the UIResource properties, the names of most of the properties are self-explanatory. One property, `List.timeFactor`, requires a bit of extra descriptive text. By default, the `JList` comes with behavior for keyboard selection. As you type, the `JList` will find the entry that matches what you've typed so far. This is done with the help of the public `int getNextMatch(String prefix, int startIndex, Position.Bias bias)` method. The “so far” bit is controlled by the `List.timeFactor` setting. As long as the delay between keystrokes doesn't exceed the number of milliseconds specified by `List.timeFactor` (default of 1000), the new key pressed is added to the prior keys. Once the factor is exceeded, the search string is reset.

Creating a Dual List Box

The example presented in this section creates a new Swing component called a `DualListBox`. The primary purpose of a dual list box is to create two lists of choices: one to pick from and one that makes up your result set. This works great when the initial choice list is sizable. Trying to multi-select from a `JList` that contains many selections across multiple screens can be annoying, especially if you happen to deselect what you've already selected because you didn't have the Shift or Ctrl key held down. With a dual list box, the user selects items in the first list and moves them into the second. The user can easily scroll through the two lists without fear of accidentally deselecting anything. Figure 13-12 shows how the `DualListBox` might look in use.

**Figure 13-12.** *The DualListBox in action*

To use this custom component, create it by calling the constructor, `DualListBox` `sdual = new DualListBox()`, and then fill it with data by using either `setSourceElements()` or `addSourceElements()`; each takes either a `ListModel` or an array argument. The add version supplements the existing choices, whereas the set version clears out the choices first. When it's time to ask the component what the user selected, you can ask for an `Iterator` of the chosen elements with `destinationIterator()`. Some properties you may want to change include the following:

- The source choices' title (Available Choices in the example)
- The destination choices' title (Your Choices in the example)
- The source or destination list cell renderer
- The source or destination visible row count
- The source or destination foreground color or background color

The complete source code for this new `DualListBox` component follows. Listing 13-9 contains the first class `SortedListModel`, which provides a sorted `ListModel`. Internally, this takes advantage of a `TreeSet`.

Listing 13-9. *Sorted List Model*

```
import javax.swing.*;
import java.util.*;

public class SortedListModel extends AbstractListModel {

    SortedSet<Object> model;

    public SortedListModel() {
        model = new TreeSet<Object>();
    }

    public int getSize() {
        return model.size();
    }

    public Object getElementAt(int index) {
        return model.toArray()[index];
    }

    public void add(Object element) {
        if (model.add(element)) {
            fireContentsChanged(this, 0, getSize());
        }
    }
}
```

```
public void addAll(Object elements[]) {
    Collection<Object> c = Arrays.asList(elements);
    model.addAll(c);
    fireContentsChanged(this, 0, getSize());
}

public void clear() {
    model.clear();
    fireContentsChanged(this, 0, getSize());
}

public boolean contains(Object element) {
    return model.contains(element);
}

public Object firstElement() {
    return model.first();
}

public Iterator iterator() {
    return model.iterator();
}

public Object lastElement() {
    return model.last();
}

public boolean removeElement(Object element) {
    boolean removed = model.remove(element);
    if (removed) {
        fireContentsChanged(this, 0, getSize());
    }
    return removed;
}
}
```

Listing 13-10 shows the `DualListBox` source. The included `main()` method demonstrates the component.

Listing 13-10. *Dual List Box Sample*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import java.util.Iterator;

public class DualListBox extends JPanel {
```

```

private static final Insets EMPTY_INSETS = new Insets(0,0,0,0);
private static final String ADD_BUTTON_LABEL = "Add >>";
private static final String REMOVE_BUTTON_LABEL = "<< Remove";
private static final String DEFAULT_SOURCE_CHOICE_LABEL =
    "Available Choices";
private static final String DEFAULT_DEST_CHOICE_LABEL =
    "Your Choices";
private JLabel sourceLabel;
private JList sourceList;
private SortedListModel sourceListModel;
private JList destList;
private SortedListModel destListModel;
private JLabel destLabel;
private JButton addButton;
private JButton removeButton;

public DualListBox() {
    initScreen();
}

public String getSourceChoicesTitle() {
    return sourceLabel.getText();
}

public void setSourceChoicesTitle(String newValue) {
    sourceLabel.setText(newValue);
}

public String getDestinationChoicesTitle() {
    return destLabel.getText();
}

public void setDestinationChoicesTitle(String newValue) {
    destLabel.setText(newValue);
}

public void clearSourceListModel() {
    sourceListModel.clear();
}

public void clearDestinationListModel() {
    destListModel.clear();
}

public void addSourceElements(ListModel newValue) {
    fillListModel(sourceListModel, newValue);
}

public void setSourceElements(ListModel newValue) {
    clearSourceListModel();
    addSourceElements(newValue);
}

public void addDestinationElements(ListModel newValue) {
    fillListModel(destListModel, newValue);
}
}

```

```
private void fillListModel(SortedListModel model, ListModel newValues) {
    int size = newValues.getSize();
    for (int i=0; i<size; i++) {
        model.add(newValues.getElementAt(i));
    }
}

public void addSourceElements(Object newValue[]) {
    fillListModel(sourceListModel, newValue);
}

public void setSourceElements(Object newValue[]) {
    clearSourceListModel();
    addSourceElements(newValue);
}

public void addDestinationElements(Object newValue[]) {
    fillListModel(destListModel, newValue);
}

private void fillListModel(SortedListModel model, Object newValues[]) {
    model.addAll(newValues);
}

public Iterator sourceIterator() {
    return sourceListModel.iterator();
}

public Iterator destinationIterator() {
    return destListModel.iterator();
}

public void setSourceCellRenderer(ListCellRenderer newValue) {
    sourceList.setCellRenderer(newValue);
}

public ListCellRenderer getSourceCellRenderer() {
    return sourceList.getCellRenderer();
}

public void setDestinationCellRenderer(ListCellRenderer newValue) {
    destList.setCellRenderer(newValue);
}

public ListCellRenderer getDestinationCellRenderer() {
    return destList.getCellRenderer();
}

public void setVisibleRowCount(int newValue) {
    sourceList.setVisibleRowCount(newValue);
    destList.setVisibleRowCount(newValue);
}

public int getVisibleRowCount() {
    return sourceList.getVisibleRowCount();
}
```

```

public void setSelectionBackground(Color newValue) {
    sourceList.setSelectionBackground(newValue);
    destList.setSelectionBackground(newValue);
}
public Color getSelectionBackground() {
    return sourceList.getSelectionBackground();
}
public void setSelectionForeground(Color newValue) {
    sourceList.setSelectionForeground(newValue);
    destList.setSelectionForeground(newValue);
}
public Color getSelectionForeground() {
    return sourceList.getSelectionForeground();
}
private void clearSourceSelected() {
    Object selected[] = sourceList.getSelectedValues();
    for (int i=selected.length-1; i >= 0; --i) {
        sourceListModel.removeElement(selected[i]);
    }
    sourceList.getSelectionModel().clearSelection();
}
private void clearDestinationSelected() {
    Object selected[] = destList.getSelectedValues();
    for (int i=selected.length-1; i >= 0; --i) {
        destListModel.removeElement(selected[i]);
    }
    destList.getSelectionModel().clearSelection();
}
private void initScreen() {
    setBorder(BorderFactory.createEtchedBorder());
    setLayout(new GridBagLayout());
    sourceLabel = new JLabel(DEFAULT_SOURCE_CHOICE_LABEL);
    sourceListModel = new SortedListModel();
    sourceList = new JList(sourceListModel);
    add(sourceLabel,
        new GridBagConstraints(0, 0, 1, 1, 0, 0, GridBagConstraints.CENTER,
            GridBagConstraints.NONE, EMPTY_INSETS, 0, 0));
    add(new JScrollPane(sourceList),
        new GridBagConstraints(0, 1, 1, 5, .5, 1, GridBagConstraints.CENTER,
            GridBagConstraints.BOTH, EMPTY_INSETS, 0, 0));

    addButton = new JButton(ADD_BUTTON_LABEL);
    add(addButton,
        new GridBagConstraints(1, 2, 1, 2, 0, .25, GridBagConstraints.CENTER,
            GridBagConstraints.NONE, EMPTY_INSETS, 0, 0));
    addButton.addActionListener(new AddListener());
    removeButton = new JButton(REMOVE_BUTTON_LABEL);

```

```

add(removeButton,
    new GridBagConstraints(1, 4, 1, 2, 0, .25, GridBagConstraints.CENTER,
        GridBagConstraints.NONE, new Insets(0,5,0,5), 0, 0));
removeButton.addActionListener(new RemoveListener());

destLabel = new JLabel(DEFAULT_DEST_CHOICE_LABEL);
destListModel = new SortedListModel();
destList = new JList(destListModel);
add(destLabel,
    new GridBagConstraints(2, 0, 1, 1, 0, 0, GridBagConstraints.CENTER,
        GridBagConstraints.NONE, EMPTY_INSETS, 0, 0));
add(new JScrollPane(destList),
    new GridBagConstraints(2, 1, 1, 5, .5, 1.0, GridBagConstraints.CENTER,
        GridBagConstraints.BOTH, EMPTY_INSETS, 0, 0));
}

private class AddListener implements ActionListener {
    public void actionPerformed(ActionEvent e) {
        Object selected[] = sourceList.getSelectedValues();
        addDestinationElements(selected);
        clearSourceSelected();
    }
}

private class RemoveListener implements ActionListener {
    public void actionPerformed(ActionEvent e) {
        Object selected[] = destList.getSelectedValues();
        addSourceElements(selected);
        clearDestinationSelected();
    }
}

public static void main(String args[]) {
    Runnable runner = new Runnable() {
        public void run() {
            JFrame frame = new JFrame("Dual List Box Tester");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
            DualListBox dual = new DualListBox();
            dual.addSourceElements(
                new String[] {"One", "Two", "Three"});
            dual.addSourceElements(
                new String[] {"Four", "Five", "Six"});
            dual.addSourceElements(
                new String[] {"Seven", "Eight", "Nine"});
            dual.addSourceElements(
                new String[] {"Ten", "Eleven", "Twelve"});
            dual.addSourceElements(
                new String[] {"Thirteen", "Fourteen", "Fifteen"});

```

```

        dual.addSourceElements(
            new String[] {"Sixteen", "Seventeen", "Eighteen"});
        dual.addSourceElements(
            new String[] {"Nineteen", "Twenty", "Thirty"});
        frame.add(dual, BorderLayout.CENTER);
        frame.setSize(400, 300);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Adding Element-Level Tooltips to List Items

As described in Chapter 4, all Swing components support displaying tooltip text. By calling the `setToolTipText()` method of a component, you can display any single text string over that component. In the case of a `JList` component (or for that matter, any component that contains multiple items such as a `JTree` or `JTable`), this single tooltip text string may not be sufficient. You may wish to display a different tip over each item in a component.

Displaying item-level tips takes a little more work. To display different tooltip text over each item, you must create a subclass of `JList`. From within this subclass, you must manually register the component with the `ToolTipManager`. This is normally done for you when you call `setToolTipText()`. But, because you won't be calling this method, you must manually notify the manager, as follows:

```
ToolTipManager.sharedInstance().registerComponent(this);
```

After you notify the `ToolTipManager`, the manager will then notify the component whenever the mouse moves over the component. This allows you to override the public `String getToolTipText(MouseEvent mouseEvent)` method to provide the appropriate tip for the item under the mouse pointer. Using some kind of `Hashtable`, `HashMap`, or `Properties` list allows you to map the item the mouse is over to item-specific tooltip text.

```

public String getToolTipText(MouseEvent event) {
    Point p = event.getPoint();
    int location = locationToIndex(p);
    String key = (String)model.getElementAt(location);
    String tip = tipProps.getProperty(key);
    return tip;
}

```

Figure 13-13 shows how the `PropertiesList` example class demonstrates various tooltips based on whichever element the mouse pointer is resting over. The complete source for the example follows in Listing 13-11.




Figure 13-13. A *JList* with different element-level tooltip text

Listing 13-11. Custom Tooltips for List Elements

```
import java.awt.*;
import java.awt.event.*;
import java.util.*;
import javax.swing.*;

public class PropertiesList extends JList {

    SortedListModel model;
    Properties tipProps;

    public PropertiesList(Properties props) {
        model = new SortedListModel();
        setModel(model);
        ToolTipManager.sharedInstance().registerComponent(this);

        tipProps = props;
        addProperties(props);
    }
    private void addProperties(Properties props) {
        // Load
        Enumeration names = props.propertyNames();
        while (names.hasMoreElements()) {
            model.add(names.nextElement());
        }
    }
}
```

```

public String getToolTipText(MouseEvent event) {
    Point p = event.getPoint();
    int location = locationToIndex(p);
    String key = (String)model.getElementAt(location);
    String tip = tipProps.getProperty(key);
    return tip;
}

public static void main (String args[]) {
    Runnable runner = new Runnable() {
        public void run() {
            JFrame frame = new JFrame("Custom Tip Demo");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
            Properties props = System.getProperties();
            PropertiesList list = new PropertiesList(props);
            JScrollPane scrollPane = new JScrollPane(list);
            frame.add(scrollPane);
            frame.setSize(300, 300);
            frame.setVisible(true);
        }
    };
    EventQueue.invokeLater(runner);
}
}

```

JComboBox Class

The `JComboBox` component of the Swing component set is a multiple-part component that allows a user to choose from a predefined set of choices with the help of a pull-down list. In its basic configuration, a `JComboBox` acts like a `JLabel` to display the current user selection. Embedded within the `JLabel` is a pop-up menu containing choices within a `JList` control. When the desired choice isn't available, the `JComboBox` can use a `JTextField` to enter a new choice. The `JList` part is automatically embedded within a `JScrollPane` when desired; you don't need to manually create the `JList` or place it in the `JScrollPane`. In addition, the text field for editing is disabled by default, permitting a user to select from the set of predefined choices only. Figure 13-14 illustrates two `JComboBox` components: one that is not editable showing its list of choices, and another that is editable and not showing its choices.




Figure 13-14. Sample `JComboBox` components

Four essential elements define the `JComboBox` component and its implementation:

- A data model for holding the `JComboBox` data, as defined by the `ListModel` interface
- A cell renderer for drawing the elements of the `JComboBox`, as described by the `ListCellRenderer` interface
- An editor for entering choices not part of the predefined data model, as defined by the `ComboBoxEditor` interface
- A keystroke manager for handling keyboard input to select elements of the `JComboBox`, as described by the `KeySelectionManager` interface

Many of the `JComboBox` capabilities are shared with the `JList` component. This isn't accidental; the two components are fairly similar. Let's now look at the `JComboBox` in more detail.

Creating JComboBox Components

Like the `JList` component, the `JComboBox` component has four constructors, allowing you to create one based on your initial data structure. *Unlike* the `JList` component, the default model used by the array and `Vector` constructor permits adding and removing data elements.

```
public JComboBox()
```

```
JComboBox comboBox = new JComboBox();
```

```
public JComboBox(Object listData[])
```

```
String labels[] = { "Chardonnay", "Sauvignon", "Riesling", "Cabernet", "Zinfandel",  
    "Merlot", "Pinot Noir", "Sauvignon Blanc", "Syrah", "Gewürztraminer"};
```

```
JComboBox comboBox = new JComboBox(labels);
```

```
public JComboBox(Vector listData)
```

```
Vector vector = aBufferedImage.getSources();
```

```
JComboBox comboBox = new JComboBox(vector);
```

```
public JComboBox(ComboBoxModel model)
```

```
ResultSet results = aJDBCStatement.executeQuery("SELECT columnName FROM tableName");
```

```
DefaultComboBoxModel model = new DefaultComboBoxModel();
```

```
while (result.next())
```

```
    model.addElement(results.getString(1));
```

```
JComboBox comboBox = new JComboBox(model);
```

JComboBox Properties

After you create a `JComboBox` component, you can modify each of its many properties. Table 13-10 shows the 22 properties of `JComboBox`.

Table 13-10. *JComboBox Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
action	Action	Read-write bound
actionCommand	String	Read-write
actionListeners	ActionListener[]	Read-only
editable	boolean	Read-write bound
editor	ComboBoxEditor	Read-write bound
enabled	boolean	Write-only bound
itemCount	int	Read-only
itemListeners	ItemListener[]	Read-only
keySelectionManager	JComboBox.KeySelectionManager	Read-write
lightWeightPopupEnabled	boolean	Read-write
maximumRowCount	int	Read-write bound
model	ComboBoxModel	Read-write bound
popupMenuListeners	PopupMenuListener[]	Read-only
popupVisible	boolean	Read-write
prototypeDisplayValue	Object	Read-write bound
renderer	ListCellRenderer	Read-write bound
selectedIndex	int	Read-write
selectedItem	Object	Read-write
selectedObjects	Object[]	Read-only
UI	ComboBoxUI	Read-write
UIClassID	String	Read-only

The significant properties of the `JComboBox` are concerned with the display of the pop-up list. You can control the maximum number of visible entries in the pop-up list by setting the `maximumRowCount` property. The `lightWeightPopupEnabled` property setting helps determine the type of window to use when displaying the pop-up menu of choices. If the component fits completely within the top-level window of the program, the component will be lightweight. If it doesn't fit, it will be heavyweight. If you're mixing AWT and Swing components in a program, you can force the pop-up menu of choices to be heavyweight by setting the `lightWeightPopupEnabled` property to `true`. This will force the pop-up to appear above other components. The remaining property related to the pop-up list is the `popupVisible` property, which allows you to programmatically display the pop-up list.

Note Besides setting the `popupVisible` property, you can use the public void `hidePopup()` and `showPopup()` methods to toggle the pop-up list's visibility status.

Rendering JComboBox Elements

The rendering of elements within a `JComboBox` is done with a `ListCellRenderer`. This is the same renderer that is used for a `JList` component. Once you've created a renderer for either one of these two components, you can use that renderer for the other component. To reuse the `ComplexCellRenderer` from earlier in the chapter (Listing 13-6), you could add the following lines to the `ComplexRenderingSample` example (Listing 13-7) to have the two components share the same renderer.

```
JComboBox comboBox = new JComboBox(elements);
comboBox.setRenderer(renderer);
frame.add(comboBox, BorderLayout.NORTH);
```

The result of adding these lines is shown in Figure 13-15.



Figure 13-15. A `JComboBox` with a custom renderer

Not all renderers will work as expected with both the `JComboBox` and `JList` components. For instance, the `FocusedTitleListCellRenderer` demonstrated earlier in Figure 13-6 wouldn't show the "Focused" title border in a `JComboBox` because the choices never had the input focus. In addition, different components may have different default colors (a different unselected background color, in this case). It may be necessary to ask what color the component normally would be rendered in, and then act accordingly.

Selecting JComboBox Elements

The `JComboBox` component supports at least three different events related to selection. You can listen for keyboard input to support key selection with the help of the `JComboBox.KeySelectionManager` class. You can also listen with an `ActionListener` or an `ItemListener` to find out when the selected item of the `JComboBox` changes.

If you want to programmatically select an element, use `public void setSelectedItem(Object element)` or `public void setSelectedIndex(int index)`.

Tip To programmatically deselect the current choice of a `JComboBox`, call `setSelectedIndex()` with an argument of `-1`.

Listening to Keyboard Events with a `KeySelectionManager`

The `JComboBox` has a public inner interface that's fairly important. `KeySelectionManager`, and its default implementation, manages selection from the keyboard of items within the `JComboBox`. The default manager locates the next element that corresponds to the pressed key. It has memory, so if you have entries that start with similar prefixes, users can continue typing until there is enough of a match to be unique. If you don't like this behavior, you can either turn it off or create a new key selection manager.

Note The `KeySelectionManager` works only in combo boxes that are not editable.

If you want to turn off the key-selection capabilities, you can't do so by simply setting the `keySelectionManager` property to null. Instead, you must create an implementation of the interface with an appropriate method. The single method of the interface is `public int selectionForKey(char aKey, ComboBoxModel aModel)`. In the event the pressed key doesn't match any elements, the routine needs to return `-1`. Otherwise, it should return the position of the matched element. So, to ignore keyboard input, the routine should always return `-1`, as shown here:

```
JComboBox.KeySelectionManager manager =
    new JComboBox.KeySelectionManager() {
        public int selectionForKey(char aKey, ComboBoxModel aModel) {
            return -1;
        }
    };
aJCombo.setKeySelectionManager(manager);
```

Listening to `JComboBox` Events with an `ActionListener`

The primary means of listening for selection events is through an `ActionListener`, possibly set with `setAction(Action)`. It will tell you when an element has been selected within a `JComboBox`. Unfortunately, the listener doesn't know which element is selected.

Note Setting the `ActionListener` through `setAction(Action)` also configures the tooltip text and the enabled state of the `JComboBox` based on the `Action`.

Because the `ActionListener` can't identify the selected element, it must ask the `JComboBox` that served as the source of the event. To determine the selected element from the `JComboBox`, use either `getSelectedItem()` or `getSelectedIndex()`. If an index of `-1` is returned, then the currently selected item isn't part of the model. This seemingly impossible situation happens when the `JComboBox` is editable and the user has entered a value that isn't part of the original model.

Note The text string `comboBoxChanged` is the action command for the `ActionEvent` sent to the `ActionListener` when an item within a `JComboBox` changes.

Listening to `JComboBox` Events with an `ItemListener`

If you use an `ItemListener` to find out when the selected item within a `JComboBox` changes, you'll also learn which item was deselected.

To demonstrate both the `ActionListener` and the `ItemListener`, the program shown in Listing 13-12 attaches both of them to the same `JComboBox`. The `ActionListener` prints its "action command," as well as the currently selected item. The `ItemListener` prints the affected item and the state change for it, as well as the currently selected item.

Listing 13-12. *JComboBox Selection Sample*

```
import javax.swing.*;
import javax.swing.event.*;
import java.awt.*;
import java.awt.event.*;
import java.io.*;

public class SelectingComboSample {
    static private String selectedString(ItemSelectable is) {
        Object selected[] = is.getSelectedObjects();
        return ((selected.length == 0) ? "null" : (String)selected[0]);
    }

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                String labels[] = {"Chardonnay", "Sauvignon", "Riesling", "Cabernet",
                    "Zinfandel", "Merlot", "Pinot Noir", "Sauvignon Blanc", "Syrah",
                    "Gewürztraminer"};
                JFrame frame = new JFrame("Selecting JComboBox");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JComboBox comboBox = new JComboBox(labels);
                frame.add(comboBox, BorderLayout.SOUTH);
```

```

final JTextArea textArea = new JTextArea();
textArea.setEditable(false);
JScrollPane sp = new JScrollPane(textArea);
frame.add(sp, BorderLayout.CENTER);

ItemListener itemListener = new ItemListener() {
    public void itemStateChanged(ItemEvent itemEvent) {
        StringWriter sw = new StringWriter();
        PrintWriter pw = new PrintWriter(sw);
        int state = itemEvent.getStateChange();
        String stateString =
            ((state == ItemEvent.SELECTED) ? "Selected" : "Deselected");
        pw.print("Item: " + itemEvent.getItem());
        pw.print(", State: " + stateString);
        ItemSelectable is = itemEvent.getItemSelectable();
        pw.print(", Selected: " + selectedString(is));
        pw.println();
        textArea.append(sw.toString());
    }
};
comboBox.addItemListener(itemListener);

ActionListener actionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        StringWriter sw = new StringWriter();
        PrintWriter pw = new PrintWriter(sw);
        pw.print("Command: " + actionEvent.getActionCommand());
        ItemSelectable is = (ItemSelectable)actionEvent.getSource();
        pw.print(", Selected: " + selectedString(is));
        pw.println();
        textArea.append(sw.toString());
    }
};
comboBox.addActionListener(actionListener);

frame.setSize(400, 200);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Figure 13-16 shows the results after the program has been running for some time.




Figure 13-16. *Listening for JComboBox selections*

Listening to JComboBox Events with a ListDataListener

You can attach a `ListDataListener` to the data model of the `JComboBox`. This listener would then be notified when the selected element of the model changes. Unfortunately, the listener would also be notified of other data model changes. In other words, using a `ListDataListener` to find out when an element of a `JComboBox` is selected is *not* a recommended option.

Note Mouse movement and cursor movement events within a `JComboBox` don't change the selected entry; mouse release events do change the selected entry. Any registered listeners would be notified when a selected mouse button is released over an element within the `JComboBox` pop-up list.

Editing JComboBox Elements

You may want to use a combo box like a text field in which you list the most likely text input from the user, but also allow the user to enter something else. By enabling the `editable` property of the `JComboBox`, you've added this capability. To demonstrate, Figure 13-17 shows an editable `JComboBox`. The window also contains a text area that reports the current selected item and index. Even if you manually enter one of the choices within the `JComboBox`, `getSelectedIndex()` will report the proper position. Remember that if you enter a value that's not present, `getSelectedIndex()` returns `-1`.




Figure 13-17. *Using an editable JComboBox*

The source for the example in Figure 13-17 is shown in Listing 13-13.

Listing 13-13. *Editable JComboBox Sample*

```

import java.awt.*;
import javax.swing.*;
import java.awt.event.*;
public class EditComboBox {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                String labels[] = {"Chardonnay", "Sauvignon", "Riesling", "Cabernet",
                    "Zinfandel", "Merlot", "Pinot Noir", "Sauvignon Blanc", "Syrah",
                    "Gewürztraminer"};
                JFrame frame = new JFrame("Editable JComboBox");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                final JComboBox comboBox = new JComboBox(labels);
                comboBox.setMaximumRowCount(5);
                comboBox.setEditable(true);
                frame.add(comboBox, BorderLayout.NORTH);

                final JTextArea textArea = new JTextArea();
                JScrollPane scrollPane = new JScrollPane(textArea);
                frame.add(scrollPane, BorderLayout.CENTER);

                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        textArea.append("Selected: " + comboBox.getSelectedItem());
                        textArea.append(", Position: " + comboBox.getSelectedIndex());
                        textArea.append(System.getProperty("line.separator"));
                    }
                };
                comboBox.addActionListener(actionListener);

                frame.setSize(300, 200);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

By default, the input field provided for editing is a `JTextField`. The default `JTextField` serves as a good editor if your data model consists of text strings. However, once your model contains a different type of object (for example, colors), you need to provide a different editor. By default, once you type in the text field (editing the results of `toString()` for your element), the object is treated as a `String`. Technically, a different editor isn't always necessary. If you can

parse the contents of the text field as a string to the proper data type, then do that. But, if you want to restrict the input in any manner (for example, allow only numeric input) or provide a better input mechanism, you must provide your own editor. The interface that defines the necessary behavior is called `ComboBoxEditor` and its definition is shown here.

```
public interface ComboBoxEditor {  
    // Properties  
    public Component getEditorComponent();  
    public Object getItem();  
    public void setItem(Object anObject);  
    // Listeners  
    public void addActionListener(ActionListener l);  
    public void removeActionListener(ActionListener l);  
    // Other methods  
    public void selectAll();  
}
```

Note The default editor is the `BasicComboBoxEditor` implementation in the `javax.swing.plaf.basic` package.

The `add/remove listener` methods are necessary for notifying any listeners when the `ComboBoxEditor` value has changed. It's not necessary for you to add a listener, and normally you won't do that. Nevertheless, the methods are part of the interface, so they'll need to be implemented if you want to provide your own editor.

The `getEditorComponent()` method returns the `Component` object used for the editor. You can use either an AWT or a Swing component for the editor (for example, a `JColorChooser` for color selection). The `selectAll()` method is called when the editor is first shown. It tells the editor to select everything within it. Selecting everything allows a user to merely type over the current input for the default `JTextField` case. Some editors may not require use of this method.

The item property methods demand the most work when you're providing a custom editor. You'll need to supply a method to map the specific pieces of the `Object` subclass to the components in order to present the data to be edited. You then need to get the data from the editor so that the data can be stored back in an instance of the original object.

To demonstrate, the source code in Listing 13-14 is a `ComboBoxEditor` for the `Color` class. A custom editor is necessary because there's no automatic way to parse the results of editing the default string shown for a `Color`. This editor will use a `JColorChooser` for the user to pick a new color value. The `getItem()` method needs to return only the current value, a `Color`. The `setItem()` method needs to convert the object passed to a `Color` object; the argument to `setItem()` is an `Object`. The `setItem()` method could be made to accept only `Color` arguments. However, for this example, any string that's decodable with the `Color.decode()` method is also supported.

Listing 13-14. *A Color Combo Box Editor*

```

import java.awt.*;
import javax.swing.*;
import javax.swing.event.*;
import java.awt.event.*;

public class ColorComboBoxEditor implements ComboBoxEditor {
    final protected JButton editor;
    protected EventListenerList listenerList = new EventListenerList();
    public ColorComboBoxEditor(Color initialColor) {
        editor = new JButton("");
        editor.setBackground(initialColor);
        ActionListener actionListener = new ActionListener() {
            public void actionPerformed(ActionEvent e) {
                Color currentBackground = editor.getBackground();
                Color color = JColorChooser.showDialog(
                    editor, "Color Chooser", currentBackground);
                if ((color != null) && (currentBackground != color)) {
                    editor.setBackground(color);
                    fireActionEvent(color);
                }
            }
        };
        editor.addActionListener(actionListener);
    }
    public void addActionListener(ActionListener l) {
        listenerList.add(ActionListener.class, l);
    }
    public Component getEditorComponent() {
        return editor;
    }
    public Object getItem() {
        return editor.getBackground();
    }
    public void removeActionListener(ActionListener l) {
        listenerList.remove(ActionListener.class, l);
    }
    public void selectAll() {
        // Ignore
    }
    public void setItem(Object newValue) {
        if (newValue instanceof Color) {
            Color color = (Color)newValue;
            editor.setBackground(color);
        } else {

```

```

        // Try to decode
        try {
            Color color = Color.decode(newValue.toString());
            editor.setBackground(color);
        } catch (NumberFormatException e) {
            // Ignore - value unchanged
        }
    }
}

protected void fireActionEvent(Color color) {
    Object listeners[] = listenerList.getListenerList();
    for (int i = listeners.length-2; i>=0; i-=2) {
        if (listeners[i] == ActionListener.class) {
            ActionEvent actionEvent =
                new ActionEvent(editor, ActionEvent.ACTION_PERFORMED, color.toString());
            ((ActionListener)listeners[i+1]).actionPerformed(actionEvent);
        }
    }
}
}
}
}

```

To use the new editor, you need to associate it with a `JComboBox`. After you change the `EditComboBox` example shown earlier (Listing 13-13) to make the data model consist of an array of `Color` objects, you can then install the editor by adding the following:

```

Color color = (Color)comboBox.getSelectedItem();
ComboBoxEditor editor = new ColorComboBoxEditor(color);
comboBox.setEditor(editor);

```

A complete test program follows in Listing 13-15. It's different from the `EditComboBox` because below the `JComboBox` is a `JLabel` that stays in sync with the currently selected color of the `JComboBox`. There's also a custom cell renderer that sets the background color to the value of the cell.

Listing 13-15. *Custom JComboBox Editor Sample*

```

import java.awt.*;
import javax.swing.*;
import java.awt.event.*;
public class ColorComboBox {
    static class ColorCellRenderer implements ListCellRenderer {
        protected DefaultListCellRenderer defaultRenderer =
            new DefaultListCellRenderer();
        // Width doesn't matter as the combo box will size
        private final static Dimension preferredSize = new Dimension(0, 20);
        public Component getListCellRendererComponent(JList list, Object value,
            int index, boolean isSelected, boolean cellHasFocus) {
            JLabel renderer = (JLabel)defaultRenderer.getListCellRendererComponent(
                list, value, index, isSelected, cellHasFocus);

```

```

        if (value instanceof Color) {
            renderer.setBackground((Color)value);
        }
        renderer.setPreferredSize(preferredSize);
        return renderer;
    }
}

public static void main(String args[]) {
    Runnable runner = new Runnable() {
        public void run() {
            Color colors[] = {Color.BLACK, Color.BLUE, Color.CYAN, Color.DARK_GRAY,
                Color.GRAY, Color.GREEN, Color.LIGHT_GRAY, Color.MAGENTA,
                Color.ORANGE, Color.PINK, Color.RED, Color.WHITE, Color.YELLOW};
            JFrame frame = new JFrame("Color JComboBox");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

            final JComboBox comboBox = new JComboBox(colors);
            comboBox.setMaximumRowCount(5);
            comboBox.setEditable(true);
            comboBox.setRenderer(new ColorCellRenderer());
            Color color = (Color)comboBox.getSelectedItem();
            ComboBoxEditor editor = new ColorComboBoxEditor(color);
            comboBox.setEditor(editor);
            frame.add(comboBox, BorderLayout.NORTH);

            final JLabel label = new JLabel();
            label.setOpaque(true);
            label.setBackground((Color)comboBox.getSelectedItem());
            frame.add(label, BorderLayout.CENTER);

            ActionListener actionListener = new ActionListener() {
                public void actionPerformed(ActionEvent actionEvent) {
                    Color selectedColor = (Color)comboBox.getSelectedItem();
                    label.setBackground(selectedColor);
                }
            };
            comboBox.addActionListener(actionListener);

            frame.setSize(300, 200);
            frame.setVisible(true);
        }
    };
    EventQueue.invokeLater(runner);
}
}

```

Figure 13-18 shows the screen and a visible editor.




Figure 13-18. *Using a custom ComboBoxEditor*

Customizing a JComboBox Look and Feel

Each installable Swing look and feel provides a different JComboBox appearance and set of default UIResource value settings for the component. Figure 13-19 shows the appearance of the JComboBox component for the preinstalled set of look and feel types: Motif, Windows, and Ocean.




Figure 13-19. *JComboBox under different look and feel types*

The available set of `UIResource`-related properties for a `JComboBox` is shown in Table 13-11. The `JComboBox` component has 21 different properties.

Table 13-11. *JComboBox UIResource Elements*

Property String	Object Type
<code>ComboBox.actionMap</code>	<code>ActionMap</code>
<code>ComboBox.ancestorInputMap</code>	<code>InputMap</code>
<code>ComboBox.background</code>	<code>Color</code>
<code>ComboBox.border</code>	<code>Border</code>
<code>ComboBox.buttonBackground</code>	<code>Color</code>
<code>ComboBox.buttonDarkShadow</code>	<code>Color</code>
<code>ComboBox.buttonHighlight</code>	<code>Color</code>
<code>ComboBox.buttonShadow</code>	<code>Color</code>
<code>ComboBox.control</code>	<code>Color</code>
<code>ComboBox.controlForeground</code>	<code>Color</code>
<code>ComboBox.disabledBackground</code>	<code>Color</code>
<code>ComboBox.disabledForeground</code>	<code>Color</code>
<code>ComboBox.font</code>	<code>Font</code>
<code>ComboBox.foreground</code>	<code>Color</code>
<code>ComboBox.rendererUseListColors</code>	<code>Boolean</code>
<code>ComboBox.selectionBackground</code>	<code>Color</code>
<code>ComboBox.selectionForeground</code>	<code>Color</code>
<code>ComboBox.showPopupOnNavigation</code>	<code>Boolean</code>
<code>ComboBox.timeFactor</code>	<code>Long</code>
<code>ComboBox.togglePopupText</code>	<code>String</code>
<code>ComboBoxUI</code>	<code>String</code>

Changing the pop-up icon is one example of customizing the look and feel. To do this, you'll need to install a new user interface. (This process is discussed at length in Chapter 20.) Basically, you inherit the default functionality from either the `BasicComboBoxUI` or `MetalComboBoxUI` user interface delegate, and then override only the protected `JButton createArrowButton()` method.

Figure 13-20 shows the results of this change to the `JComboBox` user interface.




Figure 13-20. *Altering the JComboBox pop-up button*

The source for the JComboBox example shown in Figure 13-20 follows in Listing 13-16.

Listing 13-16. *Custom JComboBox Pop-up Button*

```
import java.awt.*;
import javax.swing.*;
import javax.swing.plaf.*;
import javax.swing.plaf.basic.*;

public class PopupComboSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                String labels[] = {"Chardonnay", "Sauvignon", "Riesling", "Cabernet",
                                   "Zinfandel", "Merlot", "Pinot Noir", "Sauvignon Blanc", "Syrah",
                                   "Gewürztraminer"};
                JFrame frame = new JFrame("Popup JComboBox");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JComboBox comboBox = new JComboBox(labels);
                comboBox.setMaximumRowCount(5);
                comboBox.setUI((ComboBoxUI)MyComboBoxUI.createUI(comboBox));
                frame.add(comboBox, BorderLayout.NORTH);

                frame.setSize (300, 200);
                frame.setVisible (true);
            }
        };
        EventQueue.invokeLater(runner);
    }

    static class MyComboBoxUI extends BasicComboBoxUI {
        public static ComponentUI createUI(JComponent c) {
            return new MyComboBoxUI();
        }
    }
}
```

```

protected JButton createArrowButton() {
    JButton button = new BasicArrowButton(BasicArrowButton.EAST);
    return button;
}
}
}

```

Sharing the Data Model for a JComboBox and JList

You may have noticed several similarities between the parts that make up the JComboBox and JList. You can use the same data model and same renderer for both components. You've already seen how to share a renderer between components, in the "Rendering JComboBox Elements" section earlier in this chapter. The example presented in this section demonstrates how you could share the same data model across several components.

The example has two editable combo boxes and one JList, all sharing one data model. It also presents a button that you can click to dynamically add items to the data model. Because the data model will be associated with several components, you'll notice that each of them has additional options to choose from after selecting the button. Figure 13-21 shows what the screen might look like after adding several elements.




Figure 13-21. *Sharing a data model across components*

Listing 13-17 shows the source for the shared data model example.

Listing 13-17. Shared Data Model

```

import java.awt.*;
import java.awt.event.*;
import javax.swing.*;

public class SharedDataSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                final String labels[] = {"Chardonnay", "Sauvignon", "Riesling",
                    "Cabernet", "Zinfandel", "Merlot", "Pinot Noir", "Sauvignon Blanc",
                    "Syrah", "Gewürztraminer"};
            }
        };
    }
}

```

```

final DefaultComboBoxModel model = new DefaultComboBoxModel(labels);

JFrame frame = new JFrame("Shared Data");
frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

JPanel panel = new JPanel();
JComboBox comboBox1 = new JComboBox(model);
comboBox1.setMaximumRowCount(5);
comboBox1.setEditable(true);

JComboBox comboBox2 = new JComboBox(model);
comboBox2.setMaximumRowCount(5);
comboBox2.setEditable(true);
panel.add(comboBox1);
panel.add(comboBox2);
frame.add(panel, BorderLayout.NORTH);

JList jlist = new JList(model);
JScrollPane scrollPane = new JScrollPane(jlist);
frame.add(scrollPane, BorderLayout.CENTER);

JButton button = new JButton("Add");
frame.add(button, BorderLayout.SOUTH);
ActionListener actionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        int index = (int)(Math.random()*labels.length);
        model.addElement(labels[index]);
    }
};
button.addActionListener(actionListener);

frame.setSize(300, 200);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Note When running the program shown in Listing 13-17, if you share a data model across multiple `JComboBox` components, there can't be a different selected element within each component. When an element is "selected" in one, it's selected in all. This seems to be a bug in the MVC design of the `JComboBox`. In addition, because a `ListSelectionModel` manages selection for the `JList`, changing the selected element of a `JComboBox` has no effect on the selected elements within a `JList` sharing the same model.

Summary

This chapter has demonstrated how to use Swing's `JList` and `JComboBox` components. You've seen how both components support their own data model, renderer, selection capabilities, and even a custom editor for the `JComboBox` component. Although all these capabilities are customizable, each of the components is readily usable with its default configuration.

In Chapter 14, you will start to explore the Swing text components, including `TextField` and `TextArea`.



Spinner Model Controls

In the previous chapter, you learned how to work with the basic list controls: `JList` and `JComboBox`. In this chapter, you will move on to the `JSpinner` component, introduced with the 1.4 version of the JDK.

JSpinner Class

The `JSpinner` works like a cross between a `JList` or `JComboBox` component with a `JFormattedTextField`. In either the `JList` and `JComboBox` control, the user can select input from a predetermined set of values. The `JSpinner` also allows this type of selection. The other half of the component is the `JFormattedTextField`. How to display or enter the value isn't controlled by a list cell renderer, as in a `JList`; instead, you get a `JFormattedTextField` for entry and a couple of arrows on the side to navigate through the different values available for the text field. (The `JFormattedTextField` is covered in Chapters 15 and 16.)

Figure 14-1 shows what the spinner looks like for several different types of input. At the top of Figure 14-1 is a `JSpinner` with the days of the week in French provided to a `SpinnerListModel`. In the middle, you have a `JSpinner` for a date via the `SpinnerDateModel` class. On the bottom is the `JSpinner` usage with the `SpinnerNumberModel`. Each of these three work in its own mysterious way, as you'll learn later in this chapter.




Figure 14-1. *JSpinner examples*

Many classes are involved when creating and manipulating `JSpinner` components, foremost the `JSpinner` class itself. The primary two sets of classes involved are the `SpinnerModel` interface, for containing the set of selectable items for the control, and, the `JSpinner.DefaultEditor` implementations, for catching all the selections. Thankfully, many of the other classes involved work behind the scenes, so, for example, once you provide the numeric range in a `SpinnerNumberModel` and associate the spinner with its model, your work is essentially done.

Creating JSpinner Components

The JSpinner class includes two constructors for initializing the component:

```
public JSpinner()
JSpinner spinner = new JSpinner();

public JSpinner(SpinnerModel model)
SpinnerModel model = new SpinnerListModel(args);
JSpinner spinner = new JSpinner(model);
```

You can start with no data model and associate it later with the tracking method of JSpinner. Alternatively, you can start up the component with a full model, in an implementation of the SpinnerModel interface, of which three concrete subclasses are available: SpinnerDateModel, SpinnerListModel, and SpinnerNumberModel, along with their abstract parent class AbstractSpinnerModel. If you don't specify a model, the SpinnerNumberModel is used. While the renderer and editor for the component is a JFormattedTextField, the editing is basically done through a series of inner classes of JSpinner: DateEditor, ListEditor, and NumberFormat, with its support class in its parent DefaultEditor.

JSpinner Properties

In addition to creating the JSpinner object, you can certainly reconfigure it, through one of the nine properties listed in Table 14-1.

Table 14-1. *JSpinner Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
changeListeners	ChangeListener[]	Read-only
editor	JComponent	Read-write bound
model	SpinnerModel	Read-write bound
nextValue	Object	Read-only
previousValue	Object	Read-only
UI	SpinnerUI	Read-write
UIClassID	String	Read-only
value	Object	Read-write

The value property allows you to change the current setting for the component. The `nextValue` and `previousValue` properties allow you to peek at entries of the model in the different directions, without changing the selection within the application itself.

Listening for JSpinner Events with a ChangeListener

The JSpinner directly supports a single type of event listener: `ChangeListener`. Among other places, the listener is notified when the `commitEdit()` method is called for the associated component, telling you the spinner value changed. To demonstrate, Listing 14-1 attaches a custom `ChangeListener` to the source used to generate the program associated with Figure 14-1.

Listing 14-1. JSpinner with ChangeListener

```
import java.awt.*;
import javax.swing.*;
import javax.swing.event.*;
import java.text.*;
import java.util.*;

public class SpinnerSample {
    public static void main (String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("JSpinner Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                DateFormatSymbols symbols =
                    new DateFormatSymbols(Locale.FRENCH);
                ChangeListener listener = new ChangeListener() {
                    public void stateChanged(ChangeEvent e) {
                        System.out.println("Source: " + e.getSource());
                    }
                };

                String days[] = symbols.getWeekdays();
                SpinnerModel model1 = new SpinnerListModel(days);
                JSpinner spinner1 = new JSpinner(model1);
                spinner1.addChangeListener(listener);
                JLabel label1 = new JLabel("French Days/List");
                JPanel panel1 = new JPanel(new BorderLayout());
                panel1.add(label1, BorderLayout.WEST);
                panel1.add(spinner1, BorderLayout.CENTER);
                frame.add(panel1, BorderLayout.NORTH);
            }
        };
    }
}
```

```

SpinnerModel model2 = new SpinnerDateModel();
JSpinner spinner2 = new JSpinner(model2);
spinner2.addChangeListener(listener);
JLabel label2 = new JLabel("Dates/Date");
JPanel panel2 = new JPanel(new BorderLayout());
panel2.add(label2, BorderLayout.WEST);
panel2.add(spinner2, BorderLayout.CENTER);
frame.add(panel2, BorderLayout.CENTER);

SpinnerModel model3 = new SpinnerNumberModel();
JSpinner spinner3 = new JSpinner(model3);
spinner3.addChangeListener(listener);
JLabel label3 = new JLabel("Numbers");
JPanel panel3 = new JPanel(new BorderLayout());
panel3.add(label3, BorderLayout.WEST);
panel3.add(spinner3, BorderLayout.CENTER);
frame.add(panel3, BorderLayout.SOUTH);

frame.setSize(200, 90);
frame.setVisible (true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Running this program demonstrates the use of this listener (of course, you'll find far more meaningful ways to use a `ChangeListener`).

Customizing a JSpinner Look and Feel

As with all Swing components, the `JSpinner` control has a different appearance under each of the system-defined look and feel types, as shown in Figure 14-2. The component primarily looks just like a text field; the difference is in the drawing of the arrows.



Figure 14-2. *JSpinner under different look and feel types*

The set of 11 `UIResource` properties for a `JSpinner` is shown in Table 14-2. These are limited to drawing the text field and the arrows.

Table 14-2. *JSpinner UIResource Elements*

Property String	Object Type
Spinner.actionMap	ActionMap
Spinner.ancestorInputMap	InputMap
Spinner.arrowButtonBorder	Border
Spinner.arrowButtonInsets	Insets
Spinner.arrowButtonSize	Dimension
Spinner.background	Color
Spinner.border	Border
Spinner.editorBorderPainted	Boolean
Spinner.font	Font
Spinner.foreground	Color
SpinnerUI	String

SpinnerModel Interface

So far, you've seen how to interact with the main `JSpinner` class. The `SpinnerModel` interface is the data model for the component. The definition of `SpinnerModel` follows:

```
public interface SpinnerModel {
    // Properties
    public Object getValue();
    public void setValue(Object);
    public Object getNextValue();
    public Object getPreviousValue();
    // Listeners
    public void addChangeListener(ChangeListener);
    public void removeChangeListener(ChangeListener);
}
```

The six methods of `SpinnerModel` map directly to those of `JSpinner`. The `JSpinner` methods just redirect the method calls to that of the model, though in the case of the listener methods, the event source is where you attach the listener.

AbstractSpinnerModel Class

The base implementation of the `SpinnerModel` interface is the `AbstractSpinnerModel` class. It provides for the management and notification of the listener list. Subclasses must implement the other four value-related methods of the interface. Three concrete implementations of the `SpinnerModel` interface are provided: `SpinnerDateModel`, `SpinnerListModel`, and `SpinnerNumberModel`.

SpinnerDateModel Class

As might be inferred from its name, the `SpinnerDateModel` provides for the selection of dates. This class has two constructors: one that defaults to selecting all dates and another that allows you to limit the range.

```
public SpinnerDateModel()
SpinnerModel model = new SpinnerDateModel();
JSpinner spinner = new JSpinner(model);

public SpinnerDateModel(Date value, Comparable start, Comparable end,
    int calendarField)
Calendar cal = Calendar.getInstance();
Date now = cal.getTime();
cal.add(Calendar.YEAR, -50);
Date startDate = cal.getTime();
cal.add(Calendar.YEAR, 100);
Date endDate = cal.getTime();
SpinnerModel model =
    new SpinnerDateModel(now, startDate, endDate, Calendar.YEAR);
JSpinner spinner = new JSpinner(model);
```

If you don't specify any parameters, there is no start or end point. The example shown here uses parameters to provide a 100-year range. The last field should be one of the following constants from the `Calendar` class:

- `Calendar.AM_PM`
- `Calendar.DAY_OF_MONTH`
- `Calendar.DAY_OF_WEEK`
- `Calendar.DAY_OF_WEEK_IN_MONTH`
- `Calendar.DAY_OF_YEAR`
- `Calendar.ERA`
- `Calendar.HOUR`
- `Calendar.HOUR_OF_DAY`
- `Calendar.MILLISECOND`
- `Calendar.MINUTE`
- `Calendar.MONTH`
- `Calendar.SECOND`
- `Calendar.WEEK_OF_MONTH`
- `Calendar.WEEK_OF_YEAR`
- `Calendar.YEAR`

Note The `SpinnerDateModel` does not include any of the time zone-related constants of `Calendar`. You cannot scroll through those within a `JSpinner` via a `SpinnerDateModel`.

Table 14-3 lists the three properties from the `SpinnerModel` interface and four specific to the `SpinnerDateModel`.

Table 14-3. *SpinnerDateModel Properties*

Property Name	Data Type	Access
<code>calendarField</code>	<code>int</code>	Read-write
<code>date</code>	<code>Date</code>	Read-only
<code>end</code>	<code>Comparable</code>	Read-write
<code>nextValue</code>	<code>Object</code>	Read-only
<code>previousValue</code>	<code>Object</code>	Read-only
<code>start</code>	<code>Comparable</code>	Read-write
<code>value</code>	<code>Object</code>	Read-only

Typically, the only new property you'll use is for getting the final date, although all that does is wrap the result of `getValue()` in the appropriate data type. If you've provided a range of dates to the constructor, the previous or next values will be `null` when the current value is at an edge condition.

SpinnerListModel Class

The `SpinnerListModel` provides for selection from a list of entries, or at least their string representation. This class has three constructors:

```
public SpinnerListModel()
SpinnerModel model = new SpinnerListModel();
JSpinner spinner = new JSpinner(model);

public SpinnerListModel(List<?> values)
List<String> list = args;
SpinnerModel model = new SpinnerListModel(list);
JSpinner spinner = new JSpinner(model);

public SpinnerListModel(Object[] values)
SpinnerModel model = new SpinnerListModel(args);
JSpinner spinner = new JSpinner(model);
```

When no arguments are provided, the model contains a single element: the string empty. The List version retains a reference to the list. It does not copy the list. If you change the list, you change the elements in the model. The array version creates a private inner class instance of a List that can't be added to. For both the List and array versions, the initial selection will be the first element. If either is empty, an `IllegalArgumentException` will be thrown.

As shown in Table 14-4, the only property added beyond those from the interface is to get or set the list.

Table 14-4. *SpinnerListModel Properties*

Property Name	Data Type	Access
list	List<?>	Read-write
nextValue	Object	Read-only
previousValue	Object	Read-only
value	Object	Read-write

SpinnerNumberModel Class

The `SpinnerNumberModel` provides for the selection of a number from an open or closed range of values. That number can be any of the subclasses of `Number`, including `Integer` and `Double`. It has four constructors, with the first three provided just as convenience methods to the last.

```
public SpinnerNumberModel()
```

```
SpinnerModel model = new SpinnerNumberModel();
JSpinner spinner = new JSpinner(model);
```

```
public SpinnerNumberModel(double value, double minimum, double maximum,
    double stepSize)
```

```
SpinnerModel model = new SpinnerNumberModel(50, 0, 100, .25);
JSpinner spinner = new JSpinner(model);
```

```
public SpinnerNumberModel(int value, int minimum, int maximum, int stepSize)
```

```
SpinnerModel model = new SpinnerNumberModel(50, 0, 100, 1);
JSpinner spinner = new JSpinner(model);
```

```
public SpinnerNumberModel(Number value, Comparable minimum, Comparable maximum,
    Number stepSize)
```

```
Number value = new Integer(50);
Number min = new Integer(0);
Number max = new Integer(100);
Number step = new Integer(1);
SpinnerModel model = new SpinnerNumberModel(value, min, max, step);
JSpinner spinner = new JSpinner(model);
```

If the minimum or maximum value is null, the range is open-ended. For the no-argument version, the initial value is 0 and step is 1. The step size is literal, so if you set the step to .333, there will be no rounding off.

Table 14-5 shows the properties for `SpinnerNumberModel`. The added properties are the same as those provided by the constructor.

Table 14-5. *SpinnerNumberModel Properties*

Property Name	Data Type	Access
maximum	Comparable	Read-write
minimum	Comparable	Read-write
nextValue	Object	Read-only
number	Number	Read-only
previousValue	Object	Read-only
stepSize	Number	Read-write
value	Object	Read-write

Custom Models

Typically, the available models for the `JSpinner` are sufficient, so you don't need to subclass. However, that isn't always the case. For example, you might want to use a custom model that wraps the `SpinnerListModel`—instead of stopping at the first or last element, it wraps around to the other end. One such implementation is shown in Listing 14-2.

Listing 14-2. *RolloverSpinnerListModel Class*

```
import javax.swing.*.*;
import java.util.*;

public class RolloverSpinnerListModel extends SpinnerListModel {

    public RolloverSpinnerListModel(List<?> values) {
        super(values);
    }

    public RolloverSpinnerListModel(Object[] values) {
        super(values);
    }
}
```

```
public Object getNextValue() {
    Object returnValue = super.getNextValue();
    if (returnValue == null) {
        returnValue = getList().get(0);
    }
    return returnValue;
}

public Object getPreviousValue() {
    Object returnValue = super.getPreviousValue();
    if (returnValue == null) {
        List list = getList();
        returnValue = list.get(list.size() - 1);
    }
    return returnValue;
}
}
```

JSpinner Editors

For each of the models available for a `JSpinner`, a secondary support class, an inner class of `JSpinner`, is available. Whereas the model allows you to control what is selectable for the component, the spinner editors allow you to control how to display and edit each selectable value.

JSpinner.DefaultEditor Class

The `setEditor()` method of `JSpinner` allows you to have any `JComponent` as the editor for the `JSpinner`. While you certainly can do that, more typically, you will work with a subclass of `JSpinner.DefaultEditor`. It provides the basics you will need when working with simple editors based on `JFormattedTextField`. It contains a single constructor:

```
public JSpinner.DefaultEditor(JSpinner spinner)
JSpinner spinner = new JSpinner();
JComponent editor = JSpinner.DefaultEditor(spinner);
spinner.setEditor(editor);
```

As Table 14-6 shows, there are two properties for the editor.

Table 14-6. *JSpinner.DefaultEditor Properties*

Property Name	Data Type	Access
spinner	JSpinner	Read-only
textField	JFormattedTextField	Read-only

Without knowing which type of model you were working with, what you might do at this level is change some display characteristic of the `JFormattedTextField`. More typically, though, you'll change a custom aspect for the model's editor.

JSpinner.DateEditor Class

The `DateEditor` allows you to customize the date display (and entry) using various aspects of the `SimpleDateFormat` class of the `java.text` package. See the Javadoc for `SimpleDateFormat` for a complete listing of the available formatting patterns. If you don't like the default display output, you can modify it by passing in a new format to the second constructor.

```
public JSpinner.DateEditor(JSpinner spinner)
SpinnerModel model = new SpinnerDateModel();
JSpinner spinner = new JSpinner(model);
JComponent editor = JSpinner.DateEditor(spinner);
spinner.setEditor(editor);

public JSpinner.DateEditor(JSpinner spinner, String dateFormatPattern)
SpinnerModel model = new SpinnerDateModel();
JSpinner spinner = new JSpinner(model);
JComponent editor = JSpinner.DateEditor(spinner, "MMMM yyyy");
spinner.setEditor(editor);
```

By default, the format is `M/d/yy h:mm a`, or `12/25/04 12:34 PM` for some time on Christmas in 2004 (or 1904, 1804, and so on). The latter example will show December 2004.

The editor has the two properties shown in Table 14-7.

Table 14-7. *JSpinner.DateEditor Properties*

Property Name	Data Type	Access
<code>format</code>	<code>SimpleDateFormat</code>	Read-only
<code>model</code>	<code>SpinnerDateModel</code>	Read-only

JSpinner.ListEditor Class

When working with the `SpinnerListModel`, the `ListEditor` provides no special formatting support. Instead, it offers type-ahead support. Since all entries of the model are known, the editor tries to match the characters the user has already entered with the start of one of those entries. There is only one constructor, but you should never need to access it.

```
public JSpinner.ListEditor(JSpinner spinner)
```

As shown in Table 14-8, `ListEditor` has only a single property.

Table 14-8. *JSpinner.ListEditor Properties*

Property Name	Data Type	Access
model	SpinnerListModel	Read-only

JSpinner.NumberEditor Class

The `NumberEditor` works in a manner similar to the `DateEditor`, allowing you to enter strings to customize the display format. Instead of working with the `SimpleDateFormat`, the `NumberEditor` is associated with the `DecimalFormat` class of the `java.text` package. Just like `DateEditor`, it has two constructors:

```
public JSpinner.NumberEditor(JSpinner spinner)
SpinnerModel model = new SpinnerNumberModel(50, 0, 100, .25);
JSpinner spinner = new JSpinner(model);
JComponent editor = JSpinner.NumberEditor(spinner);
spinner.setEditor(editor);

public JSpinner.NumberEditor(JSpinner spinner, String decimalFormatPattern)
SpinnerModel model = new SpinnerNumberModel(50, 0, 100, .25);
JSpinner spinner = new JSpinner(model);
JComponent editor = JSpinner.NumberEditor(spinner, "#,##0.###");
spinner.setEditor(editor);
```

The second constructor usage shows the default formatting string. It will try to use commas if the number is large enough, and it will not show decimals if the value is a whole number.

As shown in Table 14-9, this editor has two properties.

Table 14-9. *JSpinner.NumberEditor Properties*

Property Name	Data Type	Access
format	DecimalFormat	Read-only
model	SpinnerNumberModel	Read-only

Summary

In this chapter, you learned about Swing's `JSpinner` component. When your set of choices is limited to a fixed set or a range of values, a `JSpinner` allows you to select a value by spinning through the different choices. You learned how that set of choices could be provided: from a set of dates with the `SpinnerDateModel` and `DateEditor`, with the `SpinnerListModel` and `ListEditor`, or via the `SpinnerNumberModel` and `NumberEditor`.

Chapter 15 moves beyond selection from a range of values and on to where a user actually types in the whole content in the different text components.



Basic Text Components

Chapter 14 explored the dynamic input selection control offered with the `JSpinner` of the Swing component set. In this chapter, you will look at the basic capabilities of the Swing text components. The more advanced text component capabilities are covered in the next chapter.

The Swing component set features five text components. They all share a common parent class, `JTextComponent`, which defines the common behavior for all text controls.

The direct subclasses of `JTextComponent` are `JTextField`, `JTextArea`, and `JEditorPane`. `JTextField` is used for a single line of single-attributed text (that is, a single font and a single color). `JTextField` has a single subclass, `JPasswordField`, for when a `JTextField` needs to be used with an input mask for the entry of a password. `JTextArea` is used for multiple lines of single-attributed text input. `JEditorPane` is a generic editor that can support the editing of multiple-attributed input. Its subclass `JTextPane` is customized for input in plain-text style. In both cases, the input can be images as well as components, in addition to text.

Overview of the Swing Text Components

Like all other Swing components, text components live in an MVC world. The components shown in Figure 15-1, which is a class hierarchy diagram, are the various available UI delegates. The remaining part of the UI delegate model is the text view, which is based on the `View` class and discussed further in Chapter 16.

Note All `JTextComponent` subclasses are in the `javax.swing` package. With the exception of the event-related pieces, the support interfaces and classes discussed in this chapter are found in the `javax.swing.text` package (or a subpackage). The Swing-specific, text-related event pieces are found in the `javax.swing.event` package, with remaining bits in `java.awt.event` and `java.beans`.

The data model for each of the components is an implementation of the `Document` interface, of which there are five extensions (or implementations). The single-attributed components use the `PlainDocument` class as their data model, while the multiple-attributed components use `DefaultStyledDocument` as their model. Both of these classes subclass the `AbstractDocument` class, which defines their common `Document` interface implementation. The `DefaultStyledDocument` class also implements the `StyledDocument` interface, which is an extension of `Document` for supporting multiple-attributed content. An additional `Document` implementation, `HTMLDocument`,

JTextComponent Class

The `JTextComponent` class is the parent class for all the components used as textual views. It describes the common behavior shared by all text components. Among other things, this common behavior includes a `Highlighter` for selection support, a `Caret` for navigation throughout the content, a set of commands supported through the `actions` property (an array of `Action` implementers), a set of key bindings through a `Keymap` or `InputMap/ActionMap` combination, an implementation of the `Scrollable` interface so that each of the specific text components can be placed within a `JScrollPane`, and the text stored within the component. If that all sounds like a lot to manage, don't worry. This chapter will guide you through each of the pieces.

JTextComponent Properties

Table 15-1 shows the 27 properties of `JTextComponent`. These properties cover the range of capabilities you would expect from text components.

Table 15-1. *JTextComponent Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>actions</code>	<code>Action[]</code>	Read-only
<code>caret</code>	<code>Caret</code>	Read-write bound
<code>caretColor</code>	<code>Color</code>	Read-write bound
<code>caretListeners</code>	<code>CaretListener[]</code>	Read-only
<code>caretPosition</code>	<code>int</code>	Read-write
<code>componentOrientation</code>	<code>ComponentOrientation</code>	Write-only bound
<code>disabledTextColor</code>	<code>Color</code>	Read-write bound
<code>document</code>	<code>Document</code>	Read-write bound
<code>dragEnabled</code>	<code>boolean</code>	Read-write
<code>editable</code>	<code>boolean</code>	Read-write bound
<code>focusAccelerator</code>	<code>char</code>	Read-write bound
<code>highlighter</code>	<code>Highlighter</code>	Read-write bound
<code>inputMethodRequests</code>	<code>InputMethodRequests</code>	Read-only
<code>keymap</code>	<code>Keymap</code>	Read-write bound
<code>margin</code>	<code>Insets</code>	Read-write bound
<code>navigationFilter</code>	<code>NavigationFilter</code>	Read-write
<code>preferredScrollableViewportSize</code>	<code>Dimension</code>	Read-only
<code>scrollableTracksViewportHeight</code>	<code>boolean</code>	Read-only
<code>scrollableTracksViewportWidth</code>	<code>boolean</code>	Read-only

Table 15-1. *JTextComponent Properties (Continued)*

Property Name	Data Type	Access
selectedText	String	Read-only
selectedTextColor	Color	Read-write bound
selectionColor	Color	Read-write bound
selectionEnd	int	Read-write
selectionStart	int	Read-write
text	String	Read-write
UI	TextUI	Read-write

These properties can be grouped into eight basic categories:

- **Data model:** The document property is for the data model of all text components. The text property is used for treating this data model as a String.
- **Color:** The caretColor, disabledTextColor, selectedTextColor, and selectionColor properties, as well as the inherited foreground and background properties, specify the color for rendering the cursor, disabled text, selected text, selected text background, regular text, and regular text background.
- **Caret:** The caret, caretPosition, and navigationFilter properties are for navigating through the document.
- **Highlighter:** The highlighter, selectionStart, and selectionEnd properties are responsible for highlighting the selectedText section of the document.
- **Margin:** The margin property is for specifying how far the text contents appear from the edges of the text component.
- **Events:** The actions and keymap properties describe which capabilities the text component supports. In the case of the Action[] for the actions property, the capabilities are a series of ActionListener implementations that you can associate with components for event handling. For instance, instead of creating an ActionListener to perform cut, copy, and paste operations, you find the appropriate Action within the actions property and associate it with a component. The keymap property works in a similar manner, but it associates Action implementations with specific keys. For instance, it contains a key map entry for what to do when the PageUp key is pressed. The caretListeners property allows you to discover the set of CaretListener objects observing the text component. The dragEnabled setting describes if the component supports dragging text from within the component. (For information about drag-and-drop support within Swing, see Chapter 19.)
- **Scrollable interface:** The properties preferredScrollableViewportSize, scrollableTracksViewportHeight, and scrollableTracksViewportWidth are implementations of the respective Scrollable interface methods.

- **State:** The `editable` and `focusTraversable` properties describe various states of the text components. The `editable` property allows you to make a text component read-only. For the read-only `focusTraversable` property, text components are in the focus cycle (that is, they can be tabbed into) when they're enabled. The `focusAccelerator` is used when a neighboring `JLabel` has the text component set in its `labelFor` property, allowing you to use the visible mnemonic of the `JLabel` to move focus into the text component. The `componentOrientation` setting describes how the component's text will be drawn. Use this for languages like Hebrew where left-to-right is not necessarily the best way to draw characters. The `JTextComponent` inherits an `opaque` property from `JComponent`. When the `opaque` property is set to `false`, the contents of the area behind the text component bleed through, allowing you to have an image background if desired. See Figure 15-2 for how this might appear.

Listing 15-1 is the source code used to generate Figure 15-2. If you comment out the `setOpaque(false)` line, a background image will not be shown.




Figure 15-2. An opaque text component with an image background

Listing 15-1. Drawing in the Background of a Component

```
import javax.swing.*;
import java.awt.*;

public class BackgroundSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Background Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                final ImageIcon imageIcon = new ImageIcon("draft.gif");
                JTextArea textArea = new JTextArea() {
                    Image image = imageIcon.getImage();
                    Image grayImage = GrayFilter.createDisabledImage(image);
                    {setOpaque(false);} // instance initializer
                };
                frame.add(textArea);
                frame.setVisible(true);
            }
        };
        SwingUtilities.invokeLater(runner);
    }
}
```

```

        public void paint (Graphics g) {
            g.drawImage(grayImage, 0, 0, this);
            super.paint(g);
        }
    };
    JScrollPane scrollPane = new JScrollPane(textArea);
    frame.add(scrollPane, BorderLayout.CENTER);
    frame.setSize(250, 250);
    frame.setVisible(true);
}
}
};
EventQueue.invokeLater(runner);
}
}

```

JTextComponent Operations

The `JTextComponent` defines the basic framework for many of the operations performed on the text controls.

- **I/O:** The public void `read(Reader in, Object description)` and public void `write(Writer out)` methods (both throw `IOException`) allow you to read or write the text component contents with ease.
- **Clipboard access:** The public void `cut()`, public void `copy()`, and public void `paste()` methods provide direct access to the system clipboard.
- **Positioning:** The public void `moveCaretPosition(int position)` method allows you to position the caret. The position represents a one-dimensional location indicating the number of characters to precede the caret from the beginning of the text component.
- **Selection:** The public void `replaceSelection(String content)`, public void `selectAll()`, and public void `select(int selectionStart, int selectionEnd)` methods allow you to select part of the content within the component and replace the content that is selected.
- **Conversion:** The public `Rectangle modelToView(int position)` throws `BadLocationException` and public `int viewToModel(Point point)` methods allow you (or, more likely, allow the system) to map a position within the `JTextComponent` to a physical mapping within the representation of the contents for the specific text UI delegate.

Now that you've had an overview of the `JTextComponent` class, it's time to look at its different subclasses. First up is the `JTextField`, which will be used to demonstrate the operations just listed.

JTextField Class

The `JTextField` component is the text component for a single line of input. The data model for a `JTextField` is the `PlainDocument` implementation of the `Document` interface. The `PlainDocument` model limits input to single-attributed text, meaning that it must be a single font and color.

When the Enter key is pressed within the `JTextField`, it automatically notifies any registered `ActionListener` implementations.

Creating a `JTextField`

There are five constructors for the `JTextField` component:

```
public JTextField()
JTextField textField = new JTextField();

public JTextField(String text)
JTextField textField = new JTextField("Initial Text");

public JTextField(int columnWidth)
JTextField textField = new JTextField(14);

public JTextField(String text, int columnWidth)
JTextField textField = new JTextField("Initial Text", 14);

public JTextField(Document model, String text, int columnWidth)
JTextField textField = new JTextField(aModel, null, 14);
```

By default, you get an empty text field, zero columns wide, with a default initial model. You can specify the initial text for the `JTextField` and how wide you want the component to be. Width is specified as the number of *m* characters in the current font that will fit within the component. There's no restriction on the number of characters that can be input. If you specify the `Document` data model in the constructor, you will probably want to specify a `null` initial-text argument. Otherwise, the current contents of the document will be replaced by the initial text for the text field.

Using `JLabel` Mnemonics

In the discussion of mnemonics in Chapter 4, you learned that the various button classes can have a keyboard shortcut that causes the button component to be selected. The special mnemonic character is usually underlined to indicate this visually. If the user presses the mnemonic character, along with a platform-specific mnemonic activation key, such as `Alt` for both `Windows` and `UNIX`, the button is activated/selected. You can provide a similar capability for a `JTextField`, and all other text components, with the help of a `JLabel`.

You can set the display mnemonic for a label, but instead of selecting the label when the mnemonic key is pressed, selection causes an associated component to get the input focus. The display mnemonic is set with the public `void setDisplayedMnemonic(character)` method, in which `character` is either an `int` or a `char`. Using the `KeyEvent` constants when changing the mnemonic setting simplifies initialization considerably.

The following source demonstrates how to interconnect a specific `JLabel` and `JTextField`.

```
JLabel label = new JLabel("Name: ");
label.setDisplayedMnemonic(KeyEvent.VK_N);
JTextField textField = new JTextField();
label.setLabelFor(textField);
```

In addition to calling the `setDisplayedMnemonic()` method, you must also call the public `void setLabelFor(Component component)` method of `JLabel`. This configures the `JLabel` to move input focus to the text field when the special mnemonic value is pressed.

Figure 15-3 shows what this sample program might look like. The complete source for the program follows in Listing 15-2.




Figure 15-3. *Connecting a `JLabel` and a `JTextField`*

Listing 15-2. *Connected `JLabel` and `JTextField`*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class LabelSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Label Focus Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                JPanel panel = new JPanel(new BorderLayout());
                JLabel label = new JLabel("Name: ");
                label.setDisplayedMnemonic(KeyEvent.VK_N);
                JTextField textField = new JTextField();
                label.setLabelFor(textField);
                panel.add(label, BorderLayout.WEST);
                panel.add(textField, BorderLayout.CENTER);
                frame.add(panel, BorderLayout.NORTH);
                frame.add(new JButton("Somewhere Else"), BorderLayout.SOUTH);
                frame.setSize(250, 150);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

JTextField Properties

Table 15-2 lists the 14 properties of `JTextField`.

Table 15-2. *JTextField Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>actionCommand</code>	<code>String</code>	Write-only
<code>action</code>	<code>Action</code>	Read-write bound
<code>actionListeners</code>	<code>ActionListener[]</code>	Read-only
<code>actions</code>	<code>Action[]</code>	Read-only
<code>columns</code>	<code>int</code>	Read-write
<code>document</code>	<code>Document</code>	Write-only bound
<code>font</code>	<code>Font</code>	Write-only
<code>horizontalAlignment</code>	<code>int</code>	Read-write bound
<code>horizontalVisibility</code>	<code>BoundedRangeModel</code>	Read-only
<code>preferredSize</code>	<code>Dimension</code>	Read-only
<code>scrollOffset</code>	<code>int</code>	Read-write
<code>UIClassID</code>	<code>String</code>	Read-only
<code>validateRoot</code>	<code>boolean</code>	Read-only

There's a tight coupling between the `horizontalVisibility` and `scrollOffset` properties. The `BoundedRangeModel` for the `horizontalVisibility` property of `JTextField` represents the width range required for displaying the contents of the text field. If there isn't enough space to display the contents, the `scrollOffset` setting reflects how far off to the left the text has scrolled. As the user navigates through the text within the `JTextField`, the `scrollOffset` value is automatically updated. For example, the text field in Figure 15-4 contains the 26 letters of the alphabet plus the 10 cardinal numbers: `ABCDEFGHIJKLMNOPQRSTUVWXYZ1234567890`. Not all these characters fit in the field; therefore, the letters *A* through *J* have scrolled off to the left.



Figure 15-4. The `scrollOffset` property reflects how far to the left the field's contents have scrolled; here, it is not at zero, so the beginning contents (*A–J*) have scrolled off to the left.

By changing the `scrollOffset` setting, you can control which part of the text field is visible. To ensure that the beginning of the contents for the text field is visible, set the `scrollOffset` setting to zero. To make sure that the *end* of the contents is visible, you need to ask the `horizontalVisibility` property what the extent of the `BoundedRangeModel` is, to determine the width of the range, and then set the `scrollOffset` setting to the extent setting, as follows:

```
BoundedRangeModel model = textField.getHorizontalVisibility();
int extent = model.getExtent();
textField.setScrollOffset(extent);
```

By changing the `horizontalAlignment` property setting, you can right-, left-, or center-justify the contents of a `JTextField`. By default, the text alignment is left-justified. The public `void setHorizontalAlignment(int alignment)` method takes an argument of `JTextField.LEFT`, `JTextField.CENTER`, `JTextField.RIGHT`, `JTextField.LEADING` (the default), or `JTextField.TRAILING` to specify the contents alignment. Figure 15-5 shows how the alignment setting affects the contents.




Figure 15-5. *Text field alignments*

Note You can set the document property, inherited from `JTextComponent`, to any implementation of the `Document` interface. If you use a `StyledDocument` with a `JTextField`, the UI delegate will ignore all style attributes. The `StyledDocument` interface is discussed in Chapter 16.

JTextComponent Operations with a JTextField

Have you ever looked for an easy way to load or save the contents of a text component? The Swing text components provide such a method. Additionally, the Swing text components have built-in support to access the system clipboard for cut, copy, and paste operations. These operations are possible with all `JTextComponent` subclasses. They're shown here specifically for the `JTextField` because they need a specific implementation to be truly demonstrated. You can perform the same tasks with the `JPasswordField`, `JTextArea`, `JEditorPane`, and `JTextPane`.

Loading and Saving Content

With the public `void read(Reader in, Object description)` and `public void write(Writer out)` methods from `JTextComponent` (both throw an `IOException`), you can easily load and save the contents from any text component. With the `read()` method, the `description` argument is added as a property of the `Document` data model. This allows you to retain information about where the data came from. The following example demonstrates how to read in the contents of file name and store it in `textComponent`. The file name is automatically retained as the `description`.

```

FileReader reader = null;
try {
    reader = new FileReader(filename);
    textComponent.read(reader, filename);
} catch (IOException exception) {
    System.err.println("Load oops");
} finally {
    if (reader != null) {
        try {
            reader.close();
        } catch (IOException exception) {
            System.err.println("Error closing reader");
            exception.printStackTrace();
        }
    }
}
}

```

If you later wanted to get the description back from the data model, which happens to be the file name in this case, you would just ask, like this:

```

Document document = textComponent.getDocument();
String filename = (String)document.getProperty(Document.StreamDescriptionProperty);

```

The properties of the `Document` are simply another key/value lookup table. The key in this particular case is the class constant `Document.StreamDescriptionProperty`. If you don't want a description stored, you pass `null` as the description argument to the `read()` method. (The `Document` interface will be discussed in more detail later in this chapter.)

Before you can read a file into a text component, you need to create the file to read. This could be done outside a Java program, or you could use the `write()` method of `JTextComponent` to create the file. The following demonstrates how to use the `write()` method to write the contents. For simplicity's sake, it doesn't deal with getting the file name from the `Document`, because this would not be set initially.

```

FileWriter writer = null;
try {
    writer = new FileWriter(filename);
    textComponent.write(writer);
} catch (IOException exception) {
    System.err.println("Save oops");
} finally {
    if (writer != null) {
        try {
            writer.close();
        } catch (IOException exception) {
            System.err.println("Error closing writer");
            exception.printStackTrace();
        }
    }
}
}

```

Figure 15-6 shows a sample program that uses the loading and saving capabilities, with these options implemented through buttons (although Load and Save options are more commonly seen under a File menu). The Clear button clears the contents of the text field.




Figure 15-6. *Loading and saving a text component*

The source in Listing 15-3 puts all the pieces together in a sample program to demonstrate loading and saving streams.

Listing 15-3. *Loading and Saving Streams with a JTextComponent*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import javax.swing.text.*;
import java.io.*;

public class LoadSave {

    public static void main (String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                final String filename = "text.out";
                JFrame frame = new JFrame("Loading/Saving Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                final JTextField textField = new JTextField();
                frame.add(textField, BorderLayout.NORTH);

                JPanel panel = new JPanel();

                // Setup actions
                Action loadAction = new AbstractAction() {
                    {
                        putValue(Action.NAME, "Load");
                    }
                    public void actionPerformed(ActionEvent e) {
                        doLoadCommand(textField, filename);
                    }
                };
            }
        };
    }
}
```

```

JButton loadButton = new JButton (loadAction);
panel.add(loadButton);

Action saveAction = new AbstractAction() {
    {
        putValue(Action.NAME, "Save");
    }
    public void actionPerformed(ActionEvent e) {
        doSaveCommand(textField, filename);
    }
};
JButton saveButton = new JButton (saveAction);
panel.add(saveButton);

Action clearAction = new AbstractAction() {
    {
        putValue(Action.NAME, "Clear");
    }
    public void actionPerformed(ActionEvent e) {
        textField.setText("");
    }
};
JButton clearButton = new JButton (clearAction);
panel.add(clearButton);

frame.add(panel, BorderLayout.SOUTH);

frame.setSize(250, 150);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}

public static void doSaveCommand(JTextComponent textComponent,
    String filename) {
    FileWriter writer = null;
    try {
        writer = new FileWriter(filename);
        textComponent.write(writer);
    } catch (IOException exception) {
        System.err.println("Save oops");
        exception.printStackTrace();
    } finally {
        if (writer != null) {
            try {
                writer.close();
            }

```

```

        } catch (IOException exception) {
            System.err.println("Error closing writer");
            exception.printStackTrace();
        }
    }
}

public static void doLoadCommand(JTextComponent textComponent,
    String filename) {
    FileReader reader = null;
    try {
        reader = new FileReader(filename);
        textComponent.read(reader, filename);
    } catch (IOException exception) {
        System.err.println("Load oops");
        exception.printStackTrace();
    } finally {
        if (reader != null) {
            try {
                reader.close();
            } catch (IOException exception) {
                System.err.println("Error closing reader");
                exception.printStackTrace();
            }
        }
    }
}
}
}
}

```

Note By default, file reading and writing deals only with plain text. If the contents of a text component are styled, the styled attributes aren't saved. The `EditorKit` class can customize this loading and saving behavior. You'll explore that class in Chapter 16.

Accessing the Clipboard

To use the system clipboard for cut, copy, and paste operations, you do not need to manually concoct a Transferable clipboard object. Instead, you just call one of these three methods of the `JTextComponent` class: `public void cut()`, `public void copy()`, or `public void paste()`.

You could call these methods directly from `ActionListener` implementations associated with buttons or menu items, as in the following:

```

ActionListener cutListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        aTextComponent.cut();
    }
};

```

However, there is an easier way that doesn't require you to manually create the `ActionListener` implementations. This method involves finding an existing cut action by asking the text component. If you look at the set of `JTextComponent` properties in Table 15-1, you'll notice one property named `actions`, which is an array of `Action` objects. This property contains a predefined set of `Action` implementations that you can directly associate as an `ActionListener` with any button or menu item. Once you get the current actions for the text component, you can go through the array until you find the appropriate one. Because actions are named, you merely need to know the text string for the name. The `DefaultEditorKit` class has about 40 keys as public constants. Here is an example of getting the cut action:

```

Action actions[] = textField.getActions();
Action cutAction = TextUtilities.findAction(actions, DefaultEditorKit.cutAction);

```

All actions in the set for a text component are a type of `TextAction`, which is an extension of the `AbstractAction` class. The essential thing to know about a `TextAction` is that it acts on the last focused text component. (The `TextAction` class, along with the `DefaultEditorKit`, will be discussed more extensively in Chapter 16.) So, even though the preceding source fragment acquires the cut action from a text field, the same cut action would work for another text component on the same screen. Whichever text component had the input focus last would be the one cut when the specific `cutAction` is activated.

To help you visualize this behavior, Figure 15-7 shows a screen with a `JTextField` at the top, a `JTextArea` in the middle, and buttons on the bottom for the cut, copy, and paste operations (although these operations are more commonly available through an Edit menu). If you run the program, you'll notice that the cut, copy, and paste actions act on the last focused text component.



Figure 15-7. Accessing the system clipboard from a text component

The source code in Listing 15-4 is the complete example for finding an `Action` in the actions property array and using cut, copy, and paste.

Listing 15-4. *Accessing the System Clipboard*

```
import java.awt.*;
import java.awt.event.*;
import java.util.*;
import javax.swing.*;
import javax.swing.text.*;

public class CutPasteSample {
    public static void main (String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Cut/Paste Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JTextField textField = new JTextField();
                JTextArea textArea = new JTextArea();
                JScrollPane scrollPane = new JScrollPane(textArea);

                frame.add(textField, BorderLayout.NORTH);
                frame.add(scrollPane, BorderLayout.CENTER);

                Action actions[] = textField.getActions();

                Action cutAction =
                    TextUtilities.findAction(actions, DefaultEditorKit.cutAction);
                Action copyAction =
                    TextUtilities.findAction(actions, DefaultEditorKit.copyAction);
                Action pasteAction =
                    TextUtilities.findAction(actions, DefaultEditorKit.pasteAction);

                JPanel panel = new JPanel();
                frame.add(panel, BorderLayout.SOUTH);

                JButton cutButton = new JButton(cutAction);
                cutButton.setText("Cut");
                panel.add(cutButton);

                JButton copyButton = new JButton(copyAction);
                copyButton.setText("Copy");
                panel.add(copyButton);

                JButton pasteButton = new JButton(pasteAction);
                pasteButton.setText("Paste");
                panel.add(pasteButton);
            }
        };
        runner.run();
    }
}
```

```

        frame.setSize(250, 250);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

The example in Listing 15-4 uses the `TextUtilities` support class shown in Listing 15-5. There's no direct way to find out if a specific action for a specific key exists in the actions property array. Instead, you must manually search for it. The public static `Action findAction(Action actions[], String key)` method does the searching for you.

Listing 15-5. *TextUtilities Support Class*

```

import javax.swing.*;
import javax.swing.text.*;
import java.util.Hashtable;

public final class TextUtilities {
    private TextUtilities() {
    }

    public static Action findAction(Action actions[], String key) {
        Hashtable<Object, Action> commands = new Hashtable<Object, Action>();
        for (int i = 0; i < actions.length; i++) {
            Action action = actions[i];
            commands.put(action.getValue(Action.NAME), action);
        }
        return commands.get(key);
    }
}

```

Note For security reasons, the `cut()` and `copy()` methods of the `JPasswordField` class do not place the current contents onto the system clipboard (the system will beep instead). You can still `paste()` something from the clipboard into a `JPasswordField`, though.

Document Interface

The `Document` interface defines the data model for the different text components. Implementations of the interface are meant to store both the actual content as well as any information to mark up the content (with bold, italics, or color). While all the content will be text, the way in which the text component displays the content could result in nontextual output, such as an HTML renderer.

The data model is stored apart from the text component (the view). Therefore, if you're interested in monitoring changes to the content of a text component, you must watch the Document itself, not the text component, for changes. If the changes reach the text component, it's too late—the model has already changed. To listen for changes, attach a `DocumentListener` to the model. However, the more likely scenario for restricting input is to provide a custom model or attach a `DocumentFilter` to the `AbstractDocument`. You can also attach an `InputVerifier` to the text component. However, that wouldn't be used until the input focus tried to leave the component.

Note In addition to accessing the textual content through the Document interface, a framework is defined to support undo/redo capabilities. This will be explored in Chapter 21.

Now, let's look at the pieces that make up a Document. First, here's the base interface definition:

```
public interface Document {
    // Constants
    public final static String StreamDescriptionProperty;
    public final static String TitleProperty;
    // Listeners
    public void addDocumentListener(DocumentListener listener);
    public void removeDocumentListener(DocumentListener listener);
    public void addUndoableEditListener(UndoableEditListener listener);
    public void removeUndoableEditListener(UndoableEditListener listener);
    // Properties
    public Element getDefaultRootElement();
    public Position getEndPosition();
    public int getLength();
    public Element[ ] getRootElement();
    public Position getStartPosition();
    // Other methods
    public Position createPosition(int offset) throws BadLocationException;
    public Object getProperty(Object key);
    public String getText(int offset, int length) throws BadLocationException;
    public void getText(int offset, int length, Segment txt)
        throws BadLocationException;
    public void insertString(int offset, String str, AttributeSet a)
        throws BadLocationException;
    public void putProperty(Object key, Object value);
    public void remove(int offset, int len) throws BadLocationException;
    public void render(Runnable r);
}
```

The content within a Document is described by a series of elements in which each element implements the `Element` interface. Within each element, you can store attributes so that select

content can be made bold, italic, or colored. The elements don't store the content; they just hold the attributes. Therefore, one Document can be rendered differently from different Element sets.

The following is an example of a basic HTML document with a title and a bulleted list for content.

```
<html>

<head>
<title>Cards</title>
</head>

<body>

<h1>Suits:</h1>

<ul>
  <li>Clubs</li>
  <li>Diamonds</li>
  <li>Hearts</li>
  <li>Spades</li>
</ul>
</body>
</html>
```

Looking at the structure of the elements in this HTML document, you get a hierarchy as shown in Figure 15-8.




Figure 15-8. Examining the element makeup of a document

Although this particular document might not warrant it, multiple element hierarchies are possible. Each would store different attributes because a particular text component could have an alternative rendering of the content. Alternatively, different style sheets could be used to render the same HTML markup differently.

AbstractDocument Class

The AbstractDocument class provides the basic implementation of the Document interface. It defines the management of the listener lists, provides a read-write locking mechanism to ensure that content isn't corrupted, and enables a Dictionary for storing document properties.

Table 15-3 lists the 11 properties of the AbstractDocument class, of which 5 are defined by the Document interface itself.

Table 15-3. AbstractDocument Properties

Property Name	Data Type	Access
asynchronousLoadPriority*	int	Read-write
bidiRootElement*	Element	Read-only
defaultRootElement	Element	Read-only
documentFilter*	DocumentFilter	Read-write
documentListeners*	DocumentListener[]	Read-only
documentProperties*	Dictionary	Read-write
endPosition	Position	Read-only
length	int	Read-only
rootElements	Element[]	Read-only
startPosition	Position	Read-only
undoableEditListeners*	UndoableEditListener[]	Read-only

* These properties are specific to the AbstractDocument class. The remaining five properties are defined in the Document interface.

For the most part, you don't access any of these properties directly, except perhaps documentFilter. In the case of the documentProperties property, you get and set individual properties with the public Object getProperty(Object key) and public void putProperty(Object key, Object value) methods. For the length property, in most cases, you can simply ask for the text within a text component, and then get its length by using textComponent.getText().length().

The bidiRootElement property is for the bidirectional root element, which may be appropriate in certain Unicode character sets. You would normally just use the defaultRootElement. However, both are rarely accessed.

PlainDocument Class

The `PlainDocument` class is a specific implementation of the `AbstractDocument` class. It does not store any character-level attributes for the content. Instead, the elements describe where the content and each line in the content begin.

The program in Listing 15-6 walks through the Element tree for a `PlainDocument`, the model used for both the `JTextField` and the `JTextArea`.

Listing 15-6. *Element Walker*

```
import java.awt.*;
import java.awt.event.*;
import java.util.*;
import javax.swing.*;
import javax.swing.text.*;

public class ElementSample {
    public static void main (String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Element Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                final JTextArea textArea = new JTextArea();
                JScrollPane scrollPane = new JScrollPane(textArea);

                JButton button = new JButton("Show Elements");
                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        Document document = textArea.getDocument();
                        ElementIterator iterator = new ElementIterator(document);
                        Element element = iterator.first();
                        while (element != null) {
                            System.out.println(element.getStartOffset());
                            element = iterator.next();
                        }
                    }
                };
                button.addActionListener(actionListener);

                frame.add(scrollPane, BorderLayout.CENTER);
                frame.add(button, BorderLayout.SOUTH);

                frame.setSize(250, 250);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

Assume the contents of the `JTextArea` are as follows:

```
Hello, World
Welcome Home
Adios
```

The program would report `Element` objects starting at 0, 0, 13, and 26. The first 0 represents the start of the content; the second represents the start of the first line.

You'll learn more about `Element` in Chapter 16.

Filtering Document Models

In the AWT world, if you want to restrict input into a text field—such as to limit input to alphanumeric characters or to some numeric range of values—you attach a `KeyListener` and consume() keystrokes that you don't want to appear within the component. With the Swing text components, you could either create a new `Document` implementation and customize what's accepted in the `Document` or attach a `DocumentFilter` and let it filter input.

While you can certainly create a custom subclass of `Document`, the more object-oriented approach is to create a filter, as you don't want to change the `Document`; you just want to limit the input into the model. You then attach the newly created filter to the document by calling the `setDocumentFilter()` method of `AbstractDocument`. Filters work with both `PlainDocument` and `StyledDocument` subclasses.

`DocumentFilter` is a class, not an interface, so you must create a subclass of that to filter the text into the document of a text component. If you create a subclass of `DocumentFilter`, overriding these three methods allows you to customize input:

- `public void insertString(DocumentFilter.FilterBypass fb, int offset, String string, AttributeSet attributes):` Called when a text string is inserted into the `Document`.
- `public void remove(DocumentFilter.FilterBypass fb, int offset, int length):` Called when something is deleted.
- `public void replace(DocumentFilter.FilterBypass fb, int offset, int length, String text, AttributeSet attrs):` Called when something is inserted into the currently selected text.

To restrict input, just override each method and check to see if the new content would be valid. If the content would not be valid, reject it.

For example, to create a `DocumentFilter` subclass to limit to a numeric range, you need to override the behavior of `insertString()`, `remove()`, and `replace()`. Because you're ensuring that the input is numeric and within a valid range, you must validate the proposed input to see if it's acceptable. If it is acceptable, then you can modify the document model by calling the `insertString()`, `remove()`, or `replace()` method of the `DocumentFilter.FilterBypass` argument of each original method call. When the input is unacceptable, you throw a `BadLocationException`. Seeing this exception thrown ensures the input method framework understands the user input was invalid. This will typically trigger the system to beep. Listing 15-7 shows a custom document filter for limiting an integer range.

Listing 15-7. *Custom Document Filter*

```
import javax.swing.text.*;
import java.awt.Toolkit;

public class IntegerRangeDocumentFilter extends DocumentFilter {

    int minimum, maximum;
    int currentValue = 0;

    public IntegerRangeDocumentFilter(int minimum, int maximum) {
        this.minimum = minimum;
        this.maximum = maximum;
    }

    public void insertString(DocumentFilter.FilterBypass fb, int offset,
        String string, AttributeSet attr) throws BadLocationException {

        if (string == null) {
            return;
        } else {
            String newValue;
            Document doc = fb.getDocument();
            int length = doc.getLength();
            if (length == 0) {
                newValue = string;
            } else {
                String currentContent = doc.getText(0, length);
                StringBuffer currentBuffer = new StringBuffer(currentContent);
                currentBuffer.insert(offset, string);
                newValue = currentBuffer.toString();
            }
            currentValue = checkInput(newValue, offset);
            fb.insertString(offset, string, attr);
        }
    }

    public void remove(DocumentFilter.FilterBypass fb, int offset, int length)
        throws BadLocationException {

        Document doc = fb.getDocument();
        int currentLength = doc.getLength();
        String currentContent = doc.getText(0, currentLength);
        String before = currentContent.substring(0, offset);
        String after = currentContent.substring(length+offset, currentLength);
        String newValue = before + after;
        currentValue = checkInput(newValue, offset);
        fb.remove(offset, length);
    }
}
```

```

public void replace(DocumentFilter.FilterBypass fb, int offset, int length,
    String text, AttributeSet attrs) throws BadLocationException {

    Document doc = fb.getDocument();
    int currentLength = doc.getLength();
    String currentContent = doc.getText(0, currentLength);
    String before = currentContent.substring(0, offset);
    String after = currentContent.substring(length+offset, currentLength);
    String newValue = before + (text == null ? "" : text) + after;
    currentValue = checkInput(newValue, offset);
    fb.replace(offset, length, text, attrs);
}

private int checkInput(String proposedValue, int offset)
    throws BadLocationException {
    int newValue = 0;
    if (proposedValue.length() > 0) {
        try {
            newValue = Integer.parseInt(proposedValue);
        } catch (NumberFormatException e) {
            throw new BadLocationException(proposedValue, offset);
        }
    }
    if ((minimum <= newValue) && (newValue <= maximum)) {
        return newValue;
    } else {
        throw new BadLocationException(proposedValue, offset);
    }
}
}

```

Figure 15-9 shows the numeric range filter in use.




Figure 15-9. *Using a Document that restricts input to a range of values*

The sample program using the new `IntegerRangeDocumentFilter` follows in Listing 15-8.

Listing 15-8. *Program Using a Custom Document Filter*

```

import javax.swing.*;
import javax.swing.text.*;
import java.awt.*;
import java.awt.event.*;

public class RangeSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Range Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                frame.setLayout(new GridLayout(3, 2));

                frame.add(new JLabel("Range: 0-255"));
                JTextField textFieldOne = new JTextField();
                Document textDocOne = textFieldOne.getDocument();
                DocumentFilter filterOne = new IntegerRangeDocumentFilter(0, 255);
                ((AbstractDocument)textDocOne).setDocumentFilter(filterOne);
                frame.add(textFieldOne);

                frame.add(new JLabel("Range: -100-100"));
                JTextField textFieldTwo = new JTextField();
                Document textDocTwo = textFieldTwo.getDocument();
                DocumentFilter filterTwo = new IntegerRangeDocumentFilter(-100, 100);
                ((AbstractDocument)textDocTwo).setDocumentFilter(filterTwo);
                frame.add(textFieldTwo);

                frame.add(new JLabel("Range: 1000-2000"));
                JTextField textFieldThree = new JTextField();
                Document textDocThree = textFieldThree.getDocument();
                DocumentFilter filterThree = new IntegerRangeDocumentFilter(1000, 2000);
                ((AbstractDocument)textDocThree).setDocumentFilter(filterThree);
                frame.add(textFieldThree);

                frame.setSize(250, 150);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

If you try out this program, you'll notice a couple of interesting issues. The first text field, with a range of 0 to 255, works fine. You can enter and delete characters at will, as long as the content is within the range.

In the second text field, the valid range is –100 to +100. Although you can enter any of the 201 numbers into the text field, if you want a negative number, you need to enter something like 3, left arrow, and minus sign (-). Because the text field validates input with each key, the - by itself isn't valid. You would need to either specifically accept a - as valid input in the `checkInput()` method of the custom `DocumentFilter` or force users to enter negative numbers in an awkward manner.

The third text field presents an even more troublesome situation. The valid range of input is 1000–2000. As you press each key to enter a number, such as 1500, it's rejected. You can't build up the input to 1500 because, by themselves, 1, 5, and 0 are not valid input. Instead, to enter a number into this text field, you must enter it somewhere *else*, place it into the system clipboard, and then use Ctrl-V to paste it into the text field as the field's final value. You can't use Backspace to correct a mistake, because no three-digit numbers are valid.

While the `IntegerRangeDocumentFilter` class shown in Listing 15-7 presents a workable `DocumentFilter` for any integer range, it works best with ranges of positive numbers that begin at zero. If you don't mind seeing the temporarily invalid input in the fields, it may be better to just attach an `InputVerifier` to deal with validation when leaving the text field.

DocumentListener and DocumentEvent Interfaces

If you're interested in finding out when the content of a text component changes, you can attach an implementation of the `DocumentListener` interface to the `Document` model of the component.

```
public interface DocumentListener implements EventListener {
    public void changedUpdate(DocumentEvent documentEvent);
    public void insertUpdate(DocumentEvent documentEvent);
    public void removeUpdate(DocumentEvent documentEvent);
}
```

From the three interface methods, you can find out if the contents were added to (`insertUpdate()`), removed (`removeUpdate()`), or stylistically changed (`changedUpdate()`). Notice that the latter is an attribute change versus a content change.

The interface method will receive an instance of `DocumentEvent`, from which you can find out where the change occurred, as well as the type of change, as follows:

```
public interface DocumentEvent {
    public Document getDocument();
    public int getLength();
    public int getOffset();
    public DocumentEvent.EventType getType();
    public DocumentEvent.ElementChange getChange(Element element);
}
```

The offset property of the event is where the change started. The length property of the event tells the length of the change that happened. The type of the event can be derived from whichever one of the three `DocumentListener` methods were called. In addition, the `DocumentEvent.EventType` class has three constants—`CHANGE`, `INSERT`, and `REMOVE`—so you can find out which event type happened directly from the type property.

The `getChange()` method of `DocumentEvent` requires an `Element` to return a `DocumentEvent.ElementChange`. You normally use the default root element from the `Document`, as in the following example.

```
Document documentSource = documentEvent.getDocument();
Element rootElement = documentSource.getDefaultRootElement();
DocumentEvent.ElementChange change = documentEvent.getChange(rootElement);
```

Once you have your `DocumentEvent.ElementChange` instance, you can find out the added and removed elements, if you need that level of information.

```
public interface DocumentEvent.ElementChange {
    public Element[ ] getChildrenAdded();
    public Element[ ] getChildrenRemoved();
    public Element getElement();
    public int getIndex();
}
```

Caret and Highlighter Interfaces

Now that you understand the data model aspect of a text component, you can look at some aspects of its selection rendering through the `Caret` and `Highlighter` interfaces. Remember that these are properties of the text component, not the data model.

The `Caret` interface describes what's usually referred to as the *cursor*: the location in the document where you can insert text. The `Highlighter` interface provides the basis for how to paint selected text. These two interfaces, their related interfaces, and their implementations are rarely altered. The text components simply use their default implementations with the `DefaultCaret` and `DefaultHighlighter` classes.

Although you probably won't alter the caret and highlighter behavior for a text component, you should know that there are many interrelated classes working together. For the `Highlighter` interface, the predefined implementation is called `DefaultHighlighter`, which extends another implementation called `LayeredHighlighter`. The `Highlighter` also manages a collection of `Highlighter.Highlight` objects to designate highlighted sections.

The `DefaultHighlighter` creates a `DefaultHighlighter.HighlightPainter` to paint the highlighted section(s) of text. The `HighlightPainter` is an implementation of the `Highlighter.HighlightPainter` interface and extends the `LayeredHighlighter.LayerPainter` class. Each section to paint is described by a `Highlighter.Highlight`, where the `Highlighter` manages the set. The actual `HighlightPainter` is created by the `DefaultCaret` implementation.

The `Highlighter` interface describes how to paint selected text within a text component. If you don't like the color, you can simply change the `TextField.selectionBackground` UI property setting to a different color.

```
public interface Highlighter {
    // Properties
    public Highlighter.Highlight[ ] getHighlights();
    // Other methods
    public Object addHighlight(int p0, int p1, Highlighter.HighlightPainter p)
        throws BadLocationException;
```

```
public void changeHighlight(Object tag, int p0, int p1)
    throws BadLocationException;
public void deinstall(JTextComponent component);
public void install(JTextComponent component)
public void paint(Graphics g);
public void removeAllHighlights();
public void removeHighlight(Object tag);
}
```

The Caret interface describes the current cursor, as well as several selection attributes. Of the Highlighter and Caret interfaces, the latter is the one that you would actually use, although it isn't necessary to subclass it.

```
public interface Caret {
    // Properties
    public int getBlinkRate();
    public void setBlinkRate(int newValue);
    public int getDot();
    public void setDot(int newValue);
    public Point getMagicCaretPosition();
    public void setMagicCaretPosition(Point newValue);
    public int getMark();
    public boolean isSelectionVisible();
    public void setSelectionVisible(boolean newValue);
    public boolean isVisible();
    public void setVisible(boolean newValue);
    // Listeners
    public void addChangeListener(ChangeListener l);
    public void removeChangeListener(ChangeListener l);
    // Other methods
    public void deinstall(JTextComponent c);
    public void install(JTextComponent c);
    public void moveDot(int dot);
    public void paint(Graphics g);
}
```

Table 15-4 lists the six attributes of Caret.

Table 15-4. *Caret Properties*

Property Name	Data Type	Access
blinkRate	int	Read-write
dot	int	Read-write
magicCaretPosition	Point	Read-write
mark	int	Read-only
selectionVisible	boolean	Read-write
visible	boolean	Read-write

The `blinkRate` is the millisecond delay between the flashes of the caret. The `dot` property is the current position within the text component of the cursor. To move the cursor to another position so that some text will be highlighted, add a call to the `moveDot(int newPosition)` method. This sets the `mark` property to the old `dot` position and sets the new `dot` setting to the new position.

The `magicCaretPosition` property deals with moving up and down lines of different lengths. For example, suppose the following three lines of text were on your screen:

```
Friz Freleng
Mel Blanc
What's up Doc?
```

Now suppose that the current cursor position is between the *n* and *g* on the first line. If you pressed the down arrow twice, you would want the cursor to stay at the same horizontal position, instead of moving to the end of the shorter second line. It's the `magicCursorPosition` property that retains this information, so that the cursor ends up being between the *D* and the *o* in the third line. Without the magic position retained, the cursor would fall in between the *p* and the word space of the last line.

One useful instance of using the caret is to find the current screen location in response to a keystroke. That way, you can pop up a menu at the current cursor position. This would be similar to the Code Insights option in JBuilder or IntelliSense in Visual Studio, in which the tool helps you complete method calls by popping up a menu of methods. Given the current dot location in the model, map it to the position in the view with the public `Rectangle modelToView(int position)` method of `JTextComponent` (which can throw a `BadLocationException`). Then use the `Rectangle` returned as the location to pop up the menu, as shown in Figure 15-10.




Figure 15-10. Using the *Caret* to determine a pop-up location

The program in Listing 15-9 will show a `JPopupMenu` at the location where the period (.) key is pressed in the text field.

Listing 15-9. Mapping *Caret Location* to *Pop-Up Position*

```
import javax.swing.*;
import javax.swing.text.*;
import javax.swing.plaf.*;
import java.awt.*;
import java.awt.event.*;
```

```

public class PopupSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Popup Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                final JPopupMenu popup = new JPopupMenu();
                JMenuItem menuItem1 = new JMenuItem("Option 1");
                popup.add(menuItem1);

                JMenuItem menuItem2 = new JMenuItem("Option 2");
                popup.add(menuItem2);

                final JTextField textField = new JTextField();
                frame.add(textField, BorderLayout.NORTH);

                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        try {
                            int dotPosition = textField.getCaretPosition();
                            Rectangle popupLocation = textField.modelToView(dotPosition);
                            popup.show(textField, popupLocation.x, popupLocation.y);
                        } catch (BadLocationException badLocationException) {
                            System.err.println("Oops");
                        }
                    }
                };
                KeyStroke keystroke =
                    KeyStroke.getKeyStroke(KeyEvent.VK_PERIOD, 0, false);
                textField.registerKeyboardAction(actionListener, keystroke,
                    JComponent.WHEN_FOCUSED);

                frame.setSize(250, 150);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

CaretListener Interface and CaretEvent Class

You can listen for cursor movements in two ways: associate a `ChangeListener` with the `Caret` or associate a `CaretListener` with the `JTextComponent`. Working directly with the `JTextComponent` is the easier approach, though both will function equally well.

In the case of the `CaretListener`, there's a single method defined by the interface:

```
public interface CaretListener implements EventListener {
    public void caretUpdate (CaretEvent caretEvent);
}
```

When the listener is notified, a `CaretEvent` is sent, which reports on the new dot and mark locations.

```
public abstract class CaretEvent extends EventObject {
    public CaretEvent(Object source);
    public abstract int getDot();
    public abstract int getMark();
}
```

To demonstrate, Figure 15-11 shows a program with a `CaretListener` attached to the inner `JTextArea`. When the `CaretEvent` happens, the current dot value is sent to the top text field and the current mark setting is sent to the button. In the example, the cursor dot is at the beginning of the second line, with the mark at the end.




Figure 15-11. *CaretListener sample*

Listing 15-10 shows the source associated with the example in Figure 15-11.

Listing 15-10. *Listening for Caret Changes*

```
import javax.swing.*;
import javax.swing.event.*;
import java.awt.*;

public class CaretSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Caret Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JTextArea textArea = new JTextArea();
                JScrollPane scrollPane = new JScrollPane(textArea);
                frame.add(scrollPane, BorderLayout.CENTER);
            }
        };
        SwingUtilities.invokeLater(runner);
    }
}
```

```

        final JTextField dot = new JTextField();
        dot.setEditable(false);
        JPanel dotPanel = new JPanel(new BorderLayout());
        dotPanel.add(new JLabel("Dot: "), BorderLayout.WEST);
        dotPanel.add(dot, BorderLayout.CENTER);
        frame.add(dotPanel, BorderLayout.NORTH);

        final JTextField mark = new JTextField();
        mark.setEditable(false);
        JPanel markPanel = new JPanel(new BorderLayout());
        markPanel.add(new JLabel("Mark: "), BorderLayout.WEST);
        markPanel.add(mark, BorderLayout.CENTER);
        frame.add(markPanel, BorderLayout.SOUTH);

        CaretListener listener = new CaretListener() {
            public void caretUpdate(CaretEvent caretEvent) {
                dot.setText(Integer.toString(caretEvent.getDot()));
                mark.setText(Integer.toString(caretEvent.getMark()));
            }
        };

        textArea.addCaretListener(listener);

        frame.setSize(250, 150);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

NavigationFilter Class

Similar to the way you can limit input to the text component's document by associating a `DocumentFilter` with a `Document`, you can limit where the caret can go by associating a `NavigationFilter` with a `JTextComponent`. The class has three methods:

```

public void setDot(NavigationFilter.FilterBypass fb, int dot, Position.Bias bias)

public void moveDot(NavigationFilter.FilterBypass fb, int dot, Position.Bias bias)

public int getNextVisualPositionFrom(JTextComponent text, int pos,
    Position.Bias bias, int direction, Position.Bias[] biasRet)

```

To limit movement, you would typically override the first two, leaving the default implementation of the latter. For instance, Listing 15-11 shows a program that has a reserved area (say, the title of a report) at the beginning of the `JTextArea`. If you try to set or move the caret (dot) to the reserved area, the filter rejects the change and moves the caret to after the area.

Listing 15-11. *Restricting Caret Movement*

```

import javax.swing.*;
import javax.swing.text.*;
import javax.swing.event.*;
import java.awt.*;

public class NavigationSample {
    private static final String START_STRING = "Start\n";
    private static final int START_STRING_LENGTH = START_STRING.length();

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Navigation Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JTextArea textArea = new JTextArea(START_STRING);
                textArea.setCaretPosition(START_STRING_LENGTH);
                JScrollPane scrollPane = new JScrollPane(textArea);
                frame.add(scrollPane, BorderLayout.CENTER);

                NavigationFilter filter = new NavigationFilter() {
                    public void setDot(NavigationFilter.FilterBypass fb, int dot,
                        Position.Bias bias) {
                        if (dot < START_STRING_LENGTH) {
                            fb.setDot(START_STRING_LENGTH, bias);
                        } else {
                            fb.setDot(dot, bias);
                        }
                    }
                    public void moveDot(NavigationFilter.FilterBypass fb, int dot,
                        Position.Bias bias) {
                        if (dot < START_STRING_LENGTH) {
                            fb.setDot(START_STRING_LENGTH, bias);
                        } else {
                            fb.setDot(dot, bias);
                        }
                    }
                };

                textArea.setNavigationFilter(filter);

                frame.setSize(250, 150);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

Figure 15-12 shows the screen after typing some information into the text component.




Figure 15-12. *NavigationFilter sample*

Keymap Interface

In “MVC-speak,” the keymap property of the text component is the Controller part. It maps `KeyStroke` objects to individual actions through the `Keymap` interface. (The `KeyStroke` class was discussed in Chapter 2.) When you register the `KeyStroke` to the `JTextComponent` with `registerKeyboardAction()`, as in the `PopupSample` program shown in Listing 15-9 earlier in this chapter, the text component stores this mapping from `KeyStroke` to `Action` in a `Keymap`. For instance, the Backspace key is mapped to delete the previous character. If you want to add another binding, you just register another keystroke.

Note In reality, the `Keymap` is just a front to the `ActionMap/InputMap` pair. The `JTextComponent` relies on some internal workings to indirectly use the `ActionMap/InputMap` classes.

You can also add actions for keystrokes directly to the `Keymap`. This allows you to share a keymap across multiple text components, as long as they all share the same extended behavior.

```
public interface Keymap {
    // Properties
    public Action[ ] getBoundActions();
    public KeyStroke[ ] getBoundKeyStrokes();
    public Action getDefaultAction();
    public void setDefaultAction(Action action);
    public String getName();
    public Keymap getResolveParent();
    public void setResolveParent(Keymap parent);
    // Other methods
    public void addActionForKeyStroke(KeyStroke keystroke, Action action);
    public Action getAction(KeyStroke keystroke);
    public KeyStroke[ ] getKeyStrokesForAction(Action action);
    public boolean isLocallyDefined(KeyStroke keystroke);
    public void removeBindings();
    public void removeKeyStrokeBinding(KeyStroke keystroke);
}
```

For some applications, you may also want to *remove* keystrokes from the key map. For instance, the `JTextField` has an entry in the key map for the Enter key so that any registered `ActionListener` objects are notified. If the `JTextField` is on a screen where a button has been designated as the default, pressing Enter won't select the default button, as desired. Getting rid of the default behavior is a simple process of requesting the removal of the single `KeyStroke` from the `Keymap`, as shown here:

```
Keymap keymap = textField.getKeymap();
KeyStroke keystroke = KeyStroke.getKeyStroke(KeyEvent.VK_ENTER, 0, false);
keymap.removeKeyStrokeBinding(keystroke);
```

Then, when you press Enter in the text field, the default button is activated, as shown in Figure 15-13.




Figure 15-13. Using the default button after removing the Enter binding from the `Keymap`

The program source for the example in Figure 15-13 is shown in Listing 15-12.

Listing 15-12. Working with the Default Button

```
import javax.swing.*;
import javax.swing.text.*;
import java.awt.*;
import java.awt.event.*;

public class DefaultSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Default Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JTextField textField = new JTextField();
                frame.add(textField, BorderLayout.NORTH);

                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        System.out.println(actionEvent.getActionCommand() + " selected");
                    }
                };
            }
        };
    }
};
```

```

        JPanel panel = new JPanel();
        JButton defaultButton = new JButton("Default Button");
        defaultButton.addActionListener(actionListener);
        panel.add(defaultButton);

        JButton otherButton = new JButton("Other Button");
        otherButton.addActionListener(actionListener);
        panel.add(otherButton);

        frame.add(panel, BorderLayout.SOUTH);

        Keymap keymap = textField.getKeymap();
        KeyStroke keystroke =
            KeyStroke.getKeyStroke(KeyEvent.VK_ENTER, 0, false);
        keymap.removeKeyStrokeBinding(keystroke);

        frame.getRootPane().setDefaultButton(defaultButton);

        frame.setSize(250, 150);
        frame.setVisible(true);
    }
};
    EventQueue.invokeLater(runner);
}
}

```

JTextComponent.KeyBinding Class

The `JTextComponent` class stores the specific key bindings with the help of the `JTextComponent.KeyBinding` class. The current look and feel defines the default set of the key bindings for text components, such as the familiar Ctrl-X for cut, Ctrl-C for copy, and Ctrl-V for paste on a Microsoft Windows platform.

Handling JTextField Events

Dealing with events in Swing text components is completely different from dealing with events in AWT text components. Although you can still attach an `ActionListener` to listen for when the user presses the Enter key in the text field, attaching a `KeyListener` or a `TextListener` is no longer useful.

To validate input, it is better to attach an `InputVerifier` than a `FocusListener`. However, input validation tends to be best left to the `Document` to accomplish or implemented when a user submits a form.

Listening to JTextField Events with an ActionListener

The `JTextField` will notify any registered `ActionListener` objects when the user presses Enter from within the text field. The component sends an `ActionEvent` to the `ActionListener` objects.

Part of this `ActionEvent` is an action command. By default, the action command of the event is the current contents of the component. With the Swing `JTextField`, you can also set this action command to be something different from the content. The `JTextField` has an `actionCommand` property. When it is set to null (the default setting), the action command for the `ActionEvent` takes the contents of the component. However, if you set the `actionCommand` property for the `JTextField`, then that `actionCommand` setting is part of the `ActionEvent`.

The following code demonstrates this difference. There are two text fields. When Enter is pressed in the first text field, causing the registered `ActionListener` to be notified, “Yo” is printed out. When Enter is pressed in the second text field, the contents are printed out.

```
JTextField nameTextField = new JTextField();
JTextField cityTextField = new JTextField();
ActionListener actionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        System.out.println("Command: " + actionEvent.getActionCommand());
    }
};
nameTextField.setActionCommand("Yo");
nameTextField.addActionListener(actionListener);
cityTextField.addActionListener(actionListener);
```

Listening to JTextField Events with an KeyListener

With the Swing text components, you normally don’t listen for key events with a `KeyListener`—at least not to validate input. Running the following example demonstrates that you can still find out when a key has been pressed or released, not just when it has been typed.

```
KeyListener keyListener = new KeyListener() {
    public void keyPressed(KeyEvent keyEvent) {
        printIt("Pressed", keyEvent);
    }
    public void keyReleased(KeyEvent keyEvent) {
        printIt("Released", keyEvent);
    }
    public void keyTyped(KeyEvent keyEvent) {
        printIt("Typed", keyEvent);
    }
    private void printIt(String title, KeyEvent keyEvent) {
        int keyCode = keyEvent.getKeyCode();
        String keyText = KeyEvent.getKeyText(keyCode);
        System.out.println(title + " : " + keyText);
    }
};
nameTextField.addKeyListener(keyListener);
cityTextField.addKeyListener(keyListener);
```

Listening to JTextField Events with an InputVerifier

Implementing the `InputVerifier` interface allows you to do field-level validation of a `JTextField`. Before focus moves out of a text component, the verifier runs. If the input isn't valid, the verifier rejects the change and keeps input focus within the given component.

In the following example, if you try to move the input focus beyond the text field, you'll find that you can't, unless the contents of the text field are empty or the contents consist of the string "Exit".

```
InputVerifier verifier = new InputVerifier() {
    public boolean verify(JComponent input) {
        final JTextComponent source = (JTextComponent)input;
        String text = source.getText();
        if ((text.length() != 0) && !(text.equals("Exit"))) {
            Runnable runnable = new Runnable() {
                public void run() {
                    JOptionPane.showMessageDialog (source, "Can't leave.",
                        "Error Dialog", JOptionPane.ERROR_MESSAGE);
                }
            };
           .EventQueue.invokeLater(runnable);
            return false;
        } else {
            return true;
        }
    }
};
nameTextField.setInputVerifier(verifier);
cityTextField.setInputVerifier(verifier);
```

Listening to JTextField Events with a DocumentListener

To find out when the contents of the text component changed, you need to associate a listener with the data model. In this case, the data model is `Document` and the listener is a `DocumentListener`. The following example just tells you when and how the model changed. Remember that `changedUpdate()` is for attribute changes. Do not use a `DocumentListener` for input validation.

```
DocumentListener documentListener = new DocumentListener() {
    public void changedUpdate(DocumentEvent documentEvent) {
        printIt(documentEvent);
    }
    public void insertUpdate(DocumentEvent documentEvent) {
        printIt(documentEvent);
    }
    public void removeUpdate(DocumentEvent documentEvent) {
        printIt(documentEvent);
    }
    private void printIt(DocumentEvent documentEvent) {
        DocumentEvent.EventType type = documentEvent.getType();
```

```

String typeString = null;
if (type.equals(DocumentEvent.EventType.CHANGE)) {
    typeString = "Change";
} else if (type.equals(DocumentEvent.EventType.INSERT)) {
    typeString = "Insert";
} else if (type.equals(DocumentEvent.EventType.REMOVE)) {
    typeString = "Remove";
}
System.out.print("Type : " + typeString + " / ");
Document source = documentEvent.getDocument();
int length = source.getLength();
try {
    System.out.println("Contents: " + source.getText(0, length));
} catch (BadLocationException badLocationException) {
    System.out.println("Contents: Unknown");
}
}
};
nameTextField.getDocument().addDocumentListener(documentListener);
cityTextField.getDocument().addDocumentListener(documentListener);

```

Putting It All Together

Now that you've seen the usage of the listeners separately, let's put them all together within one example. Figure 15-14 shows the end result of this endeavor. Keep in mind that the magic word to tab out of a component is "Exit."




Figure 15-14. *JTextField event demonstration*

The source behind the program in Figure 15-14 is shown in Listing 15-13.

Listing 15-13. Text Event Handling

```

import javax.swing.*;
import javax.swing.text.*;
import javax.swing.event.*;
import java.awt.*;
import java.awt.event.*;

public class JTextFieldSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {

```

```

public void run() {
    JFrame frame = new JFrame("TextField Listener Example");
    frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

    JPanel namePanel = new JPanel(new BorderLayout());
    JLabel nameLabel = new JLabel("Name: ");
    nameLabel.setDisplayedMnemonic(KeyEvent.VK_N);
    JTextField nameTextField = new JTextField();
    nameLabel.setLabelFor(nameTextField);
    namePanel.add(nameLabel, BorderLayout.WEST);
    namePanel.add(nameTextField, BorderLayout.CENTER);
    frame.add(namePanel, BorderLayout.NORTH);

    JPanel cityPanel = new JPanel(new BorderLayout());
    JLabel cityLabel = new JLabel("City: ");
    cityLabel.setDisplayedMnemonic(KeyEvent.VK_C);
    JTextField cityTextField = new JTextField();
    cityLabel.setLabelFor(cityTextField);
    cityPanel.add(cityLabel, BorderLayout.WEST);
    cityPanel.add(cityTextField, BorderLayout.CENTER);
    frame.add(cityPanel, BorderLayout.SOUTH);

    ActionListener actionListener = new ActionListener() {
        public void actionPerformed(ActionEvent actionEvent) {
            System.out.println("Command: " + actionEvent.getActionCommand());
        }
    };
    nameTextField.setActionCommand("Yo");
    nameTextField.addActionListener(actionListener);
    cityTextField.addActionListener(actionListener);

    KeyListener keyListener = new KeyListener() {
        public void keyPressed(KeyEvent keyEvent) {
            printIt("Pressed", keyEvent);
        }
        public void keyReleased(KeyEvent keyEvent) {
            printIt("Released", keyEvent);
        }
        public void keyTyped(KeyEvent keyEvent) {
            printIt("Typed", keyEvent);
        }
        private void printIt(String title, KeyEvent keyEvent) {
            int keyCode = keyEvent.getKeyCode();
            String keyText = KeyEvent.getKeyText(keyCode);
            System.out.println(title + " : " + keyText + " / " +
                               keyEvent.getKeyChar());
        }
    };
};

```

```

nameTextField.addKeyListener(keyListener);
cityTextField.addKeyListener(keyListener);

InputVerifier verifier = new InputVerifier() {
    public boolean verify(JComponent input) {
        final JTextComponent source = (JTextComponent)input;
        String text = source.getText();
        if ((text.length() != 0) && !(text.equals("Exit"))) {
            JOptionPane.showMessageDialog (source, "Can't leave.",
                "Error Dialog", JOptionPane.ERROR_MESSAGE);
            return false;
        } else {
            return true;
        }
    }
};

nameTextField.setInputVerifier(verifier);
cityTextField.setInputVerifier(verifier);

DocumentListener documentListener = new DocumentListener() {
    public void changedUpdate(DocumentEvent documentEvent) {
        printIt(documentEvent);
    }
    public void insertUpdate(DocumentEvent documentEvent) {
        printIt(documentEvent);
    }
    public void removeUpdate(DocumentEvent documentEvent) {
        printIt(documentEvent);
    }
    private void printIt(DocumentEvent documentEvent) {
        DocumentEvent.EventType type = documentEvent.getType();
        String typeString = null;
        if (type.equals(DocumentEvent.EventType.CHANGE)) {
            typeString = "Change";
        } else if (type.equals(DocumentEvent.EventType.INSERT)) {
            typeString = "Insert";
        } else if (type.equals(DocumentEvent.EventType.REMOVE)) {
            typeString = "Remove";
        }
        System.out.print("Type : " + typeString + " / ");
        Document source = documentEvent.getDocument();
        int length = source.getLength();
    }
};

```

```
        try {
            System.out.println("Contents: " + source.getText(0, length));
        } catch (BadLocationException badLocationException) {
            System.out.println("Contents: Unknown");
        }
    }
};
nameTextField.getDocument().addDocumentListener(documentListener);
cityTextField.getDocument().addDocumentListener(documentListener);

frame.setSize(250, 100);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}
```

Customizing a JTextField Look and Feel

Each installable Swing look and feel provides a different JTextField appearance and set of default UIResource values. The available set of 25 UIResource-related properties for a JTextField is shown in Table 15-5.


Table 15-5. *JTextField UIResource Elements*

Property String	Object Type
text	Color
textHighlight	Color
textHighlightText	Color
textInactiveText	Color
TextField.actionMap	ActionMap
TextField.background	Color
TextField.border	Border
TextField.caretAspectRatio	Number
TextField.caretBlinkRate	Integer
TextField.caretForeground	Color
TextField.darkShadow	Color
TextField.disabledBackground	Color
TextField.focusInputMap	InputMap
TextField.font	Font

Table 15-5. *JTextField UIResource Elements (Continued)*

Property String	Object Type
<code>TextField.foreground</code>	Color
<code>TextField.highlight</code>	Color
<code>TextField.inactiveBackground</code>	Color
<code>TextField.inactiveForeground</code>	Color
<code>TextField.keyBindings</code>	<code>KeyBinding[]</code>
<code>TextField.light</code>	Color
<code>TextField.margin</code>	Insets
<code>TextField.selectionBackground</code>	Color
<code>TextField.selectionForeground</code>	Color
<code>TextField.shadow</code>	Color
<code>TextFieldUI</code>	String

Figure 15-15 shows the appearance of the `JTextField` component for the preinstalled set of look and feel types: Motif, Windows, and Ocean.

**Figure 15-15.** *JTextField under different look and feel types*

JPasswordField Class

The `JPasswordField` component is designed for input of passwords. Instead of echoing what the user types, a special input mask is displayed. It works like a `JTextField` with an input mask of *. You can't unset the mask, nor can you cut or copy the contents of the password component. The intention is to enhance security.

Creating a JPasswordField

The `JPasswordField` class has the same five constructors as the `JTextField`:

```
public JPasswordField()  
JPasswordField passwordField = new JPasswordField();  
  
public JPasswordField(String text)  
JPasswordField passwordField = new JPasswordField("Initial Password");  
  
public JPasswordField(int columnWidth)  
JPasswordField passwordField = new JPasswordField(14);  
  
public JPasswordField(String text, int columnWidth)  
JPasswordField passwordField = new JPasswordField("Initial Password", 14);  
  
public JPasswordField(Document model, String text, int columnWidth)  
JPasswordField passwordField = new JPasswordField(aModel, "Initial Password", 14);
```

With the no-argument constructor, you get an empty input field zero columns wide, a default initial Document model, and an echo character of *. Although you can specify the initial text in the constructor, you’re usually prompting a user for a password to verify the user’s identity, not to see if the user can submit a form. Therefore, a JPasswordField tends to be empty at startup. As with the JTextField, you can also specify the initial width, assuming that the layout manager of the container in which the JPasswordField is placed will honor this request.

You can also specify the Document data model for the password field in a constructor. When specifying the Document data model, you should specify a null initial-text argument; otherwise, the current contents of the document will be replaced by the initial text for the password field. In addition, you should *not* try to use a custom Document with a JPasswordField. Because the component doesn’t display any visual feedback besides how many characters have been entered, it can be confusing to a user if you tried to restrict input to only numeric data.

JPasswordField Properties

Table 15-6 shows the four properties of JPasswordField.

Table 15-6. *JPasswordField Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
echoChar	char	Read-write
password	char[]	Read-only
UIClassID	String	Read-only

Setting the echoChar property allows you to use a mask character other than the default asterisk (*) character. If the echoChar property is set to the character \ u0000 (0), the public boolean echoCharIsSet() method returns false. In all other cases, the method returns true.

Caution The `JPasswordField` also has a deprecated read-only text property, which you should avoid using. You should use the `password` property instead, because it returns a `char[]` that can be cleared immediately after usage. A `String` must wait for the garbage collector to dispose of it.

Customizing a `JPasswordField` Look and Feel

The `JPasswordField` is a subclass of a `JTextField`. It has the same appearance under all the predefined look and feel types as the `JTextField` (see Figure 15-15). The one difference is that the current `echoChar` property setting masks the content. This is shown in Figure 15-16. The top text component is a `JTextField`; the bottom one is a `JPasswordField`.




Figure 15-16. *`JPasswordField` sample in Ocean theme*

The set of 17 `UIResource`-related properties for a `JPasswordField` is shown in Table 15-7.

Table 15-7. *`JPasswordField` `UIResource` Elements*

Property String	Object Type
<code>PasswordField.actionMap</code>	<code>ActionMap</code>
<code>PasswordField.background</code>	<code>Color</code>
<code>PasswordField.border</code>	<code>Border</code>
<code>PasswordField.caretAspectRatio</code>	<code>Number</code>
<code>PasswordField.caretBlinkRate</code>	<code>Integer</code>
<code>PasswordField.caretForeground</code>	<code>Color</code>
<code>PasswordField.disabledBackground</code>	<code>Color</code>
<code>PasswordField.focusInputMap</code>	<code>InputMap</code>
<code>PasswordField.font</code>	<code>Font</code>
<code>PasswordField.foreground</code>	<code>Color</code>
<code>PasswordField.inactiveBackground</code>	<code>Color</code>
<code>PasswordField.inactiveForeground</code>	<code>Color</code>
<code>PasswordField.keyBindings</code>	<code>KeyBinding[]</code>

Table 15-7. *JPasswordField UIResource Elements (Continued)*

Property String	Object Type
PasswordField.margin	Insets
PasswordField.selectionBackground	Color
PasswordField.selectionForeground	Color
PasswordFieldUI	String

JFormattedTextField Class

The `JFormattedTextField` provides support for the input of formatted text. When the component is created, you define a mask for the input. That mask can be in the form of one of four styles: a `java.text.Format` object, an `AbstractFormatter`, an `AbstractFormatterFactory`, or an actual value of a different type (such as 3.141592).

The system provides several abstract formatters for you to work with, depending on the type of data you want a user to input. For instance, the `NumberFormatter` is available to enter numbers, and the `DateFormatter` is available for entering dates. There is also a `MaskFormatter` for describing input with edit strings, like "XXX-XX-XXX" for a United States social security number. If you want different display and edit formats, you can use the `AbstractFormatterFactory`. You'll learn more about formatters and formatter factories in Chapter 16.

Creating a JFormattedTextField

There are six constructors for the `JFormattedTextField` class:

```
public JFormattedTextField()
JFormattedTextField formattedField = new JFormattedTextField();

public JFormattedTextField(Format format)
DateFormat format = new SimpleDateFormat("yyyy--MMM--dd");
JFormattedTextField formattedField = new JFormattedTextField(format);

public JFormattedTextField(JFormattedTextField.AbstractFormatter formatter)
DateFormat displayFormat = new SimpleDateFormat("yyyy--MMM--dd");
DateFormatter displayFormatter = new DateFormatter(displayFormat);
JFormattedTextField formattedField = new JFormattedTextField(displayFormatter);

public JFormattedTextField(JFormattedTextField.AbstractFormatterFactory factory)
DateFormat displayFormat = new SimpleDateFormat("yyyy--MMM--dd");
DateFormatter displayFormatter = new DateFormatter(displayFormat);
DateFormat editFormat = new SimpleDateFormat("MM/dd/yy");
DateFormatter editFormatter = new DateFormatter(editFormat);
DefaultFormatterFactory factory = new DefaultFormatterFactory(
    displayFormatter, displayFormatter, editFormatter);
JFormattedTextField formattedField = new JFormattedTextField(factory);
```

```

public JFormattedTextField(JFormattedTextField.AbstractFormatterFactory factory,
    Object currentValue)
DateFormat displayFormat = new SimpleDateFormat("yyyy-MM-dd");
DateFormatter displayFormatter = new DateFormatter(displayFormat);
DateFormat editFormat = new SimpleDateFormat("MM/dd/yy");
DateFormatter editFormatter = new DateFormatter(editFormat);
DefaultFormatterFactory factory = new DefaultFormatterFactory(
    displayFormatter, displayFormatter, editFormatter);
JFormattedTextField formattedField = new JFormattedTextField(factory, new Date());

public JFormattedTextField(Object value)
JFormattedTextField formattedField = new JFormattedTextField(new Date());

```

The no-argument version requires you to configure it later. The other constructors allow you to configure what and how input will be accepted into the component.

JFormattedTextField Properties

Table 15-8 shows the eight properties of `JFormattedTextField`. Instead of getting the contents of the `JFormattedTextField` as a `String` via the `text` property, as you would with a `JTextField`, you get it as an `Object` via the `value` property. Thus, if your formatter were for a `Date` object, the value you get back could be cast to `java.util.Date`.

Table 15-8. *JFormattedTextField Properties*

Property Name	Data Type	Access
<code>actions</code>	<code>Action[]</code>	Read-only
<code>document</code>	<code>Document</code>	Write-only
<code>editValid</code>	<code>boolean</code>	Read-only
<code>focusLostBehavior</code>	<code>int</code>	Read-write
<code>formatter</code>	<code>JFormattedTextField.AbstractFormatter</code>	Read-only
<code>formatterFactory</code>	<code>JFormattedTextField.AbstractFormatterFactory</code>	Read-write bound
<code>UIClassID</code>	<code>String</code>	Read-only
<code>value</code>	<code>Object</code>	Read-write bound

Listing 15-14 demonstrates the user of `JFormattedTextField` with custom formatters and factories. Notice that when you edit the bottom text field, the display format and edit format are different.

Listing 15-14. *JFormattedTextField Example*

```

import javax.swing.*;
import javax.swing.text.*;
import javax.swing.event.*;
import java.awt.*;
import java.awt.event.*;
import java.util.*;
import java.text.*;

public class FormattedSample {
    public static void main(final String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Formatted Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JPanel datePanel = new JPanel(new BorderLayout());
                JLabel dateLabel = new JLabel("Date: ");
                dateLabel.setDisplayedMnemonic(KeyEvent.VK_D);
                DateFormat format = new SimpleDateFormat("yyyy--MMMM--dd");
                JFormattedTextField dateTextField = new JFormattedTextField(format);
                dateLabel.setLabelFor(dateTextField);
                datePanel.add(dateLabel, BorderLayout.WEST);
                datePanel.add(dateTextField, BorderLayout.CENTER);
                frame.add(datePanel, BorderLayout.NORTH);

                JPanel date2Panel = new JPanel(new BorderLayout());
                JLabel date2Label = new JLabel("Date 2: ");
                date2Label.setDisplayedMnemonic(KeyEvent.VK_A);
                DateFormat displayFormat = new SimpleDateFormat("yyyy--MMMM--dd");
                DateFormatter displayFormatter = new DateFormatter(displayFormat);
                DateFormat editFormat = new SimpleDateFormat("MM/dd/yy");
                DateFormatter editFormatter = new DateFormatter(editFormat);
                DefaultFormatterFactory factory = new DefaultFormatterFactory(
                    displayFormatter, displayFormatter, editFormatter);
                JFormattedTextField date2TextField = new JFormattedTextField(factory,
                    new Date());
                date2Label.setLabelFor(date2TextField);
                date2Panel.add(date2Label, BorderLayout.WEST);
                date2Panel.add(date2TextField, BorderLayout.CENTER);
                frame.add(date2Panel, BorderLayout.SOUTH);

                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        JFormattedTextField source =
                            (JFormattedTextField)actionEvent.getSource();
                        Object value = source.getValue();
                    }
                };
            }
        };
        SwingUtilities.invokeLater(runner);
    }
}

```

```

        System.out.println("Class: " + value.getClass());
        System.out.println("Value: " + value);
    }
};
dateTextField.addActionListener(actionListener);
date2TextField.addActionListener(actionListener);

frame.setSize(250, 100);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Customizing a JFormattedTextField Look and Feel

Like the JPasswordField, JFormattedTextField is a subclass of a JTextField. It, too, has the same appearance as the JTextField under all the predefined look and feel types (see Figure 15-15). To customize its display, you can change any of the set of 16 UIResource-related properties for a JFormattedTextField, as shown in Table 15-9.

Table 15-9. *JFormattedTextField UIResource Elements*

Property String	Object Type
FormattedTextField.actionMap	ActionMap
FormattedTextField.background	Color
FormattedTextField.border	Border
FormattedTextField.caretAspectRatio	Number
FormattedTextField.caretBlinkRate	Integer
FormattedTextField.caretForeground	Color
FormattedTextField.focusInputMap	InputMap
FormattedTextField.font	Font
FormattedTextField.foreground	Color
FormattedTextField.inactiveBackground	Color
FormattedTextField.inactiveForeground	Color
FormattedTextField.keyBindings	KeyBinding[]
FormattedTextField.margin	Insets
FormattedTextField.selectionBackground	Color
FormattedTextField.selectionForeground	Color
FormattedTextFieldUI	String

JTextArea Class

The `JTextArea` component is the text component for multiple-line input. Similar to the `JTextField`, the data model for a `JTextArea` is the `PlainDocument` implementation of the `Document` interface. Therefore, the `JTextArea` is limited to single-attributed text. As with other Swing components that may require scrolling, the `JTextArea` doesn't support scrolling itself. You need to place each `JTextArea` within a `JScrollPane` to allow a user to properly scroll through the contents of a `JTextArea`.

Creating a JTextArea

There are six constructors for creating a `JTextArea`:

```
public JTextArea()  
JTextArea textArea = new JTextArea();  
  
public JTextArea(Document document)  
Document document = new PlainDocument();  
JTextArea textArea = new JTextArea(document);  
  
public JTextArea(String text)  
JTextArea textArea = new JTextArea("...");  
  
public JTextArea(int rows, int columns)  
JTextArea textArea = new JTextArea(10, 40);  
  
public JTextArea(String text, int rows, int columns)  
JTextArea textArea = new JTextArea("...", 10, 40);  
  
public JTextArea(Document document, String text, int rows, int columns)  
JTextArea textArea = new JTextArea(document, null, 10, 40);
```

Unless otherwise specified, the text area is able to hold zero rows and columns of content. Although this might sound like a serious limitation, you're just telling the text area to let the current `LayoutManager` worry about the size of your text area. The contents of the `JTextArea` are initially empty unless specified from either the starting text string or the `Document` model.

Note Other initial settings for a `JTextArea` include having a tab stop every eight positions and turning off word wrap. For more on tab stops, see the `TabStop` and `TabSet` class descriptions in Chapter 16.

After creating a `JTextArea`, remember to place the `JTextArea` into a `JScrollPane`. Then if there isn't sufficient space on the screen, the `JScrollPane` will manage the scrolling for you.

```

JTextArea textArea = new JTextArea();
JScrollPane scrollPane = new JScrollPane(textArea);
content.add(scrollPane);

```

Figure 15-17 shows how a `JTextArea` looks within a `JScrollPane` and outside a `JScrollPane`. In the `JTextArea` not in the `JScrollPane`, you can't see the text that falls below the bottom screen border. By design, moving the cursor into that area doesn't cause the content at the top to move up.




Figure 15-17. A `JTextArea` without a `JScrollPane` and one within a `JScrollPane`

JTextArea Properties

Table 15-10 shows the 12 properties of `JTextArea`.

Table 15-10. *JTextArea Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>columns</code>	<code>int</code>	Read-write
<code>font</code>	<code>Font</code>	Write-only
<code>lineCount</code>	<code>int</code>	Read-only
<code>lineWrap</code>	<code>boolean</code>	Read-write bound
<code>preferredScrollableViewportSize</code>	<code>Dimension</code>	Read-only
<code>preferredSize</code>	<code>Dimension</code>	Read-only
<code>rows</code>	<code>int</code>	Read-write
<code>scrollableTracksViewportWidth</code>	<code>boolean</code>	Read-only
<code>tabSize</code>	<code>int</code>	Read-write bound
<code>UIClassID</code>	<code>String</code>	Read-only
<code>wrapStyleWord</code>	<code>boolean</code>	Read-write bound

The rows and columns properties come directly from the constructor arguments. The preferredScrollableViewportSize and scrollableTracksViewportWidth properties come from implementing the Scrollable interface for scrolling support. The font and preferredSize properties merely customize the behavior inherited from JTextComponent.

That leaves the more interesting properties of lineCount, tabSize, and lineWrap with wrapStyleWord to examine. The lineCount property allows you to find out how many lines are in the text area. This is useful for sizing purposes. The tabSize property allows you to control the tab position interval within the text area. By default, this value is 8.

The lineWrap and wrapStyleWord properties work together. By default, the wrapping of long lines is disabled. If you enable line wrapping (by setting the lineWrap property to true), the point at which long lines wrap depends on the wrapStyleWord property setting. Initially, this property is false, which means that if the lineWrap property is true, line wrapping happens at character boundaries. If both lineWrap and wrapStyleWord are true, then each word from a line that doesn't fit is wrapped to another line, as it is in a word processor. So, to get the word wrap capabilities that most people want, you should set both properties to true for your JTextArea:

```
JTextArea textArea = new JTextArea("...");
textArea.setLineWrap(true);
textArea.setWrapStyleWord(true);
JScrollPane scrollPane = new JScrollPane(textArea);
```

Note The Ctrl-Tab and Shift-Ctrl-Tab key combinations allow users to change focus from within JTextArea components without needing to subclass the component.

Handling JTextArea Events

No events are specific to a JTextArea. You can use one of the inherited listeners from JTextComponent (or one of its parents) or attach an InputVerifier.

At times, you'll just have a JTextArea on the screen and get its contents after the user presses a button. Other times, there's a bit more planning involved, where you might monitor input as it is entered, and possibly convert something like :-) to a smiley face: ☺.

Customizing a JTextArea Look and Feel

Each installable Swing look and feel provides a different JTextArea appearance and set of default UIResource values. Figure 15-18 shows the appearance of the JTextArea component for the preinstalled set of look and feel types. Notice that the primary difference in the appearance of each is the scrollbar from the JScrollPane, which is not a part of the actual JTextArea.




Figure 15-18. *JTextArea* under different look and feel types

The available set of 15 UIResource-related properties for a `JTextArea` is listed in Table 15-11.

Table 15-11. *JTextArea* UIResource Elements

Property String	Object Type
<code>TextArea.actionMap</code>	ActionMap
<code>TextArea.background</code>	Color
<code>TextArea.border</code>	Border
<code>TextArea.caretAspectRatio</code>	Number
<code>TextArea.caretBlinkRate</code>	Integer
<code>TextArea.caretForeground</code>	Color
<code>TextArea.focusInputMap</code>	InputMap
<code>TextArea.font</code>	Font
<code>TextArea.foreground</code>	Color
<code>TextArea.inactiveForeground</code>	Color
<code>TextArea.keyBindings</code>	KeyBinding[]
<code>TextArea.margin</code>	Insets
<code>TextArea.selectionBackground</code>	Color
<code>TextArea.selectionForeground</code>	Color
<code>TextAreaUI</code>	String

JEditorPane Class

The JEditorPane class provides the ability to display and edit multiple-attributed text. While the JTextField and JTextArea support only single-color, single-font content, the JEditorPane allows you to tag your content with various styles (such as bold, italics, 14-point Helvetica, right-justified paragraphs) or with the appearance of an HTML viewer, as shown in Figure 15-19.



Figure 15-19. Sample JEditorPane as an HTML viewer

Note The HTML support for JEditorPane is only at the HTML 3.2 level with some extensions, whereas HTML 4.0x is the current version as of this writing. Cascading Style Sheets (CSS) are partially supported.

The JEditorPane supports the display and editing of multiple-attributed text through the help of an EditorKit specific to the text-markup mechanism. Predefined kits exist to support raw text, HTML documents, and Rich Text Format (RTF) documents. Because the content is multiple-attributed, the PlainDocument model is no longer sufficient. Instead, Swing provides a StyledDocument in the form of the DefaultStyledDocument class for maintaining the document model. The remaining part of the mix is the new HyperlinkListener/HyperlinkEvent event-handling pair for monitoring hyperlink operations within the document.

Creating a JEditorPane

The JEditorPane has four constructors:

```
public JEditorPane()
JEditorPane editorPane = new JEditorPane();

public JEditorPane(String type, String text)
String content = "<H1>Got Java?</H1>";
String type = "text/html";
JEditorPane editorPane = new JEditorPane(type, content);

public JEditorPane(String urlString) throws IOException
JEditorPane editorPane = new JEditorPane("http://www.apress.com");

public JEditorPane(URL url) throws IOException
URL url = new URL("http://www.apress.com");
JEditorPane editorPane = new JEditorPane(url);
```

The no-argument constructor creates an empty JEditorPane. If you want to initialize the contents, you can directly specify the text and its MIME type. Or, you can specify the URL for where to get the contents. The URL can be specified as either a String or a URL object. When you specify the contents as a URL, the JEditorPane determines the MIME type from the response.

JEditorPane Properties

Table 15-12 shows the 11 properties of JEditorPane. Most of the properties just customize the behavior of the parent classes.

Table 15-12. *JEditorPane Properties*

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
contentType	String	Read-write
editorKit	EditorKit	Read-write bound
hyperlinkListeners	HyperlinkListener[]	Read-only
page	URL	Read-write bound
page	String	Write-only bound
preferredSize	Dimension	Read-only
scrollableTracksViewportHeight	boolean	Read-only
scrollableTracksViewportWidth	boolean	Read-only
text	String	Read-write
UIClassID	String	Read-only

Note The page property is nonstandard in the sense it has two setter methods, but only one getter.

Four interesting properties of `JEditorPane` are the `editorKit`, `contentType`, `page`, and `text`. The `editorKit` property is configured based on the type of content in the editor pane. It is covered in more detail in Chapter 16, with its `DefaultEditorKit`, `StyledEditorKit`, and `HTMLEditorKit` implementations. The `contentType` property represents the MIME type of the content inside the document. This property tends to be automatically set when you set up the content in the constructor (or elsewhere). In the event the editor kit is unable to determine the MIME type, you can manually set it. The three MIME types with built-in support are `text/html`, `text/plain`, and `text/rtf`, as reported by the `getContentType()` method of the predefined editor kits.

The page property allows you to change the displayed contents to reflect the contents of a specific URL so that you can use the contents in some manner not programmed into the environment. The text property allows you to find out what the textual content is based on the current Document model.

Handling JEditorPane Events

Because `JEditorPane` is just another text area component with some special display characteristics, it supports the same set of listeners for event handling as does the `JTextArea` component. In addition, the `JEditorPane` provides a special listener-event combination to deal with hyperlinks within a document.

The `HyperlinkListener` interface defines one method, `public void hyperlinkUpdate(HyperlinkEvent hyperlinkEvent)`, which works with a `HyperlinkEvent` to respond to—not surprisingly—a hyperlink event. The event includes a `HyperlinkEvent.EventType` that reports on the type of event and allows you to react differently, either by following the link when selected or possibly changing the cursor when moving the mouse over (or off) the hyperlink (although this happens by default).

Here is the `HyperlinkListener` definition:

```
public interface HyperlinkListener implements EventListener {
    public void hyperlinkUpdate(HyperlinkEvent hyperlinkEvent);
}
```

And, here is the `HyperlinkEvent` definition:

```
public class HyperlinkEvent extends EventObject {
    // Constructors
    public HyperlinkEvent(Object source, HyperlinkEvent.EventType type, URL url);
    public HyperlinkEvent(Object source, HyperlinkEvent.EventType type, URL url,
        String description);
    public HyperlinkEvent(Object source, HyperlinkEvent.EventType type, URL url,
        String description, Element sourceElement)
    // Properties
    public String getDescription();
}
```

```

public HyperlinkEvent.EventType getEventType();
public Element getSourceElement();
public URL getURL();
}

```

The hyperlink event types will be one of three constants within the `HyperlinkEvent.EventType` class:

- **ACTIVATED:** Usually involving a mouse click over the appropriate content
- **ENTERED:** Moving the mouse over the hyperlink content
- **EXITED:** Moving the mouse out of the hyperlink content

Therefore, if you want to create a `HyperlinkListener` that displays the URL in a status bar while over a hyperlink and follows the hyperlink when activated, you can create your own miniature HTML help viewer. The `HyperlinkListener` implementation in Listing 15-15 will do the trick for you. There are `println` statements present in the listener to display the URL when the mouse is over the URL and when the URL is activated.

Listing 15-15. *HyperlinkListener Example*

```

import java.awt.*;
import javax.swing.*;
import javax.swing.text.*;
import javax.swing.event.*;
import java.io.*;
import java.net.*;

public class ActivatedHyperlinkListener implements HyperlinkListener {

    Frame frame;
    JEditorPane editorPane;

    public ActivatedHyperlinkListener(Frame frame, JEditorPane editorPane) {
        this.frame = frame;
        this.editorPane = editorPane;
    }

    public void hyperlinkUpdate(HyperlinkEvent hyperlinkEvent) {
        HyperlinkEvent.EventType type = hyperlinkEvent.getEventType();
        final URL url = hyperlinkEvent.getURL();
        if (type == HyperlinkEvent.EventType.ENTERED) {
            System.out.println("URL: " + url );
        } else if (type == HyperlinkEvent.EventType.ACTIVATED) {
            System.out.println("Activated");
            Runnable runner = new Runnable() {
                public void run() {

```

```

        // Retain reference to original
        Document doc = editorPane.getDocument();
        try {
            editorPane.setPage(url);
        } catch (IOException ioException) {
            JOptionPane.showMessageDialog(frame, "Error following link",
                "Invalid link", JOptionPane.ERROR_MESSAGE);
            editorPane.setDocument(doc);
        }
    }
};
EventQueue.invokeLater(runner);
}
}
}
}

```

Tip Don't forget to make the `JEditorPane` read-only with a call to `setEditable(false)`. Otherwise, the viewer acts as an editor.

Listing 15-16 is a complete example using our new `ActivatedHyperlinkListener` class. The frame it creates looks like the page shown earlier in Figure 15-19, although in the figure, the About link has been followed.

Listing 15-16. *JEditorPane Example*

```

import javax.swing.*.*;
import javax.swing.event.*;
import java.awt.*.*;
import java.io.*.*;

public class EditorPaneSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("EditorPane Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                try {
                    JEditorPane editorPane = new JEditorPane("http://www.google.com");
                    editorPane.setEditable(false);

                    HyperlinkListener hyperlinkListener =
                        new ActivatedHyperlinkListener(frame, editorPane);
                    editorPane.addHyperlinkListener(hyperlinkListener);
                }
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

```

        JScrollPane scrollPane = new JScrollPane(editorPane);
        frame.add(scrollPane);
    } catch (IOException e) {
        System.err.println("Unable to load: " + e);
    }

    frame.setSize(640, 480);
    frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Customizing a JEditorPane Look and Feel

The appearance of the JEditorPane is similar to that of a JTextArea (see Figure 15-18). Although the supported contents differ, the look-and-feel-related attributes usually aren't different.

The available set of 15 UIResource-related properties for a JEditorPane is shown in Table 15-13. Their names are similar to those of the JTextArea settings.

Table 15-13. *JEditorPane UIResource Elements*

Property String	Object Type
EditorPane.actionMap	ActionMap
EditorPane.background	Color
EditorPane.border	Border
EditorPane.caretAspectRatio	Number
EditorPane.caretBlinkRate	Integer
EditorPane.caretForeground	Color
EditorPane.focusInputMap	InputMap
EditorPane.font	Font
EditorPane.foreground	Color
EditorPane.inactiveForeground	Color
EditorPane.keyBindings	KeyBinding[]
EditorPane.margin	Insets
EditorPane.selectionBackground	Color
EditorPane.selectionForeground	Color
EditorPaneUI	String

JTextPane Class

The JTextPane is a specialized form of the JEditorPane designed especially for the editing (and display) of styled text. It differs from the JEditorPane only in its manner of providing the content to display because the text isn't tagged with the styles as it would be in an HTML or RTF document.

The JTextPane relies on three interfaces for the setting of text attributes: AttributeSet for a basic collection of attributes, MutableAttributeSet for a changeable collection of attributes, and Style for a set of attributes to be associated with a part of a StyledDocument.

This section will introduce JTextPane. See Chapter 16 for additional information about configuring styles for different parts of the styled content within a JTextPane.

Creating a JTextPane

There are only two constructors for JTextPane:

```
public JTextPane()  
JTextPane textPane = new JTextPane();  
JScrollPane scrollPane = new JScrollPane(textPane);  
  
public JTextPane(StyledDocument document)  
StyledDocument document = new DefaultStyledDocument();  
JTextPane textPane = new JTextPane(document);  
JScrollPane scrollPane = new JScrollPane(textPane);
```

The no-argument constructor initially has zero contents. The second constructor allows you to create the Document first, and then use it in the JTextPane.

Tip Remember to place your JTextPane within a JScrollPane if the contents will be larger than the available screen space.

JTextPane Properties

Table 15-14 shows the eight properties of JTextPane. You'll look at these in greater detail in Chapter 16.

Table 15-14. *JTextPane Properties*

Property Name	Data Type	Access
characterAttributes	AttributeSet	Read-only
document	Document	Write-only bound
editorKit	EditorKit	Write-only bound

Table 15-14. *JTextPane Properties (Continued)*

Property Name	Data Type	Access
inputAttributes	MutableAttributeSet	Read-only
logicalStyle	Style	Read-write
paragraphAttributes	AttributeSet	Read-only
styledDocument	StyledDocument	Read-write*
UIClassID	String	Read-only

* Changing the *styledDocument* property triggers a bound property notification on the document property.

Customizing a JTextPane Look and Feel

The `JTextPane` is a subclass of a `JEditorPane`. It has the same appearance under all the predefined look and feel types as the `JTextArea` (see Figure 15-18). Although the contents might differ, the look and feel is the same.

The available set of `UIResource`-related properties for a `JTextPane` is shown in Table 15-15. For the `JTextPane` component, there are 15 different properties. Their names are similar to the `JTextArea` settings.

Table 15-15. *JTextPane UIResource Elements*

Property String	Object Type
<code>TextPane.actionMap</code>	<code>ActionMap</code>
<code>TextPane.background</code>	<code>Color</code>
<code>TextPane.border</code>	<code>Border</code>
<code>TextPane.caretAspectRatio</code>	<code>Number</code>
<code>TextPane.caretBlinkRate</code>	<code>Integer</code>
<code>TextPane.caretForeground</code>	<code>Color</code>
<code>TextPane.focusInputMap</code>	<code>InputMap</code>
<code>TextPane.font</code>	<code>Font</code>
<code>TextPane.foreground</code>	<code>Color</code>
<code>TextPane.inactiveForeground</code>	<code>Color</code>
<code>TextPane.keyBindings</code>	<code>KeyBinding[]</code>
<code>TextPane.margin</code>	<code>Insets</code>
<code>TextPane.selectionBackground</code>	<code>Color</code>
<code>TextPane.selectionForeground</code>	<code>Color</code>
<code>TextPaneUI</code>	<code>String</code>

Loading a JTextPane with Content

Listing 15-17 provides an example that loads the content for a `StyledDocument` for a `JTextPane`. This is just to give you an idea of the possibilities. The details of using `Style`, `SimpleAttributeSet`, and `StyleConstants` will be discussed in Chapter 16.

Listing 15-17. *JTextPane Example*

```
import javax.swing.*;
import javax.swing.text.*;
import javax.swing.event.*;
import java.awt.*;

public class TextPaneSample {
    private static String message =
        "In the beginning, there was COBOL, then there was FORTRAN, " +
        "then there was BASIC, ... and now there is Java.\n";

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("TextPane Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                StyleContext context = new StyleContext();
                StyledDocument document = new DefaultStyledDocument(context);

                Style style = context.getStyle(StyleContext.DEFAULT_STYLE);
                StyleConstants.setAlignment(style, StyleConstants.ALIGN_RIGHT);
                StyleConstants.setFontSize(style, 14);
                StyleConstants.setSpaceAbove(style, 4);
                StyleConstants.setSpaceBelow(style, 4);

                // Insert content
                try {
                    document.insertString(document.getLength(), message, style);
                } catch (BadLocationException badLocationException) {
                    System.err.println("Oops");
                }

                SimpleAttributeSet attributes = new SimpleAttributeSet();
                StyleConstants.setBold(attributes, true);
                StyleConstants.setItalic(attributes, true);

                // Insert content
                try {
                    document.insertString(document.getLength(), "Hello Java", attributes);
```

```

    } catch (BadLocationException badLocationException) {
        System.err.println("Oops");
    }

    // Third style for icon/component
    Style labelStyle = context.getStyle(StyleContext.DEFAULT_STYLE);

    Icon icon = new ImageIcon("Computer.gif");
    JLabel label = new JLabel(icon);
    StyleConstants.setComponent(labelStyle, label);

    // Insert content
    try {
        document.insertString(document.getLength(), "Ignored", labelStyle);
    } catch (BadLocationException badLocationException) {
        System.err.println("Oops");
    }

    JTextPane textPane = new JTextPane(document);
    textPane.setEditable(false);
    JScrollPane scrollPane = new JScrollPane(textPane);
    frame.add(scrollPane, BorderLayout.CENTER);

    frame.setSize(300, 150);
    frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

The key line of the source code is the call to `insertString()` and its style argument:

```
document.insertString(document.getLength(), message, style);
```

Figure 15-20 shows how a `JTextPane` might look like with a few paragraphs of content. Notice that the content is not restricted to just text; it can have images as well.




Figure 15-20. Sample `JTextPane`

Summary

In this chapter, you began to explore the details of the Swing text components. You initially looked at the root text component, `JTextComponent`, and the many operations it defines for all other text components. You then explored the specific text components of `JTextField`, `JPasswordField`, `JFormattedTextField`, `JTextArea`, `JEditorPane`, and `JTextPane`.

You also explored the various pieces that make up the different components. You delved into the data model for the text components, based on the `Document` interface, for the `AbstractDocument` and `PlainDocument` classes. You also looked at creating a custom document filter via `DocumentFilter` for restricting input to a text component. In addition, you explored the `Caret` and `Highlighter` interfaces for displaying the cursor and highlighted text, the `NavigationFilter` for limiting movement within the text component, as well as the `Keymap` to make the text component act as the controller. As the controller, the `Keymap` converts a user's keystrokes into specific actions that affect the model for the text component.

You also looked at how events are handled within the Swing text components. In addition to the basic AWT event handling classes, Swing adds some new ones designed for listening for cursor movement with the `CaretListener` and document content changes with the `DocumentListener`. The `JEditorPane` also provides another event handler with the `HyperlinkListener`. And there is the general Swing support for input verification through `InputVerifier`.

In Chapter 16, you'll further explore the Swing text components. This chapter touched on the basic features of all the components, while the next chapter goes into all the gory details of working with the `TextAction`, formatting input for a `JFormattedTextField`, and configuring `Style` objects to work with a `StyledDocument`. You'll also look into shuffling through the tags of your `HTMLDocument`.



Advanced Text Capabilities

In Chapter 15, you were introduced to the myriad capabilities of the Swing text components. In this chapter, you'll continue on the same path by looking at some advanced capabilities that will prove useful in special situations.

The Swing text components ship with many prefabricated features. For instance, as you saw in Chapter 15, although text components have methods such as `cut()`, `copy()`, and `paste()` to work with the system clipboard, you really don't need to use them. This is because the Swing text components come with their own predefined set of `Action` objects, which you'll explore in this chapter. To use `Action` objects, just attach them to a component, such as a button or menu item, and then simply select the component that triggers the `Action`. For text components, the `Action` object is an instance of `TextAction`, which has a nice additional feature of knowing which text component last had the input focus.

In this chapter, you'll also look at how to create stylized text for display in a `JTextPane`. If you want to display multicolored text documents or different font styles, the `JTextPane` component provides a series of interfaces and classes to describe the attributes attached to the document. The `AttributeSet` interface gives you these on a read-only basis, and the `MutableAttributeSet` interface extends `AttributeSet` in order to set attributes. You'll see how the `SimpleAttributeSet` class implements both of these interfaces by offering a `Hashtable` to store the text attributes, and how the `StyleConstants` class helps to configure the many text attributes you can apply. And, you'll learn how to work with tab stops within your text documents, including how to define leader characters and how text is aligned.

Next, you'll get a glimpse of the different editor kits that Swing provides, focusing on the inner workings of the `HTMLDocument`. When the `JEditorPane` displays HTML, the `HTMLEditorKit` controls how to load and display the HTML content into an `HTMLDocument`. You'll see how the parser loads the content and how to iterate through the different tags in the document.

Lastly, you'll learn how to take advantage of the formatted input options and validation available with the `JFormattedTextField` component. You'll see how to provide for formatted dates and numbers, as well as masked input like telephone and social security numbers.

Using Actions with Text Components

The `TextAction` class is a special case of the `Action` interface that was defined with the other Swing event-handling capabilities in Chapter 2 and briefly reviewed in Chapter 15. The purpose of the `TextAction` class is to provide concrete `Action` implementations that can work with text components. These implementations are smart enough to know which text component most recently had the input focus and therefore should be the subject of the action.

For every text component, you need a way to associate keystrokes with specific actions. This is done via the `Keymap` interface, which maps a `KeyStroke` to a `TextAction`, so that separate `KeyListener` objects don't need to be associated with the text component for each keystroke in order to listen for it. Key maps can be shared across multiple components and/or customized for a particular look and feel. The `JTextComponent` also has `getKeymap()` and `setKeymap()` methods that allow you to read or customize the key map.

Note Although the Swing text components use `TextAction`, `KeyStroke`, and `Keymap`, they still support the ability to attach a `KeyListener`. Using a `KeyListener`, however, usually isn't appropriate, especially when you want to restrict input to match certain criteria. The better approach for restricting input is to come up with a custom `DocumentFilter`, as demonstrated in Chapter 15, or use an `InputVerifier`. In addition, the actual `Keymap` implementation is just a wrapper to the `InputMap/ActionMap` combination used for keyboard-action mapping in the nontextual Swing components.

The text components come with many predefined `TextAction` implementations. Through a default key map, the text components know about these predefined actions, so they know how to insert and remove content, as well as how to track the positions of both the cursor and caret. If the text component supports stylized content, as `JTextPane` does, there are additional default actions to support this content. All these implementations derive from the JFC/Swing technology editor kits. As discussed in the “The Editor Kits” section later in this chapter, an editor kit provides a logical grouping of the various ways to edit a specific type of text component.

Listing Actions

To find out which actions a `JTextComponent` supports, you merely ask by using the public `Action[] getActions()` method. This will return an array of `Action` objects, usually of type `TextAction`, that can be used like any other `Action`, such as for creating buttons on a `JToolBar`.

Figure 16-1 shows a program that will list the actions for the different predefined components. Pick a component from the `JRadioButton` group, and its list of text actions will be displayed in the text area. For each action, the program shows the action name and class name.




Figure 16-1. *TextAction* list demonstration

The same set of 53 actions is available for all text components. `JTextField`, `JFormattedTextField`, and `JPasswordField` have one extra action, called `notify-field-accept`, used for detecting when the Enter key is pressed while in the text component. The `JFormattedTextField` has a second extra action, `reset-field-edit`, for when the contents don't validate against the provided format mask. `JTextPane` adds its own set of about 20 more actions for dealing with multiple-attributed text.

Listing 16-1 shows the source used to generate Figure 16-1. The `RadioButtonUtils` class was created in Chapter 5.

Listing 16-1. *Listing Text Component Actions*

```
import javax.swing.*;
import javax.swing.text.*;
import java.awt.*;
import java.awt.event.*;
import java.io.*;
import java.util.*;

public class ListActions {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("TextAction List");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                String components[] = {
                    "JTextField", "JFormattedTextField", "JPasswordField",
                    "JTextArea", "JTextPane", "JEditorPane"};

                final JTextArea textArea = new JTextArea();
                textArea.setEditable(false);
                JScrollPane scrollPane = new JScrollPane(textArea);
                frame.add(scrollPane, BorderLayout.CENTER);

                ActionListener actionListener = new ActionListener() {
                    public void actionPerformed(ActionEvent actionEvent) {
                        // Determine which component selected
                        String command = actionEvent.getActionCommand();
                        JTextComponent component = null;
                        if (command.equals("JTextField")) {
                            component = new JTextField();
                        } else if (command.equals("JFormattedTextField")) {
                            component = new JFormattedTextField();
                        } else if (command.equals("JPasswordField")) {
                            component = new JPasswordField();
                        }
                    }
                };
            }
        };
        runner.run();
    }
}
```

```

    } else if (command.equals("JTextArea")) {
        component = new JTextArea();
    } else if (command.equals("JTextPane")) {
        component = new JTextPane();
    } else {
        component = new JEditorPane();
    }

    // Process action list
    Action actions[] = component.getActions();
    // Define comparator to sort actions
    Comparator<Action> comparator = new Comparator<Action>() {
        public int compare(Action a1, Action a2) {
            String firstName = (String)a1.getValue(Action.NAME);
            String secondName = (String)a2.getValue(Action.NAME);
            return firstName.compareTo(secondName);
        }
    };
    Arrays.sort(actions, comparator);
    StringWriter sw = new StringWriter();
    PrintWriter pw = new PrintWriter(sw, true);
    int count = actions.length;
    pw.println("Count: " + count);
    for (int i=0; i<count; i++) {
        pw.print (actions[i].getValue(Action.NAME));
        pw.print (" : ");
        pw.println(actions[i].getClass().getName());
    }
    pw.close();
    textArea.setText(sw.toString());
    textArea.setCaretPosition(0);
}
};

final Container componentsContainer =
    RadioButtonUtils.createRadioButtonGrouping(components,
        "Pick to List Actions", ActionListener);

frame.add(componentsContainer, BorderLayout.WEST);
frame.setSize(400, 250);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Using Actions

So far, you've seen that there are many predefined `TextAction` implementations available for the various text components, but you haven't used any of them. By making a few minor changes to Listing 16-1, you can enhance the program in order to activate it. The modified program is shown in Listing 16-2. With this version, when one of the radio buttons is selected, that type of text component will be displayed where the text list of `Action` objects appears in Figure 16-1. In addition, the different `Action` objects are added to a new `JMenuBar` placed at the top of the display window.

Note In the program shown in Listing 16-2, after all the menu buttons are activated, you're stuck with a text label that might not be exactly what you want. However, you can easily change this with the public `void setText(String label)` method of `JMenuItem`. If you do this, remember that you need to know what's in the menu item to change the label to something meaningful.

Listing 16-2. *Enabling Text Component Actions*

```
import javax.swing.*;
import javax.swing.text.*;
import java.awt.*;
import java.awt.event.*;
import java.io.*;
import java.util.*;

public class ActionsMenuBar {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                final JFrame frame = new JFrame("TextAction Usage");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                final JScrollPane scrollPane = new JScrollPane();
                frame.add(scrollPane, BorderLayout.CENTER);

                final JMenuBar menuBar = new JMenuBar();
                frame.setJMenuBar(menuBar);

                ActionListener actionListener = new ActionListener() {
                    JTextComponent component;
                    public void actionPerformed(ActionEvent actionEvent) {
                        // Determine which component selected
                        String command = actionEvent.getActionCommand();
                        if (command.equals("JTextField")) {
                            component = new JTextField();
                        }
                    }
                };
            }
        };
        runner.run();
    }
}
```

```

    } else if (command.equals("JFormattedTextField")) {
        component = new JFormattedTextField();
    } else if (command.equals("JPasswordField")) {
        component = new JPasswordField();
    } else if (command.equals("JTextArea")) {
        component = new JTextArea();
    } else if (command.equals("JTextPane")) {
        component = new JTextPane();
    } else {
        component = new JEditorPane();
    }
    scrollPane.setViewportView(component);
    // Process action list
    Action actions[] = component.getActions();
    menuBar.removeAll();
    menuBar.revalidate();
    JMenu menu = null;
    for (int i=0, n=actions.length; i<n; i++) {
        if ((i % 10) == 0) {
            menu = new JMenu("From " + i);
            menuBar.add(menu);
        }
        menu.add(actions[i]);
    }
    menuBar.revalidate();
}
};

String components[] = {
    "JTextField", "JFormattedTextField", "JPasswordField",
    "JTextArea", "JTextPane", "JEditorPane"};
final Container componentsContainer =
    RadioButtonUtils.createRadioButtonGrouping(components,
        "Pick to List Actions", actionListener);
frame.add(componentsContainer, BorderLayout.WEST);

frame.setSize(400, 300);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Figure 16-2 shows some of the available operations for a JTextArea. When you select the different menu options, the JTextComponent is appropriately affected.




Figure 16-2. *TextAction list usage demonstration*

This technique is useful because it shows that you can readily discover the supported operations of a text component and provide access to that behavior without knowing precisely what the actual behavior is. This is just one demonstration of the many ways you can use TextAction objects.

Finding Actions

Although listing and using Action objects related to a text component is a fairly malleable process, unless you know what you're looking for, it isn't very useful. Thankfully, the DefaultEditorKit has 46 class constants that match many of the shared 46 (out of 53) Action objects of all the text components. The class constants' names more or less reflect their functionality. The JTextField adds an additional constant for the Action shared with JFormattedTextField and JPasswordField. Unfortunately, the names associated with the extra actions available to the JTextPane aren't class constants of any text component and are just used internally within the StyledEditorKit, where you will find the additional Action implementations defined.

Note One additional Action exists primarily for debugging purposes. Its Action name is `dump-model`, and it lacks a class constant to go with it. When initiated, the method literally dumps out the Document model Element structure for the text component.

Table 16-1 lists the 47 constants available to help you locate the predefined Action you're seeking.

Table 16-1. *TextAction Name Constants*

<code>DefaultEditorKit.backwardAction</code>	<code>DefaultEditorKit.previousWordAction</code>
<code>DefaultEditorKit.beepAction</code>	<code>DefaultEditorKit.readOnlyAction</code>
<code>DefaultEditorKit.beginAction</code>	<code>DefaultEditorKit.selectAllAction</code>
<code>DefaultEditorKit.beginLineAction</code>	<code>DefaultEditorKit.selectionBackwardAction</code>
<code>DefaultEditorKit.beginParagraphAction</code>	<code>DefaultEditorKit.selectionBeginAction</code>
<code>DefaultEditorKit.beginWordAction</code>	<code>DefaultEditorKit.selectionBeginLineAction</code>
<code>DefaultEditorKit.copyAction</code>	<code>DefaultEditorKit.selectionBeginParagraphAction</code>
<code>DefaultEditorKit.cutAction</code>	<code>DefaultEditorKit.selectionBeginWordAction</code>
<code>DefaultEditorKit.defaultKeyTypedAction</code>	<code>DefaultEditorKit.selectionDownAction</code>
<code>DefaultEditorKit.deleteNextCharAction</code>	<code>DefaultEditorKit.selectionEndAction</code>
<code>DefaultEditorKit.deletePrevCharAction</code>	<code>DefaultEditorKit.selectionEndLineAction</code>
<code>DefaultEditorKit.downAction</code>	<code>DefaultEditorKit.selectionEndParagraphAction</code>
<code>DefaultEditorKit.endAction</code>	<code>DefaultEditorKit.selectionEndWordAction</code>
<code>DefaultEditorKit.endLineAction</code>	<code>DefaultEditorKit.selectionForwardAction</code>
<code>DefaultEditorKit.endParagraphAction</code>	<code>DefaultEditorKit.selectionNextWordAction</code>
<code>DefaultEditorKit.endWordAction</code>	<code>DefaultEditorKit.selectionPreviousWordAction</code>
<code>DefaultEditorKit.forwardAction</code>	<code>DefaultEditorKit.selectionUpAction</code>
<code>DefaultEditorKit.insertBreakAction</code>	<code>DefaultEditorKit.selectLineAction</code>
<code>DefaultEditorKit.insertContentAction</code>	<code>DefaultEditorKit.selectParagraphAction</code>
<code>DefaultEditorKit.insertTabAction</code>	<code>DefaultEditorKit.selectWordAction</code>
<code>DefaultEditorKit.nextWordAction</code>	<code>DefaultEditorKit.upAction</code>
<code>DefaultEditorKit.pageDownAction</code>	<code>DefaultEditorKit.writableAction</code>
<code>DefaultEditorKit.pageUpAction</code>	<code>JTextField.notifyAction</code>
<code>DefaultEditorKit.pasteAction</code>	

With such a huge list of constants, what on earth do you *do* with them? Well, first you find the constant for the predefined `TextAction` you want to use (or learn the necessary text string if no constant is provided). This is relatively easy because the names are fairly self-explanatory.

To demonstrate, Listing 16-3 contains a program that shows how to work with these constants. The program has two text areas to show that `TextAction` objects really know to work with the last text component that had the input focus. One set of menu items includes two options that are used to switch the text area from read-only to writable. This action is done using the `DefaultEditorKit.readOnlyAction` and `DefaultEditorKit.writableAction` names. The other set of menu items includes options for cut, copy, and paste support, whose constants are `DefaultEditorKit.cutAction`, `DefaultEditorKit.copyAction`, and `DefaultEditorKit.pasteAction`. Because the constants are `String` values, you need to look up the actual `Action` object to use.

The lookup process requires getting the `ActionMap` for the component with `getActionMap()`, and then searching for the key with the `get()` method of `ActionMap`, as in this example:

```
Action readAction = component.getActionMap().get(DefaultEditorKit.readOnlyAction);
```

Listing 16-3. *Using Text Component Actions*

```
import javax.swing.*;
import javax.swing.text.*;
import java.awt.*;
import java.awt.event.*;
import java.io.*;
import java.util.*;

public class UseActions {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Use TextAction");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                Dimension empty = new Dimension(0,0);

                final JTextArea leftArea = new JTextArea();
                JScrollPane leftScrollPane = new JScrollPane(leftArea);
                leftScrollPane.setPreferredSize(empty);

                final JTextArea rightArea = new JTextArea();
                JScrollPane rightScrollPane = new JScrollPane(rightArea);
                rightScrollPane.setPreferredSize(empty);

                JSplitPane splitPane = new JSplitPane(JSplitPane.HORIZONTAL_SPLIT,
                    leftScrollPane, rightScrollPane);

                JMenuBar menuBar = new JMenuBar();
                frame.setJMenuBar(menuBar);
                JMenu menu = new JMenu("Options");
                menuBar.add(menu);
                JMenuItem menuItem;

                Action readAction =
                    leftArea.getActionMap().get(DefaultEditorKit.readOnlyAction);
                menuItem = menu.add(readAction);
                menuItem.setText("Make read-only");
                Action writeAction =
                    leftArea.getActionMap().get(DefaultEditorKit.writableAction);
                menuItem = menu.add(writeAction);
                menuItem.setText("Make writable");
```

```

        menu.addSeparator();

        Action cutAction =
            leftArea.getActionMap().get(DefaultEditorKit.cutAction);
        menuItem = menu.add(cutAction);
        menuItem.setText("Cut");
        Action copyAction =
            leftArea.getActionMap().get(DefaultEditorKit.copyAction);
        menuItem = menu.add(copyAction);
        menuItem.setText("Copy");
        Action pasteAction =
            leftArea.getActionMap().get(DefaultEditorKit.pasteAction);
        menuItem = menu.add(pasteAction);
        menuItem.setText("Paste");

        frame.add(splitPane, BorderLayout.CENTER);
        frame.setSize(400, 250);
        frame.setVisible(true);
        splitPane.setDividerLocation(.5);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Figure 16-3 shows the program at work. Notice that for each JMenuItem created, the text label changes to give it a more user-friendly setting.




Figure 16-3. *Specific TextAction usage demonstration*

By asking for specific TextAction instances, you don't need to constantly recode repetitive operations. In fact, if you constantly find yourself repeating the same operations over and over with a text component, it's probably time for you to create your own TextAction objects.

Creating Styled Text

In Chapter 15, you looked at displaying plain text and HTML. With the Swing text components—or at least the `JTextPane`—you can also display stylized text, in which different blocks of text can have multiple attributes. These attributes might include boldface, italics, a different font or color at the character level, or justification at the paragraph level, just as with any of the modern word processors.

To support these capabilities, Swing supplies many different interfaces and classes, all of which start with the specialized Document interface extension of `StyledDocument`. The Document interface was introduced in Chapter 15, focusing on the `PlainDocument` implementation class. The `StyledDocument` interface, or more precisely, the `DefaultStyledDocument` implementation, manages a series of styles and attribute sets for the contents of a Document.

The various styles used by a `StyledDocument` are described initially by the `AttributeSet` interface, which is a set of key/value pairs of read-only attributes. The key for an attribute might be “current font,” in which the setting would be the font to use. To actually change the font, you need to move on to the `MutableAttributeSet` interface, which supplies the ability to add and remove attributes. For instance, if you had an `AttributeSet` for “bold,” you could use `MutableAttributeSet` to also add italics, underlining, or colorization (or all three) to the set.

For a simple implementation of `AttributeSet`, there is the `StyleContext.SmallAttributeSet` class, which uses an array to manage the set of attributes. For an implementation of the `MutableAttributeSet` interface, there is the `SimpleAttributeSet` class, which uses a `Hashtable` to manage the attributes. More complex attribute sets move on to the `Style` interface, which adds a name to the set of attributes as defined by a `MutableAttributeSet`. The actual `Style` implementation class is the `StyleContext.NamedStyle` class. Besides adding a name, the `Style` interface adds the ability to have a `ChangeListener` monitor a set of attributes for changes.

The class that manages the set of `Style` objects for a `StyledDocument` is the `StyleContext` class. An implementation of the `AbstractDocument.AttributeContext` interface, `StyleContext` uses the `StyleConstants` class, which defines various attributes for commonly used styles. When working with HTML documents, the `StyleContext` is actually a `StyleSheet`, which may help you in understanding the whole arrangement. Keep in mind that all of the classes and interfaces discussed here (except `StyleSheet`) are required just to set up the Document data model for a particular `JTextPane`.

StyledDocument Interface and DefaultStyledDocument Class

The `StyledDocument` interface extends the Document interface by adding the ability to store styles for the content of the document. These styles can describe the character or paragraph attributes, such as color, orientation, or font.

```
public interface StyledDocument extends Document {
    public Style addStyle(String nm, Style parent);
    public Color getBackground(AttributeSet attribute);
    public Element getCharacterElement(int position);
    public Font getFont(AttributeSet attribute);
    public Color getForeground(AttributeSet attribute);
```

```

public Style getLogicalStyle(int position);
public Element getParagraphElement(int position);
public Style getStyle(String name);
public void removeStyle(String name);
public void setCharacterAttributes(int offset, int length, AttributeSet s,
    boolean replace);
public void setLogicalStyle(int position, Style style);
public void setParagraphAttributes(int offset, int length, AttributeSet s,
    boolean replace);
}

```

The `DefaultStyledDocument` class is the implementation of the `StyledDocument` interface provided with the Swing components. It serves as the data model for the `JTextPane` component.

Creating a `DefaultStyledDocument`

You can create a `DefaultStyledDocument` in any one of the three ways listed here:

```

public DefaultStyledDocument()
DefaultStyledDocument document = new DefaultStyledDocument();

public DefaultStyledDocument(StyleContext styles)
StyleContext context = new StyleContext();
DefaultStyledDocument document = new DefaultStyledDocument(context);

public DefaultStyledDocument(AbstractDocument.Content content, StyleContext styles)
AbstractDocument.Content content = new StringContent();
DefaultStyledDocument document = new DefaultStyledDocument(content, context);

```

You can share the `StyleContext` between multiple documents or use the default context. In addition, you can predefine the content using one of the `AbstractDocument.Content` implementations, either `GapContent` or `StringContent`. It is the responsibility of one of these `Content` implementations to store the actual `Document` content.

`DefaultStyledDocument` Properties

Besides having a default root element to describe the contents of the document, the `DefaultStyledDocument` makes available the style names as an `Enumeration`. These are the only two properties defined at the `DefaultStyledDocument` level, as shown in Table 16-2. There are other properties you can get for a `DefaultStyledDocument`; however, they require the position or `AttributeSet` from which to get them.

Table 16-2. *DefaultStyledDocument Properties*

Property Name	Data Type	Access
<code>defaultRootElement</code>	<code>Element</code>	Read-only
<code>styleNames</code>	<code>Enumeration</code>	Read-only

AttributeSet Interface

The `AttributeSet` interface describes a read-only set of key/value attributes, allowing you access to the descriptive content of a series of attributes. If the set of attributes lacks a specific key defined for it, the `AttributeSet` supports the ability to look elsewhere by traveling up a chain to a resolving parent for the parent's definition of the attribute. This allows the `AttributeSet` to define a core set of attributes and lets developers (or possibly even users) modify only the set of attributes they want to change. Unless you want someone to change the defaults globally, you shouldn't provide direct access to the resolving parent. That way, you never lose any of the original settings.

```
public interface AttributeSet {
    // Constants
    public final static Object NameAttribute;
    public final static Object ResolveAttribute;
    // Properties
    public int getAttributeCount();
    public Enumeration getAttributeNames();
    public AttributeSet getResolveParent();
    // Other methods
    public boolean containsAttribute(Object name, Object value);
    public boolean containsAttributes(AttributeSet attributes);
    public AttributeSet copyAttributes();
    public Object getAttribute(Object key);
    public boolean isDefined(Object attrName);
    public boolean isEqual(AttributeSet attr);
}
```

MutableAttributeSet Interface

The `MutableAttributeSet` interface describes how you would go about adding to or removing from the set of attributes, as well as how to set the resolving parent.

```
public interface MutableAttributeSet extends AttributeSet {
    public void addAttribute(Object name, Object value);
    public void addAttributes(AttributeSet attributes);
    public void removeAttribute(Object name);
    public void removeAttributes(AttributeSet attributes);
    public void removeAttributes(Enumeration names);
    public void setResolveParent(AttributeSet parent);
}
```

SimpleAttributeSet Class

The `SimpleAttributeSet` class is the first implementation of the `AttributeSet` interface. When you begin using it, you'll finally be able to see just how to create the multiple-attributed text for display in the `JTextPane`. The `SimpleAttributeSet` class is a specific implementation of `AttributeSet` that relies on a standard `Hashtable` for managing the key/attribute pairs.

Creating a SimpleAttributeSet

SimpleAttributeSet has two constructors:

```
public SimpleAttributeSet()
SimpleAttributeSet attributeSet1 = new SimpleAttributeSet();

public SimpleAttributeSet(AttributeSet source)
SimpleAttributeSet attributeSet2 = new SimpleAttributeSet(attributeSet1);
```

You would typically create an empty SimpleAttributeSet, and then set its attributes, as in the first constructor listed. Or, you can instead provide the initial settings for the set of attributes in the constructor. Note that this is *not* the resolving parent—it’s just an initialized data structure.

SimpleAttributeSet Properties

Table 16-3 displays the four properties of SimpleAttributeSet. They provide access to the set of attributes, let you know whether any attributes exist, and identify the resolving parent (if any).

Table 16-3. *SimpleAttributeSet Properties*

Property Name	Data Type	Access
attributeCount	int	Read-only
attributeNames	Enumeration	Read-only
empty	boolean	Read-only
resolveParent	AttributeSet	Read-write

Using a SimpleAttributeSet

To create an appropriate AttributeSet to use with a SimpleAttributeSet, you need to discover the keys for the attributes you want to alter. You’ll see some helper methods shortly in the StyleConstants class covered in the next section. All the keys are hidden away in four public inner classes of StyleConstants: CharacterConstants, ColorConstants, FontConstants, and ParagraphConstants, as shown in Table 16-4.

Table 16-4. *Key Constants for Storing AttributeSet Values*

AttributeSet Key Constants	Value Type	Default Setting
CharacterConstants.Background	Color	Color.BLACK
ColorConstants.Background	Color	Color.BLACK
CharacterConstants.BidiLevel	Integer	0
CharacterConstants.Bold	Boolean	false
FontConstants.Bold	Boolean	false

Table 16-4. *Key Constants for Storing AttributeSet Values*

AttributeSet Key Constants	Value Type	Default Setting
CharacterConstants.ComponentAttribute	Component	null
CharacterConstants.Family	String	"Monospaced"
FontConstants.Family	String	"Monospaced"
CharacterConstants.Foreground	Color	Color.BLACK
ColorConstants.Foreground	Color	Color.BLACK
CharacterConstants.IconAttribute	Icon	null
CharacterConstants.Italic	Boolean	false
FontConstants.Italic	Boolean	false
CharacterConstants.Size	Integer	12
FontConstants.Size	Integer	12
CharacterConstants.StrikeThrough	Boolean	false
CharacterConstants.Subscript	Boolean	false
CharacterConstants.Superscript	Boolean	false
CharacterConstants.Underline	Boolean	false
ParagraphConstants.Alignment	Integer	ALIGN_LEFT
ParagraphConstants.FirstLineIndent	Float	0
ParagraphConstants.LeftIndent	Float	0
ParagraphConstants.LineSpacing	Float	0
ParagraphConstants.Orientation	unknown	unknown
ParagraphConstants.RightIndent	Float	0
ParagraphConstants.SpaceAbove	Float	0
ParagraphConstants.SpaceBelow	Float	0
ParagraphConstants.TabSet	TabSet	null

For example, to populate the `StyledDocument` for a `JTextPane`, after creating the `DefaultStyledDocument`, you add content to it by calling the public `void insertString(int offset, String contents, AttributeSet attributes)` method, which happens to throw a `BadLocationException`. You can then change the attribute set and add more attributes. So, if you wanted to create content that was both bold *and* italic, you would add two attributes to a `SimpleAttributeSet` and insert the content into the document:

```
SimpleAttributeSet attributes = new SimpleAttributeSet();
attributes.addAttribute(StyleConstants.CharacterConstants.Bold, Boolean.TRUE);
attributes.addAttribute(StyleConstants.CharacterConstants.Italic, Boolean.TRUE);
```

```
// Insert content
try {
    document.insertString(document.getLength(), "Hello, Java", attributes);
} catch (BadLocationException badLocationException) {
    System.err.println("Oops");
}
```

Figure 16-4 shows how a JTextPane would appear with the words “Hello, Java” and a second insertion displayed.



Figure 16-4. *SimpleAttributeSet usage demonstration*

The source for the program shown in Figure 16-4 is presented in Listing 16-4.

Listing 16-4. *Using a SimpleAttributeSet*

```
import javax.swing.*.*;
import javax.swing.text.*;
import javax.swing.event.*;
import java.awt.*.*;

public class SimpleAttributeSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Simple Attributes");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                StyledDocument document = new DefaultStyledDocument();

                SimpleAttributeSet attributes = new SimpleAttributeSet();
                attributes.addAttribute(StyleConstants.CharacterConstants.Bold,
                    Boolean.TRUE);
                attributes.addAttribute(StyleConstants.CharacterConstants.Italic,
                    Boolean.TRUE);
```

```

// Insert content
try {
    document.insertString(document.getLength(), "Hello, Java",
        attributes);
} catch (BadLocationException badLocationException) {
    System.err.println("Bad insert");
}

attributes = new SimpleAttributeSet();
attributes.addAttribute(StyleConstants.CharacterConstants.Bold,
    Boolean.FALSE);
attributes.addAttribute(StyleConstants.CharacterConstants.Italic,
    Boolean.FALSE);
attributes.addAttribute(StyleConstants.CharacterConstants.Foreground,
    Color.LIGHT_GRAY);

// Insert content
try {
    document.insertString(document.getLength(),
        " - Good-bye Visual Basic", attributes);
} catch (BadLocationException badLocationException) {
    System.err.println("Bad insert");
}

JTextPane textPane = new JTextPane(document);
textPane.setEditable(false);
JScrollPane scrollPane = new JScrollPane(textPane);
frame.add(scrollPane, BorderLayout.CENTER);

frame.setSize(300, 150);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

In summary, to specify the style of the content, simply set up the attribute set, insert the content, and then repeat the steps for each bit of content you want to add.

StyleConstants Class

The `StyleConstants` class is chock-full of helper methods to simplify setting attribute sets. And you don't need to burrow into the constants of the inner classes of `StyleConstants`, because the class makes them available through class constants at the `StyleConstants` level.

```

public static final Object Alignment;
public static final Object Background;
public static final Object BidilLevel;
public static final Object Bold;
public static final Object ComponentAttribute;
public static final String ComponentElementName;
public static final Object ComposedTextAttribute;
public static final Object Family;
public static final Object FirstLineIndent;
public static final Object FontFamily;
public static final Object FontSize;
public static final Object Foreground;
public static final Object IconAttribute;
public static final String IconElementName;
public static final Object Italic;
public static final Object LeftIndent;
public static final Object LineSpacing;
public static final Object ModelAttribute;
public static final Object NameAttribute;
public static final Object Orientation;
public static final Object ResolveAttribute;
public static final Object RightIndent;
public static final Object Size;
public static final Object SpaceAbove;
public static final Object SpaceBelow;
public static final Object StrikeThrough;
public static final Object Subscript;
public static final Object Superscript;
public static final Object TabSet;
public static final Object Underline;

```

Several static methods allow you to modify a `MutableAttributeSet` using more logical method names, without requiring you to know the more obscure `AttributeSet` name. Use the `StyleConstants` variables of `ALIGN_CENTER`, `ALIGN_JUSTIFIED`, `ALIGN_LEFT`, and `ALIGN_RIGHT` for the `int` argument to `setAlignment()`. The remaining settings are self-explanatory.

```

public static void setAlignment(MutableAttributeSet a, int align);
public static void setBackground(MutableAttributeSet a, Color fg);
public static void setBidilLevel(MutableAttributeSet a, int o);
public static void setBold(MutableAttributeSet a, boolean b);
public static void setComponent(MutableAttributeSet a, Component c);
public static void setFirstLineIndent(MutableAttributeSet a, float i);
public static void setFontFamily(MutableAttributeSet a, String fam);
public static void setFontSize(MutableAttributeSet a, int s);
public static void setForeground(MutableAttributeSet a, Color fg);
public static void setIcon(MutableAttributeSet a, Icon c);
public static void setItalic(MutableAttributeSet a, boolean b);
public static void setLeftIndent(MutableAttributeSet a, float i);

```

```

public static void setLineSpacing(MutableAttributeSet a, float i);
public static void setRightIndent(MutableAttributeSet a, float i);
public static void setSpaceAbove(MutableAttributeSet a, float i);
public static void setSpaceBelow(MutableAttributeSet a, float i);
public static void setStrikeThrough(MutableAttributeSet a, boolean b);
public static void setSubscript(MutableAttributeSet a, boolean b);
public static void setSuperscript(MutableAttributeSet a, boolean b);
public static void setTabSet(MutableAttributeSet a, TabSet tabs);
public static void setUnderline(MutableAttributeSet a, boolean b);

```

For instance, instead of calling the following to make the `SimpleAttributeSet` both bold and italic:

```

attributes.addAttribute(StyleConstants.CharacterConstants.Bold, Boolean.TRUE)
attributes.addAttribute(StyleConstants.CharacterConstants.Italic, Boolean.TRUE)

```

you could use the following:

```

StyleConstants.setBold(attributes, true);
StyleConstants.setItalic(attributes, true);

```

As you can see, the latter form is much more readable and easier to maintain!

■ **Tip** Besides methods to change `AttributeSet` objects, the `StyleConstants` class provides many other methods that let you check the status of an `AttributeSet` to see if a setting is currently enabled or disabled.

TabStop and TabSet Classes

One of the key constants for storing `AttributeSet` values is the `ParagraphConstants.TabSet` attribute. The `TabSet` class represents a collection of `TabStop` objects, each defining a tab position, alignment, and leader. If you wanted to define your own tab stops for a `JTextPane`, you could create a set of `TabStop` objects, one for each tab stop, create the `TabSet`, and then associate the `TabSet` with a `MutableAttributeSet`.

Creating a TabStop

The `TabStop` class isn't a JavaBean component in the typical sense; it does not have a no-argument constructor. Instead, you must specify the position, in pixels, at which to place the tab stop. It has two constructors:

```

public TabStop(float position)
TabStop stop = new TabStop(40);

```

```

public TabStop(float position, int align, int leader)
TabStop stop = new TabStop(40, TabStop.ALIGN_DECIMAL, TabStop.LEAD_DOTS);

```

Note Although theoretically it can be specified, the `leader` argument to the `TabStop` constructor is currently ignored by the predefined text components.

TabStop Properties

Table 16-5 displays the three properties of `TabStop`, each initialized by the constructor.

Table 16-5. *TabStop Properties*

Property Name	Data Type	Access
<code>alignment</code>	<code>int</code>	Read-only
<code>leader</code>	<code>int</code>	Read-only
<code>position</code>	<code>int</code>	Read-only

Four alignment settings are specified by the five constants listed in Table 16-6. Figure 16-5 shows how the different settings are displayed.

Table 16-6. *TabStop Alignment Settings*

Alignment	Description
<code>ALIGN_BAR</code>	Starts at tab position
<code>ALIGN_LEFT</code>	Starts at tab position
<code>ALIGN_CENTER</code>	Centers over tab position
<code>ALIGN_DECIMAL</code>	Places decimal point at tab position
<code>ALIGN_RIGHT</code>	Ends at tab position



Figure 16-5. *TabStop alignment*

Note Although the `ALIGN_BAR` and `ALIGN_LEFT` are technically different constants, their alignment setting currently yields the same result. They are defined per the Rich Text Format (RTF) specification.

Using TabStop Objects

Once you have a `TabStop` object, or a group of them, you pass the object to the `TabSet` constructor in an array of `TabStop` objects like this:

```
TabSet tabset = new TabSet(new TabStop[] {tabstop})
```

As an example, Listing 16-5 shows the source for the `TabStop` alignment program shown in Figure 16-5.

Listing 16-5. *Using Tabs*

```
import javax.swing.*;
import javax.swing.text.*;
import javax.swing.event.*;
import java.awt.*;

public class TabSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Tab Attributes");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                StyledDocument document = new DefaultStyledDocument();

                int positions[] = {TabStop.ALIGN_BAR, TabStop.ALIGN_CENTER,
                    TabStop.ALIGN_DECIMAL, TabStop.ALIGN_LEFT, TabStop.ALIGN_RIGHT};
                String strings[] = {"\tBAR\n", "\tCENTER\n", "\t3.14159265\n",
                    "\tLEFT\n", "\tRIGHT\n"};

                SimpleAttributeSet attributes = new SimpleAttributeSet();

                for (int i=0, n=positions.length; i<n; i++) {
                    TabStop tabstop = new TabStop(150, positions[i], TabStop.LEAD_DOTS);
                    try {
                        int position = document.getLength();
                        document.insertString(position, strings[i], null);
                        TabSet tabset = new TabSet(new TabStop[] {tabstop});
                        StyleConstants.setTabSet(attributes, tabset);
                        document.setParagraphAttributes(position, 1, attributes, false);
                    } catch (BadLocationException badLocationException) {
                        System.err.println("Bad Location");
                    }
                }
            }
        }
    }
}
```

```

        JTextPane textPane = new JTextPane(document);
        textPane.setEditable(false);
        JScrollPane scrollPane = new JScrollPane(textPane);
        frame.add(scrollPane, BorderLayout.CENTER);

        frame.setSize(300, 150);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

In addition to specifying a position and alignment, you can specify which character you want to appear as a leader in the white space created by the tab character. By default, nothing exists there; therefore, the constant is `LEAD_NONE`. The other `TabStop` values create a line of periods (dots), equal signs, hyphens, thick lines, or underlines: `LEAD_DOTS`, `LEAD_EQUALS`, `LEAD_HYPHENS`, `LEAD_THICKLINE`, or `LEAD_UNDERLINE`. Unfortunately, this option is available but unsupported. While a nonstandard Swing component *might* support this capability, the standard ones currently do not support the different leader settings.

Style Interface

The `Style` interface is one more of the enhanced ways to specify an `AttributeSet`. It adds a name to the `MutableAttributeSet` and the ability to attach a `ChangeListener` to a `Style` in order to monitor changes to the attribute settings. For instance, you can configure a bold-italic style as shown here:

```

String BOLD_ITALIC = "BoldItalic";
Style style = (Style)document.getStyle(StyleContext.DEFAULT_STYLE);
StyleConstants.setBold(style, true);
StyleConstants.setItalic(style, true);
document.addStyle(BOLD_ITALIC, null);

```

Later, you can attach the style to some text:

```

style = document.getStyle(BOLD_ITALIC);
document.insertString(document.getLength(), "Hello, Java", style);

```

StyleContext Class

The `StyleContext` class manages the styles for a styled document. With the help of the `StyleContext.NamedStyle` class, you can just let the `JTextPane` to do its own thing, because the `StyleContext` knows when something needs to be done. For HTML documents, the `StyleContext` is more specifically a `StyleSheet`.

The Editor Kits

You briefly saw some of the default `EditorKit` capabilities of `TextAction` objects earlier in this chapter, in the “Using Actions with Text Components” section. The `EditorKit` class serves as the mastermind for pulling together all the different aspects of the text components. It creates documents, manages actions, and creates the visual representation of the document or `View`. In addition, an `EditorKit` knows how to read or write the document to a stream. Each document type requires its own `EditorKit`, so different ones are provided with the JFC/Project Swing components for both HTML and RTF text, as well as plain and styled text.

The actual display of the Document contents is done through the `EditorKit` with the help of a `ViewFactory`. For each Element of the Document, the `ViewFactory` determines which `View` is created for that element and rendered by the text component delegate. For each different type of element, there is a different `View` subclass.

Loading HTML Documents

In Chapter 15, you saw how the `read()` and `write()` methods of the `JTextComponent` allow you to read in and write out content for a text component. While the `LoadSave` example from Listing 15-3 in Chapter 15 demonstrated this process for the `JTextField`, it works with all the text components, as you would expect. The only requirement for making sure the loading and saving is done for the proper document type is to change the editor kit for the document.

To demonstrate, here’s how you could load an HTML file as a `StyledDocument` into a `JEditorPane`:

```
JEditorPane editorPane = new JEditorPane();
editorPane.setEditorKit(new HTMLEditorKit());
reader = new FileReader(filename);
editorPane.read(reader, filename);
```

It is that easy. The content type of the component is set to be `text/html` and loads in the content from `filename` to be displayed as HTML content. One thing worth noting is that the loading is done asynchronously.

If you need to load the content in synchronously, so that you can wait until everything is loaded, such as for parsing purposes, the process is a bit more involved. You need to work with the HTML parser (`HTMLEditorKit.Parser` class in `javax.swing.text.html` package), the parser delegator (`ParserDelegator` in the `javax.swing.text.html.parser` package), and the parser callback (`HTMLEditorKit.ParserCallback`) that you get from the `HTMLDocument` (as an `HTMLDocument.HTMLReader`). It sounds more complicated than it really is. To demonstrate, the following code loads a file synchronously into the `JEditorPane`.

```
reader = new FileReader(filename);
// First create empty HTMLDocument to read into
HTMLEditorKit htmlKit = new HTMLEditorKit();
HTMLDocument htmlDoc = (HTMLDocument)htmlKit.createDefaultDocument();
// Next create the parser
HTMLEditorKit.Parser parser = new ParserDelegator();
// Then get HTMLReader (parser callback) from document
HTMLEditorKit.ParserCallback callback = htmlDoc.getReader(0);
```

```
// Finally load the reader into it
// The final true argument says to ignore the character set
parser.parse(reader, callback, true);
// Examine contents
```

Iterating Through HTML Documents

After you have the HTML document loaded, in addition to just displaying the content inside a JEditorPane, you may find it necessary to parse through the content yourself to pull out various pieces. The HTMLDocument supports at least two manners of iteration through the content via the HTMLDocument.Iterator and ElementIterator classes.

HTMLDocument.Iterator Class

To use the HTMLDocument.Iterator, you ask an HTMLDocument to give you the iterator for a specific HTML.Tag. Then, for each instance of the tag in the document, you can look at the attributes of the tag.

The HTML.Tag class includes 76 class constants for all the standard HTML tags (which the HTMLToolkit understands), such as HTML.Tag.H1 for the <H1> tag. These constants are listed in Table 16-7.

Table 16-7. *HTML Tag Constants*

A	DIR	IMG	SCRIPT
ADDRESS	DIV	IMPLIED	SELECT
APPLET	DL	INPUT	SMALL
AREA	DT	ISINDEX	SPAN
B	EM	KBD	STRIKE
BASE	FONT	LI	STRONG
BASEFONT	FORM	LINK	STYLE
BIG	FRAME	MAP	SUB
BLOCKQUOTE	FRAMESET	MENU	SUP
BODY	H1	META	TABLE
BR	H2	NOFRAMES	TD
CAPTION	H3	OBJECT	TEXTAREA
CENTER	H4	OL	TH
CITE	H5	OPTION	TITLE
CODE	H6	P	TR
COMMENT	HEAD	PARAM	TT
CONTENT	HR	PRE	U
DD	HTML	S	UL
DFN	I	SAMP	VAR

Note Only those HTML tag constants that have been previously flagged as a block tag—where the `isBlock()` method for the tag returns `true`—will work with the `HTMLDocument.Iterator`. For instance, `STRONG` is not a block tag, while `H1` is.

After you have the specific iterator to work with, you can look at the specific attributes and content of each instance of the tag through the help of the class properties shown in Table 16-8.

Table 16-8. *HTMLDocument.Iterator Properties*

Property Name	Data Type	Access
<code>attributes</code>	<code>AttributeSet</code>	Read-only
<code>endOffset</code>	<code>int</code>	Read-only
<code>startOffset</code>	<code>int</code>	Read-only
<code>tag</code>	<code>HTML.Tag</code>	Read-only
<code>valid</code>	<code>boolean</code>	Read-only

The other piece of the iteration process is the `next()` method, which lets you get the next instance of the tag in the document. The basic structure of using this iterator is as follows:

```
// Get the iterator
HTMLDocument.Iterator iterator = htmlDoc.getIterator(HTML.Tag.A);

// For each valid one
while (iterator.isValid()) {

    // Process element

    // Get the next one
    iterator.next();
}
```

This can also be expressed in a basic for loop construct:

```
for (HTMLDocument.Iterator iterator = htmlDoc.getIterator(HTML.Tag.A);
     iterator.isValid();
     iterator.next()) {
    // Process element
}
```

Listing 16-6 demonstrates the use of `HTMLDocument.Iterator`. This program prompts you for a URL from the command line, loads the file synchronously, looks for all the `<A>` tags, and then displays all the anchors listed as `HREF` attributes. Think of this as a simple “spidering” application in which you can build up a database of URL links between documents. The start

and end offsets are also used to get the linking text. Just pass in the URL of the location you want to scan to run the program.

Listing 16-6. *Iterating Across HTML Documents for Links*

```
import java.io.*;
import java.net.*;
import javax.swing.*;
import javax.swing.text.*;
import javax.swing.text.html.*;
import javax.swing.text.html.parser.*;
public class DocumentIteratorExample {

    public static void main(String args[]) throws Exception {

        if (args.length != 1) {
            System.err.println("Usage: java DocumentIteratorExample input-URL");
        }

        // Load HTML file synchronously
        URL url = new URL(args[0]);
        URLConnection connection = url.openConnection();
        InputStream is = connection.getInputStream();
        InputStreamReader isr = new InputStreamReader(is);
        BufferedReader br = new BufferedReader(isr);

        HTMLEditorKit htmlKit = new HTMLEditorKit();
        HTMLDocument htmlDoc = (HTMLDocument)htmlKit.createDefaultDocument();
        HTMLEditorKit.Parser parser = new ParserDelegator();
        HTMLEditorKit.ParserCallback callback = htmlDoc.getReader(0);
        parser.parse(br, callback, true);

        // Parse
        for (HTMLDocument.Iterator iterator = htmlDoc.getIterator(HTML.Tag.A);
            iterator.isValid();
            iterator.next()) {

            AttributeSet attributes = iterator.getAttributes();
            String srcString = (String)attributes.getAttribute(HTML.Attribute.HREF);
            System.out.print(srcString);
            int startOffset = iterator.getStartOffset();
            int endOffset = iterator.getEndOffset();
            int length = endOffset - startOffset;
            String text = htmlDoc.getText(startOffset, length);
            System.out.println(" - " + text);
        }
        System.exit(0);
    }
}
```

ElementIterator Class

Another way of examining the contents of an `HTMLDocument` is through the `ElementIterator` (which is not specific to HTML documents). When working with an `ElementIterator`, you basically see all the `Element` objects of the document and ask each one what it is. If the object is something you are interested in working with, you can get a closer look.

To get the iterator for a document, just ask like this:

```
ElementIterator iterator = new ElementIterator(htmlDoc);
```

The `ElementIterator` is not meant to be a simple sequential iterator. It is bidirectional with `next()` and `previous()` methods and supports going back to the beginning with `first()`. Although `next()` and `previous()` return the next or previous element to work with, you can also get the element at the current position by using `current()`. Here is the basic looping method through a document:

```
Element element;
ElementIterator iterator = new ElementIterator(htmlDoc);
while ((element = iterator.next()) != null) {
    // Process element
}
```

How do you find out which element you have in case you want to ignore it if it isn't interesting? You need to get its name and type from its attribute set.

```
AttributeSet attributes = element.getAttributes();
Object name = attributes.getAttribute(StyleConstants.NameAttribute);
if (name instanceof HTML.Tag) {
```

Now you can look for specific tag types, such as `HTML.Tag.H1`, `HTML.Tag.H2`, and so on. The actual content for the tag would be in a child element of the element. To demonstrate, the following shows how to search for H1, H2, and H3 tags in a document, while displaying the appropriate titles associated with the tags.

```
if ((name instanceof HTML.Tag) && ((name == HTML.Tag.H1) ||
    (name == HTML.Tag.H2) || (name == HTML.Tag.H3))) {
    // Build up content text as it may be within multiple elements
    StringBuffer text = new StringBuffer();
    int count = element.getElementCount();
    for (int i=0; i<count; i++) {
        Element child = element.getElement(i);
        AttributeSet childAttributes = child.getAttributes();
        if (childAttributes.getAttribute(StyleConstants.NameAttribute) ==
            HTML.Tag.CONTENT) {
            int startOffset = child.getStartOffset();
            int endOffset = child.getEndOffset();
            int length = endOffset - startOffset;
            text.append(htmlDoc.getText(startOffset, length));
        }
    }
}
```

To try this out, you'll need to actually find a web page that uses H1, H2, or H3 tags. This isn't easy these days. Alternatively, you can just switch the H1, H2, and H3 to different tags that you know you will find.

JFormattedTextField Formats

In Chapter 15, you got a little taste of the `JFormattedTextField` component. Now, you'll get the rest of the meal. A `JFormattedTextField` is used for accepting formatted input from a user. This sounds simple, but is actually quite important and involved. Without a `JFormattedTextField`, getting formatted input isn't as easy as it sounds. Throwing in localization requirements makes life really interesting.

Not only does the `JFormattedTextField` component support entering input in a formatted fashion, but it also allows the user to use the keyboard to increment and decrement the input value; for example, to scroll through the available months in a date.

For a `JFormattedTextField`, the validation magic is controlled by the `focusLostBehavior` property. This can be set to one of four values:

- `COMMIT_OR_REVERT`: This is the default. When the component loses focus, the component automatically calls the `commitEdit()` method internally. This will parse the component's contents and throw a `ParseException` on error, reverting the contents to the most recent valid value.
- `COMMIT`: This setting is similar to `COMMIT_OR_REVERT`, but it leaves the invalid contents within the field, allowing the user to modify the setting.
- `REVERT`: This setting always reverts the value.
- `PERSIST`: This setting essentially does nothing. When the `focusLostBehavior` property is set to `PERSIST`, you should manually call `commitEdit()` yourself to see if the contents are valid before using the contents.

Dates and Numbers

For starters, let's see how to use the `JFormattedTextField` to accept input that should be internationalized. This includes all forms of dates, times, and numbers—basically, anything whose format can be acquired from a `DateFormat` or `NumberFormat` object.

If you provide a `Date` object or `Number` subclass to the `JFormattedTextField` constructor, the component passes the input `String` to the constructor of that object type to do the input validation. Instead, you should work with the `InternationalFormatter` class in the `java.swing.text` package by passing a `DateFormat` or `NumberFormat` into the constructor. This allows you to specify long versus short form for dates and times, as well as currency, percentage, floats, and integers for numbers.

Date and Time Formats

To demonstrate date and time formatting, the example in Listing 16-7 accepts various date and time input. From top to bottom, the inputs are short date format for default locale, full date format for United States English, medium date format for Italian, day of week in French, and short time format for the default locale.

Listing 16-7. *Formatted Date and Time Input*

```
import javax.swing.*;
import javax.swing.text.*;
import javax.swing.event.*;
import java.awt.*;
import java.text.*;
import java.util.*;

public class DateInputSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Date/Time Input");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JLabel label;
                JFormattedTextField input;
                JPanel panel;

                BoxLayout layout =
                    new BoxLayout(frame.getContentPane(), BoxLayout.Y_AXIS);
                frame.setLayout(layout);

                Format shortDate =
                    DateFormat.getDateInstance(DateFormat.SHORT);
                label = new JLabel("Short date:");
                input = new JFormattedTextField(shortDate);
                input.setValue(new Date());
                input.setColumns(20);
                panel = new JPanel(new FlowLayout(FlowLayout.RIGHT));
                panel.add(label);
                panel.add(input);
                frame.add(panel);

                Format fullUSDate =
                    DateFormat.getDateInstance(DateFormat.FULL, Locale.US);
                label = new JLabel("Full US date:");
                input = new JFormattedTextField(fullUSDate);
                input.setValue(new Date());
                input.setColumns(20);
                panel = new JPanel(new FlowLayout(FlowLayout.RIGHT));
                panel.add(label);
                panel.add(input);
                frame.add(panel);
            }
        };
        SwingUtilities.invokeLater(runner);
    }
}
```

```

        Format mediumItalian =
            DateFormat.getDateInstance(DateFormat.MEDIUM, Locale.ITALIAN);
        label = new JLabel("Medium Italian date:");
        input = new JFormattedTextField(mediumItalian);
        input.setValue(new Date());
        input.setColumns(20);
        panel = new JPanel(new FlowLayout(FlowLayout.RIGHT));
        panel.add(label);
        panel.add(input);
        frame.add(panel);

        Format dayOfWeek = new SimpleDateFormat("E", Locale.FRENCH);
        label = new JLabel("French day of week:");
        input = new JFormattedTextField(dayOfWeek);
        input.setValue(new Date());
        input.setColumns(20);
        panel = new JPanel(new FlowLayout(FlowLayout.RIGHT));
        panel.add(label);
        panel.add(input);
        frame.add(panel);

        Format shortTime = DateFormat.getTimeInstance(DateFormat.SHORT);
        label = new JLabel("Short time:");
        input = new JFormattedTextField(shortTime);
        input.setValue(new Date());
        input.setColumns(20);
        panel = new JPanel(new FlowLayout(FlowLayout.RIGHT));
        panel.add(label);
        panel.add(input);
        frame.add(panel);

        frame.pack();
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Figure 16-6 shows an example of running the program. To start the program in a different locale, you can set the `user.language` and `user.country` settings from the command line with a command similar to the following:

```
java -Duser.language=fr -Duser.country=FR DateInputSample
```

However, this will alter the valid input only for those formats without a specific locale set.




Figure 16-6. *Formatted JFormattedTextField date and time input*

Number Formats

Numbers work similarly to dates, just with the `java.text.NumberFormat` class, instead of the `DateFormat` class. The localization that can be done here is with `getCurrencyInstance()`, `getInstance()`, `getIntegerInstance()`, `getNumberInstance()`, and `getPercentInstance()`.

The `NumberFormat` class will deal with the placement of the necessary commas, periods, percent signs, and so on. While inputting the numbers, extra characters like commas for thousands aren't required. The component will add them after they are input where appropriate, as shown in the example in Figure 16-7. Notice the positions of decimal points and commas and how they differ from locale to locale.




Figure 16-7. *Formatted JFormattedTextField numeric input*

Listing 16-8 shows the program that generated Figure 16-7. Each input field starts with a value of 2424.50. In the case of the integer version, the input value is rounded. When setting the contents of a `JFormattedTextField`, use the `setValue()` method, not the `setText()` method. This will ensure that the text contents are validated.

Listing 16-8. Formatted Numeric Input

```
import javax.swing.*;
import javax.swing.text.*;
import javax.swing.event.*;
import java.awt.*;
import java.text.*;
import java.util.*;
```

```

public class NumberInputSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Number Input");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                Font font = new Font("SansSerif", Font.BOLD, 16);

                JLabel label;
                JFormattedTextField input;
                JPanel panel;

                BoxLayout layout =
                    new BoxLayout(frame.getContentPane(), BoxLayout.Y_AXIS);
                frame.setLayout(layout);

                Format currency =
                    NumberFormat.getCurrencyInstance(Locale.UK);
                label = new JLabel("UK Currency:");
                input = new JFormattedTextField(currency);
                input.setValue(2424.50);
                input.setColumns(20);
                input.setFont(font);
                panel = new JPanel(new FlowLayout(FlowLayout.RIGHT));
                panel.add(label);
                panel.add(input);
                frame.add(panel);

                Format general = NumberFormat.getInstance();
                label = new JLabel("General/Instance:");
                input = new JFormattedTextField(general);
                input.setValue(2424.50);
                input.setColumns(20);
                input.setFont(font);
                panel = new JPanel(new FlowLayout(FlowLayout.RIGHT));
                panel.add(label);
                panel.add(input);
                frame.add(panel);

                Format integer = NumberFormat.getIntegerInstance(Locale.ITALIAN);
                label = new JLabel("Italian integer:");
                input = new JFormattedTextField(integer);
                input.setValue(2424.50);
                input.setColumns(20);
                input.setFont(font);
            }
        };
        new Thread(runner).start();
    }
}

```

```

panel = new JPanel(new FlowLayout(FlowLayout.RIGHT));
panel.add(label);
panel.add(input);
frame.add(panel);

Format number = NumberFormat.getNumberInstance(Locale.FRENCH);
label = new JLabel("French Number:");
input = new JFormattedTextField(number);
input.setValue(2424.50);
input.setColumns(20);
input.setFont(font);
panel = new JPanel(new FlowLayout(FlowLayout.RIGHT));
panel.add(label);
panel.add(input);
frame.add(panel);

label = new JLabel("Raw Number:");
input = new JFormattedTextField(2424.50);
input.setColumns(20);
input.setFont(font);
panel = new JPanel(new FlowLayout(FlowLayout.RIGHT));
panel.add(label);
panel.add(input);
frame.add(panel);
frame.pack();
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

The last of the five `JFormattedTextField` examples in Figure 16-7 initializes the component with a double. The value 2424.50 is auto-boxed into a `Double` object. There's nothing wrong with passing an object to the constructor. However, you might notice some irregularities while entering values into the field. A value seems to always start with one decimal point, even though more input digits are accepted. Instead of using a `Format` object to go from text to `Object` and back, the `Double` constructor that accepts a `String` is used.

When you pass in a `java.text.Format` object to the `JFormattedTextField` constructor, this internally is mapped to either a `DateFormatter` or `NumberFormatter` object. Both of these are subclasses of the `InternationalFormatter` class. The inner class named `JFormattedTextField.AbstractFormatterFactory` manages the use of the formatter objects within `JFormattedTextField`. The factory will `install()` the formatter as the user enters the `JFormattedTextField` and `uninstall()` it on departure, ensuring the formatter is active in only one text field at a time. These `install()` and `uninstall()` methods are inherited by the formatter classes from the `JFormattedTextField.AbstractFormatter` superclass of all formatters.

Input Masks

Beyond numbers and dates, the `JFormattedTextField` supports user input following a pattern or mask. For instance, if an input field is a United States social security number (SSN), it has a typical pattern of number, number, number, dash, number, number, dash, number, number, number, number. With the help of the `MaskFormatter` class, you can specify the mask using the characters listed in Table 16-9.

Table 16-9. *Special Characters for Masks*

Character	Description
#	Matches numeric character (<code>Character.isDigit()</code>)
H	Matches hexadecimal number (0–9, a–f, and A–F)
A	Matches alphanumeric character (<code>Character.isLetterOrDigit()</code>)
?	Matches alphabetic character (<code>Character.isLetter()</code>)
U	Matches uppercase letter; maps lowercase to uppercase
L	Matches lowercase letter; maps uppercase to lowercase
*	Wildcard, matches any character
'	Escape character to have literal strings/separators in input field

For example, this formatter creates an SSN mask:

```
new MaskFormatter("###'-##'-####")
```

The apostrophes in the mask mean the character after each is treated literally—in this case, as a dash. You have the option of passing this formatter to the `JFormattedTextField` constructor or configuring the text field with the `setMask()` method.

To demonstrate, Listing 16-9 includes two `JFormattedTextField` components: one to accept SSNs and the other United States phone numbers.

Listing 16-9. *Formatted Masked Input*

```
import javax.swing.*.*;
import javax.swing.text.*;
import javax.swing.event.*;
import java.awt.*.*;
import java.text.*;
import java.util.*;

public class MaskInputSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Mask Input");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
```

```

JLabel label;
JFormattedTextField input;
JPanel panel;
MaskFormatter formatter;

BoxLayout layout =
    new BoxLayout(frame.getContentPane(), BoxLayout.Y_AXIS);
frame.setLayout(layout);

try {
    label = new JLabel("SSN");
    formatter = new MaskFormatter("###'-##'-####");
    input = new JFormattedTextField(formatter);
    input.setValue("123-45-6789");
    input.setColumns(20);
    panel = new JPanel(new FlowLayout(FlowLayout.RIGHT));
    panel.add(label);
    panel.add(input);
    frame.add(panel);
} catch (ParseException e) {
    System.err.println("Unable to add SSN");
}

try {
    label = new JLabel("US Phone");
    formatter = new MaskFormatter("'(###)' ###'-####");
    input = new JFormattedTextField(formatter);
    input.setColumns(20);
    panel = new JPanel(new FlowLayout(FlowLayout.RIGHT));
    panel.add(label);
    panel.add(input);
    frame.add(panel);
} catch (ParseException e) {
    System.err.println("Unable to add Phone");
}

frame.pack();
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Figure 16-8 shows the output of the program. In this example, the SSN field starts with an initial value, while the phone number field does not.




Figure 16-8. *Formatted masked input in JFormattedTextFields*

The MaskFormatter does provide some customization options. By default, the formatter is in overwrite mode, so as you type, the entered digits will replace each number and space in the input field. Set the `overwriteMode` property to `false` to disable this. Typically, this isn't necessary, though for entering in long dates, it can be helpful.

If you wish to have a different character as the placeholder character, before a position is filled in the mask, set the `placeholderCharacter` property of the MaskFormatter. To demonstrate, add the following line to the phone number formatter in Listing 16-9:

```
formatter.setPlaceholder('*');
```

You'll see the results in the bottom text field shown in Figure 16-9.




Figure 16-9. *Formatted masked input with a placeholder*

Another useful MaskFormatter property is `validCharacters`, for restricting which alphanumeric characters are valid for an input field.

DefaultFormatterFactory Class

The DefaultFormatterFactory class found in the `javax.swing.text` package offers a way to have different formatters for displaying values, editing values, and a special case of a null value. It offers five constructors, starting with no parameters and then adding an additional `AbstractFormatter` parameter for each constructor.

```
public DefaultFormatterFactory()
```

```
DefaultFormatterFactory factory = new DefaultFormatterFactory()
```

```
public DefaultFormatterFactory(JFormattedTextField.AbstractFormatter defaultFormat)
```

```
DateFormat defaultFormat = new SimpleDateFormat("yyyy-MM-dd");
```

```
DateFormatter defaultFormatter = new DateFormatter(defaultFormat);
```

```
DefaultFormatterFactory factory = new DefaultFormatterFactory(defaultFormatter);
```

```
public DefaultFormatterFactory(JFormattedTextField.AbstractFormatter defaultFormat,  
    JFormattedTextField.AbstractFormatter displayFormat)
```

```
DateFormat displayFormat = new SimpleDateFormat("yyyy-MM-dd");
```

```
DateFormatter displayFormatter = new DateFormatter(displayFormat);
```

```
DefaultFormatterFactory factory = new DefaultFormatterFactory(displayFormatter,  
    displayFormatter);
```

```

public DefaultFormatterFactory(JFormattedTextField.AbstractFormatter defaultFormat,
    JFormattedTextField.AbstractFormatter displayFormat,
    JFormattedTextField.AbstractFormatter editFormat)
DateFormat displayFormat = new SimpleDateFormat("yyyy-MM-dd");
DateFormatter displayFormatter = new DateFormatter(displayFormat);
DateFormat editFormat = new SimpleDateFormat("MM/dd/yy");
DateFormatter editFormatter = new DateFormatter(editFormat);
DefaultFormatterFactory factory = new DefaultFormatterFactory(
    displayFormatter, displayFormatter, editFormatter);

public DefaultFormatterFactory(JFormattedTextField.AbstractFormatter defaultFormat,
    JFormattedTextField.AbstractFormatter displayFormat,
    JFormattedTextField.AbstractFormatter editFormat,
    JFormattedTextField.AbstractFormatter nullFormat)
DateFormat displayFormat = new SimpleDateFormat("yyyy-MM-dd");
DateFormatter displayFormatter = new DateFormatter(displayFormat);
DateFormat editFormat = new SimpleDateFormat("MM/dd/yy");
DateFormatter editFormatter = new DateFormatter(editFormat);
DateFormat nullFormat = new SimpleDateFormat("'null'");
DateFormatter nullFormatter = new DateFormatter(nullFormat);
DefaultFormatterFactory factory = new DefaultFormatterFactory(
    displayFormatter, displayFormatter, editFormatter, nullFormatter);

```

There isn't much magic in the use of `DefaultFormatterFactory`. Just create one and pass it along to the `JFormattedTextField` constructor. Then the state of the text field will determine which formatter is used to show the current value. Typically, the display formatter is repeated for the default settings. If any of the formatters is null or unset, the default formatter will be used instead.

Summary

In this chapter, you saw several of the more advanced aspects of working with the JFC/Project Swing text components. You looked into how to use the predefined `TextAction` objects to create working user interfaces without defining any of your own event-handling capabilities. In addition, you explored the `JTextPane` and how to create multiple-attributed text within a `JTextPane` through the `AttributeSet`, `MutableAttributeSet`, `SimpleAttributeSet`, and `StyleConstants`. You also saw how to create tab stops within a `Document` and glanced at the `EditorKit` facilities of Swing, exploring the details of the `HTMLEditorKit` specifically. Finally, you learned more about accepting formatted input with the `JFormattedTextField`.

For additional information about the Swing text package, be sure to stop by The Swing Connection at <http://java.sun.com/products/jfc/tsc/articles/text/overview/>.

In Chapter 17, you'll explore the Swing component for displaying hierarchical data: the `JTree`.



Trees

In Chapter 16, you looked at how to work with the text document capabilities within the Swing component set. In this chapter, you'll learn how to work with Swing's tree class, the `JTree` component.

Introducing Trees

The `JTree` component is the visual component for displaying hierarchical data elements, also known as *nodes*. Using this tree metaphor, imagine the tree is flipped upside down. The node at the top of the tree is called the *root*. Extending from the root node of the tree are branches to other nodes. If a node does not have any branches coming out of it, that node is called a *leaf node*. See Figure 17-1 for a simple `JTree`.



Figure 17-1. *Sample JTree*

Many interconnected classes are used in the composition of the `JTree`. First, the `JTree` implements the `Scrollable` interface, so that you can place the tree within a `JScrollPane` for scroll management. The display of each node within the tree is controlled by implementations of the `TreeCellRenderer` interface; by default, the implementation is the `DefaultTreeCellRenderer` class. Nodes of a tree are editable with implementations of `TreeCellEditor`. Two editor implementations are available: one offering a text field with `DefaultTreeCellEditor` and one offering a check box or combo box with `DefaultCellEditor`, which extends from the generic `AbstractCellEditor`. If these classes don't provide what you need, you can place custom editors within an `EditorContainer`.

Note The `DefaultCellEditor` class can also be used as a cell editor with the `JTable` component. The `JTable` component is described in Chapter 18.

By default, the actual nodes of the `JTree` are implementations of the `TreeNode` interface or its subinterface `MutableTreeNode`. The `DefaultMutableTreeNode` class is one such implementation that's commonly used, with the `JTree.DynamicUtilTreeNode` inner class helping to create the tree nodes. The many tree nodes make up the `TreeModel` for the `JTree`, stored by default into an instance of the `DefaultTreeModel` class.

Tree selection is managed by a `TreeSelectionModel` implementation, with a default implementation of `DefaultTreeSelectionModel` available. The `JTree.EmptySelectionModel` is also available if you do not want the nodes of the tree to be selectable. The path of nodes from the root of the tree to the selected node is maintained within a `TreePath`, with the help of a `RowMapper` implementation to map rows to paths.

Note The tree-specific classes are found in the `javax.swing.tree` package. The event-related classes are in the `javax.swing.event` package.

JTree Class

The `JTree` class forms the basis for visually displaying a set of hierarchical data elements.

Creating a JTree

There are seven different ways to create a `JTree`, with five different ways to specify the nodes:

```
public JTree()
JTree tree = new JTree();

public JTree(Hashtable value)
JTree tree = new JTree(System.getProperties());

public JTree(Object value[])
public static void main (String args[]) {
    JTree tree = new JTree(args);
    ...
}

public JTree(Vector value)
Vector vector = new Vector();
vector.add("One");
vector.add("Two");
JTree tree = new JTree(vector);
```

```
public JTree(TreeModel value)
JTree tree = new JTree(aTreeModel);

public JTree(TreeNode value)
JTree tree = new JTree(aTreeNode);

public JTree(TreeNode value, boolean asksAllowsChildren)
JTree tree = new JTree(aTreeNode, true);
```

The first of the constructors is the no-argument variety. Surprisingly, it has a default data model with some nodes in it (see Figure 17-1). Normally, you would change the data model of the default tree after creation with `setModel(TreeModel newModel)`.

The next three constructors seem to belong together. Creation of a `JTree` from a `Hashtable` made up of key/value pairs uses the set of keys for the nodes and values for the children, whereas creation from an array or `Vector` uses the elements as the nodes. This may seem to imply that the tree is only one level deep, but actually the tree can be infinitely deep if the key or element itself is in a `Hashtable`, an array, or a `Vector`.

The remaining three constructors use the custom data structures of `JTree`, which will be explained later in this chapter. By default, only those nodes that have children are leaf nodes. However, trees can be constructed with partial nodes that won't get children until later. The last of these three constructors causes a method to be called when you try to open a parent node, instead of the parent node just looking for child nodes.

Tip If the value for a key in a `Hashtable` is another `Hashtable`, array, or `Vector`, you can create a multi-level tree by using the top-level `Hashtable` as the constructor argument.

As I mentioned, using a `Hashtable`, an array, or a `Vector` as the argument in the constructor tree does, in fact, allow you to create multilevel trees. There are two minor problems with this, however: the root node isn't visible, and it automatically has a data element of root. The text label for any other nodes of type `Hashtable`, array, or `Vector` is the result of `toString()`. The default text is not desirable in any of these three instances. You get either the results of the `toString()` method of the `Object` class for an array or a label that includes a list of all the elements in the `Hashtable` or `Vector`. In the case of an `Object` array, the output would look something like `[Ljava.lang.Object;@fa8d8993`. This is certainly not something you want to show a user.

Although you cannot override `toString()` (because there is no array class to subclass), you can subclass `Hashtable` or `Vector` to provide a different `toString()` behavior. Offering a name to the constructor of this new class allows you to provide a text label to use in the tree when the `Hashtable` or `Vector` is not the root node. The class shown in Listing 17-1 defines this behavior for a `Vector` subclass. In addition to the constructor providing a name, the class also adds a constructor that initializes the `Vector` to the contents of an array.

Listing 17-1. *Named Vector*

```

import java.util.Vector;
public class NamedVector<E> extends Vector<E> {
    String name;
    NamedVector(String name) {
        this.name = name;
    }
    NamedVector(String name, E elements[]) {
        this.name = name;
        for (int i=0, n=elements.length; i<n; i++) {
            add(elements[i]);
        }
    }
    public String toString() {
        return "[" + name + "]";
    }
}

```

Figure 17-2 shows an example of the `NamedVector` class in action.




Figure 17-2. *Sample JTree with the Vector subclass node*

Listing 17-2 shows the source used to generate the example in Figure 17-2.

Listing 17-2. *Named Vector Usage*

```

import javax.swing.*;
import javax.swing.tree.*;
import java.awt.*;
import java.util.*;

public class TreeArraySample {
    public static void main(final String args[]) {
        Runnable runner = new Runnable() {

```

```

public void run() {
    JFrame frame = new JFrame("JTreeSample");
    frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

    Vector<String> oneVector = new NamedVector<String>("One", args);
    Vector<String> twoVector = new NamedVector<String>("Two",
        new String[]{"Mercury", "Venus", "Mars"});
    Vector<Object> threeVector = new NamedVector<Object>("Three");
    threeVector.add(System.getProperties());
    threeVector.add(twoVector);
    Object rootNodes[] = {oneVector, twoVector, threeVector};
    Vector<Object> rootVector = new NamedVector<Object>("Root", rootNodes);
    JTree tree = new JTree(rootVector);
    frame.add(tree, BorderLayout.CENTER);
    frame.setSize(300, 300);
    frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}
}

```

Scrolling Trees

If you created and ran the program in Listing 17-2, you would notice one small problem. When all the parent nodes are open, the tree is too big for the initial screen size. Not only that, but you also can't see the nodes at the bottom of the tree. To fix this situation, it's necessary to place instances of the `JTree` class within a `JScrollPane` so that the scroll pane can manage the scrolling aspects of the tree. Similar to the `JTextArea` class described in Chapter 15, the `JTree` class implements the `Scrollable` interface for scrolling support.

Replacing the two boldfaced lines in the example in Listing 17-2 with the following three lines will place the tree within a scroll pane. This will cause the tree to appear in a scrollable region when the tree is too large for the available display space.

```

// Change from
JTree tree = new JTree(rootVector);
frame.add(tree, BorderLayout.CENTER);
// To
JTree tree = new JTree(rootVector);
JScrollPane scrollPane = new JScrollPane(tree);
frame.add(scrollPane, BorderLayout.CENTER);

```

In addition to using a `JScrollPane` for scrolling, you can manually scroll the visible content in the scrolling region. Use the public `void scrollPathToVisible(TreePath path)` and public `void scrollRowToVisible(int row)` methods to move a particular tree path or row into some part of the visible area. The *row* of a node indicates the number of nodes above the current node to the top of the tree. This differs from the *level* of the tree, which is the number of ancestors (or parent nodes) a node has. Figure 17-3 should help you visualize this difference. In the

window on the left, the soccer node is at level 2 and row 8. When the colors node is closed, as in the window on the right, the soccer node remains on level 2 but moves to row 4, because the blue, violet, red, and yellow rows are no longer visible.




Figure 17-3. Rows versus levels of a tree

JTree Properties

Table 17-1 lists the 40 specific properties of JTree. You will explore many of these as you look at the different classes that make up JTree.

Table 17-1. JTree Properties

Property Name	Data Type	Access
accessibleContext	AccessibleContext	Read-only
anchorSelectionPath	TreePath	Read-write bound
cellEditor	TreeCellEditor	Read-write bound
cellRenderer	TreeCellRenderer	Read-write bound
dragEnabled	boolean	Read-write
editable	boolean	Read-write bound
editing	boolean	Read-only
editingPath	TreePath	Read-only
expandsSelectedPath	boolean	Read-write bound
fixedRowHeight	boolean	Read-only
invokesStopCellEditing	boolean	Read-write bound
largeModel	boolean	Read-write bound
lastSelectedPathComponent	Object	Read-only
leadSelectionPath	TreePath	Read-write bound

Table 17-1. *JTree Properties (Continued)*

Property Name	Data Type	Access
leadSelectionRow	int	Read-only
maxSelectionRow	int	Read-only
minSelectionRow	int	Read-only
model	TreeModel	Read-write bound
preferredScrollableViewportSize	Dimension	Read-only
rootVisible	boolean	Read-write bound
rowCount	int	Read-only
rowHeight	int	Read-write bound
scrollableTracksViewportHeight	boolean	Read-only
scrollableTracksViewportWidth	boolean	Read-only
scrollsOnExpand	boolean	Read-write bound
selectionCount	int	Read-only
selectionEmpty	boolean	Read-only
selectionModel	TreeSelectionModel	Read-write bound
selectionPath	TreePath	Read-write
selectionPaths	TreePath[]	Read-write
selectionRow	int	Write-only
selectionRows	int[]	Read-write
showsRootHandles	boolean	Read-write bound
toggleClickCount	int	Read-write bound
treeExpansionListeners	TreeExpansionListener[]	Read-only
treeSelectionListeners	TreeSelectionListener[]	Read-only
treeWillExpandListeners	TreeWillExpandListener[]	Read-only
UI	TreeUI	Read-write
UIClassID	String	Read-only
visibleRowCount	int	Read-write bound

Some JTree properties are closely interrelated. For instance, when the `rowHeight` property is positive, it means that the node at each row is displayed with a fixed height, no matter what size the nodes within the tree should be. When the `rowHeight` property is negative, the `cellRenderer` property determines the `rowHeight`. So, the value of `rowHeight` determines the setting of the

`fixedRowHeight` property. Changing the value of `rowHeight` to a value such as 12 pixels results in the `fixedRowHeight` property having a setting of `true`.

The `largeModel` property setting is a suggestion to the `TreeUI` to help it display the tree. Initially, this setting is `false` because a tree has many data elements and you don't want the user interface component to cache excessive information (such as node renderer sizes) about the tree. For smaller models, caching information about a tree doesn't require as much memory.

The current setting of `lastSelectedPathComponent` property is the contents of the last selected node. At any time, you can ask a tree what is selected. If nothing is selected, this property's value will be `null`. Because trees support multiple selections, the `lastSelectedPathComponent` property doesn't necessarily return *all* selected nodes. You can also modify the selection path with the `anchorSelectionPath` and `leadSelectionPath` properties.

The three selection row properties—`leadSelectionRow`, `minSelectionRow`, and `maxSelectionRow`—are interesting in that the row values can change based on another parent node's opening or closing. When a single node in the tree is selected, all three properties have the same setting. You can get an array of all selected row indices with the `selectionRows` property. However, there is no way to map a row number to a node in the tree. Instead, use the `selectionPaths` property, which provides an array of `TreePath` elements. As you'll soon see, each `TreePath` includes the selected node and all nodes on the path from the root node to the selected node.

There are three visibility-related settings of a tree. You can adjust the preferred number of rows to display for the tree by setting the `visibleRowCount` property. By default, the setting is 20. This setting is valid only when a particular tree is within a `JScrollPane` or some other component that uses the `Scrollable` interface. The second visibility-related setting has to do with whether the root node is visible. When the tree is created from a `Hashtable`, `array`, or `Vector` constructor, the root isn't visible. Otherwise, it will be visible initially. Changing the `rootVisible` property allows you to alter this setting. The other visibility-related setting has to do with the icon next to the root node. By default, there is no icon at the root level to show the open or closed state of the root of the tree. All nonroot nodes always have this type of icon. To show the root icon, set the `showsRootHandles` property to `true`.

Three additional selection-oriented properties are also available. The `toggleClickCount` property allows you to control how many clicks over a parent node will trigger selection or expansion of the node. The default setting is 2. The `scrollsOnExpand` property causes the tree to scroll when a node is expanded such that as many descendants as possible will be visible. By default, this is `true`. The third property, `expandsSelectedPath`, is `true` by default, causing the selected path for a node to be expanded when programmatically selected. If, however, you don't wish to expand the tree upon programmatic selection, you can set this to `false` and leave the path hidden.

Customizing a JTree Look and Feel

Each installable Swing look and feel provides a different `JTree` appearance and set of default `UIResource` values. Figure 17-4 shows the appearance of the `JTree` container for the preinstalled set of look and feel types: `Motif`, `Windows`, and `Ocean`.




Figure 17-4. *JTree* under different look and feel types

The available set of `UIResource`-related properties for a `JTree` is shown in Table 17-2. For the `JTree` component, there are 43 different properties.

Table 17-2. *JTree* `UIResource` Elements

Property String	Object Type
<code>Tree.actionMap</code>	<code>ActionMap</code>
<code>Tree.ancestorInputMap</code>	<code>InputMap</code>
<code>Tree.background</code>	<code>Color</code>
<code>Tree.changeSelectionWithFocus</code>	<code>Boolean</code>
<code>Tree.closedIcon</code>	<code>Icon</code>
<code>Tree.collapsedIcon</code>	<code>Icon</code>
<code>Tree.drawDashedFocusIndicator</code>	<code>Boolean</code>
<code>Tree.drawHorizontalLines</code>	<code>Boolean</code>
<code>Tree.drawsFocusBorderAroundIcon</code>	<code>Boolean</code>
<code>Tree.drawVerticalLines</code>	<code>Boolean</code>
<code>Tree.editorBorder</code>	<code>Border</code>
<code>Tree.editorBorderSelectionColor</code>	<code>Color</code>
<code>Tree.expandedIcon</code>	<code>Icon</code>
<code>Tree.expanderSize</code>	<code>Integer</code>

Table 17-2. *JTree UIResource Elements (Continued)*

Property String	Object Type
Tree.focusInputMap	InputMap
Tree.focusInputMap.RightToLeft	InputMap
Tree.font	Font
Tree.foreground	Color
Tree.hash	Color
Tree.iconBackground	Color
Tree.iconForeground	Color
Tree.iconHighlight	Color
Tree.iconShadow	Color
Tree.leafIcon	Icon
Tree.leftChildIndent	Integer
Tree.line	Color
Tree.lineTypeDashed	Boolean
Tree.openIcon	Icon
Tree.padding	Integer
Tree.paintLines	Boolean
Tree.renderUseTreeColors	Boolean
Tree.rightChildIndent	Integer
Tree.rowHeight	Integer
Tree.scrollsHorizontallyAndVertically	Boolean
Tree.scrollsOnExpand	Boolean
Tree.selectionBackground	Color
Tree.selectionBorderColor	Color
Tree.selectionForeground	Color
Tree.showsRootHandles	Boolean
Tree.textBackground	Color
Tree.textForeground	Color
Tree.timeFactor	Integer
TreeUI	String

Of the many different `JTree` resources, five are for the various icons displayed within the `JTree`. To see how the five icons are positioned, examine Figure 17-5. If you just want to change the icons (and possibly the colors) of a tree, all you need to do is change the icon properties with lines such as the following:

```
UIManager.put("Tree.openIcon", new DiamondIcon(Color.RED, false));
```




Figure 17-5. *JTree* icons

The purpose of the `Tree.hash` color property may not be immediately obvious. This color is for the lines drawn to connect nodes. With the Metal look and feel, and Ocean theme, by default, angled lines connect the nodes. To enable the drawing of these lines, you must set the `JTree.lineStyle` client property. This property isn't a `UIResource` property, but rather a client property set with the public final void `putClientProperty(Object key, Object value)` method of `JComponent`. The `JTree.lineStyle` property has the following valid settings:

- None, for not drawing lines to connect nodes
- Angled, the default setting for Ocean, for drawing lines in the `Tree.hash` color to connect the nodes
- Horizontal, for drawing horizontal lines between first-level nodes in the `Tree.line` color

Note The `JTree.lineStyle` client property is used only by the Metal look and feel. If the current look and feel isn't Metal or one of its themes like Ocean, the property setting will be ignored if set (unless a custom look and feel takes advantage of the setting). The other system-provided look and feel classes don't use this setting.

With client properties, you first must create the tree and then set the property. This client property is specific to tree components, and it is not set for all trees. Therefore, creating a tree with no lines entails using the following lines of code:

```
JTree tree = new JTree();
tree.putClientProperty("JTree.lineStyle", "None");
```

Figure 17-6 shows the results.



Figure 17-6. A *JTree* with no connection lines

The following lines produce horizontal lines between level-one nodes:

```
UIManager.put("Tree.line", Color.GREEN);
JTree tree = new JTree();
tree.putClientProperty("JTree.lineStyle", "Horizontal");
```

Figure 17-7 shows how the horizontal lines appear.



Figure 17-7. A *JTree* with horizontal level lines

TreeCellRenderer Interface

Each of the nodes within the *JTree* has an installed cell *renderer*. It's the responsibility of the renderer to draw the node and clearly display its state. The default renderer is basically a *JLabel*, which allows you to have both text and an icon within the node. However, any component can serve as the node renderer. The default renderer displays an icon that represents the state of the node.

Note The tree cell renderer is just that—a renderer. If the renderer were, say, a *JButton*, it wouldn't be selectable but would nevertheless be drawn to look just like a *JButton*.

The configuration of each node renderer is defined by the *TreeCellRenderer* interface. Any class implementing this interface can serve as a renderer for your *JTree*.

```
public interface TreeCellRenderer {
    public Component getTreeCellRendererComponent(JTree tree, Object value,
        boolean selected, boolean expanded, boolean leaf, int row, boolean hasFocus);
}
```

When it's time to draw a tree node, that tree asks its registered `TreeCellRenderer` how to display that specific node. The node itself is passed in as the value argument so that the renderer has access to its current state to determine how to render this state. To change the installed renderer, use `public void setCellRenderer(TreeCellRenderer renderer)`.

DefaultTreeCellRenderer Class

The `DefaultTreeCellRenderer` class serves as the default tree cell renderer. This class is a `JLabel` subclass, so it can support capabilities such as displaying tooltip text or pop-up menus specific to a node. It has only a no-argument constructor.

When used by a `JTree`, the `DefaultTreeCellRenderer` uses the various default icons (as shown earlier in Figure 17-5) to display the current state of the node and a text representation of the data for the node. The text representation is acquired by calling the `toString()` method for each node of the tree.

DefaultTreeCellRenderer Properties

Table 17-3 shows the 14 properties added (or altered) with `DefaultTreeCellRenderer`. Because the default renderer happens to be a `JLabel`, you also acquire many additional properties from it.

Table 17-3. *DefaultTreeCellRenderer Properties*

Property Name	Data Type	Access
<code>background</code>	Color	Write-only
<code>backgroundNonSelectionColor</code>	Color	Read-write
<code>backgroundSelectionColor</code>	Color	Read-write
<code>borderSelectionColor</code>	Color	Read-write
<code>closedIcon</code>	Icon	Read-write
<code>defaultClosedIcon</code>	Icon	Read-only
<code>defaultLeafIcon</code>	Icon	Read-only
<code>defaultOpenIcon</code>	Icon	Read-only
<code>font</code>	Font	Read-write
<code>leafIcon</code>	Icon	Read-write
<code>openIcon</code>	Icon	Read-write
<code>preferredSize</code>	Dimension	Read-only
<code>textNonSelectionColor</code>	Color	Read-write
<code>textSelectionColor</code>	Color	Read-write

If you don't like working with the `UIManager` or just want to change the icons, font, or colors for a single tree, you don't need to create a custom tree cell renderer. Instead, you can ask the tree for its renderer and customize it to display the icons, font, or colors you want. Figure 17-8 shows a `JTree` with an altered renderer. Instead of creating a new renderer, the existing default renderer was customized with the following source:

```
JTree tree = new JTree();
DefaultTreeCellRenderer renderer = (DefaultTreeCellRenderer)tree.getCellRenderer();
// Swap background colors
Color backgroundSelection = renderer.getBackgroundSelectionColor();
renderer.setBackgroundSelectionColor(renderer.getBackgroundNonSelectionColor());
renderer.setBackgroundNonSelectionColor(backgroundSelection);
// Swap text colors
Color textSelection = renderer.getTextSelectionColor();
renderer.setTextSelectionColor(renderer.getTextNonSelectionColor());
renderer.setTextNonSelectionColor(textSelection);
```



Figure 17-8. A `JTree` with an altered default renderer

Remember that `TreeUI` caches renderer size information. If a change to the renderer changes the renderer size, this cache isn't updated. To get around the problem, it's necessary to signal to the tree that the cache is invalid. One such signal is to change the `rowHeight` property. As long as the current `rowHeight` property setting isn't positive, the `TreeUI` must ask the renderer for its height. Therefore, decreasing the value by 1 has a side effect of invalidating the cached renderer size information, causing the tree to be displayed with the proper initial sizes for all the renderers. Adding the following source to the previous example demonstrates this.

```
renderer.setFont(new Font("Dialog", Font.BOLD | Font.ITALIC, 32));
int rowHeight = tree.getRowHeight();
if (rowHeight <= 0) {
    tree.setRowHeight(rowHeight - 1);
}
```

The window on the left in Figure 17-9 shows the effect this addition has on Figure 17-8. If you didn't change the `rowHeight` property to invalidate the display cache, you would get the effect shown in the right window instead.




Figure 17-9. You must properly modify the size of a tree renderer.

Creating a Custom Renderer

If the nodes of your `JTree` consist of information that is too complex to display within the text of a single `JLabel`, you can create your own renderer. As an example, consider a tree in which the nodes describe books by their title, author, and price, as shown in Figure 17-10. In this case, the renderer can be a container in which a separate component displays each part.




Figure 17-10. A `JTree` with a custom renderer

To describe each book in this example, you need to define a class for storing the necessary information, as shown in Listing 17-3.

Listing 17-3. Book Class Definition

```
public class Book {
    String title;
    String authors;
    float price;
    public Book(String title, String authors, float price) {
        this.title = title;
        this.authors = authors;
        this.price = price;
    }
}
```

```

    public String getTitle() {
        return title;
    }
    public String getAuthors() {
        return authors;
    }
    public float getPrice() {
        return price;
    }
}

```

To render a book as a node in the tree, you need to create a `TreeCellRenderer` implementation. Because the books are leaf nodes, the custom renderer will use a `DefaultTreeCellRenderer` to render all the other nodes. The key part of the renderer is the `getTreeCellRendererComponent()`. In the event that the node data received by this method is of type `Book`, it stores the appropriate information in the different labels and returns a `JPanel` as the renderer, with labels for each of the book titles, authors, and prices. Otherwise, the `getTreeCellRendererComponent()` method returns the default renderer.

Listing 17-4 contains the source for this custom renderer. Notice that it uses the same selection colors as the remaining nodes of the tree so that the book nodes don't appear out of place.

Listing 17-4. *Book Cell Renderer*

```

import javax.swing.*.*;
import javax.swing.tree.*;
import java.awt.*.*;

public class BookCellRenderer implements TreeCellRenderer {
    JLabel titleLabel;
    JLabel authorsLabel;
    JLabel priceLabel;
    JPanel renderer;
    DefaultTreeCellRenderer defaultRenderer = new DefaultTreeCellRenderer();
    Color backgroundSelectionColor;
    Color backgroundNonSelectionColor;
    public BookCellRenderer() {
        renderer = new JPanel(new GridLayout(0, 1));
        titleLabel = new JLabel(" ");
        titleLabel.setForeground(Color.BLUE);
        renderer.add(titleLabel);
        authorsLabel = new JLabel(" ");
        authorsLabel.setForeground(Color.BLUE);
        renderer.add(authorsLabel);
        priceLabel = new JLabel(" ");
        priceLabel.setHorizontalAlignment(JLabel.RIGHT);
    }
}

```

```

        priceLabel.setForeground(Color.RED);
        renderer.add(priceLabel);
        renderer.setBorder(BorderFactory.createLineBorder(Color.BLACK));
        backgroundSelectionColor = defaultRendererer.getBackgroundSelectionColor();
        backgroundNonSelectionColor = defaultRendererer.getBackgroundNonSelectionColor();
    }
    public Component getTreeCellRendererComponent(JTree tree, Object value,
        boolean selected, boolean expanded, boolean leaf, int row, boolean hasFocus) {
        Component returnValue = null;
        if ((value != null) && (value instanceof DefaultMutableTreeNode)) {
            Object userObject = ((DefaultMutableTreeNode)value).getUserObject();
            if (userObject instanceof Book) {
                Book book = (Book)userObject;
                titleLabel.setText(book.getTitle());
                authorsLabel.setText(book.getAuthors());
                priceLabel.setText("" + book.getPrice());
                if (selected) {
                    renderer.setBackground(backgroundSelectionColor);
                } else {
                    renderer.setBackground(backgroundNonSelectionColor);
                }
                renderer.setEnabled(tree.isEnabled());
                returnValue = renderer;
            }
        }
        if (returnValue == null) {
            returnValue = defaultRendererer.getTreeCellRendererComponent(tree, value,
                selected, expanded, leaf, row, hasFocus);
        }
        return returnValue;
    }
}

```

Tip The JLabel components are created with an initial text label consisting of a space. Having a nonempty label gives each component some dimensions. The TreeUI caches node sizes to improve performance. Having an initial size for the labels ensures that the cache is initialized properly.

The last remaining part is the test program, shown in Listing 17-5. The majority of it just creates arrays of Book objects. It reuses the NamedVector class from Listing 17-1 to help create the tree branches. The code lines necessary for changing the tree cell renderer are boldfaced. Running the program demonstrates the custom renderer, as shown earlier in Figure 17-10.

Listing 17-5. *Using the Custom Book Cell Renderer*

```

import javax.swing.*.*;
import javax.swing.tree.*;
import java.awt.*.*;
import java.util.*.*;

public class BookTree {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Book Tree");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                Book javaBooks[] = {
                    new Book("Core Java 2", "Horstmann/Cornell", 49.99f),
                    new Book("Effective Java", "Bloch", 34.99f),
                    new Book("Java Collections", "Zukowski", 49.95f)
                };
                Book netBooks[] = {
                    new Book("Beginning VB .NET 1.1 Databases", "Maharry", 49.99f),
                    new Book("Beginning VB.NET Databases", "Willis", 39.99f)
                };
                Vector<Book> javaVector = new NamedVector<Book>("Java Books", javaBooks);
                Vector<Book> netVector = new NamedVector<Book>(".NET Books", netBooks);
                Object rootNodes[] = {javaVector, netVector};
                Vector<Object> rootVector = new NamedVector<Object>("Root", rootNodes);
                JTree tree = new JTree(rootVector);
                TreeCellRenderer renderer = new BookCellRenderer();
                tree.setCellRenderer(renderer);
                JScrollPane scrollPane = new JScrollPane(tree);
                frame.add(scrollPane, BorderLayout.CENTER);
                frame.setSize(300, 300);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

Note Don't worry about the details of `DefaultMutableTreeNode` just yet. Unless otherwise directed, all the nodes of every tree are a `DefaultMutableTreeNode`. Each array element placed in a `Vector` in Listing 17-5 defines the data for that specific node. This data is then stored in the `userObject` property of its `DefaultMutableTreeNode`.

Working with Tree Tooltips

If you want a tree to display tooltips for the nodes, you must register the component with the `ToolTipManager`. If you don't register the component, the renderer will never get the opportunity to display tooltips. The renderer displays the tip, not the tree, so setting tooltip text for the tree is ignored. The following line shows how you to register a specific tree with the `ToolTipManager`.

```
ToolTipManager.sharedInstance().registerComponent(aTree);
```

Once you've notified the `ToolTipManager` that you want the tree to display tooltip text, you must tell the renderer what text to display. Although you can directly set the text with the following lines, this results in a constant setting for all nodes.

```
DefaultTreeCellRenderer renderer = (DefaultTreeCellRenderer)aTree.getCellRenderer();
renderer.setToolTipText("Constant Tool Tip Text");
```

Instead of providing a constant setting, one alternative is to provide the renderer with a table of tooltip strings so that the renderer can determine at runtime the string to display as the tooltip text. The renderer in Listing 17-6 is one such example that relies on a `java.util.Dictionary` implementation (like a `Hashtable`) to store a mapping from nodes to tooltip text. If a tip exists for a specific node, the renderer associates the tip with it.

Listing 17-6. *Tooltip Cell Renderer*

```
import javax.swing.*.*;
import javax.swing.tree.*;
import java.awt.*.*;
import java.util.*;

public class ToolTipTreeCellRenderer implements TreeCellRenderer {
    DefaultTreeCellRenderer renderer = new DefaultTreeCellRenderer();
    Dictionary tipTable;

    public ToolTipTreeCellRenderer (Dictionary tipTable) {
        this.tipTable = tipTable;
    }

    public Component getTreeCellRendererComponent(JTree tree, Object value,
        boolean selected, boolean expanded, boolean leaf, int row,
        boolean hasFocus) {
        renderer.getTreeCellRendererComponent(tree, value, selected, expanded,
            leaf, row, hasFocus);
        if (value != null) {
            Object tipKey;
            if (value instanceof DefaultMutableTreeNode) {
                tipKey = ((DefaultMutableTreeNode)value).getUserObject();
            }
        }
    }
}
```

```

    } else {
        tipKey = tree.convertValueToText(value, selected, expanded, leaf,
            row, hasFocus);
    }
    renderer.setToolTipText((String)tipTable.get(tipKey));
}
return renderer;
}
}

```

Note The example in Listing 17-6 takes advantage of the `JTree` method `public String convertValueToText(Object value, boolean selected, boolean expanded, boolean leaf, int row, boolean hasFocus)` to convert the tree node value to a text string. The value parameter is normally a `DefaultMutableTreeNode`, described later in this chapter. When the value parameter is not a `DefaultMutableTreeNode`, using `convertValueToText()` allows the renderer to support other types of tree nodes.

Using the new `ToolTipTreeCellRenderer` class simply involves creating the Properties list, filling it with tooltip text for the necessary nodes, and then associating the renderer with the tree. Figure 17-11 shows the renderer in action.




Figure 17-11. A *JTree* with tooltips, using the new *ToolTipTreeCellRenderer*

The complete sample program used to generate the screen in Figure 17-11 is shown next in Listing 17-7. This tree uses the list of system properties as the tree nodes. The tooltip text is the current setting for the specific property. When using the `ToolTipTreeCellRenderer`, be sure to register the tree with the `ToolTipManager`.

Listing 17-7. *Using a Tooltip Cell Renderer*

```

import javax.swing.*.*;
import javax.swing.tree.*;
import java.awt.*;
import java.util.*;

```

```

public class TreeTips {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Tree Tips");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                Properties props = System.getProperties();
                JTree tree = new JTree(props);
                TooltipManager.sharedInstance().registerComponent(tree);
                TreeCellRenderer renderer = new TooltipTreeCellRenderer(props);
                tree.setCellRenderer(renderer);
                JScrollPane scrollPane = new JScrollPane(tree);
                frame.add(scrollPane, BorderLayout.CENTER);
                frame.setSize(300, 150);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

Although this example creates a new tree cell renderer, the behavior is only customizing what has already been done for the `DefaultTreeCellRenderer`. Instead of needing to configure the icons and text yourself, let the default renderer do it for you. Then add the tooltip text.

Editing Tree Nodes

In addition to supporting individualized tree cell renderers, `JTree` components can be editable, allowing users to change the contents of any node of the tree. By default, trees are read-only. To make a tree editable, just change the editable property setting to return `true`:

```
aTree.setEditable(true);
```

By default, the editor is a text field. There is also built-in support for picking choices from combo boxes or check boxes. If you prefer, you can create a customized editor for a tree, just as you can create a custom cell renderer.

Note Unfortunately, the built-in check box editor works better within a table than within a tree, where the column label is the name and the value is the cell.

Figure 17-12 shows a tree using the default editor. To enable the editor, select a node, and then double-click it. If the node isn't a leaf node, selecting it will also display or hide the node's children.




Figure 17-12. *An editable JTree with the default editor*

A series of classes is available to support editing tree nodes. Many are shared with the JTable component because both can support editable cells. The `CellEditor` interface forms the basis for the `TreeCellEditor` interface. Any editor implementation for a `JTree` must implement the `TreeCellEditor` interface. The `DefaultCellEditor` (which extends `AbstractCellEditor`) offers one such editor implementation, and the `DefaultTreeCellEditor` offers another. Let's now look at these interfaces and classes in more detail.

CellEditor Interface

The `CellEditor` interface defines the necessary basics for any editor used with a `JTree` or `JTable`, as well as for any third-party components that need an editor. Besides defining how to manage a list of `CellEditorListener` objects, the interface describes how to determine if a particular node or cell is editable and what the new value is after the editor has changed its value.

```
public interface CellEditor {
    // Properties
    public Object getCellEditorValue();
    // Listeners
    public void addCellEditorListener(CellEditorListener l);
    public void removeCellEditorListener(CellEditorListener l);
    // Other methods
    public void cancelCellEditing();
    public boolean isCellEditable(EventObject event);
    public boolean shouldSelectCell(EventObject event);
    public boolean stopCellEditing();
}
```

TreeCellEditor Interface

The `TreeCellEditor` interface works similarly to the `TreeCellRenderer` interface. However, the `getXXXComponent()` method does not have an argument that tells the editor it has the input focus, because in the case of an editor, it must already have the input focus. Any class implementing the `TreeCellEditor` interface can serve as an editor for your `JTree`.

```
public interface TreeCellEditor implements CellEditor {
    public Component getTreeCellEditorComponent(JTree tree, Object value,
        boolean isSelected, boolean expanded, boolean leaf, int row);
}
```

DefaultCellEditor Class

The `DefaultCellEditor` class serves as an editor for both tree nodes and table cells. The class allows you to easily provide a text editor, combo box editor, or check box editor to modify the contents of a node or cell.

The `DefaultTreeCellEditor` class, described next, uses this class to provide an editor for a customized text field, maintaining the appropriate node-type icon based on a `TreeCellRenderer`.

Creating a DefaultCellEditor

When you create a `DefaultCellEditor` instance, you provide the `JTextField`, `JComboBox`, or `JCheckBox` to use as the editor.

```
public DefaultCellEditor(JTextField editor)
JTextField textField = new JTextField();
TreeCellEditor editor = new DefaultCellEditor(textField);

public DefaultCellEditor(JComboBox editor)
public static void main (String args[]) {
    JComboBox comboBox = new JComboBox(args);
    TreeCellEditor editor = new DefaultCellEditor(comboBox);
    ...
}

public DefaultCellEditor(JCheckBox editor)
JCheckBox checkBox = new JCheckBox();
TreeCellEditor editor = new DefaultCellEditor(checkBox);
```

With a `JTree`, you should use the `DefaultTreeCellEditor` if you want a `JTextField` editor. That text field will share the same font and use the appropriate editor border for the tree. When a `JCheckBox` is used as the editor, the node for the tree should be either a `Boolean` value or a `String` that can be converted to a `Boolean`. (If you are unfamiliar with conversion from `String` to `Boolean`, see the Javadoc for the `Boolean` constructor that accepts a `String`.)

After creating an editor, you tell the tree to use it with a call similar to `tree.setCellEditor(editor)`. And don't forget to make the tree editable with `tree.setEditable(true)`. For instance, if you wanted an editable combo box as your editor, the following source code would work:

```
JTree tree = new JTree(...);
tree.setEditable(true);
String elements[] = { "Root", "chartreuse", "rugby", "sushi" };
JComboBox comboBox = new JComboBox(elements);
comboBox.setEditable(true);
TreeCellEditor editor = new DefaultCellEditor(comboBox);
tree.setCellEditor(editor);
```

This code produces the screen shown in Figure 17-13 when editing the basketball node. Notice that there is no icon to indicate the type of node being edited. This is rectified with the

DefaultTreeCellEditor class. The DefaultCellEditor is primarily for use within a JTable, not a JTree.



Figure 17-13. An editable JTree with a JComboBox editor

Caution When you use a noneditable JComboBox as the cell editor, if the set of choices doesn't include the original node setting, it's impossible to get back to the original setting once the node value changes.

To see how awkward the appearance of a JCheckBox is with the DefaultCellEditor as a TreeCellEditor, take a look at Figure 17-14.



Figure 17-14. An editable JTree with a JCheckBox editor

Figure 17-14 uses the following source:

```
Object array[] =
    {Boolean.TRUE, Boolean.FALSE, "Hello"}; // Hello will map to false
JTree tree = new JTree(array);
tree.setEditable(true);
tree.setRootVisible(true);
JCheckBox checkBox = new JCheckBox();
TreeCellEditor editor = new DefaultCellEditor(checkBox);
tree.setCellEditor(editor);
```

Note Use of the JCheckBox with the DefaultCellEditor isn't recommended with a JTree. See the "Creating a Better Check Box Node Editor" section later in this chapter for an implementation that's more appropriate for a tree.

The awkwardness of the JCheckBox editor and custom text field editor within the DefaultTreeCellEditor leaves the JComboBox as the only TreeCellEditor you'll get from DefaultCellEditor. However, you still might want to place the combo box editor within a DefaultTreeCellEditor to display the appropriate type icon next to the node.

DefaultCellEditor Properties

The DefaultCellEditor has only three properties, which are listed in Table 17-4. The editor can be any AWT component, not just a lightweight Swing component. Keep in mind the hazards of mixing heavyweight and lightweight components, if you do choose to use a heavyweight component as the editor. If you want to find out what the current setting is for the editor component, ask for the setting of the cellEditorValue property.

Table 17-4. *DefaultCellEditor Properties*

Property Name	Data Type	Access
cellEditorValue	Object	Read-only
clickCountToStart	int	Read-write
component	Component	Read-only

DefaultTreeCellEditor Class

The DefaultTreeCellEditor class is the TreeCellEditor that is automatically used by a JTree when you make a tree editable but you don't associate an editor with that tree. The DefaultTreeCellEditor combines the icons from a TreeCellRenderer with a TreeCellEditor to return a combined editor.

The default component used as the editor is a JTextField. This text editor is special in that it tries to limit its height to the original cell renderer and prefers the font of the tree so that it won't appear out of place. The editor uses two public inner classes to accomplish this feat: DefaultTreeCellEditor.EditorContainer and DefaultTreeCellEditor.DefaultTextField.

There are two constructors for DefaultTreeCellEditor. Normally, you don't need to call the first constructor because it's automatically created for you by the user interface when it determines that the node is editable. However, it may be necessary if you want to customize the default editor in some manner.

```
public DefaultTreeCellEditor(JTree tree, DefaultTreeCellRenderer renderer)
JTree tree = new JTree(...);
DefaultTreeCellRenderer renderer = (DefaultTreeCellRenderer)tree.getCellRenderer();
TreeCellEditor editor = new DefaultTreeCellEditor(tree, renderer);

public DefaultTreeCellEditor(JTree tree, DefaultTreeCellRenderer renderer,
    TreeCellEditor editor)
public static void main (String args[]) {
    JTree tree = new JTree(...);
    DefaultTreeCellRenderer renderer =
        (DefaultTreeCellRenderer)tree.getCellRenderer();
```

```

JComboBox comboBox = new JComboBox(args);
TreeCellEditor comboEditor = new DefaultCellEditor(comboBox);
TreeCellEditor editor = new DefaultTreeCellEditor(tree, renderer, comboEditor);
...
}

```

Creating a Proper ComboBox Editor for a Tree

As Figure 17-13 showed, using a `JComboBox` as the `TreeCellEditor` via a `DefaultCellEditor` doesn't place the appropriate node-type icon next to the editor. If you want the icons present, you need to combine the `DefaultCellEditor` with a `DefaultTreeCellEditor` to get an editor with both an icon and an editor. It's really not as hard as it sounds. It just involves two extra steps: getting the renderer for the tree (from which to get the icons), and then combining the icon with the editor to get a new editor. The following source demonstrates this:

```

JTree tree = new JTree();
tree.setEditable(true);
DefaultTreeCellRenderer renderer = (DefaultTreeCellRenderer)tree.getCellRenderer();
String elements[] = { "Root", "chartreuse", "rugby", "sushi" };
JComboBox comboBox = new JComboBox(elements);
comboBox.setEditable(true);
TreeCellEditor comboEditor = new DefaultCellEditor(comboBox);
TreeCellEditor editor = new DefaultTreeCellEditor(tree, renderer, comboEditor);
tree.setCellEditor(editor);

```

The improved output is shown in Figure 17-15.




Figure 17-15. An editable `JTree` with a `JComboBox` editor and tree icons

Creating an Editor Just for Leaf Nodes

In some cases, you will want only the leaf nodes of a tree to be editable. Returning `null` from the `getTreeCellEditorComponent()` request effectively makes a node not editable. Unfortunately, this causes a `NullPointerException` to be thrown by the user interface class.

Instead of returning `null`, you can override the default behavior of the public `boolean isCellEditable(EventObject object)` method, which is part of the `CellEditor` interface. If the original return value is `true`, you can do an additional check to see if the selected node of the tree is a leaf. Nodes of a tree implement the `TreeNode` interface (described later in this chapter in the “`TreeNode` Interface” section). This interface happens to have the method public

`boolean isLeaf()`, which provides the answer you're looking for. The class definition for a leaf node cell editor is shown in Listing 17-8.

Listing 17-8. *Tree Cell Editor for Leaf Nodes*

```
import javax.swing.*;
import javax.swing.tree.*;
import java.awt.*;
import java.util.EventObject;

public class LeafCellEditor extends DefaultTreeCellEditor {

    public LeafCellEditor(JTree tree, DefaultTreeCellRenderer renderer) {
        super(tree, renderer);
    }

    public LeafCellEditor(JTree tree, DefaultTreeCellRenderer renderer,
        TreeCellEditor editor) {
        super(tree, renderer, editor);
    }

    public boolean isCellEditable(EventObject event) {
        // Get initial setting
        boolean returnValue = super.isCellEditable(event);
        // If still possible, check if current tree node is a leaf
        if (returnValue) {
            Object node = tree.getLastSelectedPathComponent();
            if ((node != null) && (node instanceof TreeNode)) {
                TreeNode treeNode = (TreeNode)node;
                returnValue = treeNode.isLeaf();
            }
        }
        return returnValue;
    }
}
```

You use the `LeafCellEditor` in the same way as a `DefaultTreeCellRenderer`. It requires a `JTree` and `DefaultTreeCellRenderer` for its constructor. In addition, it supports an optional `TreeCellEditor`. If one isn't provided, a `JTextField` is used as the editor.

```
JTree tree = new JTree();
tree.setEditable(true);
DefaultTreeCellRenderer renderer = (DefaultTreeCellRenderer)tree.getCellRenderer();
TreeCellEditor editor = new LeafCellEditor(tree, renderer);
tree.setCellEditor(editor);
```

CellEditorListener Interface and ChangeEvent Class

Before exploring the creation of a complete `TreeCellEditor`, take a look at the `CellEditorListener` interface definition. The interface contains two methods that are used with a `CellEditor`.

```
public interface CellEditorListener implements EventListener {  
    public void editingCanceled(ChangeEvent changeEvent);  
    public void editingStopped(ChangeEvent changeEvent);  
}
```

The editor calls the `editingCanceled()` method of the registered listeners to signal that the editing of the node's value has been aborted. The `editingStopped()` method is called to signal the completion of an editing session.

Normally, it's not necessary to create a `CellEditorListener`. However, when creating a `TreeCellEditor` (or any `CellEditor`), it is necessary to manage a list of its listeners and notify those listeners when necessary. Thankfully, this is managed for you automatically with the help of the `AbstractCellEditor`.

Creating a Better Check Box Node Editor

Using the `JCheckBox` editor provided by the `DefaultCellEditor` class isn't a good option when working with a `JTree`. Although the editor can be wrapped into a `DefaultTreeCellEditor` to get the appropriate tree icon next to it, you can't display text within the check box (that is, besides `true` or `false`). Other text strings can be displayed within the tree, but once a node is edited, the text label for the edited node can only be `true` or `false`.

To have an editable check box with a text label as the tree cell editor, you must create your own. The complete process involves creating three classes—a data model for each node of the tree, a tree cell renderer to render this custom data structure, and the actual editor—plus a test program to connect them all.

Note The renderer and editor created here will support check-box–like data only for editing leaf nodes. If you want to support check boxes for nonleaf nodes, you need to pull out the code that checks for leaf nodes.

Creating the `CheckBoxNode` Class

The first class to be created is for the data model for each leaf node of the tree. You could use the same data model as the `JCheckBox` class, but that includes extraneous information at each node that you don't need. The only information necessary is the selected state of the node and its text label. With the addition of some setter and getter methods for the state and label, the class is basically defined, as shown in Listing 17-9. The other classes are not quite this easy to formulate.

Listing 17-9. *Custom Node Data for a JTree*

```
public class CheckBoxNode {
    String text;
    boolean selected;
    public CheckBoxNode(String text, boolean selected) {
        this.text = text;
        this.selected = selected;
    }
    public boolean isSelected() {
        return selected;
    }
    public void setSelected(boolean newValue) {
        selected = newValue;
    }
    public String getText() {
        return text;
    }
    public void setText(String newValue) {
        text = newValue;
    }
    public String toString() {
        return getClass().getName() + "[" + text + "/" + selected + "]";
    }
}
```

Creating the CheckBoxNodeRenderer Class

The renderer will have two parts. For nonleaf nodes, you can use the `DefaultTreeCellRenderer` because those nodes aren't meant to be `CheckBoxNode` elements. For the renderer for leaf nodes of type `CheckBoxNode`, you need to map the data structure into an appropriate renderer. Because these nodes contain a selection state and a text label, the `JCheckBox` acts as a good renderer for the leaf nodes.

The easier of the two to explain is the nonleaf node renderer. In this example, it simply configures a `DefaultTreeCellRenderer` as it would normally; nothing special is done.

The renderer for the leaf nodes requires a bit more work. Before even configuring any nodes, you need to make it look like the default renderer. The constructor acquires the necessary fonts and various colors from the look and feel for the renderer, ensuring that the two renderers will appear similar.

The definition for the tree cell renderer, class `CheckBoxNodeRenderer`, is shown in Listing 17-10.

Listing 17-10. *Custom Node Renderer for a JTree*

```

import javax.swing.*.*;
import javax.swing.border.*;
import javax.swing.tree.*;
import java.awt.*.*;

public class CheckBoxNodeRenderer implements TreeCellRenderer {
    private JCheckBox leafRenderer = new JCheckBox();
    private DefaultTreeCellRenderer nonLeafRenderer = new DefaultTreeCellRenderer();
    Color selectionBorderColor, selectionForeground, selectionBackground,
        textForeground, textBackground;

    protected JCheckBox getLeafRenderer() {
        return leafRenderer;
    }

    public CheckBoxNodeRenderer() {
        Font fontValue;
        fontValue = UIManager.getFont("Tree.font");
        if (fontValue != null) {
            leafRenderer.setFont(fontValue);
        }
        Boolean booleanValue =
            (Boolean)UIManager.get("Tree.drawsFocusBorderAroundIcon");
        leafRenderer.setFocusPainted((booleanValue != null) &&
            (booleanValue.booleanValue()));

        selectionBorderColor = UIManager.getColor("Tree.selectionBorderColor");
        selectionForeground = UIManager.getColor("Tree.selectionForeground");
        selectionBackground = UIManager.getColor("Tree.selectionBackground");
        textForeground = UIManager.getColor("Tree.textForeground");
        textBackground = UIManager.getColor("Tree.textBackground");
    }

    public Component getTreeCellRendererComponent(JTree tree, Object value,
        boolean selected, boolean expanded, boolean leaf, int row, boolean hasFocus) {

        Component returnValue;
        if (leaf) {

            String stringValue = tree.convertValueToText(value, selected, expanded,
                leaf, row, false);
            leafRenderer.setText(stringValue);
            leafRenderer.setSelected(false);

            leafRenderer.setEnabled(tree.isEnabled());

```

```

        if(selected) {
            leafRenderer.setForeground(selectionForeground);
            leafRenderer.setBackground(selectionBackground);
        } else {
            leafRenderer.setForeground(textForeground);
            leafRenderer.setBackground(textBackground);
        }

        if ((value != null) && (value instanceof DefaultMutableTreeNode)) {
            Object userObject = ((DefaultMutableTreeNode)value).getUserObject();
            if (userObject instanceof CheckBoxNode) {
                CheckBoxNode node = (CheckBoxNode)userObject;
                leafRenderer.setText(node.getText());
                leafRenderer.setSelected(node.isSelected());
            }
        }
        returnValue = leafRenderer;
    } else {
        returnValue = nonLeafRenderer.getTreeCellRendererComponent(tree, value,
            selected, expanded, leaf, row, hasFocus);
    }
    return returnValue;
}
}
}

```

Note The `getLeafRenderer()` method is a helper method you'll need in the editor.

Creating the `CheckBoxNodeEditor` Class

The `CheckBoxNodeEditor` class is the last part of creating a better check box node editor. It serves as the `TreeCellEditor` implementation, allowing you to support editing of trees whose leaf node data is of type `CheckBoxNode`. The `TreeCellEditor` interface is an extension of the `CellEditor` implementation, so you must implement the methods of both interfaces. You can't extend `DefaultCellEditor` or `DefaultTreeCellEditor`, because they would require you to use the `JCheckBox` editor implementation they provide, instead of the new one you're creating here. However, you can extend `AbstractCellEditor` and add the necessary `TreeCellEditor` interface implementation. An `AbstractCellEditor` manages the list of `CellEditorListener` objects for you and has methods to notify the list of listeners upon either stopping or canceling editing.

Because the editor acts as the renderer, you'll need to use the earlier `CheckBoxNodeRenderer` to get the basic renderer appearance. This will ensure that the editor appears similar to the renderer. Because the renderer for the leaf nodes will be a `JCheckBox`, this works perfectly well to enable you to change the node state. The editor `JCheckBox` will be active and changeable, allowing a user to change from a selected state to an unselected state, and vice versa. If instead the editor were the standard `DefaultTreeCellRenderer`, you would need to manage the creation of selection changes.

Now that the class hierarchy has been set up, the first method to examine is the public `Object getCellEditorValue()` method of `CellEditor`. The purpose of this method is to convert the data as stored within the node editor into the data as stored within the node. The user interface calls this method to get the editor's value after it has determined that the user has successfully changed the data within the editor. In this method, you need to create a new object each time. Otherwise, the same node will be in the tree multiple times, causing all nodes to be equal to the renderer for the last edited node. To convert the editor to the data model, it's necessary to ask the editor what its current label and selected state are, and then create and return a new node.

```
public Object getCellEditorValue() {  
    JCheckBox checkbox = renderer.getLeafRenderer();  
    CheckBoxNode checkBoxNode =  
        new CheckBoxNode(checkbox.getText(), checkbox.isSelected());  
    return checkBoxNode;  
}
```

Note It's not the job of the editor to directly access the node within the tree to update it. The `getCellEditorValue()` method returns the appropriate node object so that the user interface can notify the tree of any changes.

If you were to implement the `CellEditor` interface yourself, you would also need to manage the list of `CellEditorListener` objects yourself. You would need to manage the list with the `addCellEditorListener()` and `removeCellEditorListener()` methods, and provide methods that notify the list of listeners for each method in the interface. But, because you'll be subclassing `AbstractCellEditor`, it's not necessary to do this yourself. You just need to know that the class provides `fireEditingCanceled()` and `fireEditingStopped()` methods in order to notify the listener list at the appropriate times.

The next `CellEditor` method, `cancelCellEditing()`, is called when a new node of the tree is selected, announcing that the editing process of the prior selection has stopped and any interim update has been aborted. The method is capable of doing anything, such as destroying any necessary interim objects used by the editor. However, what the method should do is call `fireEditingCanceled()`; this ensures that any registered `CellEditorListener` objects are notified of the cancellation. The `AbstractCellEditor` does this for you. Unless you need to do some interim operations, it's not necessary to override this behavior.

The `stopCellEditing()` method of the `CellEditor` interface returns a boolean. This method is called to see if editing of the current node can stop. If any validation needs to be done to determine whether editing can stop, you would check here. For the `CheckBoxNodeEditor` in this example, no validation check is necessary. Therefore, editing can always stop, allowing the method to always return `true`.

You would call the `fireEditingStopped()` method when you want to have the editor stop editing. For instance, if the editor were a text field, pressing `Enter` within the text field could act as the signal to stop editing. In the case of the `JCheckBox` editor, selection could act as a signal to stop the editor. If `fireEditingStopped()` isn't called, the tree data model isn't updated.

To stop editing after selection of the `JCheckBox`, attach an `ItemListener` to it.

```

ItemListener itemListener = new ItemListener() {
    public void itemStateChanged(ItemEvent itemEvent) {
        if (stopCellEditing()) {
            fireEditingStopped();
        }
    }
};
editor.addItemListener(itemListener);

```

The next method of the `CellEditor` interface to look at is `public boolean isCellEditable(EventObject event)`. The method returns a `boolean` to state whether the node at the source of the event is editable. To find out if the event happens at a particular node, you need a reference to the tree where the editor is to be used. You can add this requirement to the constructor of the editor.

To find out which node is at a specific position during an event, you can ask the tree for the path of nodes to the event location. The path is returned as a `TreePath` object, which is examined again later in this chapter in the “`TreePath` Class” section. The last component of the tree path is the specific node where the event happened. It is this node that you must check to determine if it’s editable. If it is editable, the method returns `true`; if it isn’t editable, `false` is returned. In the case of the tree to be created here, a node is editable if it’s a leaf node and it contains `CheckBoxNode` data.

```

JTree tree;

public CheckBoxNodeEditor(JTree tree) {
    this.tree = tree;
}

public boolean isCellEditable(EventObject event) {
    boolean returnValue = false;
    if (event instanceof MouseEvent) {
        MouseEvent mouseEvent = (MouseEvent)event;
        TreePath path = tree.getPathForLocation(mouseEvent.getX(), mouseEvent.getY());
        if (path != null) {
            Object node = path.getLastPathComponent();
            if ((node != null) && (node instanceof DefaultMutableTreeNode)) {
                DefaultMutableTreeNode treeNode = (DefaultMutableTreeNode)node;
                Object userObject = treeNode.getUserObject();
                returnValue = ((treeNode.isLeaf()) && (userObject instanceof CheckBoxNode));
            }
        }
    }
    return returnValue;
}

```

The `shouldSelectCell()` method of the `CellEditor` interface allows you to decide whether a node is selectable. For the editor in this example, all editable cells should be selectable. However,

this method allows you to look at a specific node to see if it can be selected. By default, `AbstractCellEditor` returns `true` for this method.

The remaining method, `getTreeCellEditorComponent()`, is from the `TreeCellEditor` interface. You'll need a reference to a `CheckBoxNodeRenderer` to get and use that as the editor. There are two minor changes besides just passing through all the arguments. Editors should always be selected and have the input focus. This simply forces two arguments to always be `true`. When the node is selected, the background is filled in. When focused, a border surrounds the editor when `UIManager.get("Tree.drawsFocusBorderAroundIcon")` reports `true`.

```
CheckBoxNodeRenderer renderer = new CheckBoxNodeRenderer();
public Component getTreeCellEditorComponent(JTree tree, Object value,
    boolean selected, boolean expanded, boolean leaf, int row) {

    // Editor always selected / focused
    return renderer.getTreeCellRendererComponent(tree, value, true, expanded, leaf,
        row, true);
}
```

Listing 17-11 shows everything put together, presenting the complete `CheckBoxNodeEditor` class source.

Listing 17-11. *Custom Node Editor for a JTree*

```
import javax.swing.*.*;
import javax.swing.event.*;
import javax.swing.tree.*;
import java.awt.*.*;
import java.awt.event.*;
import java.util.EventObject;

public class CheckBoxNodeEditor extends AbstractCellEditor implements
    TreeCellEditor {

    CheckBoxNodeRenderer renderer = new CheckBoxNodeRenderer();

    ChangeEvent changeEvent = null;

    JTree tree;

    public CheckBoxNodeEditor(JTree tree) {
        this.tree = tree;
    }

    public Object getCellEditorValue() {
        JCheckBox checkbox = renderer.getLeafRenderer();
        CheckBoxNode checkBoxNode =
            new CheckBoxNode(checkbox.getText(), checkbox.isSelected());
        return checkBoxNode;
    }
}
```

```

public boolean isCellEditable(EventObject event) {
    boolean returnValue = false;
    if (event instanceof MouseEvent) {
        MouseEvent mouseEvent = (MouseEvent)event;
        TreePath path = tree.getPathForLocation(mouseEvent.getX(), mouseEvent.getY());
        if (path != null) {
            Object node = path.getLastPathComponent();
            if ((node != null) && (node instanceof DefaultMutableTreeNode)) {
                DefaultMutableTreeNode treeNode = (DefaultMutableTreeNode)node;
                Object userObject = treeNode.getUserObject();
                returnValue = ((treeNode.isLeaf()) &&
                    (userObject instanceof CheckBoxNode));
            }
        }
    }
    return returnValue;
}

public Component getTreeCellEditorComponent(JTree tree, Object value,
    boolean selected, boolean expanded, boolean leaf, int row) {

    Component editor = renderer.getTreeCellRendererComponent(tree, value, true,
        expanded, leaf, row, true);

    // Editor always selected / focused
    ItemListener itemListener = new ItemListener() {
        public void itemStateChanged(ItemEvent itemEvent) {
            if (stopCellEditing()) {
                fireEditingStopped();
            }
        }
    };
    if (editor instanceof JCheckBox) {
        ((JCheckBox)editor).addItemListener(itemListener);
    }
    return editor;
}
}

```

Note Notice that there's no direct change of the data in the tree node. It's not the role of the editor to change the node. The editor only gets the new node value, returning it with `getCellEditorValue()`.

Creating the Test Program

The test program in Listing 17-12 consists primarily of creating the `CheckBoxNode` elements. In addition to creating the tree data, the tree must have the renderer and editor associated with it and be made editable.

Listing 17-12. *Using the Custom Node Editor*

```
import javax.swing.*;
import javax.swing.tree.*;
import java.awt.*;
import java.util.Vector;

public class CheckBoxNodeTreeSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("CheckBox Tree");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                CheckBoxNode accessibilityOptions[] = {
                    new CheckBoxNode("Move system caret with focus/selection changes", false),
                    new CheckBoxNode("Always expand alt text for images", true)
                };
                CheckBoxNode browsingOptions[] = {
                    new CheckBoxNode("Notify when downloads complete", true),
                    new CheckBoxNode("Disable script debugging", true),
                    new CheckBoxNode("Use AutoComplete", true),
                    new CheckBoxNode("Browse in a new process", false)
                };
                Vector<CheckBoxNode> accessVector =
                    new NamedVector<CheckBoxNode>("Accessibility", accessibilityOptions);
                Vector<CheckBoxNode> browseVector =
                    new NamedVector<CheckBoxNode>("Browsing", browsingOptions);
                Object rootNodes[] = {accessVector, browseVector};
                Vector<Object> rootVector = new NamedVector<Object>("Root", rootNodes);
                JTree tree = new JTree(rootVector);

                CheckBoxNodeRenderer renderer = new CheckBoxNodeRenderer();
                tree.setCellRenderer(renderer);

                tree.setCellEditor(new CheckBoxNodeEditor(tree));
                tree.setEditable(true);
            }
        };
        runner.run();
    }
}
```

```

        JScrollPane scrollPane = new JScrollPane(tree);
        frame.add(scrollPane, BorderLayout.CENTER);
        frame.setSize(300, 150);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Running the program and selecting a `CheckBoxNode` will enable the editor. After the editor is enabled, selecting the editor again causes the state of the node within the tree to change. The editor stays enabled until a different tree node is selected. Figure 17-16 shows an example of the editor in use.




Figure 17-16. *The new `CheckBoxNodeEditor` in action*

Working with the Nodes of the Tree

When you create a `JTree`, the type of objects at any spot in the tree can be any `Object`. There is no requirement that the nodes of the tree implement any interface or subclass any class. Nevertheless, the Swing component libraries provide a pair of interfaces and one class for working with tree nodes. The default data model for the tree, `DefaultTreeModel`, uses these interfaces and the class. However, the tree data model interface, `TreeModel`, permits any type of object to be a tree node.

The base interface for nodes is `TreeNode`, which defines a series of methods describing a read-only, parent-children aggregation relationship. Expanding on `TreeNode` is the `MutableTreeNode` interface, which allows you to programmatically connect nodes and store information at each node. The class that implements the two interfaces is the `DefaultMutableTreeNode` class. Besides implementing the methods of the two interfaces, the class provides a set of methods for traversing the tree and inquiring about the state of various nodes.

Keep in mind that although these node objects are available, much work can be still performed without involving these interfaces and classes, as previously shown in this chapter.

TreeNode Interface

The `TreeNode` interface describes one possible definition for an individual part of a tree. It's used by one implementation of `TreeModel`, the `DefaultTreeModel` class, to store references to the

hierarchical data that describes a tree. The interface allows you to find out which node is the parent to the current node, as well as get information about the set of child nodes. When the parent node is null, the node is the root of a tree.

```
public interface TreeNode {
    // Properties
    public boolean getAllowsChildren();
    public int getChildCount();
    public boolean isLeaf();
    public TreeNode getParent();
    // Other methods
    public Enumeration children();
    public TreeNode getChildAt(int childIndex);
    public int getIndex(TreeNode node);
}
```

Note Normally, only nonleaf nodes allow children. However, security restrictions may limit nonleaf nodes from having children, or at least showing them. Imagine a directory tree in which you don't have read access to a particular directory. Although the directory is a nonleaf node, it can't have child nodes because you don't have access to find out what those children are.

MutableTreeNode Interface

Although the `TreeNode` interface allows you to retrieve information about a hierarchy of tree nodes, it doesn't allow you to create the hierarchy. `TreeNode` just provides you access to a read-only tree hierarchy. On the other hand, the `MutableTreeNode` interface allows you to create the hierarchy and store information at a specific node within the tree.

```
public interface MutableTreeNode implements TreeNode {
    // Properties
    public void setParent(MutableTreeNode newParent);
    public void setUserObject(Object object);
    // Other methods
    public void insert(MutableTreeNode child, int index);
    public void remove(MutableTreeNode node);
    public void remove(int index);
    public void removeFromParent();
}
```

When creating the hierarchy of tree nodes, you can either create children nodes and add them to their parent or create parent nodes and add children. To associate a node with a parent node, you set its parent with `setParent()`. Using `insert()` allows you to add children to a parent node. The arguments for the `insert()` method include an index argument. This index represents the position within the set of children to add the child node provided. The index is zero-based, so an index of zero will add the node as the first child of the tree. Adding a node as the last child,

instead of the first, requires you to ask the node with `getChildCount()` how many children it already has and then add 1:

```
mutableTreeNode.insert(childMutableTreeNode, mutableTreeNode.getChildCount()+1);
```

At least for the `DefaultMutableTreeNode` class described next, `setParent()` sets a node to be the parent of a child node, even though it doesn't make the child node a child of the parent. In other words, don't call `setParent()` yourself; call `insert()`, and it will set the parent accordingly.

Caution The `insert()` method doesn't allow circular ancestry, where the child node to be added is an ancestor to the parent. If that's attempted, an `IllegalArgumentException` will be thrown.

DefaultMutableTreeNode Class

The `DefaultMutableTreeNode` class provides an implementation of the `MutableTreeNode` interface (which implements the `TreeNode` interface). When you're creating a tree from a `Hashtable`, an array, or a `Vector` constructor, `JTree` automatically creates the nodes as a set of type `DefaultMutableTreeNode`. If, on the other hand, you want to create the nodes yourself, you need to create one instance of type `DefaultMutableTreeNode` for every node in your tree.

Creating a DefaultMutableTreeNode

Three constructors are available for creating instances of `DefaultMutableTreeNode`:

```
public DefaultMutableTreeNode()
DefaultMutableTreeNode node = new DefaultMutableTreeNode();

public DefaultMutableTreeNode(Object userObject)
DefaultMutableTreeNode node = new DefaultMutableTreeNode("Node");

public DefaultMutableTreeNode(Object userObject, boolean allowsChildren)
DefaultMutableTreeNode node = new DefaultMutableTreeNode("Node", false);
```

The information stored at every node is called the *user object*. When not specified by one of the constructors, this user object is `null`. In addition, you can specify whether a node is allowed to have children.

Building DefaultMutableTreeNode Hierarchies

Building a hierarchy of nodes of type `DefaultMutableTreeNode` requires creating an instance of type `DefaultMutableTreeNode`, creating nodes for its children, and then connecting them. Before using `DefaultMutableTreeNode` directly to create the hierarchy, first let's see how to use the new `NamedVector` class to create a tree with four nodes: one root and three leaf nodes.

```
Vector vector = new NamedVector("Root", new String[]{ "Mercury", "Venus", "Mars" } );
JTree tree = new JTree(vector);
```

When `JTree` gets a `Vector` as its constructor argument, the tree creates a `DefaultMutableTreeNode` for the root node, and then creates another one for each element in the `Vector`, making each element node a child of the root node. The data for the root node unfortunately is not the "Root" you specify, but rather `root`, and isn't shown.

If, instead, you wanted to use `DefaultMutableTreeNode` to manually create the nodes of a tree, or if you wanted to display the root node, a few more lines would be necessary, as follows:

```
DefaultMutableTreeNode root = new DefaultMutableTreeNode("Root");
DefaultMutableTreeNode mercury = new DefaultMutableTreeNode("Mercury");
root.insert(mercury, 0);
DefaultMutableTreeNode venus = new DefaultMutableTreeNode("Venus");
root.insert(venus, 1);
DefaultMutableTreeNode mars = new DefaultMutableTreeNode("Mars");
root.insert(mars, 2);
JTree tree = new JTree(root);
```

Besides using the `insert()` method from `MutableTreeNode` to associate a child with a parent, `DefaultMutableTreeNode` has an `add()` method that automatically adds a child node at the end, without providing an index.

```
DefaultMutableTreeNode root = new DefaultMutableTreeNode("Root");
DefaultMutableTreeNode mercury = new DefaultMutableTreeNode("Mercury");
root.add(mercury);
DefaultMutableTreeNode venus = new DefaultMutableTreeNode("Venus");
root.add(venus);
DefaultMutableTreeNode mars = new DefaultMutableTreeNode("Mars");
root.add(mars);
JTree tree = new JTree(root);
```

Both of the previous blocks of source create a tree like the one shown in Figure 17-17.




Figure 17-17. *Using `DefaultMutableTreeNode`*

If you don't need a root node and want the same behavior as if you had used `NamedVector` at the root of a tree, you could do the following, too:

```
String elements[] = { "Mercury", "Venus", "Mars" };
JTree tree = new JTree(elements);
```

DefaultMutableTreeNode Properties

As Table 17-5 shows, there are 22 properties of `DefaultMutableTreeNode`. Most of the properties are read-only, allowing you to find out information about the tree node's position and relationships. The `userObject` property contains the data specific to the node that was provided to the `DefaultMutableTreeNode` when the node was created. The `userObjectPath` property contains an array of user objects, from the root (at index 0) to the current node (which could be the root).

Table 17-5. *DefaultMutableTreeNode Properties*

Property Name	Data Type	Access
<code>allowsChildren</code>	<code>boolean</code>	Read-write
<code>childCount</code>	<code>int</code>	Read-only
<code>depth</code>	<code>int</code>	Read-only
<code>firstChild</code>	<code>TreeNode</code>	Read-only
<code>firstLeaf</code>	<code>DefaultMutableTreeNode</code>	Read-only
<code>lastChild</code>	<code>TreeNode</code>	Read-only
<code>lastLeaf</code>	<code>DefaultMutableTreeNode</code>	Read-only
<code>leaf</code>	<code>boolean</code>	Read-only
<code>leafCount</code>	<code>int</code>	Read-only
<code>level</code>	<code>int</code>	Read-only
<code>nextLeaf</code>	<code>DefaultMutableTreeNode</code>	Read-only
<code>nextNode</code>	<code>DefaultMutableTreeNode</code>	Read-only
<code>nextSibling</code>	<code>DefaultMutableTreeNode</code>	Read-only
<code>parent</code>	<code>MutableTreeNode</code>	Read-write
<code>path</code>	<code>TreeNode[]</code>	Read-only
<code>previousLeaf</code>	<code>DefaultMutableTreeNode</code>	Read-only
<code>previousNode</code>	<code>DefaultMutableTreeNode</code>	Read-only
<code>previousSibling</code>	<code>DefaultMutableTreeNode</code>	Read-only
<code>root</code>	<code>boolean</code>	Read-only
<code>siblingCount</code>	<code>int</code>	Read-only
<code>userObject</code>	<code>Object</code>	Read-write
<code>userObjectPath</code>	<code>Object[]</code>	Read-only

Querying Node Relationships

The `DefaultMutableTreeNode` class provides several ways to determine the relationship between two nodes. In addition, you can check to see if two nodes share a common parent using the following methods:

- `isNodeAncestor(TreeNode aNode)`: Returns true if `aNode` is the current node or a parent of the current node. This recursively checks `getParent()` until `aNode` or null is found.
- `isNodeChild(TreeNode aNode)`: Returns true if the current node is the parent of `aNode`.
- `isNodeDescendant(DefaultMutableTreeNode aNode)`: Returns true if the current node is `aNode` or an ancestor of `aNode`.
- `isNodeRelated(DefaultMutableTreeNode aNode)`: Returns true if both the current node and `aNode` share the same root (are in the same tree).
- `isNodeSibling(TreeNode aNode)`: Returns true if both nodes share the same parent.

Each method returns a boolean value, indicating whether or not the relationship exists.

If two nodes are related, you can ask for the root of the tree to find a shared ancestor.

However, this ancestor might not be the closest ancestor within the tree. If a common node exists lower down in the tree, you can use the public `TreeNode getSharedAncestor(DefaultMutableTreeNode aNode)` method to find this closer ancestor. If none exists because the two nodes aren't in the same tree, null is returned.

Note If a node asks for the shared ancestor of that node and itself, the shared ancestor is the node itself. In other words, a node's closest ancestor to itself is itself.

Traversing Trees

The `TreeNode` interface and `DefaultMutableTreeNode` class provide several means of traveling to all the nodes below a specific node. Given a specific `TreeNode`, you can walk to each descendant node by going through the `children()` of each node, including the initial node. Given a specific `DefaultMutableTreeNode`, you can find all the descendants by following both `getNextNode()` and `getPreviousNode()` methods until no additional nodes are found. The following code fragment demonstrates the use of the `children()` method of `TreeNode` to traverse an entire tree, given a starting node.

```
public void printDescendants(TreeNode root) {
    System.out.println(root);
    Enumeration children = root.children();
    if (children != null) {
        while(children.hasMoreElements()) {
            printDescendants((TreeNode)children.nextElement());
        }
    }
}
```

Although the `DefaultMutableTreeNode` implementation of `TreeNode` allows you to traverse a tree via the `getNextNode()` and `getPreviousNode()` methods, these methods are extremely inefficient and should be avoided. Instead, use one of the special methods of `DefaultMutableTreeNode` to produce one `Enumeration` of all of a node's children. Before looking at the specific methods, review Figure 17-18, which shows a simple tree to traverse.




Figure 17-18. *Sample tree for traversal*

Figure 17-18 will help you understand the three special methods of `DefaultMutableTreeNode`. These methods allow you to traverse a tree in any one of three ways, each public and returning an `Enumeration`:

- `preOrderEnumeration()`: Returns an `Enumeration` of nodes, like the `printDescendants()` method. The first node in the `Enumeration` is the node itself. The next node is that node's first child, then it's the first child of that first child, and so on. Once a leaf node with no children is found, the next child of its parent is put in the `Enumeration` and its children are added to the list accordingly until no nodes are left. Starting at the root for the tree in Figure 17-18, this would result in an `Enumeration` of nodes in the following order: root, New York, Mets, Yankees, Rangers, Football, Giants, Jets, Bills, Boston, Red Sox, Celtics, Bruins, Denver, Rockies, Avalanche, Broncos.
- `depthFirstEnumeration()` and `postOrderEnumeration()`: Return an `Enumeration` that has practically the opposite behavior of `preOrderEnumeration()`. Instead of including the current node first and then adding the children, these methods add the children first and then add the current node to the `Enumeration`. For the tree in Figure 17-18, this results in an `Enumeration` of nodes in the following order: Mets, Yankees, Rangers, Giants, Jets, Bills, Football, New York, Red Sox, Celtics, Bruins, Boston, Rockies, Avalanche, Broncos, Denver, root.
- `breadthFirstEnumeration()`: Returns an `Enumeration` of nodes added by level. For the tree in Figure 17-18, the `Enumeration` would be in the following order: root, New York, Boston, Denver, Mets, Yankees, Rangers, Football, Red Sox, Celtics, Bruins, Rockies, Avalanche, Broncos, Giants, Jets, Bills.

This leaves but one question: How do you get the starting node? Well, the first node could be selected as the result of a user action, or you can ask a tree's `TreeModel` for its root node. You'll explore `TreeModel` shortly, but the source to get the root node follows. Because `TreeNode` is only one possible type of object that can be stored in a tree, the `getRoot()` method of `TreeModel` returns an `Object`.

```
TreeModel model = tree.getModel();
Object rootObject = model.getRoot();
if ((rootObject != null) && (rootObject instanceof DefaultMutableTreeNode)) {
    DefaultMutableTreeNode root = (DefaultMutableTreeNode)rootObject;
    ...
}
```

Note I can think of only one reason why you would want to create a replacement to the `TreeNode` interface to describe the basic requirements of a node in a `JTree`: if you want to use an `Iterator` from the new Java Collections API, instead of an `Enumeration` to return a list of children, you can create your own replacement to `TreeNode`. This isn't recommended, however.

JTree.DynamicUtilTreeNode Class

The `JTree` class includes an inner class, `JTree.DynamicUtilTreeNode`, which the tree uses to help create the nodes for your trees. The `DynamicUtilTreeNode` is a `DefaultMutableTreeNode` subclass that doesn't create its child nodes until they're needed. The child nodes are needed when you either expand the parent node or try to traverse a tree. Although you normally wouldn't use this class directly, you might find a place for it. To demonstrate, the following example uses a `Hashtable` to create the nodes for a tree. Instead of having an invisible node at the root of the tree (with a `userObject` property setting of `root`), the root node will have a property of `"Root"`.

```
DefaultMutableTreeNode root = new DefaultMutableTreeNode("Root");
Hashtable hashtable = new Hashtable();
hashtable.put ("One", args);
hashtable.put ("Two", new String[]{"Mercury", "Venus", "Mars"});
Hashtable innerHashtable = new Hashtable();
Properties props = System.getProperties();
innerHashtable.put (props, props);
innerHashtable.put ("Two", new String[]{"Mercury", "Venus", "Mars"});
hashtable.put ("Three", innerHashtable);
JTree.DynamicUtilTreeNode.createChildren(root, hashtable);
JTree tree = new JTree(root);
```

The code just listed creates a tree with the same nodes as shown earlier in the `TreeArraySample` program in Figure 17-2. However, the nodes at the first level of the tree are in a different order. That's because the nodes are in a `Hashtable` in this example, instead of in a `Vector` as in the `TreeArraySample`. The first-level tree elements are added in the order returned by an `Enumeration` of `Hashtable`, instead of being in the order added to the `Vector`, as Figure 17-19 shows.




Figure 17-19. *DynamicUtilTreeNode Hashtable tree sample*

TreeModel Interface

The `TreeModel` interface describes the basic data model structure for a `JTree`. It describes a parent-child aggregation relationship, which permits any object to be a parent or a child. There is one root to the tree, and all other nodes of the tree are descendants of this node. In addition to returning information about the different nodes, the model requires any implementers to manage a list of `TreeModelListener` objects so that the listeners can be notified when any nodes in the model have changed. The remaining method, `valueForPathChanged()`, is meant to provide the means of changing the contents of a node at a particular location.

```
public interface TreeModel {
    // Properties
    public Object getRoot();
    // Listeners
    public void addTreeModelListener(TreeModelListener l);
    public void removeTreeModelListener(TreeModelListener l);
    // Instance methods
    public Object getChild(Object parent, int index);
    public int getChildCount(Object parent);
    public int getIndexOfChild(Object parent, Object child);
    public boolean isLeaf(Object node);
    public void valueForPathChanged(TreePath path, Object newValue);
}
```

DefaultTreeModel Class

The `JTree` automatically creates a `DefaultTreeModel` instance to store its data model. The `DefaultTreeModel` class provides an implementation of the `TreeModel` interface that uses `TreeNode` implementations at each node.

In addition to implementing the methods of the `TreeModel` interface, as well as managing a list of `TreeModelListener` objects, the `DefaultTreeModel` class adds several helpful methods:

- `public void insertNodeInto(MutableTreeNode child, MutableParentNode parent, index int)`: Adds the child node to parent's set of children at the child position index (zero-based).
- `public void removeNodeFromParent(MutableTreenode node)`: Causes the node to be removed from tree.
- `public void nodeChanged(TreeNode node)`: Notifies the model that a node has changed.
- `public void nodesChanged(TreeNode node, int childIndices[])`: Notifies the model that the child or children of a node have changed.
- `public void nodeStructureChanged(TreeNode node)`: Notifies the model if the node and children have changed.
- `public void nodesWereInserted(TreeNode node, int childIndices[])`: Notifies the model that nodes were inserted as children of the tree node.
- `public void nodesWereRemoved(TreeNode node, int childIndices[], Object removedChildren[])`: Notifies the model that child nodes were removed from the tree and includes nodes as arguments in the method call.
- `public void reload()` / `public void reload(TreeNode node)`: Notifies the model that there were complex changes made to the nodes and that the model should be reloaded from the root node down or from a specific node down.

The first pair of methods is for directly adding or removing nodes to or from a tree. The remaining methods are for notifying the data model when tree nodes are modified. If you don't insert or remove nodes into or from the model for a displayed tree with one of the first two methods, it's your responsibility to call a method from the second set.

TreeModelListener Interface and TreeModelEvent Class

The `TreeModel` uses a `TreeModelListener` to report any changes to the model. When the `TreeModel` sends a `TreeModelEvent`, any registered listeners are notified. The interface includes notification methods for when nodes are inserted, removed, or changed, as well as one catchall method for when some or all of these operations are done simultaneously.

```
public interface TreeModelListener implements EventListener {
    public void treeNodesChanged(TreeModelEvent treeModelEvent);
    public void treeNodesInserted(TreeModelEvent treeModelEvent);
    public void treeNodesRemoved(TreeModelEvent treeModelEvent);
    public void treeStructureChanged(TreeModelEvent treeModelEvent);
}
```

TreeSelectionModel Interface

In addition to all trees supporting a data model for storing nodes, a renderer for displaying nodes, and an editor for editing them, there is a data model called `TreeSelectionModel` for selective manipulation of tree elements. The `TreeSelectionModel` interface that follows contains

methods to describe the selected set of paths to the selected nodes. Each path is stored in a `TreePath`, which itself contains a path of tree nodes from the root object to a selected node. The `TreePath` class will be explored shortly.

```
public interface TreeSelectionModel {
    // Constants
    public final static int CONTIGUOUS_TREE_SELECTION;
    public final static int DISCONTIGUOUS_TREE_SELECTION;
    public final static int SINGLE_TREE_SELECTION;
    // Properties
    public TreePath getLeadSelectionPath();
    public int getLeadSelectionRow();
    public int getMaxSelectionRow();
    public int getMinSelectionRow();
    public RowMapper getRowMapper();
    public void setRowMapper(RowMapper newMapper);
    public int getSelectionCount();
    public boolean isSelectionEmpty();
    public int getSelectionMode();
    public void setSelectionMode(int mode);
    public TreePath getSelectionPath();
    public void setSelectionPath(TreePath path);
    public TreePath[] getSelectionPaths();
    public void setSelectionPaths(TreePath paths[]);
    public int[] getSelectionRows();
    // Listeners
    public void addPropertyChangeListener(PropertyChangeListener listener);
    public void removePropertyChangeListener(PropertyChangeListener listener);
    public void addTreeSelectionListener(TreeSelectionListener listener);
    public void removeTreeSelectionListener(TreeSelectionListener listener);
    // Other methods
    public void addSelectionPath(TreePath path);
    public void addSelectionPaths(TreePath paths[]);
    public void clearSelection();
    public boolean isPathSelected(TreePath path);
    public boolean isRowSelected(int row);
    public void removeSelectionPath(TreePath path);
    public void removeSelectionPaths(TreePath paths[]);
    public void resetRowSelection();
}
```

The `TreeSelectionModel` interface supports three modes of selection, with each mode specified by a class constant: `CONTIGUOUS_TREE_SELECTION`, `DISCONTIGUOUS_TREE_SELECTION`, or `SINGLE_TREE_SELECTION`. When the selection mode is `CONTIGUOUS_TREE_SELECTION`, only nodes situated next to each other can be selected simultaneously. The `DISCONTIGUOUS_TREE_SELECTION` mode means that there are no restrictions on simultaneous selection. With the remaining mode, `SINGLE_TREE_SELECTION`, only one node can be selected at a time. If you don't want anything to be selectable, use a setting of `null`. This uses the protected `JTree.EmptySelectionModel` class.

Note The keys used to select multiple nodes are look-and-feel specific. Try using the Ctrl-select or Shift-select keyboard combinations to choose multiple nodes.

Besides changing selection modes, the remaining methods allow you to monitor attributes of the selection path. Sometimes the methods work with row numbers, and other times they work with `TreePath` objects. The selection model uses a `RowMapper` to map rows to paths for you. The abstract `AbstractLayoutCache` class provides a basic implementation of the `RowMapper` interface that is further specialized by the `FixedHeightLayoutCache` and `VariableHeightLayoutCache` classes. You should never need to access or modify the `RowMapper` or any of its implementations. To map rows to paths (or paths to rows), just ask a `JTree`.

DefaultTreeSelectionModel Class

The `DefaultTreeSelectionModel` class provides an implementation of the `TreeSelectionModel` interface that is initially in `DISCONTIGUOUS_TREE_SELECTION` mode and that supports all three selection modes. The class introduces some of its own methods for getting listener lists; the other methods are merely implementations of all the `TreeSelectionModel` interface methods, including methods for accessing the 11 properties listed in Table 17-6. In addition, `DefaultTreeSelectionModel` overrides the `clone()` methods of `Object` to be `Cloneable`.

Table 17-6. *DefaultTreeSelectionModel Properties*

Property Name	Data Type	Access
<code>leadSelectionPath</code>	<code>TreePath</code>	Read-only
<code>leadSelectionRow</code>	<code>int</code>	Read-only
<code>maxSelectionRow</code>	<code>int</code>	Read-only
<code>minSelectionRow</code>	<code>int</code>	Read-only
<code>rowMapper</code>	<code>RowMapper</code>	Read-write
<code>selectionCount</code>	<code>int</code>	Read-only
<code>selectionEmpty</code>	<code>boolean</code>	Read-only
<code>selectionMode</code>	<code>int</code>	Read-write
<code>selectionPath</code>	<code>TreePath</code>	Read-write
<code>selectionPaths</code>	<code>TreePath[]</code>	Read-write
<code>selectionRows</code>	<code>int[]</code>	Read-only

The primary reason to use the `TreeSelectionModel` is to change the selection mode of the model. For instance, the following two lines of source code change the model to single-selection mode:

```
TreeSelectionModel selectionModel = tree.getSelectionModel();
selectionModel.setSelectionMode(TreeSelectionModel.SINGLE_TREE_SELECTION);
```

If you're interested in finding out the selected path (or paths), you can ask the `JTree` directly. You don't need to get the selected path from the model.

TreeSelectionListener Interface and TreeSelectionEvent Class

When the set of selected nodes within a tree changes, a `TreeSelectionEvent` is generated and any registered `TreeSelectionListener` objects of the `TreeSelectionModel` are notified. The `TreeSelectionListener` can be registered either with the `JTree` or directly with the `TreeSelectionModel`. The interface definition follows.

```
public interface TreeSelectionListener implements EventListener {
    public void valueChanged(TreeSelectionEvent treeSelectionEvent);
}
```

TreePath Class

The last major class to examine is `TreePath`. It has been used in many of the earlier examples in this chapter. It describes a read-only collection of nodes that map a path from the root node to another node, where the root could be the top of a subtree versus the root of the whole tree. Although two constructors exist to create `TreePath` objects, you'll normally deal with them only as the return value from a method. You can also create a new path by adding an element to an existing `TreePath` with `public TreePath pathByAddingChild(Object child)`.

A `TreePath` can be thought of as an `Object` array, in which the first element of the array is the root of the tree and the last element is called the *last path component*. In between are all the components connecting them. Normally, the elements of the array will be of type `TreeNode`. However, because `TreeModel` supports objects of any type, the path property of `TreePath` is defined to be an array of `Object` nodes. Table 17-7 lists the four `TreePath` properties.

Table 17-7. *TreePath Properties*

Property Name	Data Type	Access
<code>lastPathComponent</code>	<code>Object</code>	Read-only
<code>parentPath</code>	<code>TreePath</code>	Read-only
<code>path</code>	<code>Object[]</code>	Read-only
<code>pathCount</code>	<code>int</code>	Read-only

To better understand `TreePath`, let's reuse the tree traversal sample tree from Figure 17-18, shown once more in Figure 17-20.




Figure 17-20. *TreePath sample tree*

Using Figure 17-20 to visualize a tree starting from its root, the `TreePath` for the `Jets` node would be described by its properties as follows:

- `lastPathComponent`: A `DefaultMutableTreeNode` whose user object is `Jets`.
- `parentPath`: A `TreePath` made up of the root, New York, and Football nodes.
- `path`: An array of `DefaultMutableTreeNode` nodes whose user objects are root, New York, Football, and Jets.
- `pathCount`: 4.

That's really all there is to the `TreePath` class. Just remember that you can't change an existing `TreePath`—you can only access its elements.

Additional Expansion Events

Two listeners that can be registered with a `JTree` have yet to be discussed: a `TreeExpansionListener` and a `TreeWillExpandListener`.

TreeExpansionListener Interface and TreeExpansionEvent Class

If you're interested in finding out when a tree node has been expanded or collapsed, you can register a `TreeExpansionListener` with a `JTree`. Any registered listener will be notified after the expansion or collapse of a parent node.

```

public interface TreeExpansionListener implements EventListener {
    public void treeCollapse(TreeExpansionEvent treeExpansionEvent);
    public void treeExpand(TreeExpansionEvent treeExpansionEvent);
}

```

Each of the methods has a `TreeExpansionEvent` as its argument. The `TreeExpansionEvent` class has a single method for getting the path to the expanded or collapsed node: `public TreePath getPath()`.

TreeWillExpandListener Interface and ExpandVetoException Class

The `JTree` supports the registration of a `TreeWillExpandListener`, whose definition follows.

```
public interface TreeWillExpandListener implements EventListener {
    public void treeWillCollapse(TreeExpansionEvent treeExpansionEvent)
        throws ExpandVetoException;
    public void treeWillExpand(TreeExpansionEvent treeExpansionEvent)
        throws ExpandVetoException;
}
```

The two method signatures are similar to the `TreeExpansionListener`, and they can throw an `ExpandVetoException`. Any registered listener will be notified prior to the expansion or collapse of a parent node. If the listener doesn't want the expansion or collapse to happen, that listener can throw the exception to reject the request, stopping the node from opening or closing.

To demonstrate a `TreeWillExpandListener`, the following code won't permit either the sports node to be expanded in the default data model or the colors node to be collapsed.

```
TreeWillExpandListener treeWillExpandListener = new TreeWillExpandListener() {
    public void treeWillCollapse(TreeExpansionEvent treeExpansionEvent)
        throws ExpandVetoException {
        TreePath path = treeExpansionEvent.getPath();
        DefaultMutableTreeNode node =
            (DefaultMutableTreeNode)path.getLastPathComponent();
        String data = node.getUserObject().toString();
        if (data.equals("colors")) {
            throw new ExpandVetoException(treeExpansionEvent);
        }
    }
    public void treeWillExpand(TreeExpansionEvent treeExpansionEvent)
        throws ExpandVetoException {
        TreePath path = treeExpansionEvent.getPath();
        DefaultMutableTreeNode node =
            (DefaultMutableTreeNode)path.getLastPathComponent();
        String data = node.getUserObject().toString();
        if (data.equals("sports")) {
            throw new ExpandVetoException(treeExpansionEvent);
        }
    }
};
```

Don't forget to add the listener to a tree with a line of code similar to the following:

```
tree.addTreeWillExpandListener(treeWillExpandListener)
```

Summary

In this chapter, you learned about the many classes related to the use of the `JTree` component. You looked at tree node rendering with the `TreeCellRenderer` interface and the `DefaultTreeCellRenderer` implementation. You delved into tree node editing with the `TreeCellEditor` interface, and the `DefaultCellEditor` and `DefaultTreeCellEditor` implementations.

After reviewing how to display and edit a tree, you dealt with the `TreeNode` interface, `MutableTreeNode` interface, and `DefaultMutableTreeNode` class for manually creating tree objects. You explored the `TreeModel` interface and `DefaultTreeModel` implementation for storing the data model of a tree, and the `TreeSelectionModel` interface and `DefaultTreeSelectionModel` implementation for storing the selection model for a tree.

In addition, you looked at the many event-related classes for the various tree classes, and the `TreePath` for describing node connection paths.

In Chapter 18, you'll explore the `javax.swing.table` package and its many classes that can be used with the `JTable` component.



Tables

Chapter 17 took an in-depth look at the Swing JTree component. In this chapter, you'll explore the many details of the JTable component. The component is the standard Swing component for displaying two-dimensional data in the form of a grid.

Introducing Tables

Figure 18-1 shows a simple example of a JTable. You'll notice that it includes Japanese fonts. In order to see the Kanji ideographs in this chapter's sample programs, you will need to have the necessary Japanese fonts installed. However, all the examples will work fine without configuring your environment to display Japanese fonts, but instead of seeing the ideographs, you will see characters such as question marks or boxes, depending on your platform.

Note Windows XP Service Pack 2 users will find their systems already have the necessary Japanese fonts for the examples in this chapter. If you don't already have them, one place to get these fonts for Windows systems is <http://ftp.monash.edu.au/pub/nihongo/ie3lpkja.exe>. Solaris users must contact Sun to request the Asian outline fonts for Solaris environments. For more information about configuring fonts in the Java runtime environment, refer to <http://java.sun.com/j2se/1.5.0/docs/guide/intl/fontconfig.html>.



English	Japanese
two	ni - 二
three	san - 三
four	shi - 四
five	go - 五
six	roku - 六
seven	shichi - 七
eight	hachi - 八

Figure 18-1. *Sample JTable*

Like the JTree component, the JTable component relies on numerous support classes for its inner workings. For the JTable, the support classes are found in the `javax.swing.table` package. The cells within the JTable can be selected by row, column, row and column, or individual cell.

It's the responsibility of the current `ListSelectionModel` settings to control the selection within a table.

The display of the different cells within a table is the responsibility of the `TableCellRenderer`; the `DefaultCellRenderer` offers one such implementation of the `TableCellRenderer` interface in a `JLabel` subclass.

Managing the data stored in the cells is accomplished through an implementation of the `TableModel` interface. The `AbstractTableModel` provides the basics of an implementation of the interface without any data storage. By comparison, the `DefaultTableModel` encapsulates the `TableModel` interface and uses a `Vector` of `Vector` objects for the data storage. You extend `AbstractTableModel` if you need a different type of storage than the kind supplied by the `DefaultTableModel`; for instance, if you already had the data in your own data structure.

The `TableColumnModel` interface and the `DefaultTableColumnModel` implementation of the interface manage the table's data as a series of columns. They work together with the `TableColumn` class to allow for greater flexibility in manipulating individual columns. For example, you can store columns of data in the `TableModel` in an order that's different from the display order within the `JTable`. The `TableColumnModel` manages a second `ListSelectionModel` to control table column selection.

At the top of every column is a column header. By default, the `TableColumn` class relies on the `JTableHeader` class to render a text column header. Nevertheless, you must embed the `JTable` in a scroll pane to see the default header.

Cells within a `JTable` can be editable. If a cell is editable, how the editing works depends on the `TableCellEditor` implementation, such as the `DefaultCellEditor` implementation, which extends from `AbstractCellEditor`. In addition, no classes exist to handle individual rows. Rows must be manipulated on a cell-by-cell basis. Behind the scenes, the `JTable` uses the `SizeSequence` utility class to deal with variable height rows; you won't need to manipulate it yourself.

There are additional interrelationships among the elements used by the `JTable` component. These relationships will be explored later in this chapter with each specific interface and class.

To visualize how the `JTable` elements all fit together, examine Figure 18-2.




Figure 18-2. *JTable elements*

JTable Class

First, let's look at the `JTable` class, which gives you a way to display data in tabular form (see Figures 18-1 and 18-2).

Creating a JTable

You have seven different ways to create a `JTable`. The various constructors allow you to create tables from a number of data sources.

```
public JTable()
JTable table = new JTable();

public JTable(int rows, int columns)
JTable table = new JTable(2, 3);

public JTable(Object rowData[][], Object columnNames[])
Object rowData[][] = { { "Row1-Column1", "Row1-Column2", "Row1-Column3"},
    { "Row2-Column1", "Row2-Column2", "Row2-Column3"} };
Object columnNames[] = { "Column One", "Column Two", "Column Three"};
JTable table = new JTable(rowData, columnNames);

public JTable(Vector rowData, Vector columnNames)
Vector rowOne = new Vector();
rowOne.addElement("Row1-Column1");
rowOne.addElement("Row1-Column2");
rowOne.addElement("Row1-Column3");
Vector rowTwo = new Vector();
rowTwo.addElement("Row2-Column1");
rowTwo.addElement("Row2-Column2");
rowTwo.addElement("Row2-Column3");
Vector rowData = new Vector();
rowData.addElement(rowOne);
rowData.addElement(rowTwo);
Vector columnNames = new Vector();
columnNames.addElement("Column One");
columnNames.addElement("Column Two");
columnNames.addElement("Column Three");
JTable table = new JTable(rowData, columnNames);

public JTable(TableModel model)
TableModel model = new DefaultTableModel(rowData, columnNames);
JTable table = new JTable(model);

public JTable(TableModel model, TableColumnModel columnModel)
// Swaps column order
TableColumnModel columnModel = new DefaultTableColumnModel();
TableColumn firstColumn = new TableColumn(1);
firstColumn.setHeaderValue(headers[1]);
```

```

columnModel.addColumn(firstColumn);
TableColumn secondColumn = new TableColumn(0);
secondColumn.setHeaderValue(headers[0]);
columnModel.addColumn(secondColumn);
JTable table = new JTable(model, columnModel);

public JTable(TableModel model, TableColumnModel columnModel,
    ListSelectionModel selectionModel)
// Set single selection mode
ListSelectionModel selectionModel = new DefaultListSelectionModel();
selectionModel.setSelectionMode(ListSelectionModel.SINGLE_SELECTION);
JTable table = new JTable(model, columnModel, selectionModel);

```

The no-argument constructor creates a table with no rows and no columns. The second constructor takes two integers to create an empty table with a set number of rows and columns.

Note Table cells created from `JTable` constructors are editable, not read-only. To change their contents in code, just call the public void `setValueAt(Object value, int row, int column)` method of `JTable`.

The next two constructors are useful when your tabular data is already in a specially structured form. For instance, if your data is already in the form of an array of arrays or a `Vector` of `Vector` objects, you can create a `JTable` without creating your own `TableModel`. A two-row-by-three-column table could be created from the array of { { "Row1-Column1", "Row1-Column2", "Row1-Column3"}, { "Row2-Column1", "Row2-Column2", "Row2-Column3"} }, with another array holding the column header names. Similar data structures would be necessary for the vector-based constructor.

The remaining three constructors use `JTable`-specific data structures. If any one of the three arguments is missing, default settings will be used. For example, if you don't specify a `TableColumnModel`, the default implementation `DefaultTableColumnModel` is used and is auto-filled with a display order using the column order of the `TableModel`. When the selection model is missing, the `ListSelectionModel` will use multiple-selection mode, which means that noncontiguous rows, but not columns, can be selected.

Scrolling JTable Components

Like other components that may require more space than what is available, the `JTable` component implements the `Scrollable` interface and should be placed within a `JScrollPane`. Scrollbars will appear in a `JScrollPane` when a `JTable` is too big for the available screen real estate, and column header names will appear above each column. Figure 18-3 shows how the table in Figure 18-1 would appear if it weren't within a `JScrollPane`. Notice that neither column headers nor scrollbars appear. This means you can't determine the meaning of the data, nor can you scroll to the undisplayed rows.

one	ichi - 一
two	ni - 二
three	san - 三
four	shi - 四
five	go - 五
six	roku - 六
seven	shichi - 七
eight	hachi - 八

Figure 18-3. *JTable without a JScrollPane*

Therefore, every table you create needs to be placed within a JScrollPane by using code similar to the following:

```
JTable table = new JTable(...);
JScrollPane scrollPane = new JScrollPane(table);
```

Manually Positioning the JTable View

When a JTable within a JScrollPane is added to a window, the table will automatically appear with the table positioned so that the first row and column appear in the upper-left corner. If you ever need to return the position to the origin, you can set the viewport position back to point (0, 0).

```
scrollPane.getViewport().setViewPosition(new Point(0,0));
```

For scrolling purposes, the block increment amount is the visible width and height of the viewport, depending on the direction of the scrollbar. The unit increment is 100 pixels for horizontal scrolling and the height of a single row for vertical scrolling. See Figure 18-4 for a visual representation of these increments.





Figure 18-4. *JTable scrolling increments*

Removing Column Headers

As previously stated, placing a `JTable` within a `JScrollPane` automatically produces column header labels for the different column names. If you don't want column headers, you can remove them in one of many different ways. Figure 18-5 shows an example of a table without column headers.



Row1-Column1	Row1-Column2	Row1-Column3
Row2-Column1	Row2-Column2	Row2-Column3

Figure 18-5. *JTable without column headers*

The simplest way to remove the column headers is to provide empty strings as the column header names. With the third `JTable` constructor in the previous list of seven constructors, this would involve replacing the three column names with "", the empty string.

```
Object rowData[][] = {{"Row1-Column1", "Row1-Column2", "Row1-Column3"},
    {"Row2-Column1", "Row2-Column2", "Row2-Column3"}};
Object columnNames[] = { "", "", ""};
JTable table = new JTable(rowData, columnNames);
JScrollPane scrollPane = new JScrollPane(table);
```

Because this method of removing headers also removes the description of the different columns, you might want to use another way of hiding column headers. The simplest way is to just tell the `JTable` you don't want table headers:

```
table.setTableHeader(null);
```

You could also remove headers by subclassing `JTable` and overriding the protected `configureEnclosingScrollPane()` method, or by telling every `TableColumn` that its header value is empty. These are more complicated ways of performing the same task.

Note Calling `scrollPane.setColumnHeaderView(null)` doesn't work to clear out the column headers. Instead, it causes the `JScrollPane` to use the default column headers.

JTable Properties

As Table 18-1 shows, the `JTable` has many properties, 40 in all. These 40 are in addition to the many properties inherited from the `JComponent`, `Container`, and `Component` classes.

Table 18-1. *JTable Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>autoCreateColumnsFromModel</code>	<code>boolean</code>	Read-write bound
<code>autoResizeMode</code>	<code>int</code>	Read-write bound
<code>cellEditor</code>	<code>TableCellEditor</code>	Read-write bound
<code>cellSelectionEnabled</code>	<code>boolean</code>	Read-write bound
<code>columnCount</code>	<code>int</code>	Read-only
<code>columnModel</code>	<code>TableColumnModel</code>	Read-write bound
<code>columnSelectionAllowed</code>	<code>boolean</code>	Read-write bound
<code>dragEnabled</code>	<code>boolean</code>	Read-write
<code>editing</code>	<code>boolean</code>	Read-only
<code>editingColumn</code>	<code>int</code>	Read-write
<code>editingRow</code>	<code>int</code>	Read-write
<code>editorComponent</code>	<code>Component</code>	Read-only
<code>gridColor</code>	<code>Color</code>	Read-write bound
<code>intercellSpacing</code>	<code>Dimension</code>	Read-write
<code>model</code>	<code>TableModel</code>	Read-write bound
<code>preferredScrollableViewportSize</code>	<code>Dimension</code>	Read-write
<code>rowCount</code>	<code>int</code>	Read-only
<code>rowHeight</code>	<code>int</code>	Read-write bound
<code>rowMargin</code>	<code>int</code>	Read-write bound
<code>rowSelectionAllowed</code>	<code>boolean</code>	Read-write bound
<code>scrollableTracksViewportHeight</code>	<code>boolean</code>	Read-only
<code>scrollableTracksViewportWidth</code>	<code>boolean</code>	Read-only
<code>selectedColumn</code>	<code>int</code>	Read-only
<code>selectedColumnCount</code>	<code>int</code>	Read-only
<code>selectedColumns</code>	<code>int[]</code>	Read-only
<code>selectedRow</code>	<code>int</code>	Read-only
<code>selectedRowCount</code>	<code>int</code>	Read-only
<code>selectedRows</code>	<code>int[]</code>	Read-only
<code>selectionBackground</code>	<code>Color</code>	Read-write bound
<code>selectionForeground</code>	<code>Color</code>	Read-write bound
<code>selectionMode</code>	<code>int</code>	Write-only

Table 18-1. *JTable Properties (Continued)*

Property Name	Data Type	Access
selectionModel	ListSelectionModel	Read-write bound
showGrid	boolean	Write-only
showHorizontalLines	boolean	Read-write bound
showVerticalLines	boolean	Read-write bound
surrendersFocusOnKeystroke	boolean	Read-write
tableHeader	JTableHeader	Read-write bound
UI	TableUI	Read-write
UIClassID	String	Read-only

Note Row heights are not fixed. You can change the height of an individual row with `public void setRowHeight(int row, int rowHeight)`.

Most of the `JTable` properties fit into one of three categories: display settings, selection settings, and auto-resizing settings.

Display Settings

The first subset of properties in Table 18-1 allows you to set various display options of the `JTable`. In addition to the inherited foreground and background properties from `Component`, you can change the selection foreground (`selectionForeground`) and background (`selectionBackground`) colors. You also control which (if any) gridlines appear (`showGrid`), as well as their color (`gridColor`). The `intercellSpacing` property setting deals with the extra space within table cells.

Selection Modes

You can use any one of three different types of selection modes for a `JTable`. You can select table elements one row at a time, one column at a time, or one cell at a time. These three settings are controlled by the `rowSelectionAllowed`, `columnSelectionAllowed`, and `cellSelectionEnabled` properties. Initially, only the row selection mode is allowed. Because the default `ListSelectionModel` is in multiselect mode, you can select multiple rows at a time. If you don't like multiselect mode, you can change the `selectionMode` property of the `JTable`, causing the selection mode of the rows and columns of the `JTable` to change accordingly. Cell selection is enabled when both row and column selections are enabled.

If you're interested in whether any of the rows or columns of the `JTable` are selected, you can inquire with one of the six additional properties of `JTable`: `selectedColumnCount`, `selectedColumn`, `selectedColumns`, `selectedRowCount`, `selectedRow`, and `selectedRows`.

The `ListSelectionModel` class provides constants for the different selection modes. The `ListSelectionModel` interface and `DefaultListSelectionModel` class were both covered with

the `JList` component information in Chapter 13. They're used to describe the current set of rows and columns within the `JTable` component. They have three settings:

- `MULTIPLE_INTERVAL_SELECTION` (the default)
- `SINGLE_INTERVAL_SELECTION`
- `SINGLE_SELECTION`

The `JTable` has independent selection models for both rows and columns. The row selection model is stored with the `selectionModel` property of the `JTable`. The column selection model is stored with the `TableColumnModel`. Setting the `selectionMode` property of a `JTable` sets the selection mode for the two independent selection models of the `JTable`.

Once a selection mode has been set and a user interacts with the component, you can ask the selection model what happened, or, more precisely, what the user has selected. Table 18-2 lists the properties available to facilitate selection with the `DefaultListSelectionModel`.

Table 18-2. *DefaultListSelectionModel Properties*

Property Name	Data Type	Access
<code>anchorSelectionIndex</code>	<code>int</code>	Read-write
<code>leadAnchorNotificationEnabled</code>	<code>boolean</code>	Read-write
<code>leadSelectionIndex</code>	<code>int</code>	Read-write
<code>listSelectionListeners</code>	<code>ListSelectionListener[]</code>	Read-only
<code>maxSelectionIndex</code>	<code>int</code>	Read-only
<code>minSelectionIndex</code>	<code>int</code>	Read-only
<code>selectionEmpty</code>	<code>boolean</code>	Read-only
<code>selectionModel</code>	<code>int</code>	Read-write
<code>valueIsAdjusting</code>	<code>boolean</code>	Read-write

If you're interested in knowing when a selection event happens, register a `ListSelectionListener` with the `ListSelectionModel`. The `ListSelectionListener` was demonstrated in Chapter 13 with the `JList` component.

Note All table indices are zero-based. So, the first visual column is column 0 internally.

Auto-Resize Modes

The last subset of the `JTable` properties deals with the column-resize behavior of the `JTable`. When the `JTable` is in a column or window that changes sizes, how does it react? Table 18-3 shows the five settings supported by a `JTable`.

Table 18-3. *Auto-Resize Mode Constants*

Modes	Description
AUTO_RESIZE_ALL_COLUMNS	Adjusts all column widths proportionally.
AUTO_RESIZE_LAST_COLUMN	Adjusts the rightmost column width only to give or take space as required by the column currently being altered. If no space is available within that column, then resizing will work with the previous column until a column with available space to consume is found.
AUTO_RESIZE_NEXT_COLUMN	If you're reducing the width of a neighboring column, the neighboring column will grow to fill the unused space. If you're increasing the width of a column, the neighboring column will shrink.
AUTO_RESIZE_OFF	Turns off the user's ability to resize columns. The columns can still be resized programmatically.
AUTO_RESIZE_SUBSEQUENT_COLUMNS	Adjusts the width by proportionally altering (default) columns displayed to the right of the column being changed.

Listing 18-1 demonstrates what effect each setting has when resizing table columns.

Listing 18-1. *Resizable JTable*

```
import javax.swing.*;
import javax.swing.table.*;
import java.awt.*;
import java.awt.event.*;

public class ResizeTable {
    public static void main(String args[]) {

        final Object rowData[][] = {
            {"1", "one", "ichi - \u4E00", "un", "I"},
            {"2", "two", "ni - \u4E8C", "deux", "II"},
            {"3", "three", "san - \u4E09", "trois", "III"},
            {"4", "four", "shi - \u56DB", "quatre", "IV"},
            {"5", "five", "go - \u4E94", "cinq", "V"},
            {"6", "six", "roku - \u516D", "treiza", "VI"},
            {"7", "seven", "shichi - \u4E03", "sept", "VII"},
            {"8", "eight", "hachi - \u516B", "huit", "VIII"},
            {"9", "nine", "kyu - \u4E5D", "neur", "IX"},
            {"10", "ten", "ju - \u5341", "dix", "X"}
        };
    }
```

```

final String columnNames[] = {"#", "English", "Japanese", "French", "Roman"};

Runnable runner = new Runnable() {
    public void run() {
        final JTable table = new JTable(rowData, columnNames);
        JScrollPane scrollPane = new JScrollPane(table);

        String modes[] = {"Resize All Columns", "Resize Last Column",
            "Resize Next Column", "Resize Off", "Resize Subsequent Columns"};
        final int modeKey[] = {
            JTable.AUTO_RESIZE_ALL_COLUMNS,
            JTable.AUTO_RESIZE_LAST_COLUMN,
            JTable.AUTO_RESIZE_NEXT_COLUMN,
            JTable.AUTO_RESIZE_OFF,
            JTable.AUTO_RESIZE_SUBSEQUENT_COLUMNS};
        JComboBox resizeModeComboBox = new JComboBox(modes);
        int defaultMode = 4;
        table.setAutoResizeMode(modeKey[defaultMode]);
        resizeModeComboBox.setSelectedIndex(defaultMode);
        ItemListener itemListener = new ItemListener() {
            public void itemStateChanged(ItemEvent e) {
                JComboBox source = (JComboBox)e.getSource();
                int index = source.getSelectedIndex();
                table.setAutoResizeMode(modeKey[index]);
            }
        };
        resizeModeComboBox.addItemListener(itemListener);

        JFrame frame = new JFrame("Resizing Table");
        frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

        frame.add(resizeModeComboBox, BorderLayout.NORTH);
        frame.add(scrollPane, BorderLayout.CENTER);

        frame.setSize(300, 150);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Figure 18-6 shows the initial appearance of the program. Change the JComboBox, and you change the column resize behavior.




Figure 18-6. *Demonstrating JTable resizing column modes*

Rendering Table Cells

By default, the rendering of table data is done by a `JLabel`. Whatever value is stored in the table is rendered as a text string. The odd thing is that additional default renderers are installed for classes such as `Date` and `Number` subclasses, but they're not enabled. You'll see how to enable these specialized renderers in the "Enabling the Default Table Cell Renderers" section later in this chapter.

Using the `TableCellRenderer` Interface and `DefaultTableCellRenderer` Class

The `TableCellRenderer` interface defines the single method necessary for that class to be a `TableCellRenderer`.

```
public interface TableCellRenderer {
    public Component getTableCellRendererComponent(JTable table, Object value,
        boolean isSelected, boolean hasFocus, int row, int column);
}
```

By using information given to the `getTableCellRendererComponent()` method, proper renderer components can be created and sent on their way to display the appropriate content of the `JTable`. "Proper" means renderers that reflect the table cell state that you've decided to display, such as when you want to display selected cells differently than unselected cells, or how you want the selected cell to appear when it has the input focus.

To see a simple demonstration of this, look at Figure 18-7, which shows a renderer that alternates colors based on which row the renderer is displayed within.




Figure 18-7. *JTable with custom renderer*

The source for the custom renderer used to produce the example in Figure 18-7 is shown in Listing 18-2.

Listing 18-2. *Custom Table Cell Renderer*

```

import java.awt.*;
import javax.swing.*;
import javax.swing.table.*;

public class EvenOddRenderer implements TableCellRenderer {

    public static final DefaultTableCellRenderer DEFAULT_RENDERER =
        new DefaultTableCellRenderer();

    public Component getTableCellRendererComponent(JTable table, Object value,
        boolean isSelected, boolean hasFocus, int row, int column) {
        Component renderer =
            DEFAULT_RENDERER.getTableCellRendererComponent(table, value,
                isSelected, hasFocus, row, column);
        Color foreground, background;
        if (isSelected) {
            foreground = Color.YELLOW;
            background = Color.GREEN;
        } else {
            if (row % 2 == 0) {
                foreground = Color.BLUE;
                background = Color.WHITE;
            } else {
                foreground = Color.WHITE;
                background = Color.BLUE;
            }
        }
        renderer.setForeground(foreground);
        renderer.setBackground(background);
        return renderer;
    }
}

```

Renderers for tables can be installed for individual classes or for specific columns (see the “Enabling the Default Table Cell Renderers” section later in this chapter for details). To install the renderer as the default renderer for the `JTable`—in other words, for `Object.class`—use code similar to the following:

```

TableCellRenderer renderer = new EvenOddRenderer();
table.setDefaultRenderer(Object.class, renderer);

```

Once installed, the `EvenOddRenderer` will be used for any column whose class doesn’t have a more specific renderer. It’s the responsibility of the public `Class getColumnClass()` method of `TableModel` to return the class to be used as the renderer lookup for all the cells in a particular column. The `DefaultTableModel` returns `Object.class` for everything; therefore, `EvenOddRenderer` will be used by all table cells.

Note Keep in mind that one renderer component is used for every cell of every column of a particular class. No individual renderer is created for each cell.

The sample program that used the `EvenOddRenderer` to generate Figure 18-7 is shown in Listing 18-3.

Listing 18-3. *Using the Custom Table Cell Renderer*

```
import javax.swing.*;
import javax.swing.table.*;
import java.awt.*;

public class RendererSample {

    public static void main(String args[]) {
        final Object rows[][] = {
            {"one", "ichi - \u4E00"},
            {"two", "ni - \u4E8C"},
            {"three", "san - \u4E09"},
            {"four", "shi - \u56DB"},
            {"five", "go - \u4E94"},
            {"six", "roku - \u516D"},
            {"seven", "shichi - \u4E03"},
            {"eight", "hachi - \u516B"},
            {"nine", "kyu - \u4E5D"},
            {"ten", "ju - \u5341"}
        };
        final Object headers[] = {"English", "Japanese"};
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Renderer Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                JTable table = new JTable(rows, headers);
                TableCellRenderer renderer = new EvenOddRenderer();
                table.setDefaultRenderer(Object.class, renderer);
                JScrollPane scrollPane = new JScrollPane(table);
                frame.add(scrollPane, BorderLayout.CENTER);
                frame.setSize(300, 150);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

Using Tooltips

By default, your table cell renderers will display any tooltip text you've configured them to display. Unlike with the `JTree` component, you don't need to manually register the table with the `ToolTipManager`. If, however, your table doesn't display tooltip text, the table will respond faster if you unregister the table with the `ToolTipManager` by using code such as the following:

```
// Explicitly
ToolTipManager.sharedInstance().unregisterComponent(aTable);
// Implicitly
yourTable.setTooltipText(null);
```

Handling JTable Events

There are no `JTable` events that you can register directly with the `JTable`. To find out when something happens, you must register with one of the `JTable` model classes: `TableModel`, `TableColumnModel`, or `ListSelectionModel`.

Customizing a JTable Look and Feel

Each installable Swing look and feel provides a different `JTable` appearance and set of default `UIResource` value settings. Figure 18-8 shows the appearance of the `JTable` component for the preinstalled set of look and feel types: Motif, Windows, and Ocean. In all three cases, the third row is highlighted, where the coloration shows the first column is being edited.




Figure 18-8. *JTable* under different look and feel types

The available set of `UIResource`-related properties for a `JTable` is shown in Table 18-4. The `JTable` component has 21 different properties.

Table 18-4. *JTable UIResource Elements*

Property String	Object Type
Table.actionMap	ActionMap
Table.ancestorInputMap	InputMap
Table.ancestorInputMap.RightToLeft	InputMap
Table.background	Color
Table.darkShadow	Color
Table.focusCellBackground	Color
Table.focusCellForeground	Color
Table.focusCellHighlightBorder	Border
Table.font	Font
Table.foreground	Color
Table.gridColor	Color
Table.highlight	Color
Table.light	Color
Table.rendererUseTableColors	Boolean
Table.rendererUseUIBorder	Boolean
Table.rowHeight	Integer
Table.scrollPaneBorder	Border
Table.selectionBackground	Color
Table.selectionForeground	Color
Table.shadow	Color
TableUI	String

TableModel Interface

Now that you've looked at the basics of the `JTable` component, you can learn how it internally manages its data elements. It does this with the help of classes that implement the `TableModel` interface.

The `TableModel` interface defines the framework needed by the `JTable` to acquire column headers and cell values, and modify those cell values when the table is editable. Its definition follows:

```

public interface TableModel {
    // Listeners
    public void addTableModelListener(TableModelListener l);
    public void removeTableModelListener(TableModelListener l);
    // Properties
    public int getColumnCount();
    public int getRowCount();
    // Other methods
    public Class getColumnClass(int columnIndex);
    public String getColumnName(int columnIndex);
    public Object getValueAt(int rowIndex, int columnIndex);
    public boolean isCellEditable(int rowIndex, int columnIndex);
    public void setValueAt(Object vValue, int rowIndex, int columnIndex);
}

```

AbstractTableModel Class

The `AbstractTableModel` class provides the basic implementation of the `TableModel` interface. It manages the `TableModelListener` list and default implementations for several of the `TableModel` methods. When you subclass it, all you need to provide is the actual column and row count, and the specific values (`getValueAt()`) in the table model. Column names default to labels such as *A, B, C, ..., Z, AA, BB, ...*, and the data model is read-only unless `isCellEditable()` is overridden.

If you subclass `AbstractTableModel` and make the data model editable, it's your responsibility to call one of the following `fireXXX()` methods of `AbstractTableModel` to ensure that any `TableModelListener` objects are notified when the data model changes:

```

public void fireTableCellUpdated(int row, int column);
public void fireTableChanged(TableModelEvent e);
public void fireTableDataChanged();
public void fireTableRowsDeleted(int firstRow, int lastRow);
public void fireTableRowsInserted(int firstRow, int lastRow);
public void fireTableRowsUpdated(int firstRow, int lastRow);
public void fireTableStructureChanged();

```

When you want to create a `JTable`, it's not uncommon to subclass `AbstractTableModel` in order to reuse an existing data structure. This data structure typically comes as the result of a Java Database Connectivity (JDBC) query, but there's no restriction requiring that to be the case. To demonstrate, the following anonymous class definition shows how you can treat an array as an `AbstractTableModel`:

```

TableModel model = new AbstractTableModel() {
    Object rowData[][] = {
        {"one", "ichi"},
        {"two", "ni"},
        {"three", "san"},
        {"four", "shi"},
        {"five", "go"},
        {"six", "roku"},
        {"seven", "shichi"},
    }
}

```

```

        {"eight", "hachi"},
        {"nine", "kyu"},
        {"ten", "ju"}
    };
    Object columnNames[] = {"English", "Japanese"};
    public String getColumnName(int column) {
        return columnNames[column].toString();
    }
    public int getRowCount() {
        return rowData.length;
    }
    public int getColumnCount() {
        return columnNames.length;
    }
    public Object getValueAt(int row, int col) {
        return rowData[row][col];
    }
};
JTable table = new JTable(model);
JScrollPane scrollPane = new JScrollPane(table);

```

Specifying Fixed JTable Columns

Now that you've seen the basics of how the `TableModel` and `AbstractTableModel` describe the data, you can create a `JTable` with some columns that are fixed columns and some that are not. To create columns that don't scroll, you need to place a second table in the row header view of the `JScrollPane`. Then when the user scrolls the table vertically, the two tables will remain in sync. The two tables then need to share their `ListSelectionModel`. That way, when a row in one table is selected, the row in the other table will automatically be selected. Figure 18-9 shows a table with one fixed column and four scrolling columns.




Figure 18-9. *Fixed-column JTable*

The source code used to generate Figure 18-9 is shown in Listing 18-4.

Listing 18-4. *JTable with Fixed Area*

```

import javax.swing.*;
import javax.swing.table.*;
import java.awt.*;

public class FixedTable {
    public static void main(String args[]) {

        final Object rowData[][] = {
            {"1", "one", "ichi", "un", "I", "\u4E00"},
            {"2", "two", "ni", "deux", "II", "\u4E8C"},
            {"3", "three", "san", "trois", "III", "\u4E09"},
            {"4", "four", "shi", "quatre", "IV", "\u56DB"},
            {"5", "five", "go", "cinq", "V", "\u4E94"},
            {"6", "six", "roku", "treiza", "VI", "\u516D"},
            {"7", "seven", "shichi", "sept", "VII", "\u4E03"},
            {"8", "eight", "hachi", "huit", "VIII", "\u516B"},
            {"9", "nine", "kyu", "neur", "IX", "\u4E5D"},
            {"10", "ten", "ju", "dix", "X", "\u5341"}
        };

        final String columnNames[] =
            {"#", "English", "Japanese", "French", "Roman", "Kanji"};

        final TableModel fixedColumnModel = new AbstractTableModel() {
            public int getColumnCount() {
                return 1;
            }
            public String getColumnName(int column) {
                return columnNames[column];
            }
            public int getRowCount() {
                return rowData.length;
            }
            public Object getValueAt(int row, int column) {
                return rowData[row][column];
            }
        };

        final TableModel mainModel = new AbstractTableModel() {
            public int getColumnCount() {
                return columnNames.length-1;
            }
            public String getColumnName(int column) {
                return columnNames[column+1];
            }
        }
    }
}

```

```

    public int getRowCount() {
        return rowData.length;
    }
    public Object getValueAt(int row, int column) {
        return rowData[row][column+1];
    }
};

Runnable runner = new Runnable() {
    public void run() {
        JTable fixedTable = new JTable(fixedColumnModel);
        fixedTable.setAutoResizeMode(JTable.AUTO_RESIZE_OFF);

        JTable mainTable = new JTable(mainModel);
        mainTable.setAutoResizeMode(JTable.AUTO_RESIZE_OFF);

        ListSelectionModel model = fixedTable.getSelectionModel();
        mainTable.setSelectionModel(model);

        JScrollPane scrollPane = new JScrollPane(mainTable);
        Dimension fixedSize = fixedTable.getPreferredSize();
        JViewport viewport = new JViewport();
        viewport.setView(fixedTable);
        viewport.setPreferredSize(fixedSize);
        viewport.setMaximumSize(fixedSize);
        scrollPane.setCorner(JScrollPane.UPPER_LEFT_CORNER,
            fixedTable.getTableHeader());
        scrollPane.setRowHeaderView(viewport);

        JFrame frame = new JFrame("Fixed Column Table");
        frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
        frame.add(scrollPane, BorderLayout.CENTER);
        frame.setSize(300, 150);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Enabling the Default Table Cell Renderers

Earlier, I mentioned that the `JTable` provides default renderers for `Date` and `Number` classes. Let's look at the `AbstractTableModel` class and see how to enable those renderers.

The public Class `getColumnClass(int column)` method of the `TableModel` returns the class type for a column in the data model. If the `JTable` class has a special renderer installed for that particular class, it will use it to display that class. By default, the `AbstractTableModel` (and `DefaultTableModel`) implementations of `TableModel` return `Object.class` for everything. The `AbstractTableModel` class doesn't try to be smart about guessing what's in a column. However, if you know that a particular column of the data model will always be numbers, dates, or some other class, you can have the data model return that class type. This allows the `JTable` to try to be smarter and use a better renderer.

Table 18-5 shows the preinstalled renderers within the `JTable`. If you have a table full of numbers or just one column of numbers, for example, you can override `getColumnClass()` to return `Number.class` for the appropriate columns; your numbers will be right-justified instead of left-justified. With dates, using the default renderer for the `Date` class produces better-looking, localized output.

Table 18-5. *Default JTable Renderers*

Class	Renderer	Description
Boolean	<code>JCheckBox</code>	Centered
Date	<code>JLabel</code>	Right-aligned; uses <code>DateFormat</code> for output
Double	<code>JLabel</code>	Right-aligned; uses <code>NumberFormat</code> for output
Float	<code>JLabel</code>	Right-aligned; uses <code>NumberFormat</code> for output
Icon	<code>JLabel</code>	Centered
<code>ImageIcon</code>	<code>JLabel</code>	Centered
Number	<code>JLabel</code>	Right-aligned
Object	<code>JLabel</code>	Left-aligned

Figure 18-10 shows how a table might look before and after enabling the renderers.




Figure 18-10. *Before and after enabling the renderers*

You can choose to hard-code the class names for columns or have the `getColumnClass()` method be generic and just call `getClass()` on an element in the column. Adding the following code to an `AbstractTableModel` implementation would allow the `JTable` to use its default renderers. This implementation assumes that all entries for a particular column are one class type.

```
public Class getColumnClass(int column) {
    return (getValueAt(0, column).getClass());
}
```

DefaultTableModel Class

The `DefaultTableModel` is a subclass of `AbstractTableModel` that provides its own `Vector` data structure for storage. Everything in the data model is stored within vectors internally, even when the data is initially part of an array. In other words, if you already have your data in an adequate data structure, don't use `DefaultTableModel`. Create an `AbstractTableModel` that uses the structure, instead of having a `DefaultTableModel` convert the structure for you.

Creating a DefaultTableModel

There are six constructors for `DefaultTableModel`:

```
public DefaultTableModel()
TableModel model = new DefaultTableModel()

public DefaultTableModel(int rows, int columns)
TableModel model = new DefaultTableModel(2, 3)

public DefaultTableModel(Object rowData[][], Object columnNames[])
Object rowData[][] = {{"Row1-Column1", "Row1-Column2", "Row1-Column3"},
    {"Row2-Column1", "Row2-Column2", "Row2-Column3"}};
Object columnNames[] = {"Column One", "Column Two", "Column Three"};
TableModel model = new DefaultTableModel(rowData, columnNames);

public DefaultTableModel(Vector rowData, Vector columnNames)
Vector rowOne = new Vector();
rowOne.addElement("Row1-Column1");
rowOne.addElement("Row1-Column2");
rowOne.addElement("Row1-Column3");
Vector rowTwo = new Vector();
rowTwo.addElement("Row2-Column1");
rowTwo.addElement("Row2-Column2");
rowTwo.addElement("Row2-Column3");
Vector rowData = new Vector();
rowData.addElement(rowOne);
rowData.addElement(rowTwo);
Vector columnNames = new Vector();
columnNames.addElement("Column One");
columnNames.addElement("Column Two");
columnNames.addElement("Column Three");
TableModel model = new DefaultTableModel(rowData, columnNames);
```

```
public DefaultTableModel(Object columnNames[], int rows)
TableModel model = new DefaultTableModel(columnNames, 2);
```

```
public DefaultTableModel(Vector columnNames, int rows)
TableModel model = new DefaultTableModel(columnNames, 2);
```

Four of the constructors map directly to `JTable` constructors, whereas the remaining two allow you to create empty tables from a set of column headers with a fixed number of rows. Once you've created the `DefaultTableModel`, you pass it along to a `JTable` constructor to create the actual table, and then place the table in a `JScrollPane`.

Filling a DefaultTableModel

If you choose to use a `DefaultTableModel`, you must fill it with data for your `JTable` to display anything. Along with basic routines to fill the data structure, there are additional methods to remove data or replace the entire contents:

The following methods allow you to add columns:

```
public void addColumn(Object columnName);
public void addColumn(Object columnName, Vector columnData);
public void addColumn(Object columnName, Object columnData[ ]);
```

Use these methods to add rows:

```
public void addRow(Object rowData[ ]);
public void addRow(Vector rowData);
```

These methods insert rows:

```
public void insertRow(int row, Object rowData[ ]);
public void insertRow(int row, Vector rowData);
```

This method removes rows:

```
public void removeRow( int row);
```

And finally, you can replace contents with the following two methods:

```
public void setDataVector(Object newData[ ][ ], Object columnNames[ ]);
public void setDataVector(Vector newData, Vector columnNames);
```

DefaultTableModel Properties

In addition to the `rowCount` and `columnCount` properties inherited from `AbstractTableModel`, `DefaultTableModel` has two other properties, as shown in Table 18-6. Setting the `rowCount` property allows you to enlarge or shrink the table size as you please. If you are expanding the model, the additional rows remain empty.

Table 18-6. *DefaultTableModel Properties*

Property Name	Data Type	Access
columnCount	int	Read-only
columnIdentifiers	Vector	Write-only
dataVector	Vector	Read-only
rowCount	int	Read-write

Creating a Sparse Table Model

The default table model implementations are meant for tables that are full of data, not for spreadsheets consisting of mostly empty cells. When the cells in the table are mostly empty, the default data structure for the `DefaultTableModel` will end up with plenty of wasted space. At the cost of creating a `Point` for each lookup, you can create a sparse table model that can use a `HashMap` underneath it. Listing 18-5 demonstrates one such implementation.

Listing 18-5. *Sparsely Populated Table Model*

```
import java.awt.Point;
import java.util.HashMap;
import java.util.Map;
import javax.swing.table.AbstractTableModel;

public class SparseTableModel extends AbstractTableModel {

    static final long serialVersionUID = 5774430402629969511L;

    private Map<Point, Object> lookup;
    private final int rows;
    private final int columns;
    private final String headers[];

    public SparseTableModel(int rows, String columnHeaders[]) {
        if ((rows < 0) || (columnHeaders == null)) {
            throw new IllegalArgumentException("Invalid row count/columnHeaders");
        }
        this.rows = rows;
        this.columns = columnHeaders.length;
        headers = columnHeaders;
        lookup = new HashMap<Point, Object>();
    }
}
```

```

public int getColumnCount() {
    return columns;
}

public int getRowCount() {
    return rows;
}

public String getColumnName(int column) {
    return headers[column];
}

public Object getValueAt(int row, int column) {
    return lookup.get(new Point(row, column));
}

public void setValueAt(Object value, int row, int column) {
    if ((rows < 0) || (columns < 0)) {
        throw new IllegalArgumentException("Invalid row/column setting");
    }
    if ((row < rows) && (column < columns)) {
        lookup.put(new Point(row, column), value);
    }
}
}

```

Testing this example involves creating and filling up the model, as follows:

```

String headers[] = { "English", "Japanese"};
TableModel model = new SparseTableModel(10, headers);
JTable table = new JTable(model);
model.setValueAt("one", 0, 0);
model.setValueAt("ten", 9, 0);
model.setValueAt("roku - \ u516D", 5, 1);
model.setValueAt("hachi - \ u516B", 8, 1);

```

Listening to JTable Events with a TableModelListener

If you want to dynamically update your table data, you can work with a `TableModelListener` to find out when the data changes. The interface consists of one method that tells you when the table data changes.

```

public interface TableModelListener extends EventListener {
    public void tableChanged(TableModelEvent e);
}

```

After the `TableModelListener` is notified, you can ask the `TableModelEvent` for the type of event that happened and the range of rows and columns affected. Table 18-7 shows the properties of the `TableModelEvent` you can inquire about.

Table 18-7. *TableModelEvent Properties*

Property Name	Data Type	Access
column	int	Read-only
firstRow	int	Read-only
lastRow	int	Read-only
type	int	Read-only

The event type can be one of three type constants of `TableModelEvent`: `INSERT`, `UPDATE`, or `DELETE`.

If the column property setting for the `TableModelEvent` is `ALL_COLUMNS`, then all the columns in the data model are affected. If the `firstRow` property is `HEADER_ROW`, it means the table header changed.

Sorting JTable Elements

The `JTable` component doesn't come with built-in support for sorting. Nevertheless, this feature is frequently requested. Sorting doesn't require changing the data model, but it does require changing the view of the data model that the `JTable` has. This type of change is described by the Decorator pattern, in which you maintain the same API to the data but add sorting capabilities to the view. The participants of the Decorator design pattern are as follows:

- **Component:** The component defines the service interface that will be decorated.
- **ConcreteComponent:** The concrete component is the object to be decorated.
- **Decorator:** The decorator is an abstract wrapper to a concrete component; it maintains the service interface.
- **ConcreteDecorator(s) [A, B, C, . . .]:** The concrete decorator objects extend the decorator by adding decorating responsibilities while maintaining the same programming interface. They redirect service requests to the concrete component referred to by their abstract superclass.

Note The streams of the `java.io` package are examples of the Decorator pattern. The various filter streams add capabilities to the basic stream classes and maintain the same API for access.

In the particular case for table sorting, only the `Component`, `ConcreteComponent`, and `Decorator` are required, because there is only one concrete decorator. The `Component` is the `TableModel` interface, the `ConcreteComponent` is the actual model, and the `Decorator` is the sorted model.

In order to sort, you need to maintain a mapping of the real data to the sorted data. From the user interface, you must allow the user to select a column header label to enable sorting of a particular column.

To use the sorting capabilities, you tell the custom `TableSorter` class about your data model, decorate it, and create a `JTable` from your decorated model instead of the original. To enable the sorting by picking column header labels, you need to call the custom `install()` method of the `TableHeaderSorter` class shown in the following source code for the `TableSorter` class:

```
TableSorter sorter = new TableSorter(model);
JTable table = new JTable(sorter);
TableHeaderSorter.install(sorter, table);
```

The main source code for the `TableSorter` class is shown in Listing 18-6. It extends from the `TableMap` class, which is shown in Listing 18-7. The `TableSorter` class is where all the action is. The class does the sorting and notifies others that the data has changed.

Listing 18-6. *Table Column Sorting*

```
import javax.swing.*;
import javax.swing.table.*;
import javax.swing.event.*;
import java.awt.event.*;
import java.util.*;

public class TableSorter extends TableMap implements TableModelListener {
    int indexes[] = new int[0];
    Vector sortingColumns = new Vector();
    boolean ascending = true;

    public TableSorter() {
    }

    public TableSorter(TableModel model) {
        setModel(model);
    }

    public void setModel(TableModel model) {
        super.setModel(model);
        reallocateIndexes();
        sortByColumn(0);
        fireTableDataChanged();
    }

    public int compareRowsByColumn(int row1, int row2, int column) {
        Class type = model.getColumnClass(column);
        TableModel data = model;
```

```

// Check for nulls

Object o1 = data.getValueAt(row1, column);
Object o2 = data.getValueAt(row2, column);

// If both values are null return 0
if (o1 == null && o2 == null) {
    return 0;
} else if (o1 == null) { // Define null less than everything.
    return -1;
} else if (o2 == null) {
    return 1;
}

if (type.getSuperclass() == Number.class) {
    Number n1 = (Number)data.getValueAt(row1, column);
    double d1 = n1.doubleValue();
    Number n2 = (Number)data.getValueAt(row2, column);
    double d2 = n2.doubleValue();

    if (d1 < d2)
        return -1;
    else if (d1 > d2)
        return 1;
    else
        return 0;
} else if (type == String.class) {
    String s1 = (String)data.getValueAt(row1, column);
    String s2 = (String)data.getValueAt(row2, column);
    int result = s1.compareTo(s2);

    if (result < 0)
        return -1;
    else if (result > 0)
        return 1;
    else
        return 0;
} else if (type == java.util.Date.class) {
    Date d1 = (Date)data.getValueAt(row1, column);
    long n1 = d1.getTime();
    Date d2 = (Date)data.getValueAt(row2, column);
    long n2 = d2.getTime();

    if (n1 < n2)
        return -1;
    else if (n1 > n2)
        return 1;
}

```

```

        else
            return 0;
    } else if (type == Boolean.class) {
        Boolean bool1 = (Boolean)data.getValueAt(row1, column);
        boolean b1 = bool1.booleanValue();
        Boolean bool2 = (Boolean)data.getValueAt(row2, column);
        boolean b2 = bool2.booleanValue();

        if (b1 == b2)
            return 0;
        else if (b1) // Define false < true
            return 1;
        else
            return -1;
    } else {
        Object v1 = data.getValueAt(row1, column);
        String s1 = v1.toString();
        Object v2 = data.getValueAt(row2, column);
        String s2 = v2.toString();
        int result = s1.compareTo(s2);

        if (result < 0)
            return -1;
        else if (result > 0)
            return 1;
        else
            return 0;
    }
}

public int compare(int row1, int row2) {
    for (int level=0, n=sortingColumns.size(); level < n; level++) {
        Integer column = (Integer)sortingColumns.elementAt(level);
        int result = compareRowsByColumn(row1, row2, column.intValue());
        if (result != 0) {
            return (ascending ? result : -result);
        }
    }
    return 0;
}

public void reallocateIndexes() {
    int rowCount = model.getRowCount();
    indexes = new int[rowCount];
    for (int row = 0; row < rowCount; row++) {
        indexes[row] = row;
    }
}

```

```

public void tableChanged(TableModelEvent tableModelEvent) {
    super.tableChanged(tableModelEvent);
    reallocateIndexes();
    sortByColumn(0);
    fireTableStructureChanged();
}

public void checkModel() {
    if (indexes.length != model.getRowCount()) {
        System.err.println("Sorter not informed of a change in model.");
    }
}

public void sort() {
    checkModel();
    shufflesort((int[])indexes.clone(), indexes, 0, indexes.length);
    fireTableDataChanged();
}

public void shufflesort(int from[], int to[], int low, int high) {
    if (high - low < 2) {
        return;
    }
    int middle = (low + high)/2;
    shufflesort(to, from, low, middle);
    shufflesort(to, from, middle, high);

    int p = low;
    int q = middle;

    for (int i = low; i < high; i++) {
        if (q >= high || (p < middle && compare(from[p], from[q]) <= 0)) {
            to[i] = from[p++];
        } else {
            to[i] = from[q++];
        }
    }
}

private void swap(int first, int second) {
    int temp = indexes[first];
    indexes[first] = indexes[second];
    indexes[second] = temp;
}

```

```
public Object getValueAt(int row, int column) {
    checkModel();
    return model.getValueAt(indexes[row], column);
}

public void setValueAt(Object aValue, int row, int column) {
    checkModel();
    model.setValueAt(aValue, indexes[row], column);
}

public void sortByColumn(int column) {
    sortByColumn(column, true);
}

public void sortByColumn(int column, boolean ascending) {
    this.ascending = ascending;
    sortingColumns.removeAllElements();
    sortingColumns.addElement(new Integer(column));
    sort();
    super.tableChanged(new TableModelEvent(this));
}
}
```

Note The `TableSorter` borrows heavily from the `TableExample` that comes with the JFC/Swing release.

The `TableMap` class, shown in Listing 18-7, serves as a proxy, passing along all calls to the appropriate `TableModel` class. It's the superclass of the `TableSorter` class shown in Listing 18-6.

Listing 18-7. *Table Sorting Support Map*

```
import javax.swing.table.*;
import javax.swing.event.*;

public class TableMap extends AbstractTableModel implements TableModelListener {

    TableModel model;

    public TableModel getModel() {
        return model;
    }
}
```

```

public void setModel(TableModel model) {
    if (this.model != null) {
        this.model.removeTableModelListener(this);
    }
    this.model = model;
    if (this.model != null) {
        this.model.addTableModelListener(this);
    }
}

public Class getColumnClass(int column) {
    return model.getColumnClass(column);
}

public int getColumnCount() {
    return ((model == null) ? 0 : model.getColumnCount());
}

public String getColumnName(int column) {
    return model.getColumnName(column);
}

public int getRowCount() {
    return ((model == null) ? 0 : model.getRowCount());
}

public Object getValueAt(int row, int column) {
    return model.getValueAt(row, column);
}

public void setValueAt(Object value, int row, int column) {
    model.setValueAt(value, row, column);
}

public boolean isCellEditable(int row, int column) {
    return model.isCellEditable(row, column);
}

public void tableChanged(TableModelEvent tableModelEvent) {
    fireTableChanged(tableModelEvent);
}
}

```

Installation of the sorting routines requires the registration of a `MouseListener`, as shown in Listing 18-8, so that selection within the table header triggers the sorting process. Regular mouse clicks are ascending sorts; Shift-clicks are descending sorts.

Listing 18-8. *Mouse Listener for Table Sorting*

```
import javax.swing.*;
import javax.swing.table.*;
import javax.swing.event.*;
import java.awt.event.*;
import java.util.*;

public class TableHeaderSorter extends MouseAdapter {

    private TableSorter sorter;
    private JTable table;

    private TableHeaderSorter() {
    }

    public static void install(TableSorter sorter, JTable table) {
        TableHeaderSorter tableHeaderSorter = new TableHeaderSorter();
        tableHeaderSorter.sorter = sorter;
        tableHeaderSorter.table = table;
        JTableHeader tableHeader = table.getTableHeader();
        tableHeader.addMouseListener(tableHeaderSorter);
    }

    public void mouseClicked(MouseEvent mouseEvent) {
        TableColumnModel columnModel = table.getColumnModel();
        int viewColumn = columnModel.getColumnIndexAtX(mouseEvent.getX());
        int column = table.convertColumnIndexToModel(viewColumn);
        if (mouseEvent.getClickCount() == 1 && column != -1) {
            System.out.println("Sorting ...");
            int shiftPressed = (mouseEvent.getModifiers() & InputEvent.SHIFT_MASK);
            boolean ascending = (shiftPressed == 0);
            sorter.sortByColumn(column, ascending);
        }
    }
}
```

Note Chapter 19 includes a demonstration using the `TableSorter` to sort a table of system properties.

TableColumnModel Interface

`TableColumnModel` is one of those interfaces that lives in the background and usually doesn't require much attention. It basically manages the set of columns currently being displayed by a `JTable`. Unless triggered to do otherwise, when a `JTable` is created, the component builds a

default column model from the data model, specifying that the display column order remains in the data model order.

When the `autoCreateColumnsFromModel` property of `JTable` is set (true) prior to setting the data model of the `JTable`, the `TableColumnModel` is automatically created. In addition, you can manually tell the `JTable` to create the default `TableColumnModel` if the current settings need to be reset. The public void `createDefaultColumnsFromModel()` method does the creation for you, assigning the new creation to the `TableColumnModel` of the `JTable`.

With all that automatically done for you, why do you need to look at the `TableColumnModel`? Usually, you'll need to work with this interface only when you don't like the defaults or when you want to manually move things around. In addition to maintaining a set of `TableColumn` objects, the `TableColumnModel` manages a second `ListSelectionModel`, which allows users to select columns and rows from the table.

Let's take a look at the interface definition before getting into the default implementation.

```
public interface TableColumnModel {
    // Listeners
    public void addColumnModelListener(TableColumnModelListener l);
    public void removeColumnModelListener(TableColumnModelListener l);
    // Properties
    public int getColumnCount();
    public int getColumnMargin();
    public void setColumnMargin(int newMargin);
    public Enumeration getColumns();
    public boolean getColumnSelectionAllowed();
    public void setColumnSelectionAllowed(boolean flag);
    public int getSelectedColumnCount();
    public int[] getSelectedColumns();
    public ListSelectionModel getSelectionModel();
    public void setSelectionModel(ListSelectionModel newModel);
    public int getTotalColumnWidth();
    // Other methods
    public void addColumn(TableColumn aColumn);
    public TableColumn getColumn(int columnIndex);
    public int getColumnIndex(Object columnIdentifier);
    public int getColumnIndexAtX(int xPosition);
    public void moveColumn(int columnIndex, int newIndex);
    public void removeColumn(TableColumn column);
}
```

DefaultTableColumnModel Class

The `DefaultTableColumnModel` class defines the implementation of the `TableColumnModel` interface used by the system. It describes the general appearance of the `TableColumn` objects within the `JTable` by tracking margins, width, selection, and quantity. Table 18-8 shows the nine properties for accessing the `DefaultTableColumnModel` settings.

Table 18-8. *DefaultTableColumnModel Properties*

Property Name	Data Type	Access
columnCount	int	Read-only
columnMargin	int	Read-write
columnModelListeners	TableColumnModelListener[]	Read-only
columns	Enumeration	Read-only
columnSelectionAllowed	boolean	Read-write
selectedColumnCount	int	Read-only
selectedColumns	int[]	Read-only
selectionModel	ListSelectionModel	Read-write
totalColumnWidth	int	Read-only

In addition to the class properties, you can use the following methods to add, remove, and move columns through the `TableColumn` class, which will be discussed shortly.

```
public void addColumn(TableColumn newColumn);
public void removeColumn(TableColumn oldColumn);
public void moveColumn(int currentIndex, int newIndex);
```

Listening to JTable Events with a TableColumnModelListener

One of the things you might want to do with a `TableColumnModel` is listen for `TableColumnModelEvent` objects with a `TableColumnModelListener`. The listener will be notified of any addition, removal, movement, or selection of columns, or changing of column margins, as shown by the listener interface definition. Note that the different methods don't all receive `TableColumnModelEvent` objects when the event happens.

```
public interface TableColumnModelListener extends EventListener {
    public void columnAdded(TableColumnModelEvent e);
    public void columnMarginChanged(ChangeEvent e);
    public void columnMoved(TableColumnModelEvent e);
    public void columnRemoved(TableColumnModelEvent e);
    public void columnSelectionChanged(ListSelectionEvent e);
}
```

Because the listener definition identifies the event type, the `TableColumnModelEvent` definition defines only the range of columns affected by the change, as shown in Table 18-9.

Table 18-9. *TableColumnModelEvent Properties*

Property Name	Data Type	Access
fromIndex	int	Read-only
toIndex	int	Read-only

To see a demonstration of the `TableColumnModelListener`, you can attach a listener to one of your `TableColumnModel` objects:

```
TableColumnModel columnModel = table.getColumnModel();
columnModel.addColumnModelListener(...);
```

One such listener is shown in Listing 18-9. It doesn't do much besides print a message. Nevertheless, you can use it to see when different events happen.

Listing 18-9. *Table Column Model Listener*

```
TableColumnModelListener tableColumnModelListener =
    new TableColumnModelListener() {
        public void columnAdded(TableColumnModelEvent e) {
            System.out.println("Added");
        }
        public void columnMarginChanged(ChangeEvent e) {
            System.out.println("Margin");
        }
        public void columnMoved(TableColumnModelEvent e) {
            System.out.println("Moved");
        }
        public void columnRemoved(TableColumnModelEvent e) {
            System.out.println("Removed");
        }
        public void columnSelectionChanged(ListSelectionEvent e) {
            System.out.println("Selected");
        }
    };
```

Of course, you do need to create some code to elicit certain events. For instance, margins don't appear out of thin air. But you can add the same column multiple times to add more columns (or remove them). The program shown in Listing 18-10 tests the new `TableColumnModelListener`.

Listing 18-10. *Playing with Table Columns*

```
import javax.swing.event.*;
import javax.swing.table.*;
import javax.swing.*;
import java.awt.*;

public class ColumnModelSample {
    public static void main(String args[]) {
        final Object rows[][] = {
            {"one", "ichi - \u4E00"},
            {"two", "ni - \u4E8C"},
            {"three", "san - \u4E09"},
            {"four", "shi - \u56DB"},
            {"five", "go - \u4E94"},
        };
```

```

{"six", "roku - \u516D"},
{"seven", "shichi - \u4E03"},
{"eight", "hachi - \u516B"},
{"nine", "kyu - \u4E5D"},
{"ten", "ju - \u5341"}
};

final Object headers[] = {"English", "Japanese"};
Runnable runner = new Runnable() {
    public void run() {
        JFrame frame = new JFrame("Scrollless Table");
        frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
        JTable table = new JTable(rows, headers);

        TableColumnModelListener tableColumnModelListener =
            new TableColumnModelListener() {
                public void columnAdded(TableColumnModelEvent e) {
                    System.out.println("Added");
                }
                public void columnMarginChanged(ChangeEvent e) {
                    System.out.println("Margin");
                }
                public void columnMoved(TableColumnModelEvent e) {
                    System.out.println("Moved");
                }
                public void columnRemoved(TableColumnModelEvent e) {
                    System.out.println("Removed");
                }
                public void columnSelectionChanged(ListSelectionEvent e) {
                    System.out.println("Selection Changed");
                }
            };

        TableColumnModel columnModel = table.getColumnModel();
        columnModel.addColumnModelListener(tableColumnModelListener);

        columnModel.setColumnMargin(12);

        TableColumn column = new TableColumn(1);
        columnModel.addColumn(column);

        JScrollPane pane = new JScrollPane(table);
        frame.add(pane, BorderLayout.CENTER);
        frame.setSize(300, 150);
        frame.setVisible(true);
    }
};

```

```

        EventQueue.invokeLater(runner);
    }
}

```

TableColumn Class

`TableColumn` is another important class that lives behind the scenes. Swing tables consist of a group of columns, which are made up of cells. Each of those columns is described by a `TableColumn` instance. Each instance of the `TableColumn` class stores the appropriate editor, renderer, name, and sizing information. `TableColumn` objects are then grouped together into a `TableColumnModel` to make up the current set of columns to be displayed by a `JTable`. One useful trick to remember is if you don't want a column to be displayed, remove its `TableColumn` from the `TableColumnModel` but leave it in the `TableModel`.

Creating a TableColumn

If you choose to create your `TableColumn` objects yourself, you can use any one of four constructors. They cascade by adding more constructor arguments.

```

public TableColumn()
    TableColumn column = new TableColumn()

public TableColumn(int modelIndex)
    TableColumn column = new TableColumn(2)

public TableColumn(int modelIndex, int width)
    TableColumn column = new TableColumn(2, 25)

public TableColumn(int modelIndex, int width, TableCellRenderer
    renderer, TableCellEditor editor)
    TableColumn column = new TableColumn(2, 25, aRenderer, aEditor)

```

Note All column settings start at zero. Therefore, new `TableColumn(2)` uses column 3 from the `TableModel`.

With no arguments, such as in the first constructor in this list, you get an empty column with a default width (75 pixels), a default editor, and a default renderer. The `modelIndex` argument allows you to specify which column from the `TableModel` you would like the `TableColumn` to display within the `JTable`. You can also specify a width, a renderer, or an editor if you don't like the defaults. If you like one default but not the other, you can also specify `null` for the renderer or editor.

TableColumn Properties

Table 18-10 lists the 12 properties of the `TableColumn`. These properties allow you to customize a column beyond the initial set of constructor arguments. Most of the time, everything is configured for you based on the `TableModel`. However, you can still customize individual columns through the `TableColumn` class. Yes, all the properties are bound, except for the listener list.

Note If an identifier isn't specified, the `headerValue` setting is used instead.

Table 18-10. *TableColumn Properties*

Property Name	Data Type	Access
<code>cellEditor</code>	<code>TableCellEditor</code>	Read-write bound
<code>cellRenderer</code>	<code>TableCellRenderer</code>	Read-write bound
<code>headerRenderer</code>	<code>TableCellRenderer</code>	Read-write bound
<code>headerValue</code>	<code>Object</code>	Read-write bound
<code>identifier</code>	<code>Object</code>	Read-write bound
<code>maxWidth</code>	<code>int</code>	Read-write bound
<code>minWidth</code>	<code>int</code>	Read-write bound
<code>modelIndex</code>	<code>int</code>	Read-write bound
<code>preferredWidth</code>	<code>int</code>	Read-write bound
<code>propertyChangeListeners</code>	<code>PropertyChangeListener[]</code>	Read-only
<code>resizable</code>	<code>boolean</code>	Read-write bound
<code>width</code>	<code>int</code>	Read-write bound

Caution If `headerRenderer` is null, the default header renderer is used by the column:
`TableCellRenderer headerRenderer = table.getTableHeader().getDefaultRenderer();`
 The default is not returned by the `getHeaderRenderer()` method.

Using Icons in Column Headers

By default, the header renderer for a table displays text or HTML. Although you can get multiple lines of text and images with HTML, there may come a time when you want to display regular Icon objects within a header, as shown in the example in Figure 18-11. To do this, you must change the header's renderer. The header renderer is just another `TableCellRenderer`.



◆ English	◆ Japanese
three	san - 三
four	shi - 四
five	go - 五
six	roku - 六
seven	shichi - 七
eight	hachi - 八
nine	kyu - 九

Figure 18-11. Icons in table headers

To create a flexible renderer that can display icons, have the renderer treat the value data as a `JLabel`, instead of using the value to fill the `JLabel` (or for that, matter any `JComponent`). Listing 18-11 shows one such renderer, which is used in the program that created Figure 18-11.

Listing 18-11. Custom Table Cell Renderer for *JComponents*

```
import java.awt.*;
import javax.swing.*;
import javax.swing.table.*;

public class JComponentTableCellRenderer implements TableCellRenderer {
    public Component getTableCellRendererComponent(JTable table, Object value,
        boolean isSelected, boolean hasFocus, int row, int column) {
        return (JComponent)value;
    }
}
```

Figure 18-11 shows how this renderer might appear with the `DiamondIcon` as the `Icon`. The source for the sample program is shown in Listing 18-12.

Listing 18-12. Customizing Column Headers with Icons

```
import javax.swing.*;
import javax.swing.border.*;
import javax.swing.table.*;
import java.awt.*;

public class LabelHeaderSample {
    public static void main(String args[]) {
        final Object rows[][] = {
            {"one", "ichi - \u4E00"},
            {"two", "ni - \u4E8C"},
            {"three", "san - \u4E09"},
            {"four", "shi - \u56DB"},
            {"five", "go - \u4E94"},
            {"six", "roku - \u516D"},
            {"seven", "shichi - \u4E03"},
            {"eight", "hachi - \u516B"},
            {"nine", "kyu - \u4E5D"},
        };
    }
}
```

```

        {"ten",    "ju - \u5341"}
    };
    Runnable runner = new Runnable() {
        public void run() {
            JFrame frame = new JFrame("Label Header");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
            String headers[] = {"English", "Japanese"};
            JTable table = new JTable(rows, headers);
            JScrollPane scrollPane = new JScrollPane(table);

            Icon redIcon = new DiamondIcon(Color.RED);
            Icon blueIcon = new DiamondIcon(Color.BLUE);

            Border headerBorder = UIManager.getBorder("TableHeader.cellBorder");

            JLabel blueLabel = new JLabel(headers[0], blueIcon, JLabel.CENTER);
            blueLabel.setBorder(headerBorder);
            JLabel redLabel = new JLabel(headers[1], redIcon, JLabel.CENTER);
            redLabel.setBorder(headerBorder);

            TableCellRenderer renderer = new JComponentTableCellRenderer();

            TableColumnModel columnModel = table.getColumnModel();

            TableColumn column0 = columnModel.getColumn(0);
            TableColumn column1 = columnModel.getColumn(1);

            column0.setHeaderRenderer(renderer);
            column0.setHeaderValue(blueLabel);

            column1.setHeaderRenderer(renderer);
            column1.setHeaderValue(redLabel);

            frame.add(scrollPane, BorderLayout.CENTER);
            frame.setSize(300, 150);
            frame.setVisible(true);
        }
    };
    EventQueue.invokeLater(runner);
}
}

```

JTableHeader Class

Each `JTableHeader` instance represents one of a set of headers for all the different columns. The set of `JTableHeader` objects is placed within the column header view of the `JScrollPane`.

You rarely need to work with the `JTableHeader` directly. Nevertheless, you can configure some characteristics of column headers.

Creating a `JTableHeader`

The `JTableHeader` has two constructors. One uses the default `TableColumnModel`, whereas the other explicitly specifies the model.

```

public JTableHeader()
JComponent headerComponent = new JTableHeader()

public JTableHeader(TableColumnModel columnModel)
JComponent headerComponent = new JTableHeader(aColumnModel)

```

JTableHeader Properties

As Table 18-11 shows, the `JTableHeader` has ten different properties. These properties allow you to configure what the user can do with a particular column header or how the column header is shown.

Table 18-11. *JTableHeader Properties*

Property Name	Data Type	Access
<code>accessibleContext</code>	<code>AccessibleContext</code>	Read-only
<code>columnModel</code>	<code>TableColumnModel</code>	Read-write bound
<code>draggedColumn</code>	<code>TableColumn</code>	Read-write
<code>draggedDistance</code>	<code>int</code>	Read-write
<code>reorderingAllowed</code>	<code>boolean</code>	Read-write bound
<code>resizingAllowed</code>	<code>boolean</code>	Read-write bound
<code>resizingColumn</code>	<code>TableColumn</code>	Read-write
<code>table</code>	<code>JTable</code>	Read-write bound
<code>UI</code>	<code>TableHeaderUI</code>	Read-write
<code>UIClassID</code>	<code>String</code>	Read-only

Using Tooltips in Table Headers

By default, if you set tooltip text for the table header, all of the column headers will share the same tooltip text. To specify a tooltip for a given column, you need to create or get the renderer, and then set the tooltip for the renderer. This is true for the individual cells, too. Figure 18-12 shows how the results of this customization would appear.




Figure 18-12. Header tooltips

The source for the customization in Figure 18-12 is shown in Listing 18-13. Unless you previously set the headers, it's not really necessary to check if the header for a specific column is null first.

Listing 18-13. Showing Tooltip Text in a Table Header

```
JLabel headerRenderer = new DefaultTableCellRenderer();
String columnName = table.getModel().getColumnName(0);
headerRenderer.setText(columnName);
headerRenderer.setToolTipText("Wave");
TableColumnModel columnModel = table.getColumnModel();
TableColumn englishColumn = columnModel.getColumn(0);
englishColumn.setHeaderRenderer((TableCellRenderer)headerRenderer);
```

Customizing a JTableHeader Look and Feel

The available set of UIResource-related properties for a JTableHeader is shown in Table 18-12. The five settings control the color, font, and border for the header renderers.

Table 18-12. JTableHeader UIResource Elements

Property String	Object Type
TableHeader.background	Color
TableHeader.cellBorder	Border
TableHeader.font	Font
TableHeader.foreground	Color
TableHeaderUI	String

Note For an example of creating column headers spanning multiple columns, see CodeGuru at <http://www.codeguru.com/java/Swing>.

Editing Table Cells

Editing `JTable` cells is nearly identical to editing `JTree` cells. In fact, the default table cell editor, `DefaultCellEditor`, implements both the `TableCellEditor` and `TreeCellEditor` interfaces, allowing you to use the same editor for both tables and trees.

Clicking an editable cell will place the cell in edit mode. (The number of clicks required depends on the type of editor.) The default editor for all cells is a `JTextField`. Although this works great for many data types, it's not always appropriate for many others. So, you should either not support editing of nontextual information or set up specialized editors for your `JTable`. With a `JTable`, you register an editor for a particular class type or column. Then, when the table runs across a cell of the appropriate type, the necessary editor is used.

Caution When no specialized editor is installed, the `JTextField` is used, even when it's inappropriate for the content.

TableCellEditor Interface and DefaultCellEditor Class

The `TableCellEditor` interface defines the single method necessary to get an editor cell for a `JTable`. The argument list for `TableCellEditor` is identical to the `TableCellRenderer`, with the exception of the `hasFocused` argument. Because the cell is being edited, it's already known to have the input focus.

```
public interface TableCellEditor extends CellEditor {
    public Component getTableCellEditorComponent(JTable table, Object value,
        boolean isSelected, int row, int column);
}
```

As described in Chapter 17, the `DefaultCellEditor` provides an implementation of the interface. It offers a `JTextField` as one editor, a `JCheckBox` for another, and a `JComboBox` for a third.

As Table 18-13 shows, in most cases the default editor is the `JTextField`. If the cell data can be converted to and from a string, and the class provides a constructor with a `String` argument, the editor offers the text representation of the data value for the initial editing value. You can then edit the contents.

Table 18-13. *Default JTable Editors*

Class	Editor	Information
<code>Boolean</code>	<code>JCheckBox</code>	Centered
<code>Object</code>	<code>JTextField</code>	Left-aligned

Creating a Simple Cell Editor

As a simple example of changing a non-`String` cell in a `JTable`, you can provide a fixed set of color choices to the user. Then when the user picks a color, you have the appropriate `Color` value to

return to the table model. The `DefaultCellEditor` offers a `JComboBox` for just this situation. After configuring the `ListCellRenderer` for the `JComboBox` to display colors properly, you have a `TableCellEditor` for picking colors. Figure 18-13 shows how this might appear.




Figure 18-13. *JComboBox color editor*

Tip Any time you can predefine all the choices, you can use the `JComboBox` as your editor through `DefaultCellEditor`.

Listing 18-14 shows the class that represents the `TableCellRenderer` for the `Color` column of the example shown in Figure 18-13 and the `ListCellRenderer` for the `JComboBox` `TableCellEditor`. Because of the many similarities of the two renderer components, their definitions are combined into one class.

Listing 18-14. *JComboBox As Table Cell Renderer*

```
import java.awt.*;
import javax.swing.*;
import javax.swing.table.*;

public class ComboTableCellRenderer
    implements ListCellRenderer, TableCellRenderer {
    DefaultListCellRenderer listRenderer = new DefaultListCellRenderer();
    DefaultTableCellRenderer tableRenderer = new DefaultTableCellRenderer();

    private void configureRenderer(JLabel renderer, Object value) {
        if ((value != null) && (value instanceof Color)) {
            renderer.setIcon(new ImageIcon((Color)value));
            renderer.setText("");
        } else {
            renderer.setIcon(null);
            renderer.setText((String)value);
        }
    }
}
```

```

public Component getListCellRendererComponent(JList list, Object value,
    int index, boolean isSelected, boolean cellHasFocus) {
    listRenderer =
        (DefaultListCellRenderer)listRenderer.getListCellRendererComponent(
            list, value, index, isSelected, cellHasFocus);
    configureRenderer(listRenderer, value);
    return listRenderer;
}

public Component getTableCellRendererComponent(JTable table, Object value,
    boolean isSelected, boolean hasFocus, int row, int column) {
    tableRenderer =
        (DefaultTableCellRenderer)tableRenderer.getTableCellRendererComponent(
            table, value, isSelected, hasFocus, row, column);
    configureRenderer(tableRenderer, value);
    return tableRenderer;
}
}

```

To demonstrate the use of this new combined renderer and show a simple table cell editor, the program shown in Listing 18-15 creates a data model in which one of the columns is a `Color`. After installing the renderer twice and setting up the table cell editor, the table can be shown and the `Color` column can be edited.

Listing 18-15. *Table Cell Editor Sample*

```

import javax.swing.*.*;
import javax.swing.table.*;
import java.awt.*.*;

public class EditableColorColumn {

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                Color choices[] = {Color.RED, Color.ORANGE, Color.YELLOW,
                    Color.GREEN, Color.BLUE, Color.MAGENTA};
                ComboTableCellRenderer renderer = new ComboTableCellRenderer();
                JComboBox comboBox = new JComboBox(choices);
                comboBox.setRenderer(renderer);
                TableCellEditor editor = new DefaultCellEditor(comboBox);

                JFrame frame = new JFrame("Editable Color Table");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                TableModel model = new ColorTableModel();
                JTable table = new JTable(model);
            }
        };
        runner.run();
    }
}

```

```

        TableColumn column = table.getColumnModel().getColumn(3);
        column.setCellRenderer(renderer);
        column.setCellEditor(editor);

        JScrollPane scrollPane = new JScrollPane(table);
        frame.add(scrollPane, BorderLayout.CENTER);
        frame.setSize(400, 150);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Listing 18-16 shows the table model used for this example and the next one.

Listing 18-16. *Table Model*

```

import java.awt.*;
import javax.swing.table.*;

public class ColorTableModel extends AbstractTableModel {

    Object rowData[][] = {
        {"1", "ichi - \u4E00", Boolean.TRUE, Color.RED},
        {"2", "ni - \u4E8C", Boolean.TRUE, Color.BLUE},
        {"3", "san - \u4E09", Boolean.FALSE, Color.GREEN},
        {"4", "shi - \u56DB", Boolean.TRUE, Color.MAGENTA},
        {"5", "go - \u4E94", Boolean.FALSE, Color.PINK},
    };
    String columnNames[] = {"English", "Japanese", "Boolean", "Color"};
    public int getColumnCount() {
        return columnNames.length;
    }
    public String getColumnName(int column) {
        return columnNames[column];
    }
    public int getRowCount() {
        return rowData.length;
    }
    public Object getValueAt(int row, int column) {
        return rowData[row][column];
    }
    public Class getColumnClass(int column) {
        return (getValueAt(0, column).getClass());
    }
}

```

```

    public void setValueAt(Object value, int row, int column) {
        rowData[row][column]=value;
    }
    public boolean isCellEditable(int row, int column) {
        return (column != 0);
    }
}

```

Creating a Complex Cell Editor

Although the previous example demonstrates how to provide a fixed set of choices to the user in a combo box `TableCellEditor`, offering the `JColorChooser` as an option seems to be a better choice (at least, in the case of color selection). When defining your own `TableCellEditor`, you must implement the single `TableCellEditor` method to get the appropriate component. You must also implement the seven methods of the `CellEditor` because they manage and notify a list of `CellEditorListener` objects, as well as control when a cell is editable. Starting with an `AbstractCellEditor` subclass makes defining your own `TableCellEditor` much simpler.

By extending the `AbstractCellEditor` class, only the `getCellEditorValue()` method from the `CellEditor` methods requires customization for the editor. Doing that and providing a `JButton` that pops up a `JColorChooser` when clicked provides the entire editor component. Listing 18-17 shows the code for this custom editor.

Listing 18-17. *JColorChooser As Table Cell Editor*

```

import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import javax.swing.table.*;

public class ColorChooserEditor extends AbstractCellEditor
    implements TableCellEditor {

    private JButton delegate = new JButton();

    Color savedColor;

    public ColorChooserEditor() {
        ActionListener actionListener = new ActionListener() {
            public void actionPerformed (ActionEvent actionEvent) {
                Color color = JColorChooser.showDialog(
                    delegate, "Color Chooser", savedColor);
                ColorChooserEditor.this.changeColor(color);
            }
        };
        delegate.addActionListener(actionListener);
    }
}

```

```

public Object getCellEditorValue() {
    return savedColor;
}

private void changeColor(Color color) {
    if (color != null) {
        savedColor = color;
        delegate.setIcon(new DiamondIcon(color));
    }
}

public Component getTableCellEditorComponent (JTable table, Object value,
        boolean isSelected, int row, int column) {
    changeColor((Color)value);
    return delegate;
}
}

```

Figure 18-14 shows the ColorChooserEditor in action, with the associated table in the background.




Figure 18-14. Pop-up color editor

A sample program using the new ColorChooserEditor is shown in Listing 18-18. The example reuses the earlier ColorTableModel data model shown in Listing 18-16. Setting up the ColorChooserEditor simply involves setting the TableCellEditor for the appropriate column.

Listing 18-18. *Testing Another Custom Table Cell Editor*

```

import java.awt.*;
import javax.swing.*;
import javax.swing.table.*;

public class ChooserTableSample {

    public static void main(String args[]) {

        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Editable Color Table");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                TableModel model = new ColorTableModel();
                JTable table = new JTable(model);

                TableColumn column = table.getColumnModel().getColumn(3);

                ComboTableCellRenderer renderer = new ComboTableCellRenderer();
                column.setCellRenderer(renderer);

                TableCellEditor editor = new ColorChooserEditor();
                column.setCellEditor(editor);

                JScrollPane scrollPane = new JScrollPane(table);
                frame.add(scrollPane, BorderLayout.CENTER);
                frame.setSize(400, 150);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}

```

Printing Tables

One of the newer features with JDK 5.0 is also one of the easiest to use: the ability to print tables. Through the simple method of `public boolean print()` throws `PrinterException` of `JTable`, you can print a large table across multiple pages on the printer. It will even spread the columns across multiple pages if you don't like the default behavior of fitting the table's entire width on each page.

To demonstrate this behavior, Listing 18-19 takes the basic `JTable` sample code used to generate Figure 18-1, adds some more rows to the table, and adds a print button.

Listing 18-19. *Printing Tables Sample*

```

import javax.swing.*;
import java.awt.*;
import java.awt.event.*;
import java.awt.print.*;

public class TablePrint {
    public static void main(String args[]) {
        final Object rows[][] = {
            {"one", "ichi - \u4E00"},
            {"two", "ni - \u4E8C"},
            {"three", "san - \u4E09"},
            {"four", "shi - \u56DB"},
            {"five", "go - \u4E94"},
            {"six", "roku - \u516D"},
            {"seven", "shichi - \u4E03"},
            {"eight", "hachi - \u516B"},
            {"nine", "kyu - \u4E5D"},
            {"ten", "ju - \u5341"},
            ... Repeat section at least 10 times ...
            {"one", "ichi - \u4E00"},
            {"two", "ni - \u4E8C"},
            {"three", "san - \u4E09"},
            {"four", "shi - \u56DB"},
            {"five", "go - \u4E94"},
            {"six", "roku - \u516D"},
            {"seven", "shichi - \u4E03"},
            {"eight", "hachi - \u516B"},
            {"nine", "kyu - \u4E5D"},
            {"ten", "ju - \u5341"},
        };
        final Object headers[] = {"English", "Japanese"};
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Table Printing");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                final JTable table = new JTable(rows, headers);
                JScrollPane scrollPane = new JScrollPane(table);
                frame.add(scrollPane, BorderLayout.CENTER);
                JButton button = new JButton("Print");
                ActionListener printAction = new ActionListener() {
                    public void actionPerformed(ActionEvent e) {

```

```

        try {
            table.print();
        } catch (PrinterException pe) {
            System.err.println("Error printing: " + pe.getMessage());
        }
    }
};
button.addActionListener(printAction);
frame.add(button, BorderLayout.SOUTH);
frame.setSize(300, 150);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

After clicking the Print button, the user is prompted with a typical printer selection dialog box, as shown in Figure 18-15.




Figure 18-15. *Print dialog box displayed by the printing tables example*

After the user clicks the Print button in the Print dialog box, the printing begins. A dialog window like the one shown in Figure 18-16 appears for each page printed.



Figure 18-16. *Printing progress dialog box displayed by the printing tables example*

Yes, it really is that easy to print a multiple-page table with JDK 5.0. The `print()` method returns a boolean, so you can discover if the user canceled the operation.

For those looking for more control over the printing operation, there are several other overloaded versions of the `print()` method of `JTable`. Like the simple `print()` method, they all can throw a `PrinterException`.

One `print()` version lets you specify the print mode:

```
public boolean print(JTable.PrintMode printMode)
```

The `JTable.PrintMode` argument is an enumeration of `FIT_WIDTH` and `NORMAL`. When not specified with the no-argument version of `print()`, the default is `FIT_WIDTH`.

Another version lets you specify a page header or footer:

```
public boolean print(JTable.PrintMode printMode, MessageFormat headerFormat,
    MessageFormat footerFormat)
```

`MessageFormat` comes from the `java.text` package. The one argument to the header and footer formatting string is the page number. To display the page number, include `{0}` in your formatting string where you want the page number to appear. Both will appear centered on the page, with the header in a larger font. To demonstrate, change the `print()` call in Listing 18-19 to the following (and add an import line):

```
MessageFormat headerFormat = new MessageFormat("Page {0}");
MessageFormat footerFormat = new MessageFormat("- {0} -");
table.print(JTable.PrintMode.FIT_WIDTH, headerFormat, footerFormat);
```

The final `print()` version is the all inclusive one, allowing you to not show the printer dialog box and configure what the default print request attribute set entails, such as how many copies to print.

```
public boolean print(JTable.PrintMode printMode, MessageFormat headerFormat,
    MessageFormat footerFormat, boolean showPrintDialog,
    PrintRequestAttributeSet attr, boolean interactive)
```

For those times when you desire no user interaction to print, consider using this last version.

Summary

In this chapter, you explored the inner depths of the `JTable` component. You looked at customizing the `TableModel`, `TableColumnModel`, and `ListSelectionModel` for the `JTable`. You delved into both the abstract and concrete implementations of the different table models. In addition, you examined the inner elements of the various table models, such as the `TableColumn` and `JTableHeader` classes. You also looked into how to customize the display and editing of the `JTable` cells by providing a custom `TableCellRenderer` and `TableCellEditor`. Finally, you learned about printing tables via the new `print()` method.

In Chapter 19, you'll explore the drag-and-drop architecture of the JFC/Swing component set.



Drag-and-Drop Support

D*rag-and-drop* support allows a user to highlight something in one program or area of the screen, select it, and relocate it to another program or area of the screen. For example, in Microsoft Word, you can select a paragraph and drag it to a new location.

As Java has evolved, not only has the printing support changed with nearly every release, but so has the drag-and-drop support. The last major change in drag-and-drop support happened with the J2SE 1.4 release. Prior releases had support that was extremely difficult to use, especially to get proper drag-and-drop behavior for complex (nontext) types. The JDK 5.0 version adds some bug fixes and enhancements to drag-and-drop support.

You can implement drag-and-drop within your Java program in three ways:

- For the components that come with built-in support, just enable it by calling their `setDragEnabled()` method with an argument of `true`. Those components are `JColorChooser`, `JFileChooser`, `JList`, `JTable`, `JTree`, and all the subclasses of `JTextComponent`, except `JPasswordField`.
- For components without built-in support, you typically just need to configure the `TransferHandler` for that component.
- You can also go directly to the classes found in the `java.awt.dnd` package. Thanks to the built-in support and configurability, this approach is rarely necessary.

Built-in Drag-and-Drop Support

Table 19-1 shows the components that offer built-in support for drag-and-drop. Initially, only dropping is enabled for the components that support it, but after calling `setDragEnabled(true)` for the component in question, you can enable dragging, too, if it's supported. The drag-and-drop capabilities of the Java platform involve the underlying `java.awt.datatransfer` package to move data around. Classes in this package allow you to describe the type of data to transfer.

Table 19-1. *Components with Built-in Support for Drag-and-Drop*

Component	Drag	Drop
JColorChooser	X	X
JEditorPane	X	X
JFileChooser	X	
JFormattedTextField	X	X
JList	X	
JPasswordField		X
JTable	X	
JTextArea	X	X
TextField	X	X
JTextPane	X	X
JTree	X	

Note For security reasons, you cannot drag text out of a JPasswordField component.

For the JColorChooser component, what you drag is a `java.awt.Color` object. The other oddball of the bunch is the JFileChooser, where you literally drag a `java.io.File` object around and drop it into a drop target. If the drop target doesn't support working with File objects, a string representing the path is dropped instead.

As a simple demonstration, Listing 19-1 shows a program with two JColorChooser components on a single screen. The `setDragEnabled(true)` call is made for both choosers, so you can drag-and-drop colors between the two components with minimal coding effort.

Listing 19-1. *Dragging-and-Dropping Colors Across JColorChooser Components*

```
import javax.swing.*;
import java.awt.*;

public class DoubleColor {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Double Color Choosers");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JColorChooser left = new JColorChooser();
                left.setDragEnabled(true);
                frame.add(left, BorderLayout.WEST);
```

```

JColorChooser right = new JColorChooser();
right.setDragEnabled(true);
frame.add(right, BorderLayout.EAST);

frame.pack();
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Figure 19-1 shows this program in action, after dragging several colors. The drag area is the Preview panel at the bottom. Dropping doesn't adjust the Recent list on the right side of each color chooser, and you can drop across different color chooser panels.




Figure 19-1. *Dueling JColorChoosers*

TransferHandler Class

The magic of drag-and-drop happens because of the `java.swing.TransferHandler` class, introduced with the J2SE 1.4 release. “What’s magical about it?” you might ask. With this class, you can pick which property you would like to be transferable in a drag-and-drop operation.

When you call `setDragEnabled(true)` to tell a component to support the drag gesture, the component asks the installed `TransferHandler` what to transfer. If you don’t like the default object being transferred, you can call the `setTransferHandler()` method of the component, passing in an appropriate replacement. You can also call `setTransferHandler()` when you want to enable drag-and-drop support for a component that doesn’t come with support built in.

The `TransferHandler` class has one public constructor:

```
public TransferHandler(String property)
```

The parameter to the constructor represents the property of the component that you wish to transfer. In other words, you identify the JavaBeans component property as the transferable object for the drag-and-drop operation.

For instance, to transfer the text label of a `JLabel`, you would do the following:

```
JLabel label = new JLabel("Hello, World");
label.setTransferHandler(new TransferHandler("text"));
```

Since `JLabel` doesn't have a `setDragEnabled()` method, you must tell the component what the start of the drag gesture is. Typically, this would be pressing the mouse button, so you would also need to add a `MouseListener` to the button. When you tell the `TransferHandler` to `exportAsDrag()`, that enables the dragging operation for the component.

```
MouseListener listener = new MouseAdapter() {
    public void mousePressed(MouseEvent me) {
        JComponent comp = (JComponent)me.getSource();
        TransferHandler handler = comp.getTransferHandler();
        handler.exportAsDrag(comp, me, TransferHandler.COPY);
    }
};
button.addMouseListener(listener);
```

The default behavior when the drop gesture happens—releasing the mouse in this example—would drop what was registered with the `TransferHandler`.

Listing 19-2 demonstrates a program that enables drag-and drop for the text in a `JLabel`.

Listing 19-2. *Dragging Text from a JLabel*

```
import javax.swing.*;
import java.awt.*;
import java.awt.event.*;

public class DragLabel {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Drag Label");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JLabel label = new JLabel("Hello, World");
                label.setTransferHandler(new TransferHandler("foreground"));
                MouseListener listener = new MouseAdapter() {
                    public void mousePressed(MouseEvent me) {
                        JComponent comp = (JComponent)me.getSource();
                        TransferHandler handler = comp.getTransferHandler();
                        handler.exportAsDrag(comp, me, TransferHandler.COPY);
                    }
                };
            }
        };
    }
};
```

```

        label.addMouseListener(listener);
        frame.add(label, BorderLayout.SOUTH);

        JTextField text = new JTextField();
        frame.add(text, BorderLayout.NORTH);

        frame.setSize(300, 150);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Figure 19-2 shows this program during the drag operation. Notice how the cursor changes to indicate the operation.




Figure 19-2. *Dragging text from a JLabel to a JTextField*

If instead of dragging the text of the JLabel, you wanted to drag the foreground color, the only change to the program would be to the `setTransferHandler()` line:

```
label.setTransferHandler(new TransferHandler("foreground"));
```

Then, assuming you had some place to drop the color, as in the program in Listing 19-1, you could drag the foreground color out of the label to the JColorChooser, and then drop the color out of the JColorChooser into the JLabel. Since the TransferHandler is registered for a specific property of the component, there is no explicit code necessary to handle dropping. Instead, the setter method for the property passed into the handler constructor is notified of the change.

Drag-and-Drop Support for Images

If you wish to transfer something other than a simple property, you need to create an implementation of the Transferable interface, found in the `java.awt.datatransfer` package. Transferable implementations are typically meant for transfers through the clipboard, but by having your implementation be a TransferHandler subclass, you can use it to drag-and-drop the object. The three methods of the Transferable interface are shown here:

```
public interface Transferable{
    public DataFlavor[] getTransferDataFlavors();
    public boolean isDataFlavorSupported(DataFlavor);
    public Object getTransferData(java.awt.datatransfer.DataFlavor)
        throws UnsupportedFlavorException, IOException;
}
```

One common application for this is the ability to transfer images. The exposed property of a JLabel or JButton is a javax.swing.Icon object, not a java.awt.Image object. While you can certainly transfer Icon objects within and across Java programs, a more useful behavior is to transfer Image objects to external entities, like Paint Shop Pro or Photoshop.

To create a transferable image object, the ImageSelection class, you must implement the three Transferable interface methods and override four methods of TransferHandler: getSourceActions(), canImport(), createTransferable(), and importData().

Note The class for transferring strings is called StringSelection.

The getSourceActions() method needs to report which actions you are going to support. By default, this is the TransferHandler.COPY operation when a property is set via the constructor, or TransferHandler.NONE when it is not. Since the ImageSelection class implicitly uses the icon property to get the component's image, just have the method return TransferHandler.COPY:

```
public int getSourceActions(JComponent c) {
    return TransferHandler.COPY;
}
```

There is also a TransferHandler.MOVE operation, but you typically don't want the image to be removed from the label it was copied from.

You pass the canImport() method a component and an array of DataFlavor objects. You need to verify that the component is supported and one of the flavors in the array matches the supported set:

```
private static final DataFlavor flavors[] = {DataFlavor.imageFlavor};
...
public boolean canImport(JComponent comp, DataFlavor flavor[]) {
    if (!(comp instanceof JLabel) && !(comp instanceof AbstractButton)) {
        return false;
    }
    for (int i=0, n=flavor.length; i<n; i++) {
        for (int j=0, m=flavors.length; j<m; j++) {
            if (flavor[i].equals(flavors[j])) {
                return true;
            }
        }
    }
    return false;
}
```

The `createTransferable()` method returns a reference to the `Transferable` implementation. When the clipboard paste operation is executed, or the drop gesture is performed while dragging, the `Transferable` object will be notified to get the object to transfer.

```
public Transferable createTransferable(JComponent comp) {
    // Clear
    image = null;

    if (comp instanceof JLabel) {
        JLabel label = (JLabel)comp;
        Icon icon = label.getIcon();
        if (icon instanceof ImageIcon) {
            image = ((ImageIcon)icon).getImage();
            return this;
        }
    } else if (comp instanceof AbstractButton) {
        AbstractButton button = (AbstractButton)comp;
        Icon icon = button.getIcon();
        if (icon instanceof ImageIcon) {
            image = ((ImageIcon)icon).getImage();
            return this;
        }
    }
    return null;
}
```

The `importData()` method is called when data is dropped into the component or pasted from the clipboard. It has two parameters: a `JComponent` to paste the clipboard data and the clipboard data via a `Transferable` object. Assuming the method receives a format supported by the Java platform, the component associated with the transfer handler gets a new image to display.

```
public boolean importData(JComponent comp, Transferable t) {
    if (comp instanceof JLabel) {
        JLabel label = (JLabel)comp;
        if (t.isDataFlavorSupported(flavors[0])) {
            try {
                image = (Image)t.getTransferData(flavors[0]);
                ImageIcon icon = new ImageIcon(image);
                label.setIcon(icon);
                return true;
            } catch (UnsupportedFlavorException ignored) {
            } catch (IOException ignored) {
            }
        }
    } else if (comp instanceof AbstractButton) {
        AbstractButton button = (AbstractButton)comp;
    }
```

```

    if (t.isDataFlavorSupported(flavors[0])) {
        try {
            image = (Image)t.getTransferData(flavors[0]);
            ImageIcon icon = new ImageIcon(image);
            button.setIcon(icon);
            return true;
        } catch (UnsupportedFlavorException ignored) {
        } catch (IOException ignored) {
        }
    }
}
return false;
}

```

Putting all this code together with the three methods implemented for the Transferable interface produces Listing 19-3.

Listing 19-3. *Implementing a Draggable Image*

```

import java.awt.*;
import java.awt.image.*;
import java.awt.datatransfer.*;
import java.io.*;
import javax.swing.*;

public class ImageSelection extends TransferHandler
    implements Transferable {

    private static final DataFlavor flavors[] = {DataFlavor.imageFlavor};

    private Image image;

    public int getSourceActions(JComponent c) {
        return TransferHandler.COPY;
    }

    public boolean canImport(JComponent comp, DataFlavor flavor[]) {
        if (!(comp instanceof JLabel) && !(comp instanceof AbstractButton)) {
            return false;
        }
        for (int i=0, n=flavor.length; i<n; i++) {
            for (int j=0, m=flavors.length; j<m; j++) {
                if (flavor[i].equals(flavors[j])) {
                    return true;
                }
            }
        }
    }
}

```

```

        return false;
    }

    public Transferable createTransferable(JComponent comp) {
        // Clear
        image = null;

        if (comp instanceof JLabel) {
            JLabel label = (JLabel)comp;
            Icon icon = label.getIcon();
            if (icon instanceof ImageIcon) {
                image = ((ImageIcon)icon).getImage();
                return this;
            }
        } else if (comp instanceof AbstractButton) {
            AbstractButton button = (AbstractButton)comp;
            Icon icon = button.getIcon();
            if (icon instanceof ImageIcon) {
                image = ((ImageIcon)icon).getImage();
                return this;
            }
        }
        return null;
    }

    public boolean importData(JComponent comp, Transferable t) {
        if (comp instanceof JLabel) {
            JLabel label = (JLabel)comp;
            if (t.isDataFlavorSupported(flavors[0])) {
                try {
                    image = (Image)t.getTransferData(flavors[0]);
                    ImageIcon icon = new ImageIcon(image);
                    label.setIcon(icon);
                    return true;
                } catch (UnsupportedFlavorException ignored) {
                } catch (IOException ignored) {
                }
            }
        } else if (comp instanceof AbstractButton) {
            AbstractButton button = (AbstractButton)comp;
            if (t.isDataFlavorSupported(flavors[0])) {
                try {
                    image = (Image)t.getTransferData(flavors[0]);
                    ImageIcon icon = new ImageIcon(image);
                    button.setIcon(icon);
                    return true;
                }
            }
        }
    }

```

```

        } catch (UnsupportedFlavorException ignored) {
        } catch (IOException ignored) {
        }
    }
}
return false;
}

// Transferable
public Object getTransferData(DataFlavor flavor) {
    if (isDataFlavorSupported(flavor)) {
        return image;
    }
    return null;
}

public DataFlavor[] getTransferDataFlavors() {
    return flavors;
}

public boolean isDataFlavorSupported(DataFlavor flavor) {
    return flavors[0].equals(flavor);
}
}

```

To test this, you need to create a program with a draggable `JLabel` or `AbstractButton` subclass. This is basically the same program as shown in Listing 19-2, but with only a `JLabel` with an associated image located in the center of the screen.

Listing 19-4. *Draggable Image*

```

import javax.swing.*.*;
import java.awt.*.*;
import java.awt.event.*;

public class DragImage {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Drag Image");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
            }
        };
        SwingUtilities.invokeLater(runner);
    }
}

```

```

Icon icon = new ImageIcon("dog.jpg");
JLabel label = new JLabel(icon);
label.setTransferHandler(new ImageSelection());
MouseListener listener = new MouseAdapter() {
    public void mousePressed(MouseEvent me) {
        JComponent comp = (JComponent)me.getSource();
        TransferHandler handler = comp.getTransferHandler();
        handler.exportAsDrag(comp, me, TransferHandler.COPY);
    }
};
label.addMouseListener(listener);
frame.add(new JScrollPane(label), BorderLayout.CENTER);

frame.setSize(300, 150);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Figure 19-3 shows the program in action.




Figure 19-3. *Dragging-and-dropping an image*

Summary

Drag-and-drop support in Swing is rich and varied. You get quite a bit of behavior for free for several of the standard components. If you need more, you can dig down a layer at a time until you expose the features you need.

Typically, you don't need to dig all the way into `java.awt.dnd` classes like `DragSourceDragEvent`, `DragSourceDropEvent`, or `DropTargetDragEvent` (to name a few). They are there and doing their work under the covers, but you don't need to worry about them. Instead, drag-and-drop support is typically delegated to the `TransferHandler` associated with a property of the component to drag. Just `setDragEnabled(true)` on that component, and you're ready to go. You can also set up drag-and-drop support for other items, such as images, by creating an implementation of the `Transferable` interface.

In the next chapter, you'll explore Swing's pluggable look and feel architecture. You'll learn how to customize your user interfaces without changing the code for the program.



The Pluggable Look and Feel Architecture

In Chapter 19, you examined Swing's drag-and-drop support. In this chapter, you will take an in-depth look at the pluggable look and feel (PLAF) architecture that's available when you're working with the Swing component library.

All aspects of the Swing components are Java-based. Therefore, no native source code exists, as there is with the AWT component set. If you don't like the way the components are, you can change them, and you often have many ways to do so.

The abstract `LookAndFeel` class is the root class for a specific look and feel. Each one of the installable look and feel classes, as they're described by the `UIManager.LookAndFeelInfo` class, must be a subclass of the `LookAndFeel` class. The `LookAndFeel` subclass describes the default appearance of Swing components for that specific look and feel.

The set of currently installed look and feel classes is provided by the `UIManager` class, which also manages the default display properties of all the components for a specific `LookAndFeel`. These display properties are managed within a special `UIDefaults` hash table. The display properties are either tagged with the empty `UIResource` interface or are UI delegates and therefore a subclass of the `ComponentUI` class. These properties can be stored as either `UIDefaults.LazyValue` objects or `UIDefaults.ActiveValue` objects, depending on their usage.

LookAndFeel Class

Implementations of the abstract `LookAndFeel` class describe how each of the Swing components will appear and how the user will interact with them. Each component's appearance is controlled by a UI delegate, which serves as both the view and the controller in the MVC architecture. Each of the predefined look and feel classes is contained within its own package, along with its associated UI delegate classes. When configuring the current look and feel, you can use one of the predefined look and feel classes or create your own. When you create your own look and feel, you can build on an existing look and feel, such as the `BasicLookAndFeel` class and its UI delegates, instead of creating all the UI delegates from scratch. Figure 20-1 shows the class hierarchy of the predefined look and feel classes.



Figure 20-1. *LookAndFeel class hierarchy diagram*

Each of the look and feel classes has six properties, as shown in Table 20-1.

Table 20-1. *LookAndFeel Properties*

Property Name	Data Type	Access
defaults	UIDefaults	Read-only
description	String	Read-only
ID	String	Read-only
name	String	Read-only
nativeLookAndFeel	boolean	Read-only
supportedLookAndFeel	boolean	Read-only

These properties are all read-only and mostly describe the look and feel. The defaults property is slightly different, though. Once you get its `UIDefaults` value, you can then modify its state directly through its own methods. In addition, the `UIDefaults` for a `LookAndFeel` can be directly accessed and modified through the `UIManager` class.

The `nativeLookAndFeel` property enables you to determine if a particular look and feel implementation is the native look and feel for the user's operating system. For instance, the `WindowsLookAndFeel` is native to any system running one of the Microsoft Windows operating systems. The `supportedLookAndFeel` property tells you if a particular look and feel implementation can be used. With the `WindowsLookAndFeel` implementation, this particular look and feel class is supported only if the current operating system is Microsoft Windows. Where available, the `MacLookAndFeel` implementation is supported only on MacOS computers. `MotifLookAndFeel` and `MetalLookAndFeel` are native look and feel classes that are not locked to a particular operating system.

Listing the Installed Look and Feel Classes

To discover which look and feel classes are installed in your current environment, ask the `UIManager`, as shown in Listing 20-1. The `UIManager` has a `UIManager.LookAndFeelInfo[]` `getInstalledLookAndFeels()` method that returns an array of objects providing the textual name (`public String getName()`) and class name (`public String getClassName()`) for all the installed look and feel classes.

Listing 20-1. *Listing Looking and Feel Classes*

```
import javax.swing.*;

public class ListPlafs {
    public static void main (String args[]) {
        UIManager.LookAndFeelInfo plaf[] = UIManager.getInstalledLookAndFeels();
        for (int i=0, n=plaf.length; i<n; i++) {
            System.out.println("Name: " + plaf[i].getName());
            System.out.println("  Class name: " + plaf[i].getClassName());
        }
    }
}
```

Running the program might generate the following output. Your current system configuration and/or changes to future versions of the Swing libraries could alter this result somewhat.

```
Name: Metal
  Class name: javax.swing.plaf.metal.MetalLookAndFeel
Name: CDE/Motif
  Class name: com.sun.java.swing.plaf.motif.MotifLookAndFeel
Name: Windows
  Class name: com.sun.java.swing.plaf.windows.WindowsLookAndFeel
```

Note Ocean is not a look and feel in and of itself. Instead, it is a built-in theme of the Metal look and feel. This theme happens to be the default for Metal.

Changing the Current Look and Feel

Once you know which look and feel classes are available on your system, you can have your programs use any one of them. The `UIManager` has two overloaded `setLookAndFeel()` methods for changing the installed look and feel class:

```
public static void setLookAndFeel(LookAndFeel newValue) throws
    UnsupportedLookAndFeelException

public static void setLookAndFeel(String className) throws
    ClassNotFoundException, InstantiationException, IllegalAccessException,
    UnsupportedLookAndFeelException
```

Although the first version might seem to be the more logical choice, the second one is the more frequently used version. When you ask for the installed look and feel classes with `UIManager.getInstalledLookAndFeels()`, you get back the class names as strings of the objects, not instances. Because of the exceptions that can occur when changing the look and feel, you need to place the `setLookAndFeel()` call within a try/catch block. If you're changing the look and feel for an existing window, you need to tell the component to update its appearance with

a call to the public static void `updateComponentTreeUI(Component rootComponent)` method of `SwingUtilities`. If the component hasn't been created yet, this isn't necessary.

The following source fragment demonstrates changing a look and feel:

```
try {
    UIManager.setLookAndFeel(finalLafClassName);
    SwingUtilities.updateComponentTreeUI(frame);
} catch (Exception exception) {
    JOptionPane.showMessageDialog (
        frame, "Can't change look and feel",
        "Invalid PLAF", JOptionPane.ERROR_MESSAGE);
}
```

Figure 20-2 illustrates the results of a demonstration program that can change the look and feel at runtime through either a `JComboBox` or `JButton` component. Frequently, you won't want to allow a user to change the look and feel; you may just want to set the look and feel at startup time.



Figure 20-2. Before and after changing the look and feel

Listing 20-2 shows the complete source of the program shown in Figure 20-2.

Listing 20-2. *Changing the Look and Feel*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import javax.swing.plaf.*;

public class ChangeLook {

    public static void main (String args[]) {
        Runnable runner = new Runnable() {
            public void run() {

                final JFrame frame = new JFrame("Change Look");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
```

```

ActionListener actionListener = new ActionListener() {
    public void actionPerformed(ActionEvent actionEvent) {
        Object source = actionEvent.getSource();
        String lafClassName = null;
        if (source instanceof JComboBox) {
            JComboBox comboBox = (JComboBox)source;
            lafClassName = (String)comboBox.getSelectedItem();
        } else if (source instanceof JButton) {
            lafClassName = actionEvent.getActionCommand();
        }
        if (lafClassName != null) {
            final String finalLafClassName = lafClassName;
            Runnable runnable = new Runnable() {
                public void run() {
                    try {
                        UIManager.setLookAndFeel(finalLafClassName);
                        SwingUtilities.updateComponentTreeUI(frame);
                    } catch (Exception exception) {
                        JOptionPane.showMessageDialog (
                            frame, "Can't change look and feel",
                            "Invalid PLAF", JOptionPane.ERROR_MESSAGE);
                    }
                }
            };
            EventQueue.invokeLater(runnable);
        }
    }
};

UIManager.LookAndFeelInfo looks[] =
    UIManager.getInstalledLookAndFeels();

DefaultComboBoxModel model = new DefaultComboBoxModel();
JComboBox comboBox = new JComboBox(model);

JPanel panel = new JPanel();

for (int i=0, n=looks.length; i<n; i++) {
    JButton button = new JButton(looks[i].getName());
    model.addElement(looks[i].getClassName());
    button.setActionCommand(looks[i].getClassName());
    button.addActionListener(actionListener);
    panel.add(button);
}

comboBox.addActionListener(actionListener);

```

```
        frame.add(comboBox, BorderLayout.NORTH);
        frame.add(panel, BorderLayout.SOUTH);
        frame.setSize(350, 150);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}
```

Note Notice that the actual look and feel change is made in a call to `EventQueue.invokeLater()`. This is necessary because the handling of the current event must finish before you can change the look and feel, and the change must happen on the event queue.

Besides programmatically changing the current look and feel, you can start up a program from the command line with a new look and feel. Just set the `swing.defaultlaf` system property to the look and feel class name. For instance, the following startup line would start the `ChangeLook` program, making the Motif look and feel the initial look and feel.

```
java -Dswing.defaultlaf=com.sun.java.swing.plaf.motif.MotifLookAndFeel ChangeLook
```

If you want a different default look and feel every time a program starts up, you can create a file, `swing.properties`, under the Java runtime directory (`jre` by default) with the appropriate setting. The `swing.properties` file needs to be in the `lib` directory of the Java runtime directory (`jre/lib`). For instance, the following line would cause the initial look and feel to be Motif all the time, unless changed programmatically or from the command line.

```
swing.defaultlaf=com.sun.java.swing.plaf.motif.MotifLookAndFeel
```

In addition to the `swing.defaultlaf` setting, the `swing.properties` file supports several other entries, as listed in Table 20-2. Each property allows you to override the default settings for the predefined look and feel setup. The auxiliary and multiplexing look and feel classes support accessibility, among other things. They will be discussed later in this chapter, in the “Using an Auxiliary Look and Feel” section.

Table 20-2. *Swing Properties File Entries*

Property Name	Default Value When Unset
<code>swing.defaultlaf</code>	<code>javax.swing.plaf.metal.MetalLookAndFeel</code>
<code>swing.auxiliarylaf</code>	None
<code>swing.plaf.multiplexinglaf</code>	<code>javax.swing.plaf.multi.MultiLookAndFeel</code>
<code>swing.installedlaf</code>	Metal, Motif, Windows
<code>swing.installedlaf.*.name</code>	N/A
<code>swing.installedlaf.*.class</code>	N/A

■ **Tip** The `swing.installedlaf` and `swing.auxiliarylaf` property settings are comma-separated lists of installed look and feel classes.

You may notice that the Synth class shown in the class hierarchy in Figure 20-1 is not listed in the default set of installed look and feel classes. Synth requires a secondary configuration file; it isn't something you can just switch to on the fly without defining the custom appearances. This base look and feel class provides the framework for customization. You'll learn how to use the Synth look and feel in the "SynthLookAndFeel Class" section later in this chapter.

The `WindowsClassicLookAndFeel` is used when the Windows XP style is not appropriate for the user's platform or the `swing.noop` system property is set.

Customizing the Current Look and Feel

In Chapter 3, you looked at the MVC architecture as well as how the Swing components combine the view and the controller into a UI delegate. Now, you will delve into the UI delegate for the Swing components. Basically, if you don't like how a Swing component looks, you tell the `UIManager` to change it, and then it will never again look the way it did.

UIManager Class

Whenever you need to create a Swing component, the `UIManager` class acts as a proxy to get information about the currently installed look and feel. That way, if you want to install a new look and feel or change an existing one, you don't need to tell the Swing components directly; you just inform the `UIManager`.

Each discussion of components in earlier chapters has been accompanied by a table of all the settings that can be changed through the `UIManager`. In addition, this book's appendix provides an alphabetical listing of all available settings for JDK 5.0. Once you know the property string for the setting you want to change, you call the public `Object UIManager.put(Object key, Object value)` method, which changes the property setting and returns the previous setting (if one existed). For instance, the following line changes the background to red for `JButton` components. After you put a new setting into the `UIManager` class lookup table, any components created in the future will use the new value, `Color.RED`.

```
UIManager.put("Button.background", Color.RED);
```

Once you place new settings into the lookup table for the `UIManager`, the new settings will be used when you create a new Swing component. Old components aren't automatically updated; you must call their public `void updateUI()` method if you want them to be individually updated (or call `updateComponentTreeUI()` to update a whole window of components). If you're creating your own components, or you're just curious about the current setting for one of the different component properties, you can ask the `UIManager` with one of the methods listed in Table 20-3.

Table 20-3. *UIManager UIDefaults Getter Methods*

Method Name	Return Type
getObject(Object key)	Object
getBorder(Object key)	Border
getColor(Object key)	Color
getDimension(Object key)	Dimension
getFont(Object key)	Font
getIcon(Object key)	Icon
getInsets(Object key)	Insets
getInt(Object key)	int
getString(Object key)	String
getUI(JComponent component)	ComponentUI

Each of these methods, except `getUI()`, has a second version that accepts a `Locale` argument for localization support.

In addition to the defaults property, which is used when you call the different `put()` and `get()` methods, the `UIManager` has eight class-level properties. These are listed in Table 20-4, which includes two entries for `lookAndFeel`, with two different setter methods.

Table 20-4. *UIManager Class Properties*

Property Name	Data Type	Access
<code>auxiliaryLookAndFeel</code>	<code>LookAndFeel[]</code>	Read-only
<code>crossPlatformLookAndFeelClassName</code>	<code>String</code>	Read-only
<code>defaults</code>	<code>UIDefaults</code>	Read-only
<code>installedLookAndFeel</code>	<code>UIManager.LookAndFeelInfo[]</code>	Read-write
<code>lookAndFeel</code>	<code>LookAndFeel</code>	Read-write
<code>lookAndFeel</code>	<code>String</code>	Write-only
<code>lookAndFeelDefaults</code>	<code>UIDefaults</code>	Read-only
<code>propertyChangeListeners</code>	<code>PropertyChangeListener[]</code>	Read-only
<code>systemLookAndFeelClassName</code>	<code>String</code>	Read-only

The `systemLookAndFeelClassName` property allows you to determine what the specific look and feel class name is for the user's operating system. The `crossPlatformLookAndFeelClassName` property enables you to find out what class name, by default, represents the cross-platform look and feel: `javax.swing.plaf.metal.MetalLookAndFeel`. Initially, the `lookAndFeelDefaults` property and

the defaults property are equivalent. When you want to make changes to the look and feel, you use the defaults property. That way, the settings for a predefined look and feel don't change.

UIManager.LookAndFeelInfo Class

When you ask the UIManager for the list of installed look and feel classes, you're returned an array of UIManager.LookAndFeelInfo objects. From this array, you can find out the descriptive name of the look and feel (from the name property of the LookAndFeel implementation), as well as the class name for the implementation. As Table 20-5 shows, the two settings are read-only.

Table 20-5. *UIManager.LookAndFeelInfo Properties*

Property Name	Data Type	Access
className	String	Read-only
name	String	Read-only

UIDefaults Class

The LookAndFeel classes and the UIManager use a special UIDefaults hash table to manage the Swing component properties that depend on the look and feel. The special behavior is that whenever a new setting is placed in the hash table with put(), a PropertyChangeEvent is generated and any registered PropertyChangeListener objects are notified. Many of the BasicLookAndFeel classes automatically register the UI delegate to be interested in property change events at the appropriate times.

If you need to change a number of properties at once, you can use the public void putDefaults(Object keyValuePair[]) method, which causes only one notification event. With putDefaults(), the key/value entries alternate in a single-dimension array. For instance, to cause buttons to have a default background color of pink and a foreground color of magenta, you would use the following:

```
Object newSettings[] = {"Button.background", Color.PINK,  
                        "Button.foreground", Color.MAGENTA};  
UIDefaults defaults = UIManager.getDefaults();  
defaults.putDefaults(newSettings);
```

Because UIDefaults is a Hashtable subclass, you can discover all the installed settings by using an Enumeration to loop through all the keys or values. To simplify things a little, Listing 20-3 presents a program that lists the properties sorted within a JTable. It reuses several of the table sorting classes from Chapter 18.

Note Feel free to change the UIDefaults property lister program in Listing 20-3 to support modification of property values.

Listing 20-3. *Listing UIDefault Properties*

```
import javax.swing.*;
import javax.swing.table.*;
import java.awt.*;
import java.awt.event.*;
import java.util.*;

public class ListProperties {
    static class CustomTableModel extends AbstractTableModel {
        Vector<Object> keys = new Vector<Object>();
        Vector<Object> values = new Vector<Object>();
        private static final String columnNames[] = {"Property String", "Value"};

        public int getColumnCount() {
            return columnNames.length;
        }

        public String getColumnName(int column) {
            return columnNames[column];
        }

        public int getRowCount() {
            return keys.size();
        }

        public Object getValueAt(int row, int column) {
            Object returnValue = null;
            if (column == 0) {
                returnValue = keys.elementAt(row);
            } else if (column == 1) {
                returnValue = values.elementAt(row);
            }
            return returnValue;
        }

        public synchronized void uiDefaultsUpdate(UIDefaults defaults) {
            Enumeration newKeys = defaults.keys();
            keys.removeAllElements();
            while (newKeys.hasMoreElements()) {
                keys.addElement(newKeys.nextElement());
            }
        }
    }
}
```

```

Enumeration newValues = defaults.elements();
values.removeAllElements();
while (newValues.hasMoreElements()) {
    values.addElement(newValues.nextElement());
}

fireTableDataChanged();
}
}

public static void main(String args[]) {
    Runnable runner = new Runnable() {
        public void run() {
            final JFrame frame = new JFrame("List Properties");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

            final CustomTableModel model = new CustomTableModel();
            model.uiDefaultsUpdate(UIManager.getDefaults());
            TableSorter sorter = new TableSorter(model);

            JTable table = new JTable(sorter);
            TableHeaderSorter.install(sorter, table);

            table.setAutoResizeMode(JTable.AUTO_RESIZE_ALL_COLUMNS);

            UIManager.LookAndFeelInfo looks[] =
                UIManager.getInstalledLookAndFeels();

            ActionListener actionListener = new ActionListener() {
                public void actionPerformed(ActionEvent actionEvent) {
                    final String lafClassName = actionEvent.getActionCommand();
                    Runnable runnable = new Runnable() {
                        public void run() {
                            try {
                                UIManager.setLookAndFeel(lafClassName);
                                SwingUtilities.updateComponentTreeUI(frame);
                                model.uiDefaultsUpdate(UIManager.getDefaults());
                            } catch (Exception exception) {
                                JOptionPane.showMessageDialog (
                                    frame, "Can't change look and feel",
                                    "Invalid PLAF", JOptionPane.ERROR_MESSAGE);
                            }
                        }
                    };
                    EventQueue.invokeLater(runnable);
                }
            };
        }
    };
}

```

```

JToolBar toolbar = new JToolBar();
for (int i=0, n=looks.length; i<n; i++) {
    JButton button = new JButton(looks[i].getName());
    button.setActionCommand(looks[i].getClassName());
    button.addActionListener(actionListener);
    toolbar.add(button);
}

frame.add(toolbar, BorderLayout.NORTH);
JScrollPane scrollPane = new JScrollPane(table);
frame.add(scrollPane, BorderLayout.CENTER);
frame.setSize(400, 400);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Figure 20-3 shows an example of running the property lister.




Figure 20-3. Sample property lister display

Tip To reset a property to the default for the currently installed look and feel, set it to `null`. This will cause the component to get the original default from the look and feel.

UIResource Interface

Every `UIDefaults` setting for the predefined look and feel classes uses a special marker interface, `UIResource`, that lets the UI delegate determine if a default value has been overridden. If you've changed a specific setting to a new value (for example, the `Button.background` setting to `Color.PINK`), then the `UIManager` won't replace this setting when the installed look and feel changes. This is also true of a call to `setBackground(Color.PINK)`. Only when the value for a specific property implements the `UIResource` interface will the setting change when the look and feel changes.

The `javax.swing.plaf` package contains many classes that implement the `UIResource` interface. For example, the `ColorUIResource` class treats `Color` objects as `UIResource` elements. Table 20-6 lists all of the predefined `UIResource` components available for customizing the installed look and feel.

Table 20-6. *UIResource Collection*

UIResource Implementation	Wrapped Class/Interface
<code>ActionMapUIResource</code>	<code>ActionMap</code>
<code>BasicBorders.ButtonBorder</code>	<code>Border</code>
<code>BasicBorders.FieldBorder</code>	<code>Border</code>
<code>BasicBorders.MarginBorder</code>	<code>Border</code>
<code>BasicBorders.MenuBarBorder</code>	<code>Border</code>
<code>BasicBorders.RadioButtonBorder</code>	<code>Border</code>
<code>BasicBorders.RolloverButtonBorder</code>	<code>Border</code>
<code>BasicBorders.SplitPaneBorder</code>	<code>Border</code>
<code>BasicBorders.ToggleButtonBorder</code>	<code>Border</code>
<code>BasicComboBoxEditor.UIResource</code>	<code>ComboBoxEditor</code>
<code>BasicComboBoxRenderer.UIResource</code>	<code>ListCellRenderer</code>
<code>BasicTextUI.BasicCaret</code>	<code>Caret</code>
<code>BasicTextUI.BasicHighlighter</code>	<code>Highlighter</code>
<code>BorderUIResource</code>	<code>Border</code>
<code>BorderUIResource.BevelBorderUIResource</code>	<code>Border</code>
<code>BorderUIResource.CompoundBorderUIResource</code>	<code>Border</code>
<code>BorderUIResource.EmptyBorderUIResource</code>	<code>Border</code>
<code>BorderUIResource.EtchedBorderUIResource</code>	<code>Border</code>
<code>BorderUIResource.LineBorderUIResource</code>	<code>Border</code>
<code>BorderUIResource.MatteBorderUIResource</code>	<code>Border</code>
<code>BorderUIResource.TitledBorderUIResource</code>	<code>Border</code>
<code>ColorUIResource</code>	<code>Color</code>

Table 20-6. *UIResource Collection (Continued)*

UIResource Implementation	Wrapped Class/Interface
ComponentInputMapUIResource	InputMap / ComponentInputMap
DefaultListCellRendererer.UIResource	ListCellRenderer
DefaultMenuLayout	LayoutManager / LayoutManager2
DefaultTableCellRendererer.UIResource	TableCellRenderer
DimensionUIResource	Dimension
FontUIResource	Font
IconUIResource	Icon
InputMapUIResource	InputMap
InsetsUIResource	Insets
JScrollPane.ScrollBar	JScrollBar
MetalBorders.ButtonBorder	Border
MetalBorders.Flush3DBorder	Border
MetalBorders.InternalFrameBorder	Border
MetalBorders.MenuBarBorder	Border
MetalBorders.MenuItemBorder	Border
MetalBorders.OptionDialogBorder	Border
MetalBorders.PaletteBorder	Border
MetalBorders.PopupMenuBorder	Border
MetalBorders.RolloverButtonBorder	Border
MetalBorders.ScrollPaneBorder	Border
MetalBorders.TextFieldBorder	Border
MetalBorders.ToggleButtonBorder	Border
MetalBorders.ToolBarBorder	Border
MetalCheckBoxIcon	Icon
MetalComboBoxEditor.UIResource	ComboBoxEditor
MetalIconFactory.PaletteCloseIcon	Icon
ScrollPaneLayout.UIResource	ScrollPaneLayout

The following code demonstrates the use of the `ColorUIResource` class to set the button background to a value that *will* change when the installed look and feel changes.

```
Color background = new ColorUIResource(Color.PINK);
UIManager.put("Button.background", background);
```

Without the wrapped `ColorUIResource` constructor call, the color would remain pink after a look and feel change.

Note Use of the specific `UIResource` implementation classes tends to be limited to those times when you're creating a custom look and feel or customizing an existing one.

UIDefaults.ActiveValue, UIDefaults.LazyValue, and UIDefaults.ProxyLazyValue Classes

Besides implementing the `UIResource` interface, elements in the `UIDefaults` lookup table can be lazy or active if they implement one of the inner classes of `UIDefaults`: `LazyValue` or `ActiveValue`. For example, since `Color` and `Dimension` objects aren't very resource-intensive, when such an element is placed in the `UIDefaults` table, the `Color` or `Dimension` is created and placed in the table immediately—this is called *active*. On the other hand, in the case of a resource like an `Icon`, and especially an `ImageIcon`, you want to defer creating and loading the icon class file until it's needed—this is called *lazy*. Another example of an element you might want to make lazy is a `ListCellRenderer` that needs a separate renderer for every `JList` component. Because you don't know how many renderers you'll need or which renderer will be installed, you can defer creation to a later time and get a unique version of the current renderer whenever you ask for one.

Take a look at the public `Object makeIcon(Class baseClass, String imageFile)` method of `LookAndFeel`. In order to handle the late loading of icon image files, the `LookAndFeel` class can automatically create a `LazyValue` class for loading an `Icon`. Because the image file won't be loaded until later, you need to provide the icon loader with the location of the icon image file (`baseClass`) and the file name (`imageFile`).

```
Object iconObject = LookAndFeel.makeIcon(this.getClass(), "World.gif");
UIManager.put("Tree.leafIcon", iconObject);
```

Next, look at the `UIDefaults.LazyValue` definition and create a lazy version of the `DiamondIcon`.

```
public interface UIDefaults.LazyValue {
    public Object createValue(UIDefaults table);
}
```

In classes that implement the `LazyValue` interface, their constructors need to save any information that will be passed along to the real constructor through the `createValue()` interface method. To help with creating custom lazy values, the `UIDefaults.ProxyLazyValue` class provides a way of saving this information to pass along. There are four ways to use `ProxyLazyValue` to defer object creation, which each uses reflection to create the actual object, getting the specific how (and what) from the constructor arguments:

- `public UIDefaults.ProxyLazyValue(String className)`: If object creation will use the no-argument constructor, just pass the class name as an argument.
- `public UIDefaults.ProxyLazyValue(String className, String method)`: If object creation will use a factory method that doesn't require arguments, pass the factory method along with the class name.

- `public UIDefaults.ProxyLazyValue(String className, Object[] arguments)`: If object creation will use a constructor that requires some arguments, pass the class name and array of arguments to the `ProxyLazyValue` constructor.
- `public UIDefaults.ProxyLazyValue(String className, String method, Object[] arguments)`: If object creation will use a factory method that does require arguments, pass the factory method name along with the class name and array of arguments.

For the lazy diamond icon implementation that's about to be created, you'll need to pass state information that consists of the color, selected state, and dimensions.

To test the lazy diamond icon, you can associate an instance of `UIDefaults.ProxyLazyValue` to the `Tree.openIcon` setting, as follows:

```
Integer fifteen = new Integer(15);
Object lazyArgs[] = new Object[] { Color.GREEN, Boolean.TRUE, fifteen, fifteen} ;
Object lazyDiamond = new UIDefaults.ProxyLazyValue("DiamondIcon", lazyArgs);
UIManager.put("Tree.openIcon", lazyDiamond);
```

Together with the previous change of the `Tree.leafIcon` setting to the `World.gif` icon, and using the default tree data model, the tree would look like Figure 20-4.




Figure 20-4. A tree created with lazy values

Listing 20-4 shows the source code for the example that generated Figure 20-4 by using the two lazy values.

Listing 20-4. *Lazy UIResources*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;
import javax.swing.plaf.*;

public class LazySample {
    public static void main (String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Lazy Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
```

```

Object iconObject =
    LookAndFeel.makeIcon(LazySample.class, "World.gif");
UIManager.put("Tree.leafIcon", iconObject);

Integer fifteen = new Integer(15);
Object lazyArgs[] =
    new Object[] {Color.GREEN, Boolean.TRUE, fifteen, fifteen};
Object lazyDiamond =
    new UIDefaults.ProxyLazyValue("DiamondIcon", lazyArgs);
UIManager.put("Tree.openIcon", lazyDiamond);

JTree tree = new JTree();
JScrollPane scrollPane = new JScrollPane(tree);

frame.add(scrollPane, BorderLayout.CENTER);
frame.setSize(200, 200);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

Unlike lazy values, active values act like instance-creation factories. Every time they're asked for a value with one of the `get()` methods of `UIManager`, a new instance is created and returned. The interface method is the same as that for the `UIDefault.LazyValue` interface; only the interface name is different.

```

public interface UIDefaults.ActiveValue {
    public Object createValue(UIDefaults table);
}

```

To demonstrate, Listing 20-5 defines a factory that constructs `JLabel` components. The text of the label will function as a counter to show how many labels have been created. Whenever the `createValue()` method is called, a new `JLabel` is created.

Listing 20-5. *Active Label Factory*

```

import javax.swing.*;

public class ActiveLabel implements UIDefaults.ActiveValue {
    private int counter = 0;

    public Object createValue(UIDefaults defaults) {
        JLabel label = new JLabel(""+counter++);
        return label;
    }
}

```

To create the component, you need to install the `ActiveLabel` class with `UIManager.put()`. Once the class is installed, each call to `get()` the key out of the `UIManager` results in a new component being created.

```
UIManager.put(LABEL_FACTORY, new ActiveLabel());
...
JLabel label = (JLabel)UIManager.get(LABEL_FACTORY);
```

Figure 20-5 shows the component in use. Whenever the button is clicked, the `UIManager.get()` method is called, and the component is added to the screen.




Figure 20-5. *Using active values*

Listing 20-6 shows the source for the sample program in Figure 20-5.

Listing 20-6. *Active UIResources*

```
import java.awt.*;
import java.awt.event.*;
import javax.swing.*;

public class ActiveSample {

    private static final String LABEL_FACTORY = "LabelFactory";

    public static void main (String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Active Example");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                UIManager.put(LABEL_FACTORY, new ActiveLabel());

                final JPanel panel = new JPanel();

                JButton button = new JButton("Get");
```

```

        ActionListener actionListener = new ActionListener() {
            public void actionPerformed(ActionEvent actionEvent) {
                JLabel label = (JLabel)UIManager.get(LABEL_FACTORY);
                panel.add(label);
                panel.revalidate();
            }
        };
        button.addActionListener(actionListener);

        frame.add(panel, BorderLayout.CENTER);
        frame.add(button, BorderLayout.SOUTH);
        frame.setSize(200, 200);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

Note There is a special lazy class for creating an `InputMap` lazily: the `UIDefaults.LazyInputMap` class.

Using Client Properties

If changing all the `UIResource` properties known to the `UIManager` still doesn't give you the look and feel you desire, some of the UI delegate classes can provide their own customized capabilities that are hidden from API views. These customized capabilities are provided as client properties and are accessible from two `JComponent` methods: `public final Object getClientProperty(Object key)` and `public final void putClientProperty(Object key, Object value)`. Keep in mind that the key and value here are of type `Object`. While typically the key will be a `String` and the value an object of any type, the key can also be an object of any type.

Client properties tend to be attributes of the component that are specific to the look and feel. Instead of subclassing the look and feel delegate to expose a property through a pair of getter/setter methods, the `get/put` client property methods provide access to a *private* instance-level lookup table to store a new property setting. In addition, as when making changes to the `UIDefaults`, modifying the client properties of a component notifies any registered property change listeners of the component.

Most of the specific client properties have already been discussed throughout this book with their respective components. Table 20-7 provides a single resource for finding all the configurable client properties. The left column shows the class the property is used in, excluding the package name. The middle column shows the property name, which can include both the raw text string and any class constants that are available. The right column contains the class type to store with the property name. If the class type is a `String`, a list of valid values is provided, if appropriate.

Table 20-7. *Swing's Client Properties*

Class Accessed By	Property Name	Type
AbstractButton	hideActionText	Boolean
AbstractButton	html / BasicHTML.propertyKey	View
BasicButtonListener	initialDefaultButton	JButton
BasicButtonUI	html / BasicHTML.propertyKey	View
BasicComboBoxUI	JComboBox.isTableCellEditor / BasicComboBoxUI.IS_TABLE_CELL_EDITOR	Boolean
BasicEditorPaneUI	JEditorPane.honorDisplayProperties / JEditorPane.HONOR_DISPLAY_PROPERTIES	Boolean
BasicEditorPaneUI	JEditorPane.w3cLengthUnits / JEditorPane.W3C_LENGTH_UNITS	Boolean
BasicHTML	html.base / BasicHTML.documentBaseKey	URL
BasicHTML	html / BasicHTML.propertyKey	View
BasicHTML	html.disable / BasicHTML.htmlDisable	Boolean
BasicLabelUI	html / BasicHTML.propertyKey	View
BasicListUI	List.isFileList	Boolean
BasicMenuItemUI	html / BasicHTML.propertyKey	View
BasicMenuItemUI	maxTextWidth / BasicMenuItemUI.MAX_TEXT_WIDTH	Integer
BasicMenuItemUI	maxAccWidth / BasicMenuItemUI.MAX_ACC_WIDTH	Integer
BasicPopupMenuUI	doNotCancelPopup	Boolean
BasicRadioButtonUI	html / BasicHTML.propertyKey	View
BasicRootPaneUI	temporaryDefaultButton	Object
BasicSliderUI	Slider.paintThumbArrowShape	Boolean
BasicTabbedPaneUI	__index_to_remove__	Integer
BasicTableUI	Table.isFileList	Boolean
BasicTextUI	JPasswordField.cutCopyAllowed	Boolean
BasicToggleButtonUI	html / BasicHTML.propertyKey	View
BasicToolBarUI	JToolBar.focusedCompIndex / BasicToolBarUI. FOCUSED_COMP_INDEX	Integer
BasicToolBarUI	JToolBar.isRollover / BasicToolBarUI. IS_ROLLOVER	Boolean
BasicToolTipUI	html / BasicHTML.propertyKey	View
BluePrintEngine	__arrow_direction__	Integer
DefaultCaret	caretAspectRatio	Number
DefaultCaret	caretWidth	Integer

Table 20-7. *Swing's Client Properties (Continued)*

Class Accessed By	Property Name	Type
DefaultCaret	JPasswordField.cutCopyAllowed	Boolean
DefaultDesktopManager	JDesktopPane.dragMode	String; valid values are null, outline, and faster
FrameView	charset	String
GTKFileChooserUI	GTKFileChooser.showDirectoryIcons	Boolean
GTKFileChooserUI	GTKFileChooser.showFileIcons	Boolean
JInternalFrame	wasIconOnce / DefaultDesktopManager.HAS_BEEN_ICONIFIED_PROPERTY	Boolean
JComponent	nextFocus / JComponent.NEXT_FOCUS	Component
JComponent	InputVerifier / JComponent.INPUT_VERIFIER_KEY	InputVerifier
JComponent	_WhenInFocusedWindow / JComponent.WHEN_IN_FOCUSED_WINDOW_BINDINGS	Hashtable
JComponent	ToolTipText / JComponent.TOOL_TIP_TEXT_KEY	String
JComponent	TransferHandler / JComponent.TRANSFER_HANDLER_KEY	TransferHandler
JComponent	AncestorNotifier / JComponent.ANCESTOR_NOTIFIER_KEY	AncestorNotifier
JComponent	labeledBy / JLabel.LABELED_BY_PROPERTY	JComponent / Accessible
JEditorPane	charset	String
JLabel	html / BasicHTML.propertyKey	View
JLayeredPane	layeredContainerLayer / JLayeredPane.LAYER_PROPERTY	Integer
JPasswordField	JPasswordField.cutCopyAllowed	Boolean
JPopupMenu	JPopupMenu.firePopupMenuCanceled	Boolean
JTable	JTable.autoStartsEdit	Boolean
JTable	terminateEditOnFocusLost	Boolean
JToolBar	JToolBar.isRollover	Boolean
MetalBorders	NoButtonRollover / MetalBorders.NO_BUTTON_ROLLOVER	Boolean
MetalBorders	JInternalFrame.messageType	Integer
MetalFileChooserUI	FileChooser.useShellFolder	Boolean
MetalIconFactory	paintActive	Boolean
MetalInternalFrame TitlePane ➡	JInternalFrame.messageType	Integer

Table 20-7. *Swing's Client Properties (Continued)*

Class Accessed By	Property Name	Type
MetalInternalFrameUI	JInternalFrame.isPalette / MetalInternalFrameUI.IS_PALETTE	Boolean
MetalRadioButtonUI	html / BasicHTML.propertyKey	View
MetalScrollBarUI	JScrollBar.isFreeStanding / MetalScrollBarUI.FREE_STANDING_PROP	Boolean
MetalsliderUI	JSlider.isFilled / MetalsliderUI.SLIDER_FILL	Boolean
MetalTreeUI	JTree.lineStyle / MetalTreeUI.LineStyle	String; valid values are Angled (MetalTreeUI.LEG_LINE_STYLE_STRING), Horizontal (MetalTreeUI.HORIZ_STYLE_STRING), and None (MetalTreeUI.NO_STYLE_STRING)
MotifGraphicsUtils	html / BasicHTML.propertyKey	View
MotifGraphicsUtils	maxAccWidth / MotifGraphicsUtils.MAX_ACC_WIDTH	Integer
PopupFactory	__force_heavy_weight_popup__ / PopupFactory.forceHeavyWeightPopupKey	Boolean
SpringLayout	SpringLayout.class	SpringLayout. Constraints
SwingUtilities	html / BasicHTML.propertyKey	View
SynthEditorPaneUI	JEditorPane.honorDisplayProperties / JEditorPane.HONOR_DISPLAY_PROPERTIES	Boolean
SynthGraphicUtils	html / BasicHTML.propertyKey	View
SynthMenuItemUI	html / BasicHTML.propertyKey	View
SynthToolTipUI	html / BasicHTML.propertyKey	View
WindowsDesktopManager	JInternalFrame.frameType	String; valid values are null and optionDialog
WindowsFileChooserUI	FileChooser.useShellFolder	Boolean
WindowsSliderUI	Slider.paintThumbArrowShape	Boolean
WindowsToolBarUI	XPStyle.subclass	String

Note Many of the properties in Table 20-7 are used internally by the specific component delegate implementations, and you'll never need to use them. Other properties, such as the drag mode for the desktop manager, were interim means to add capabilities while keeping the API unaltered until a new JDK version was released.

To demonstrate the use of client properties, the following two lines change the `JToolBar.isRollover` attribute of a `JToolBar` to `Boolean.TRUE`. Other toolbars might not want this attribute set to `Boolean.TRUE` and would therefore leave that setting at `Boolean.FALSE`.

```
JToolBar toolbar = new JToolBar();
toolbar.putClientProperty("JToolBar.isRollover", Boolean.TRUE);
```

Creating a New UI Delegate

Sometimes, modifying a few of the `UIResource` elements of the Swing component isn't quite enough to get the appearance or behavior you desire. When this is the case, you need to create a new UI delegate for the component. Each Swing component has its own UI delegate for controlling the view and controller aspects of its MVC architecture.

Table 20-8 provides a listing of the Swing components, the abstract class that describes the UI delegate for each component, and the specific implementations for the predefined look and feel classes. For instance, calling the `getUIClassID()` method of a `JToolBar` will return the class ID string of "ToolBarUI" for its UI delegate. If you then ask the `UIManager` for the specific implementation of this UI delegate for the currently installed look and feel with a call to `UIManager.get("ToolBarUI")`, an implementation of the abstract `ToolBarUI` class is returned. Therefore, if you want to develop a custom look and feel for the `JToolBar` component, you must create an implementation of the abstract `ToolBarUI` class.

Table 20-8. *Swing Component Delegates*

Swing Component	Class ID String	Implementation Class
<code>JButton</code>	<code>ButtonUI</code>	<code>ButtonUI</code>
<code>JCheckBox</code>	<code>CheckBoxUI</code>	<code>ButtonUI</code>
<code>JCheckBoxMenuItem</code>	<code>CheckBoxMenuItemUI</code>	<code>MenuItemUI</code>
<code>JColorChooser</code>	<code>ColorChooserUI</code>	<code>ColorChooserUI</code>
<code>JComboBox</code>	<code>ComboBoxUI</code>	<code>ComboBoxUI</code>
<code>JComponent</code>	<code>n/a</code>	<code>ComponentUI</code>
<code>JDesktopPane</code>	<code>DesktopPaneUI</code>	<code>DesktopPaneUI</code>
<code>JEditorPane</code>	<code>EditorPaneUI</code>	<code>TextUI</code>
<code>JFileChooser</code>	<code>FileChooserUI</code>	<code>FileChooserUI</code>
<code>JFormattedTextField</code>	<code>FormattedTextFieldUI</code>	<code>TextUI</code>
<code>JInternalFrame</code>	<code>InternalFrameUI</code>	<code>InternalFrameUI</code>
<code>JInternalFrame.JDesktopIcon</code>	<code>DesktopIconUI</code>	<code>DesktopIconUI</code>
<code>JLabel</code>	<code>LabelUI</code>	<code>LabelUI</code>
<code>JList</code>	<code>ListUI</code>	<code>ListUI</code>
<code>JMenu</code>	<code>MenuUI</code>	<code>MenuItemUI</code>
<code>JMenuBar</code>	<code>MenuBarUI</code>	<code>MenuBarUI</code>

Table 20-8. *Swing Component Delegates (Continued)*

Swing Component	Class ID String	Implementation Class
JMenuItem	MenuItemUI	MenuItemUI
JOptionPane	OptionPaneUI	OptionPaneUI
JPanel	PanelUI	PanelUI
JPasswordField	PasswordFieldUI	TextUI
JPopupMenu	PopupMenuUI	PopupMenuUI
JPopupMenu.Separator	PopupMenuSeparatorUI	SeparatorUI
JProgressBar	ProgressBarUI	ProgressBarUI
JRadioButton	RadioButtonUI	ButtonUI
JRadioButtonMenuItem	RadioButtonMenuItemUI	MenuItemUI
JRootPane	RootPaneUI	RootPaneUI
JScrollBar	ScrollBarUI	ScrollBarUI
JScrollPane	ScrollPaneUI	ScrollPaneUI
JSeparator	SeparatorUI	SeparatorUI
JSlider	SliderUI	SliderUI
JSpinner	SpinnerUI	SpinnerUI
JSplitPane	SplitPaneUI	SplitPaneUI
JTabbedPane	TabbedPaneUI	TabbedPaneUI
JTable	TableUI	TableUI
JTableHeader	TableHeaderUI	TableHeaderUI
JTextArea	TextAreaUI	TextUI
JTextField	TextFieldUI	TextUI
JTextPane	TextPaneUI	TextUI
JToggleButton	ToggleButtonUI	ButtonUI
JToolBar	ToolBarUI	ToolBarUI
JToolBar.Separator	ToolBarSeparatorUI	SeparatorUI
JToolTip	ToolTipUI	ToolTipUI
JTree	TreeUI	TreeUI
JViewport	ViewportUI	ViewportUI

Note Classes such as `JWindow`, `JFrame`, and `JApplet` are heavyweight components and therefore lack a UI delegate.

The `PopupComboSample` example from Chapter 13 demonstrated the creation of a new UI delegate. Listing 20-7 is a slightly changed customized `ComboBoxUI` piece, where the normal down arrow for showing the drop-down menu is replaced with a right arrow.

Listing 20-7. *Customized `ComboBoxUI`*

```
import javax.swing.*;
import javax.swing.plaf.*;
import javax.swing.plaf.basic.*;

public class MyComboBoxUI extends BasicComboBoxUI {
    public static ComponentUI createUI(JComponent c) {
        return new MyComboBoxUI();
    }
    protected JButton createArrowButton() {
        JButton button = new BasicArrowButton(BasicArrowButton.EAST);
        return button;
    }
}
```

To use the new UI delegate, you just need to create the class and associate it with the component using the `setUI()` method.

```
JComboBox comboBox = new JComboBox(labels);
comboBox.setUI((ComboBoxUI)MyComboBoxUI.createUI(comboBox));
```

Changing the `PopupComboSample` from Chapter 13 (Listing 13-16) to show two combo boxes, with the custom `ComboBoxUI` on the top and the bottom without, results in the screen shown in Figure 20-6.




Figure 20-6. *Using the new `ComboBoxUI`*

Listing 20-8 shows the updated source used to produce Figure 20-6.

Listing 20-8. *Using Customized ComboBoxUI*

```
import java.awt.*;
import javax.swing.*;
import javax.swing.plaf.*;

public class PopupComboSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                String labels[] = {"Chardonnay", "Sauvignon", "Riesling", "Cabernet",
                                   "Zinfandel", "Merlot", "Pinot Noir", "Sauvignon Blanc", "Syrah",
                                   "Gewürztraminer"};
                JFrame frame = new JFrame("Popup JComboBox");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JComboBox comboBox = new JComboBox(labels);
                comboBox.setMaximumRowCount(5);
                comboBox.setUI((ComboBoxUI)MyComboBoxUI.createUI(comboBox));
                frame.add(comboBox, BorderLayout.NORTH);

                JComboBox comboBox2 = new JComboBox(labels);
                frame.add(comboBox2, BorderLayout.SOUTH);

                frame.setSize(300, 100);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

If you want to use the new UI delegate for all components, you can let the UIManager know about the delegate before creating the components, instead of manually calling `setUI()` after creating one. In the example in Listing 20-8, you would add the following line:

```
UIManager.put("ComboBoxUI", "MyComboBoxUI")
```

If you did this, both combo boxes would then look the same.

The actual creation of the UI delegate is done somewhat indirectly, as shown by Figure 20-7. A call to the component constructor asks the UIManager for the UI delegate class. The UIManager maintains the list of delegates in its `defaults` property, a `UIDefaults` object. When the `UIDefaults` is queried for the delegate, it goes back to the component to ask which delegate is needed. After it finds the appropriate delegate implementation, the `UIDefaults` object tells the `ComponentUI` to create it, resulting in the actual UI delegate class being created. Once the UI delegate is created, it needs to be configured for the state of the specific model.




Figure 20-7. UI delegate creation sequence diagram

Creating a New Look and Feel

Unless a company wants you to customize everything to provide a unique experience, it typically isn't necessary to create a whole new look and feel from scratch. Usually, developers make minor modifications to an existing look and feel by providing some customized UI delegates. However, if you do want to create a new look and feel class, you just need to create a subclass of the `LookAndFeel` class. You still must provide the UI delegates, but their classes can now be more hidden from the Swing components, since their usage will not be known directly from the `javax.swing` component class.

Using the `WindowsLookAndFeel` on a Non-Windows Machine

To demonstrate the creation of a new look and feel class, let's create a look and feel implementation that cancels out the platform requirement for the `WindowsLookAndFeel`. By simply overriding the public boolean `isSupportedLookAndFeel()` method to return `true`, you effectively remove the platform requirement for the `WindowsLookAndFeel` class.

Note The Java license expressly forbids you from delivering applications that remove the platform requirements for the `WindowsLookAndFeel` class. So, you can work through the example here, as long as you don't deliver it.

The class definition in Listing 20-9 shows how simple the creation of a new look and feel implementation can be.

Listing 20-9. *Custom Look and Feel*

```
import javax.swing.UIManager;
import com.sun.java.swing.plaf.windows.WindowsLookAndFeel;
public class MyWindows extends WindowsLookAndFeel {
    public String getID() {
        return "MyWindows";
    }
    public String getName() {
        return "MyWindows Look and Feel";
    }
    public String getDescription() {
        return "The MyWindows Look and Feel";
    }
    public boolean isNativeLookAndFeel() {
        return false;
    }
    public boolean isSupportedLookAndFeel() {
        return true;
    }
}
```

If you use this Swing class on a non-Windows machine, you can get the look and feel to be the Windows look and feel. Just set your look and feel to be `MyWindows` and make the look and feel class file available. The class file only needs to be available in your `CLASSPATH` and will be started with the following command line:

```
java -Dswing.defaultlaf=MyWindows ClassFile
```

For the Windows look and feel change to work properly, you need to provide the image files used for the icons of the look and feel from within the `icons` subdirectory of the `MyWindows` directory structure. Table 20-9 lists those icons appropriate to the predefined look and feel types. The `MyWindows` look and feel needs all of the Windows image files.

Note Although Ocean is a theme of Metal, it does provide its own set of images.

Table 20-9. *Look and Feel Image Files*

File Name	Basic	Metal	Motif	Ocean	Windows
close-pressed.gif				X	
close.gif				X	
collapsed-rtl.gif				X	
collapsed.gif				X	
computer.gif				X	

Table 20-9. *Look and Feel Image Files (Continued)*

File Name	Basic	Metal	Motif	Ocean	Windows
Computer.gif					X
DesktopIcon.gif			X		
DetailsView.gif					X
directory.gif				X	
Directory.gif					X
Error.gif		X	X		X
error.png				X	
expanded.gif				X	
file.gif				X	
File.gif					X
floppy.gif				X	
FloppyDrive.gif					X
hardDrive.gif				X	
HardDrive.gif					X
homeFolder.gif				X	
HomeFolder.gif					X
iconify-pressed.gif				X	
iconify.gif				X	
info.png				X	
Inform.gif		X	X		X
JavaCup16.png	X				
JavaCup32.png					X
Listview.gif					X
maximize-pressed.gif				X	
maximize.gif				X	
menu.gif				X	
minimize-pressed.gif				X	
minimize.gif				X	
newFolder.gif				X	
NewFolder.gif					X
paletteClose-pressed.gif				X	
paletteClose.gif				X	

Table 20-9. *Look and Feel Image Files (Continued)*

File Name	Basic	Metal	Motif	Ocean	Windows
Question.gif		X	X		X
question.png				X	
ScrollDownArrow.gif			X		
ScrollDownArrowActive.gif			X		
ScrollKnobH.gif			X		
ScrollLeftArrow.gif			X		
ScrollLeftArrowActive.gif			X		
ScrollRightArrow.gif			X		
ScrollRightArrowActive.gif			X		
ScrollUpArrow.gif			X		
ScrollUpArrowActive.gif			X		
StandardBackground.gif			X		X
TrayBottom.gif			X		
TrayLeft.gif			X		
TrayRight.gif			X		
TrayTop.gif			X		
TreeClosed.gif			X		X
TreeCollapsed.gif					
TreeLeaf.gif					X
TreeOpen.gif			X		X
upFolder.gif				X	
UpFolder.gif					X
Warn.gif		X	X		X
warning.png				X	

Note At the very least, images for the JOptionPane message types are needed within every look and feel. Typically, these are named `Error.gif`, `Inform.gif`, `Question.gif`, and `Warn.gif`, though that isn't an absolute requirement.

If you don't want to sidestep the “native” requirement of the Windows look and feel, you can install individual UI delegates, such as the following, which uses the Windows UI delegate for the JButton component:

```
UIManager.put("ButtonUI", "com.sun.java.swing.plaf.windows.WindowsButtonUI").
```

Adding UI Delegates

Creating a new look and feel that has custom UI delegates involves creating a subclass of the LookAndFeel class. More likely, you'll create a subclass of BasicLookAndFeel or another predefined look and feel class, and then provide your custom delegates for some of the components.

If you subclass the BasicLookAndFeel class, it has a protected void initClassDefaults(UIDefaults table) method to be overridden to install your custom UI delegates. Just put the delegates in the UIDefaults table for the look and feel, instead of in your program that wants to use the new delegate.

The extension to the MetalLookAndFeel in Listing 20-10 adds the previously defined MyComboBoxUI delegate (Listing 20-7) as the ComboBoxUI delegate for the look and feel. As you define more customized components, you can add them in a similar way.

Listing 20-10. *MyMetal Look and Feel*

```
import javax.swing.UIManager;
import javax.swing.plaf.metal.MetalLookAndFeel;
public class MyMetal extends MetalLookAndFeel {
    public String getID() {
        return "MyMetal";
    }
    public String getName() {
        return "MyMetal Look and Feel";
    }
    public String getDescription() {
        return "The MyMetal Look and Feel";
    }
    public boolean isNativeLookAndFeel() {
        return false;
    }
    public boolean isSupportedLookAndFeel() {
        return true;
    }
    protected void initClassDefaults(UIDefaults table) {
        super.initClassDefaults(table);
        table.put("ComboBoxUI", "MyComboBoxUI");
    }
}
```

Note When creating your own look and feel, be sure to copy or create icons for the `JOptionPane` pop-up windows. Unless you're customizing Ocean, these icons should be named `Error.gif`, `Inform.gif`, `Question.gif`, and `Warn.gif`, and they belong in the `icons` directory under the directory where the look and feel class file exists.

Working with Metal Themes

The Metal look and feel class (`javax.swing.plaf.metal.MetalLookAndFeel`) provides the means to define *themes* to describe the default settings for the colors, fonts, and all the `UIDefaults` managed by the `UIManager`. By allowing users to change themes, they can get preferred coloration or font sizes with minimal work from the developer. By developing corporate themes, you can easily customize an interface without creating new look and feel classes or manually inserting new settings into current `UIDefaults`.

MetalTheme Class

Table 20-10 lists the 49 different properties that are available through the `MetalTheme` class. The various primary and secondary properties are abstract and must be implemented in a subclass. Of the remaining properties, the six whose names end with `Font`—`controlTextFont`, `menuTextFont`, `subTextFont`, `systemTextFont`, `userTextFont`, and `windowTextFont`—are also abstract and must be implemented by a subclass. The remaining properties, by default, reuse one of the 11 primary/secondary values (or black and white) for their settings.

Table 20-10. *MetalTheme Properties*

Property Name	Data Type	Access
<code>acceleratorForeground</code>	<code>ColorUIResource</code>	Read-only
<code>acceleratorSelectedForeground</code>	<code>ColorUIResource</code>	Read-only
<code>black</code>	<code>ColorUIResource</code>	Read-only
<code>control</code>	<code>ColorUIResource</code>	Read-only
<code>controlDarkShadow</code>	<code>ColorUIResource</code>	Read-only
<code>controlDisabled</code>	<code>ColorUIResource</code>	Read-only
<code>controlHighlight</code>	<code>ColorUIResource</code>	Read-only
<code>controlInfo</code>	<code>ColorUIResource</code>	Read-only
<code>controlShadow</code>	<code>ColorUIResource</code>	Read-only
<code>controlTextColor</code>	<code>ColorUIResource</code>	Read-only
<code>controlTextFont</code>	<code>FontUIResource</code>	Read-only

Table 20-10. *MetalTheme Properties (Continued)*

Property Name	Data Type	Access
desktopColor	ColorUIResource	Read-only
focusColor	ColorUIResource	Read-only
highlightedTextColor	ColorUIResource	Read-only
inactiveControlTextColor	ColorUIResource	Read-only
inactiveSystemTextColor	ColorUIResource	Read-only
menuBackground	ColorUIResource	Read-only
menuDisabledForeground	ColorUIResource	Read-only
menuForeground	ColorUIResource	Read-only
menuSelectedBackground	ColorUIResource	Read-only
menuSelectedForeground	ColorUIResource	Read-only
menuTextFont	FontUIResource	Read-only
name	String	Read-only
primary1	ColorUIResource	Read-only
primary2	ColorUIResource	Read-only
primary3	ColorUIResource	Read-only
primaryControl	ColorUIResource	Read-only
primaryControlDarkShadow	ColorUIResource	Read-only
primaryControlHighlight	ColorUIResource	Read-only
primaryControlInfo	ColorUIResource	Read-only
primaryControlShadow	ColorUIResource	Read-only
secondary1	ColorUIResource	Read-only
secondary2	ColorUIResource	Read-only
secondary3	ColorUIResource	Read-only
separatorBackground	ColorUIResource	Read-only
separatorForeground	ColorUIResource	Read-only
subTextFont	FontUIResource	Read-only
systemTextColor	ColorUIResource	Read-only
systemTextFont	FontUIResource	Read-only
textHighlightColor	ColorUIResource	Read-only
userTextColor	ColorUIResource	Read-only

Table 20-10. *MetalTheme Properties (Continued)*

Property Name	Data Type	Access
userTextFont	FontUIResource	Read-only
white	ColorUIResource	Read-only
windowBackground	ColorUIResource	Read-only
windowTextFont	FontUIResource	Read-only
windowTitleBackground	ColorUIResource	Read-only
windowTitleForeground	ColorUIResource	Read-only
windowTitleInactiveBackground	ColorUIResource	Read-only
windowTitleInactiveForeground	ColorUIResource	Read-only

DefaultMetalTheme and OceanTheme Classes

Contrary to the class name, the `DefaultMetalTheme` class is not the default Metal theme; the default is `OceanTheme`. `DefaultMetalTheme` calls itself the Steel theme and uses a blue and gray color scheme for the primary and secondary settings, respectively. `OceanTheme`, named `Ocean`, uses a light-blue palette with frequent gradient fills for backgrounds.

To use the Steel theme instead of the Ocean theme, you need to set the `swing.metalTheme` system property to `steel`, as shown here:

```
java -Dswing.metalTheme=steel ClassName
```

Most people prefer the newer look of `Ocean`, but `Steel` is still available for backward-compatibility, as `Ocean` is new to 5.0.

If you create your own Metal theme, you need to subclass either `OceanTheme` or `DefaultMetalTheme`, and then install the custom theme by setting the static `currentTheme` property of the `MetalLookAndFeel` class to your theme.

```
MetalTheme myTheme = new MyTheme();
MetalLookAndFeel.setCurrentTheme(myTheme);
```

Whereas most of the customizations of a `MetalTheme` are related to fonts and colors, the `public void addCustomEntriesToTable(UIDefaults table)` method allows you to override the default `UIDefaults` settings for the Metal look and feel. Therefore, not only do themes customize the fonts and colors of the Swing components, but they also can customize any one of the many `UIResource`-related properties of the Swing components.

The following code demonstrates how to set two of the scrollbar settings for a specific theme. Remember to tag these settings with the `UIResource` interface when appropriate, and don't forget to initialize the table argument by your superclass implementation (eventually, this would be `MetalTheme`).

```

public void addCustomEntriesToTable(UIDefaults table) {
    super.addCustomEntriesToTable(table);

    ColorUIResource thumbColor = new ColorUIResource(Color.MAGENTA);
    table.put("Scrollbar.thumb", thumbColor);
    table.put("ScrollBar.width", new Integer(25));
}

```

The Metalworks system demo provided with the JDK installation (jdk1.5.0\demo\jfc\Metalworks) comes with examples for customizing themes. One of the themes it defines reads the theme color settings from a property file. Instead of needing to create a new class file every time you want to change the theme of your Swing application, you can read it from a file at runtime.

```

name=Charcoal
primary1=33,66,66
primary2=66,99,99
primary3=99,99,99
secondary1=0,0,0
secondary2=51,51,51
secondary3=102,102,102
black=255,255,255
white=0,0,0

```

Figure 20-8 shows the Charcoal theme just described used within the Metalworks demonstration program. Figure 20-9 shows the Presentation theme it defines.




Figure 20-8. *Charcoal theme within the Metalworks demonstration program*




Figure 20-9. Presentation theme within the Metalworks demonstration program

Using an Auxiliary Look and Feel

Swing provides for multiple look and feel classes to be active at any one time through the `MultiLookAndFeel`, or as specified by the `swing.plaf.multiplexinglaf` property in the `swing.properties` file. When multiple look and feel classes are installed, only one look and feel will be visual and paint the screen. The remaining versions are called *auxiliary* look and feel classes and tend to be associated with accessibility options, such as for screen readers. Another possible auxiliary look and feel is that of a logger, which records those components that are interacted with in a log file.

Auxiliary look and feel classes are registered with the runtime environment by configuring the `swing.auxiliarylaf` property within the `swing.properties` file. If multiple classes are specified, the entries need to be separated by commas. In addition to using the properties file, you can install a look and feel within a program by calling the public static void `addAuxiliaryLookAndFeel(LookAndFeel lookAndFeel)` method of `UIManager`. Once installed, the multiplexing look and feel class automatically creates and manages UI delegates for all the installed look and feel classes.

To find out which auxiliary look and feel classes are installed, you can ask the `UIManager` through its public static `LookAndFeel[] getAuxiliaryLookAndFeels()` method. This returns an array of the actual `LookAndFeel` objects, unlike the `UIManager.LookAndFeelInfo` array returned by the `getInstalledLookAndFeels()` method.

Note Nothing stops multiple look and feel classes from rendering to the screen for the same component. It's the responsibility of the auxiliary look and feel creator to take care not to compete with the primary look and feel when rendering to the screen.

SynthLookAndFeel Class

The Synth look and feel is a full-fledged look and feel, not just a themed extension to Metal, Windows, or Motif. Instead of working with a `UIResource` table though, the class starts with a blank canvas and gets its entire definition from a single XML file.

Configuring Synth

The configuration of the Synth look and feel might go something like this:

```
SynthLookAndFeel synth = new SynthLookAndFeel();
Class aClass = SynthSample.class;
InputStream is = aClass.getResourceAsStream("config.xml");
synth.load(is, aClass);
UIManager.setLookAndFeel(synth);
```

And what exactly goes into the configuration file, `config.xml` here? In your configuration file, you specify how you want the specific components used in your program to appear. This is commonly called *skinning your application*, or creating a custom skin. By simply modifying an XML file, the entire appearance of your program changes; no programming is required.

The DTD is available from <http://java.sun.com/j2se/1.5.0/docs/api/javaw/swing/plaf/synth/doc-files/synth.dtd>. The file format is fully described in <http://java.sun.com/j2se/1.5.0/docs/api/javaw/swing/plaf/synth/doc-files/synthFileFormat.html>. The parser does not validate, so until tools are available to help automate the process, you'll need to use care in creating the XML file.

There are many configuration options available with Synth, but the basic XML concept is to define a style and bind it to a component. The `<style>` tag allows you to customize properties like the font, colors, insets, and background or border image.

To demonstrate, Listing 20-11 defines a custom style named `button`. Normally, the text will appear in bold 24-point, Monospaced font. When the mouse moves over the associated control, the font changes to a 48-point italic SansSerif font, and the background color changes to blue. When the component is pressed, the font changes again, this time to a 36-point bold-italic Serif font, and the background becomes red. The final part of the configuration file associates the style named `button` with the `JButton` control, via the `<bind>` tag.

Listing 20-11. *Synth Configuration*

```
<synth>
  <style id="button">
    <font name="Monospaced" size="24" style="BOLD"/>
    <state value="MOUSE_OVER">
      <font name="SansSerif" size="48" style="ITALIC"/>
      <opaque value="TRUE"/>
      <color value="BLUE" type="BACKGROUND"/>
    </state>
    <state value="PRESSED">
      <font name="Serif" size="36" style="BOLD AND ITALIC"/>
      <opaque value="TRUE"/>
      <color value="RED" type="BACKGROUND"/>
    </state>
  </style>
  <bind style="button" type="region" key="Button"/>
</synth>
```

Figure 20-10 shows what the component might look like on the screen by itself.




Figure 20-10. *Synth sample button screens*

Listing 20-12 contains the complete sample code used to generate Figure 20-10.

Listing 20-12. *Synth Sample*

```
import java.awt.*;
import java.io.*;
import java.text.*;
import javax.swing.*;
import javax.swing.plaf.synth.*;

public class SynthSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                SynthLookAndFeel synth = new SynthLookAndFeel();
                try {
                    Class aClass = SynthSample.class;
                    InputStream is = aClass.getResourceAsStream("config.xml");
                    if (is == null) {
                        System.err.println("Unable to find theme configuration");
                        System.exit(-1);
                    }
                    synth.load(is, aClass);
                } catch (ParseException e) {
                    System.err.println("Unable to load theme configuration");
                    System.exit(-2);
                }
                try {
                    UIManager.setLookAndFeel(synth);
                } catch (javax.swing.UnsupportedLookAndFeelException e) {
                    System.err.println("Unable to change look and feel");
                    System.exit(-3);
                }
                JFrame frame = new JFrame("Synth Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                JButton button = new JButton("Hello, Synth");
                frame.add(button, BorderLayout.CENTER);
                frame.setSize(300, 200);
                frame.setVisible(true);
            }
        };
        EventQueue.invokeLater(runner);
    }
}
```

Default Synth Properties

The configuration file isn't limited to just styles and bindings. In fact, if you truly do want to set a `UIResource` property, you still can, but only a limited subset is available. The file located at <http://java.sun.com/j2se/1.5.0/docs/api/javawx/swing/plaf/synth/doc-files/componentProperties.html> specifies the full set. It is much smaller than the list you'll find in this book's appendix. These settings are configured with either a `<property>` tag or a `<defaultProperty>` tag. Defaults end up in the `UIDefaults` table for the look and feel; properties are just that—settings for the specific control. Tags similar to the following would be placed within a specific `<style>` tag to be configured:

```
<property key="ScrollPane.viewportBorderInsets" type="insets" value="5 5 5 5"/>
```

or

```
<object class="javax.swing.plaf.ColorUIResource" id="color">
  <int>255</int>
  <int>0</int>
  <int>0</int>
</object>
<defaultsProperty key="Table.focusCellForeground" type="idref" value="color"/>
```

Working with Synth Images

Indirectly, using the `SynthPainter` class, you can provide images that can be used for borders around components. However, the image must be specially created, as the painter doesn't just draw the image. That one image must be used for components of all sizes, of that type, such as for all text fields. The painter shares the image across different-sized controls by breaking the component into multiple regions. The four corners are always drawn as is. The middle regions are stretched vertically and horizontally.

Figure 20-11 shows a possible border image to use. Notice how there are curves around the corners, but the middle areas don't have curves. The curves stay fixed when the border is stretched.




Figure 20-11. *Text component border*

To use the image in Figure 20-11 within your configuration file, you need to use the `<imagePainter>` tag and specify an appropriate method attribute. These map directly to the `paintXXX(SynthContext context, Graphics g, int x, int y, int w, int h, int orientation)` methods of the `SynthPainter` class. Since this image will be used for painting the text field border, the method attribute should be set to `textFieldBorder`. You also need to specify the path to the image (its file name and path relative to the location specified as the second argument to the `SynthLookAndFeel.load()` method). Insets and colors are the other items you need to specify. Here's the full style definition for just such a usage.

```

<style id="textfield">
  <opaque value="true"/>
  <state>
    <color value="#C2E2CF" type="BACKGROUND"/>
    <color value="#000000" type="TEXT_FOREGROUND"/>
  </state>
  <imagePainter method="textFieldBorder" path="text.png"
    sourceInsets="3 3 3 3" paintCenter="false"/>
  <insets top="3" left="3" bottom="3" right="3"/>
</style>
<bind style="textfield" type="region" key="TextField"/>

```

Adding a `JTextField` to the program in Listing 20-12 generates a screen similar to Figure 20-12. When you resize the screen, the text field border grows. Technically speaking, a similar definition would also work for a `JTextArea`, as there is no height restriction to the image being used here.




Figure 20-12. Using the custom text component border

Tip Much more is in store for the `SynthLookAndFeel`. In time, expect tools to help with the creation of the XML configuration files. Also expect to be able to purchase libraries that let you just plug in complete look and feel classes created with Synth. Be sure to explore SourceForge for just such a collection.

Summary

In this chapter, you explored the pluggable look and feel architecture of the Swing components. Because all aspects of the Swing components are written in the Java programming language, if you don't like a particular aspect of a component, you can simply change it. And changing it is what this chapter showed you how to do.

First, you learned how to query for the preinstalled `LookAndFeel` classes and how to change your current look and feel. Next, you learned how to customize the current look and feel by modifying its `UIDefaults` through the `UIManager`. You saw how these default settings can implement the `UIResource` interface so that the settings change when the look and feel class changes. In addition, you saw how these resources can implement the `UIDefaults.LazyValue` and `UIDefaults.ActiveValue` interfaces for better use of resources. Moreover, you saw how client

properties are hidden from the API view but are available for customizing the look and feel of a component.

To customize the look and feel of various components, you explored creating new UI delegates as well as new look and feel classes, some of which could be nonvisual or auxiliary. You also saw how the Metal look and feel contains a specialized behavior through its use of themes. Lastly, you explored customizing the Synth look and feel.

In Chapter 21, you'll look at the Swing undo framework, which is used for designing undoable and redoable operations.



The Undo Framework

In Chapter 20, you discovered how to customize your Swing-based applications by examining the pluggable look and feel architecture support. In this chapter, you'll examine the Undo Framework provided with the JFC as part of the Swing packages.

The Swing packages from Sun include a facility for supporting undo operations within your applications. It allows you to support undoable and redoable operations that change the state of your data. Although the framework is part of the Swing package hierarchy, it's usable within any application, not just component-based applications.

Working with the Undo Framework

Found in the `javax.swing.undo` package, the Undo Framework includes five classes, two interfaces, and two exceptions. To support the Undo Framework, a related interface and event are included in the `javax.swing.event` package. At the root of it all is the `UndoableEdit` interface. The interface forms the basis for encapsulating operations that can be undone or redone using the Command design pattern.

Note Although technically part of the JFC/Project Swing release as an element in the `javax.swing.undo` package, the undo facility actually belongs in the `java.util` package. Unfortunately, when Swing first came out, it needed to be usable within JDK 1.1. Because Swing text packages use this undo facility, that facility needed to be in the Swing package hierarchy. Because Sun couldn't alter the Core API set for JDK 1.1, you'll find the undo support as part of the JFC/Swing packages, and it is therefore usable under the old JDK 1.1, as well as the 1.2 and later platforms, where Swing is standard.

The root implementation class of the undoable command is the `AbstractUndoableEdit` class. Don't let the class name fool you, though—it isn't abstract. The children of the root command are the `CompoundEdit` and `StateEdit` command classes.

The `CompoundEdit` class allows you to combine multiple undoable operations, in which some of the undoable operations could be `StateEdit` objects that store state changes. The Swing text components create `DefaultDocumentEvent` commands when their contents change. The command is a subclass of `CompoundEdit` as well as an inner class of `AbstractDocument`. An additional encapsulated command is the `UndoManager`, which is a subclass of `CompoundEdit`.

The `UndoManager` manages the edit operations on an editable object by serving as an `UndoableEditListener` and responding to the creation of each `UndoableEditEvent`. When an `UndoableEdit` can't be undone, a `CannotUndoException` is thrown. In addition, when an `UndoableEdit` can't be redone, a `CannotRedoException` is thrown.

If you want to create objects that support undoable and redoable operations, the objects need to implement the `StateEditable` interface, and they can use the `UndoableEditSupport` class to help manage the list of `UndoableEdit` objects.

Before going into the details of the individual pieces of the Undo Framework, let's explore how to use it with the Swing text components. If this is all you want to do, you don't need to understand how the rest works.

Using the Undo Framework with Swing Text Components

The Swing text components already support the necessary undo and redo capabilities. You merely need to manage them with an `UndoManager` and tell the manager when to undo/redo something.

As an example, consider a program that includes a `JTextArea` with two toolbar buttons for undoing and redoing a text operation, as shown in Figure 21-1.




Figure 21-1. *Undo Swing text component usage example*

To enable the `JTextArea` shown in Figure 21-1 to support undoable operations, you must attach an `UndoableEditListener` to the `Document` of the component. Using an `UndoManager` as the listener is all you need to do. First, you create the manager, and then you attach it.

```
UndoManager manager = new UndoManager();  
textArea.getDocument().addUndoableEditListener(manager);
```

Once the manager is attached to the document of the `JTextArea`, it will monitor all changes to the contents of the text area. Because each of the Swing text components has a `Document` data model, you can associate an `UndoManager` with each of these components directly.

After attaching the manager to the text component, you must provide some means to tell the manager to undo/redo an operation. Normally this would be done through a menu selection or a toolbar button selection. In Figure 21-1, this is done with the help of buttons on a `JToolBar`, with one button for each command. For the Undo button, you want the manager to undo an operation. Therefore, the `ActionListener` for the button should call the public `void undo()` method of the `UndoManager`. The Redo button's `ActionListener` should call the manager's

`public void redo()` method. The `undo()` method and `redo()` method each throws a different exception that must be dealt with.

Because the functionality necessary for the Undo and Redo buttons is the same for all managers, you'll find a helper `UndoManagerHelper` class included in Listing 21-1 to create `Action` objects for you. These objects can be used by a `JMenuBar`, `JToolBar`, or anything else that can respond with an `ActionListener` for dealing with the undo and redo operations. You need to ask the helper class for each `Action`, and then associate that `Action` with the appropriate component. For instance, the following five lines of source code will take a previously created `UndoManager` and add the necessary buttons for a `JToolBar`:

```
JToolBar toolbar = new JToolBar();
JButton undoButton = new JButton(UndoManagerHelper.getUndoAction(manager));
toolbar.add(undoButton);
JButton redoButton = new JButton(UndoManagerHelper.getRedoAction(manager));
toolbar.add(redoButton);
```

Using the undo facility with the Swing text components is that easy. The `UndoManagerHelper` class definition is shown in Listing 21-1. If you don't like the default button labels (shown in Figure 21-1), additional methods are available that support customization. In addition, if an exception is thrown during the undo/redo operation, a warning message pops up. The warning message and pop-up window title are also customizable.

Listing 21-1. *The UndoManagerHelper Class Definition*

```
import javax.swing.*;
import javax.swing.undo.*;
import java.awt.*;
import java.awt.event.*;

public class UndoManagerHelper {

    public static Action getUndoAction(UndoManager manager, String label) {
        return new UndoAction(manager, label);
    }

    public static Action getUndoAction(UndoManager manager) {
        return new UndoAction(manager,
            (String) UIManager.get("AbstractUndoableEdit.undoText"));
    }

    public static Action getRedoAction(UndoManager manager, String label) {
        return new RedoAction(manager, label);
    }

    public static Action getRedoAction(UndoManager manager) {
        return new RedoAction(manager,
            (String) UIManager.get("AbstractUndoableEdit.redoText"));
    }
}
```

```

private abstract static class UndoRedoAction extends AbstractAction {
    UndoManager undoManager = new UndoManager();
    String errorMessage = "Cannot undo";
    String errorTitle = "Undo Problem";
    protected UndoRedoAction(UndoManager manager, String name) {
        super(name);
        undoManager = manager;
    }
    public void setErrorMessage(String newValue) {
        errorMessage = newValue;
    }
    public void setErrorTitle(String newValue) {
        errorTitle = newValue;
    }
    protected void showMessage(Object source) {
        if (source instanceof Component) {
            JOptionPane.showMessageDialog((Component)source, errorMessage,
                errorTitle, JOptionPane.WARNING_MESSAGE);
        } else {
            System.err.println(errorMessage);
        }
    }
}

public static class UndoAction extends UndoRedoAction {
    public UndoAction(UndoManager manager, String name) {
        super(manager, name);
        setErrorMessage("Cannot undo");
        setErrorTitle("Undo Problem");
    }
    public void actionPerformed(ActionEvent actionEvent) {
        try {
            undoManager.undo();
        } catch (CannotUndoException cannotUndoException) {
            showMessage(actionEvent.getSource());
        }
    }
}

public static class RedoAction extends UndoRedoAction {
    public RedoAction(UndoManager manager, String name) {
        super(manager, name);
        setErrorMessage("Cannot redo");
        setErrorTitle("Redo Problem");
    }
}

```

```

public void actionPerformed(ActionEvent actionEvent) {
    try {
        undoManager.redo();
    } catch (CannotRedoException cannotRedoException) {
        showMessage(actionEvent.getSource());
    }
}
}
}
}

```

Note One thing you can do to improve these helper actions is to have them enabled only when the particular operation is available. The `AbstractUndoableEdit.redoText` and `AbstractUndoableEdit.undoText` usages are listed in Table 21-1.

The rest of the source for the example shown in Figure 21-1 is provided in Listing 21-2. With the help of the new `UndoManagerHelper` class, the most difficult part of using the Undo Framework with the Swing text components has been greatly simplified.

Listing 21-2. *UndoManager Example with Swing Text Components*

```

import javax.swing.*;
import javax.swing.undo.*;
import java.awt.*;

public class UndoSample {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Undo Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
                JTextArea textArea = new JTextArea();
                JScrollPane scrollPane = new JScrollPane(textArea);

                UndoManager manager = new UndoManager();
                textArea.getDocument().addUndoableEditListener(manager);

                JToolBar toolbar = new JToolBar();
                JButton undoButton =
                    new JButton(UndoManagerHelper.getUndoAction(manager));
                toolbar.add(undoButton);
                JButton redoButton =
                    new JButton(UndoManagerHelper.getRedoAction(manager));
                toolbar.add(redoButton);
            }
        };
        frame.add(scrollPane);
        frame.add(toolbar);
        frame.setVisible(true);
    }
}

```

```
        frame.add(toolbar, BorderLayout.NORTH);
        frame.add(scrollPane, BorderLayout.CENTER);
        frame.setSize(300, 150);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}
```

If you plan to use the Undo Framework only with the Swing text components, you can skip reading the rest of the chapter. On the other hand, if you want to use the framework with other components, or even in a noncomponent setting, you'll want to read the remaining sections, which describe the inner workings of the framework in more detail.

The Command Design Pattern

The undo facility of the `javax.swing.undo` package utilizes the Command design pattern, which has the following participants:

- **Command:** The `UndoableEdit` interface defines the interface for executing the undo/redo operations.
- **Concrete Command:** Instances of the `AbstractUndoableEdit` class, or more specifically its subclasses, implement the necessary Command interface. They bind the commands to the receiver (`Document`) to modify its contents.
- **Client:** In the case of the Swing text components, the `Document` does the creation of the actual `AbstractUndoableEdit` subclass, an `AbstractDocument.DefaultDocumentEvent` by default.
- **Invoker:** The `UndoManager` serves as the Invoker of the `UndoableEdit` command. Normally, someone else tells the Invoker when to do the invoking. However, it's the Invoker who notifies the specific `UndoableEdit` instance when to undo/redo the command.
- **Receiver:** The `Document` is the receiver of the command from the actual `AbstractUndoableEdit` subclass. It knows how to process the request.

If you were using the Undo Framework outside the Swing text components, the Document element would be replaced with a receiver specific to your client application. You would need to create your own UndoableEdit interface implementation to act as the Concrete Command for the pattern. Instead of implementing the interface directly, you merely need to subclass the AbstractUndoableEdit class to encapsulate the specific information about your command.

The design pattern is quite powerful. No matter which command class you're using within the pattern, you can set up capabilities, such as macros for tasks along the lines of automated testing, because the Invoker can sequence the commands at its leisure.

Undo Framework Components

You've seen the Undo Framework in action with the Swing text components and reviewed the Command design pattern. Let's now look at the individual pieces of the framework.

UndoableEdit Interface

The first Undo Framework piece is the UndoableEdit interface, which has the following definition:

```
public interface UndoableEdit {
    // Properties
    public String getPresentationName();
    public String getRedoPresentationName();
    public boolean isSignificant();
    public String getUndoPresentationName();
    // Other Methods
    public boolean addEdit(UndoableEdit anEdit);
    public boolean canRedo();
    public boolean canUndo();
    public void die();
    public void redo() throws CannotRedoException;
    public boolean replaceEdit(UndoableEdit anEdit);
    public void undo() throws CannotUndoException;
}
```

This interface defines the operations that can be done to an object that should support undo and redo capabilities. In addition to describing the supported operations, the interface implicitly defines the three states that an undoable operation can be in, as shown in Figure 21-2.




Figure 21-2. *UndoableEdit* states

The flow between states goes as follows:

Undoable state: When an `UndoableEdit` command is first created, the operation is in the `Undoable` state. The purpose of the `die()` method is to release resources for an `UndoableEdit` before the garbage collector decides to clean things up and to place the command in the `Done` state. Calling the `undo()` method either throws a `CannotUndoException` or causes the command to be undone and the state to change to `Redoable`. Calling the `redo()` method either throws a `CannotRedoException` or causes the command to be redone again and the state to stay at `Undoable`.

Redoable state: When the operation is in the `Redoable` state, the command has already been undone. Calling the `die()` method releases any resources and places the command in the `Done` state. Calling the `undo()` method either throws a `CannotUndoException` or causes the command to be undone again and the state to stay at `Redoable`. Calling the `redo()` method either throws a `CannotRedoException` or causes the command to be redone, returning the state to the `Undoable` state.

Done state: When the operation is in the `Done` state, calling any of the `undo()`, `redo()`, or `die()` methods leaves the operation in the `Done` state.

Some state changes aren't commonplace; however, all state changes are supported. The specifics are left to the Command that you're using (as described in the preceding "The Command Design Pattern" section). For instance, Microsoft Word allows you to continuously repeat the last command if the capabilities make sense—such as when formatting a paragraph or just typing a phrase.

AbstractUndoableEdit Class

The `AbstractUndoableEdit` class provides a default implementation for all the methods of the `UndoableEdit` interface. Although you might guess from the name that the class is abstract, it isn't. However, developers tend to work with subclasses of the class, not with a direct instance of this class.

By default, `AbstractUndoableEdit` commands are *significant* (where `isSignificant()` returns `true`). What significance you place on the `significant` property setting depends on your usage of the command. In addition, the class restricts repetition of undoable state changes. Unless overridden by a subclass, exceptions are thrown if you try to redo something in the Undoable state or undo something in the Redoable state. The class doesn't support adding or replacing `UndoableEdit` operations.

The default presentation names for the `undoPresentationName` and `redoPresentationName` properties are `Undo` and `Redo`, respectively. These are found by looking up the `UIResource`-related properties shown in Table 21-1. There is no default for the `presentationName` property. Subclasses should provide at least a presentation name to provide something more meaningful than the default settings.

Table 21-1. *AbstractUndoableEdit UIResource Elements*

Property String	Object Type
<code>AbstractUndoableEdit.undoText</code>	<code>String</code>
<code>AbstractUndoableEdit.redoText</code>	<code>String</code>

Tip By having the `Undo` and `Redo` presentation names as `UIResource` elements, they can be translated to foreign languages, with their new text available in the same way as other `UIResource` elements.

CompoundEdit Class

The `CompoundEdit` class allows you to combine multiple undoable operations into a single operation. For instance, you may want to combine all the keystrokes for typing a whole word into a single `CompoundEdit` command. This would allow you to continuously redo the typing of a whole word in multiple places. Without combining the separate keystrokes, redoing the last command would redo only the last single keystroke.

The `CompoundEdit` class uses a read-only `inProgress` property to report whether the command is still being combined. Initially, the property is `true`. When in progress, additional commands can be added to the compound command with `addEdit(UndoableEdit)`. To mark the end of a set of commands, you call the `end()` method. Only after you combine all the commands can they be undone or redone. Figure 21-3 illustrates this.




Figure 21-3. *CompoundEdit* states

With a *CompoundEdit*, if you `undo()` the edit, all added commands are undone. This is the same with `redo()`: All commands in the set are redone.

UndoManager Class

The *UndoManager* class is a specific subclass of *CompoundEdit* that tracks the history of edit commands, potentially for an entire application. The number of undoable commands the manager can track is defined by a configurable limit property whose initial value is 100.

When `isInProgress()` reports true for a specific *CompoundEdit*, the *UndoManager* acts somewhat like a backward *CompoundEdit*, in which individual edits can be undone and redone. Once `end()` has been called, the *UndoManager* acts like a *CompoundEdit*, but without the ability to undo or redo individual edit commands. In addition, the *UndoManager* has one more available state—*Undoable* or *Redoable*—for when the manager has undone at least one command, can still undo more, but can also redo the undone command(s).

Besides being able to directly add editable operations with `addEdit()`, the manager also serves as an `UndoableEditListener`. When the `UndoableEditEvent` happens, the listener adds the event's `UndoableEdit` command to the manager with `addEdit()`. In addition, you can clear the edit queue with public void `discardAllEdits()`. After the manager receives the `end()` method, the sequence goes back to looking like Figure 21-3, leaving the bottom three states (Undoable, Redoable, and Done) shown in the chart. The whole sequencing is shown in Figure 21-4.




Figure 21-4. *UndoManager* states

Keep in mind that certain `undo()` and `redo()` calls can throw exceptions. In addition, when you ask the `UndoManager` to undo or redo an edit command, the request undoes (or redoes) all commands up to the last significant one.

The transformation of the `UndoManager` into a `CompoundEdit` might seem confusing to some users. This transformation allows you to have a secondary `UndoManager` for certain suboperations that, once completed, become a single `CompoundEdit` to be passed along to the primary `UndoManager`.

Note Some developers might find it useful to extend the `UndoManager` to expose the `UndoableEdit` list that it is managing. Then they can display the presentation names of the various edit commands. Fortunately (or unfortunately), by default, these aren't exposed.

UndoableEditListener Interface and UndoableEditEvent Class

The `UndoManager` implements the `UndoableEditListener` interface so that it can be notified when undoable operations happen. The listener has the following definition:

```
public interface UndoableEditListener extends EventListener {  
    public void undoableEditHappened(UndoableEditEvent undoableEditEvent);  
}
```

The `UndoableEditListener` uses an `UndoableEditEvent` to tell interested objects when a command that can be undone has happened. The `UndoableEditEvent` class includes one property, `edit`, which returns the `UndoableEdit` object for the event: `public UndoableEdit getEdit()`.

Of all the classes in the Swing-related packages, only the `AbstractDocument` class (as defined in the `Document` interface) comes with built-in support to add these listeners. When creating your own classes that support undoable operations, you'll need to maintain your own list of listeners with the help of the `UndoableEditSupport` class, described next.

UndoableEditSupport Class

The `UndoableEditSupport` class is similar to the JavaBeans-related classes of `PropertyChangeSupport` and `VetoableChangeSupport`. All three of these classes manage a list of a specific type of listener. In the case of the `UndoableEditSupport` class, that type of listener is the `UndoableEditListener`. You add listeners with `public void addUndoableListener(UndoableEditListener)` and remove them with `public void removeUndoableListener(UndoableEditListener)`.

When you want to notify listeners that an `UndoableEdit` operation has happened, you call the `public void postEdit(UndoableEdit)` method, which creates an `UndoableEditEvent` and calls the `undoableEditHappened()` method of each listener.

Note The `UndoableEditSupport` class also includes support for combining multiple undoable edit commands into a `CompoundEdit` with the `public void beginUpdate()` and `public void endUpdate()` methods.

The basic framework for the class usage follows in Listing 21-3. Normally, you tie the undoable event to some other operation. In this example, it's tied to the moment an `ActionEvent` happens, and therefore any registered `ActionListener` objects need to be notified.

Listing 21-3. *Managing UndoableEditListener Objects with UndoableEditSupport*

```

import javax.swing.undo.*;
import javax.swing.event.*;
import java.awt.event.*;
import java.awt.*;

public class AnUndoableComponent {
    UndoableEditSupport undoableEditSupport = new UndoableEditSupport(this);
    ActionListener actionListenerList = null;

    public void addActionListener(ActionListener actionListener) {
        actionListenerList = AWTEventMulticaster.add(actionListener,
            actionListenerList);
    }

    public void removeActionListener(ActionListener actionListener) {
        actionListenerList = AWTEventMulticaster.remove(actionListener,
            actionListenerList);
    }

    public void addUndoableEditListener(
        UndoableEditListener undoableEditListener) {
        undoableEditSupport.addUndoableEditListener(undoableEditListener);
    }

    public void removeUndoableEditListener(
        UndoableEditListener undoableEditListener) {
        undoableEditSupport.removeUndoableEditListener(undoableEditListener);
    }

    protected void fireActionPerformed(ActionEvent actionEvent) {
        if (actionListenerList != null) {
            actionListenerList.actionPerformed(actionEvent);
        }
        // Need to create your custom type of undoable operation
        undoableEditSupport.postEdit(new AbstractUndoableEdit());
    }
}

```

A Complete Undoable Program Example

Now that you've seen the main classes for the Swing Undo Framework, let's look at a complete example that defines a custom undoable class. The undoable class is a drawing panel in which each mouse click defines a point to be drawn in a polygon. Figure 21-5 shows the drawable panel in action, before and after an undo operation.




Figure 21-5. *The undoable drawing panel at work*

The main program in Listing 21-4 looks practically identical to the earlier example of supporting undo and redo operations in a Swing text component, in Listing 21-2. You simply need to create an `UndoManager` to manage the undoable operations and associate it to the undoable object. The usage of the Undo Framework works the same here, except that the undoable object is the yet-to-be-created `UndoableDrawingPanel` class (Listing 21-5).

Listing 21-4. *The UndoDrawing Test Driver*

```
import javax.swing.*.*;
import javax.swing.undo.*;
import java.awt.*.*;
public class UndoDrawing {
    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Drawing Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                UndoableDrawingPanel drawingPanel = new UndoableDrawingPanel();

                UndoManager manager = new UndoManager();
                drawingPanel.addUndoableEditListener(manager);

                JToolBar toolbar = new JToolBar();
                JButton undoButton =
                    new JButton(UndoManagerHelper.getUndoAction(manager));
                toolbar.add(undoButton);
                JButton redoButton =
                    new JButton(UndoManagerHelper.getRedoAction(manager));
                toolbar.add(redoButton);
```

```

        frame.add(toolbar, BorderLayout.NORTH);
        frame.add(drawingPanel, BorderLayout.CENTER);
        frame.setSize(300, 150);
        frame.setVisible(true);
    }
};
EventQueue.invokeLater(runner);
}
}

```

The `UndoableDrawingPanel` class is a component that draws a polygon within itself based on a set of points within the polygon. New points are added to the polygon whenever the mouse is released. If you don't want the component to support undoable operations, you don't need to do anything beyond collecting points for the drawing panel.

For the panel to support undoable operations, it must do two things:

- It must maintain a list of `UndoableEditListener` objects. This can be easily done with the help of the `UndoableEditSupport` class, as shown earlier in Listing 21-3.
- The second task involves creating an `UndoableEdit` object, prior to any state changes, and posting it to the registered listeners. Because the state of the drawing panel is the polygon, this property must be exposed in the drawing class.

Listing 21-5 shows the definition for the `UndoableDrawingPanel` class. Nothing in the class is particularly complicated. The important thing to remember when defining an undoable class is that the undoable event must be created *before* the state of the component changes. (The implementation class of the `UndoableEdit` interface, `UndoableDrawEdit`, is shown later, in Listing 21-6.)

Listing 21-5. *The UndoableDrawingPanel Main Component*

```

import javax.swing.*;
import javax.swing.event.*;
import javax.swing.undo.*;
import java.awt.*;
import java.awt.event.*;

public class UndoableDrawingPanel extends JPanel {
    UndoableEditSupport undoableEditSupport = new UndoableEditSupport(this);
    Polygon polygon = new Polygon();

```

```

public UndoableDrawingPanel() {
    MouseListener mouseListener = new MouseAdapter() {
        public void mouseReleased(MouseEvent mouseEvent) {
            undoableEditSupport.postEdit(
                new UndoableDrawEdit(UndoableDrawingPanel.this));
            polygon.addPoint(mouseEvent.getX(), mouseEvent.getY());
            repaint();
        }
    };
    addMouseListener(mouseListener);
}

public void addUndoableEditListener(
    UndoableEditListener undoableEditListener) {
    undoableEditSupport.addUndoableEditListener(undoableEditListener);
}

public void removeUndoableEditListener(
    UndoableEditListener undoableEditListener) {
    undoableEditSupport.removeUndoableEditListener(undoableEditListener);
}

public void setPolygon(Polygon newValue) {
    polygon = newValue;
    repaint();
}

public Polygon getPolygon() {
    Polygon returnValue;
    if (polygon.npoints == 0) {
        returnValue = new Polygon();
    } else {
        returnValue = new Polygon(
            polygon.xpoints, polygon.ypoints, polygon.npoints);
    }
    return returnValue;
}

protected void paintComponent(Graphics g) {
    super.paintComponent(g);
    g.drawPolygon(polygon);
}
}

```

When defining the custom implementation of the `UndoableEdit` interface, you can choose to implement the complete interface, or you can subclass the `AbstractUndoableEdit` class and override any appropriate methods. More typically, you'll just subclass `AbstractUndoableEdit`.

The minimum methods to override are `undo()` and `redo()`, although you'll probably also choose to override `getPresentationName()` to give a better name to the undoable operation.

Because the Command design pattern has the Concrete Command (that is, the `UndoableEdit` implementation) invoke the operation, the constructor must save any information necessary to make the operation undoable. In the case of the drawing panel, you need to save a reference to the panel and its current polygon. Then when the operation is asked to undo itself, the original polygon can be restored. To support redoing the undo operation, the `undo()` method must also save the new polygon; otherwise, the `redo()` operation wouldn't know how to change things back. It may sound like quite a bit of work, but it really isn't. The complete class definition for the `UndoableEdit` implementation follows in Listing 21-6.

Listing 21-6. *The UndoableDrawEdit Undoable Command*

```
import javax.swing.undo.*;
import java.awt.*;

public class UndoableDrawEdit extends AbstractUndoableEdit {
    UndoableDrawingPanel panel;
    Polygon polygon, savedPolygon;

    public UndoableDrawEdit(UndoableDrawingPanel panel) {
        this.panel = panel;
        polygon = panel.getPolygon();
    }

    public String getPresentationName() {
        return "Polygon of size " + polygon.npoints;
    }

    public void redo() throws CannotRedoException {
        super.redo();
        if (savedPolygon == null) {
            // Should never get here, as super() doesn't permit redoing
            throw new CannotRedoException();
        } else {
            panel.setPolygon(savedPolygon);
            savedPolygon = null;
        }
    }

    public void undo() throws CannotUndoException {
        super.undo();
        savedPolygon = panel.getPolygon();
        panel.setPolygon(polygon);
    }
}
```

And that's it! The last two classes make the `UndoDrawing` example class (Listing 21-4) work. When creating your own undoable classes, you will need to subclass a nonundoable class and then add the necessary support to make it undoable. In addition, you will need to define an `UndoableEdit` implementation to support your specific class.

Using an Outside Object to Manage Undo States

In the previous example, it was the responsibility of your custom `UndoableEdit` implementation to maintain the before-and-after state of the undoable object. The Swing Undo Framework also supports the ability of an object outside the undoable edit implementation to manage the state. When using an outside object for state management, it isn't necessary to implement the `UndoableEdit` interface yourself. Instead, you can use the `StateEdit` class as the `UndoableEdit` implementation. The `StateEdit` class then relies on a class to implement the `StateEditable` interface to manage the before-and-after storage of the state of an undoable object (within a `Hashtable`).

StateEditable Interface

The `StateEditable` interface consists of two methods and a meaningless string constant.

```
public interface StateEditable {  
    public final static String RCSID;  
    public void restoreState(Hashtable state);  
    public void storeState(Hashtable state);  
}
```

An object that supports the undoing of its operations stores its state with the `storeState(Hashtable)` method. This is all the information about the state of the object that can change. Then restoring the state of the object is done in the `restoreState(Hashtable)` method.

To demonstrate, let's see how to rewrite the `UndoableDrawingPanel` example. Using this interface with the updated, undoable drawing panel involves implementing the interface, and storing and getting the polygon shown earlier in Figure 21-5. That's because the polygon is the only state information we care about undoing. The source code is shown in Listing 21-7.

Listing 21-7. *The StateEditable Implementation of the Updated Component*

```
public class UndoableDrawingPanel2 extends JPanel implements StateEditable {  
  
    private static String POLYGON_KEY = "Polygon";  
    public void storeState(Hashtable state) {  
        state.put(POLYGON_KEY, getPolygon());  
    }  
}
```

```

public void restoreState(Hashtable state) {
    Polygon polygon = (Polygon)state.get(POLYGON_KEY);
    if (polygon != null) {
        setPolygon(polygon);
    }
}
}

```

The `Hashtable` that the `restoreState()` method returns contains only key/value pairs that changed. It's possible that the `get()` method of the `Hashtable` returns `null` for something that you explicitly `put()` in the hash table. Therefore, as shown in Listing 21-7, you're required to add an `if-null` check after getting any state information from the hash table.

StateEdit Class

After you've implemented the `StateEditable` interface, you can use the `StateEdit` class as the `UndoableEdit` implementation. Where the previous `UndoableDrawingPanel` example created a custom `UndoableDrawEdit`, the new class creates a `StateEdit` instance.

The `StateEdit` constructor accepts a `StateEditable` object that you're going to change and an optional presentation name. After creating the `StateEdit` object, modify the `StateEditable` object and then tell the `StateEdit` to `end()` the modifications to the `StateEditable` object. When the `StateEdit` object is told that the modifications have ended, it compares the before-and-after states of the state editable object and removes any key/value pairs that didn't change from the hash table. You can then post the `UndoableEdit` to the list of `UndoableEditListener` objects through the list maintained by the `UndoableEditSupport` class.

```

StateEdit stateEdit = new StateEdit(UndoableDrawingPanel2.this);
// Change state of UndoableDrawingPanel2
polygon.addPoint(mouseEvent.getX(), mouseEvent.getY());
// Done changing state
stateEdit.end();
undoableEditSupport.postEdit(stateEdit);

```

After the edit is posted, the `UndoManager` manages the `StateEdit` instance of `UndoableEdit`, just like any other undoable edit object. The `UndoManager` can then request the `StateEdit` object to tell its `StateEditable` object to restore its previous state. This holds for any other `UndoableEdit` object. Therefore, no other source code needs to change.

A Complete StateEditable/StateEdit Example

The reworking of the `UndoableDrawingPanel` example is presented in Listing 21-8, with the differences from Listing 21-5 shown in boldface. This version uses the `StateEditable/StateEdit` combination just described. The earlier test program is included as the `main()` method to keep the complete example together. With the exception of the class name change for the drawing panel, the test program didn't change and will still result in what you see in Figure 21-5, assuming the same set of points in the polygon.

Listing 21-8. *The Updated UndoableDrawingPanel2 Main Component*

```

import javax.swing.*;
import javax.swing.event.*;
import javax.swing.undo.*;
import java.awt.*;
import java.awt.event.*;
import java.util.Hashtable;

public class UndoableDrawingPanel2 extends JPanel implements StateEditable {
    private static String POLYGON_KEY = "Polygon";
    UndoableEditSupport undoableEditSupport = new UndoableEditSupport(this);
    Polygon polygon = new Polygon();

    public UndoableDrawingPanel2() {
        MouseListener mouseListener = new MouseAdapter() {
            public void mouseReleased(MouseEvent mouseEvent) {
                StateEdit stateEdit = new StateEdit(UndoableDrawingPanel2.this);
                polygon.addPoint(mouseEvent.getX(), mouseEvent.getY());
                stateEdit.end();
                undoableEditSupport.postEdit(stateEdit);
                repaint();
            }
        };
        addMouseListener(mouseListener);
    }

    public void addUndoableEditListener(
        UndoableEditListener undoableEditListener) {
        undoableEditSupport.addUndoableEditListener(undoableEditListener);
    }

    public void removeUndoableEditListener(
        UndoableEditListener undoableEditListener) {
        undoableEditSupport.removeUndoableEditListener(undoableEditListener);
    }

    public void storeState(Hashtable state) {
        state.put(POLYGON_KEY, getPolygon());
    }

    public void restoreState(Hashtable state) {
        Polygon polygon = (Polygon)state.get(POLYGON_KEY);
        if (polygon != null) {
            setPolygon(polygon);
        }
    }
}

```

```
public void setPolygon(Polygon newValue) {
    polygon = newValue;
    repaint();
}

public Polygon getPolygon() {
    Polygon returnValue;
    if (polygon.npoints == 0) {
        returnValue = new Polygon();
    } else {
        returnValue = new Polygon(
            polygon.xpoints, polygon.ypoints, polygon.npoints);
    }
    return returnValue;
}

protected void paintComponent(Graphics g) {
    super.paintComponent(g);
    g.drawPolygon(polygon);
}

public static void main(String args[]) {
    Runnable runner = new Runnable() {
        public void run() {
            JFrame frame = new JFrame("Drawing Sample2");
            frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);
            UndoableDrawingPanel2 drawingPanel = new UndoableDrawingPanel2();

            UndoManager manager = new UndoManager();
            drawingPanel.addUndoableEditListener(manager);

            JToolBar toolbar = new JToolBar();
            JButton undoButton =
                new JButton(UndoManagerHelper.getUndoAction(manager));
            toolbar.add(undoButton);
            JButton redoButton =
                new JButton(UndoManagerHelper.getRedoAction(manager));
            toolbar.add(redoButton);

            frame.add(toolbar, BorderLayout.NORTH);
            frame.add(drawingPanel, BorderLayout.CENTER);
            frame.setSize(300, 150);
            frame.setVisible(true);
        }
    };
};
```

```
        EventQueue.invokeLater(runner);  
    }  
}
```

Summary

This chapter took both a short look and a long look at the Undo Framework found in the `javax.swing.undo` package with support from `javax.swing.event`. You saw how the framework support arrives already built in to the Swing text components. In addition, you learned how to build support into your own classes. With the interfaces and classes found in the Undo Framework, you can make any editable object support both undo and redo capabilities.

The next chapter introduces the accessibility support for the Swing component set. There, you'll learn about the support for using assistive technologies with the components and working with audio cues.



Accessibility

A standard part of the Swing framework is support for assistive technologies. These technologies allow your Swing-based programs to be accessible to those with physical challenges. Some users need screen readers, audio cues, or just an input mode that doesn't require the mouse. Mouse-less input is typically through the keyboard, but it also could be through specialized input devices, such as those that are voice-activated.

Users don't need to be physically challenged to take advantage of options you, as the developer, can use to make your programs more accessible. For example, you might add tooltip text, which users can see by resting their mouse over the component. Limited-vision users taking advantage of accessibility devices could rely on that text to describe the component with a screen reader. Other options include keyboard accelerators and menu mnemonics, which allow users to navigate around the screen and activate actions with minimal hand movement.

This chapter offers some suggestions to help you create programs that follow federal guidelines in the United States, known as Section 508 Accessibility Requirements. For details on these requirements, refer to *Accessibility for Everybody: Understanding the Section 508 Accessibility Requirements*, by John Paul Mueller (Apress, 2003; ISBN 1-59059-086-4). Sun also offers a resource at <http://www.sun.com/access/background/laws.html>, which includes references to international resources, as well as those in the United States. And, of course, there is the JFC Assistive Technologies home page, at <http://java.sun.com/products/jfc/accessibility/>.

Accessibility Classes

The `javax.accessibility` package is both the most and least used package. Provided you configure your Swing components properly, everything happens behind the scenes. When a user taking advantage of an accessibility device runs the program, the Java Accessibility API steps in and provides the necessary information to the device. For instance, when creating an `ImageIcon`, there are two sets of constructors: those without a description argument and those with a description argument.

```
// Without description argument
public ImageIcon()
public ImageIcon(Image image)
public ImageIcon(String filename)
public ImageIcon(URL location)
public ImageIcon(byte imageData[])
```

```
// With description argument

public ImageIcon(Image image, String description)
public ImageIcon(String filename, String description)
public ImageIcon(URL location, String description)
public ImageIcon(byte imageData[], String description)
```

By creating an `ImageIcon` with a description, your program automatically becomes more accessible. In addition to creating the icon with a description argument to the constructor, you can also assign the text later by calling the `setDescription()` method.

One important interface, `Accessible`, and an abstract class, `AccessibleContext`, provide the core framework for the Java Accessibility API.

Accessible Interface

For a Swing component to work within the accessibility framework, it must implement the `Accessible` interface.

```
public interface Accessible {
    // Property
    public AccessibleContext getAccessibleContext();
}
```

As the interface definition shows, there is only one method, which gets the current `AccessibleContext` instance for the implementing class. All the standard AWT and Swing components implement the interface. Several internal aspects of components, like the system menu bar on the title pane of the `JInternalFrame`, also implement the `Accessible` interface.

AccessibleContext Class

While the `Accessible` interface is all that a component must implement, the work is actually done in the `AccessibleContext` instance that it returns. The returned context is practically another component. It maps the accessible properties to the properties of the component. For example, with the `JLabel` component, when you get its `AccessibleContext`, you are getting the concrete subclass known as `AccessibleJLabel`. This subclass maps `JLabel` properties, such as the `accessibleName` property to the text property. As shown in Table 22-1, the abstract class itself is larger than the interface.

Table 22-1. *AccessibleContext Properties*

Property Name	Data Type	Access
<code>accessibleAction</code>	<code>AccessibleAction</code>	Read-only
<code>accessibleChildrenCount</code>	<code>int</code>	Read-only
<code>accessibleComponent</code>	<code>AccessibleComponent</code>	Read-only
<code>accessibleDescription</code>	<code>String</code>	Read-write bound
<code>accessibleEditableText</code>	<code>AccessibleEditableText</code>	Read-only

Table 22-1. *AccessibleContext Properties (Continued)*

Property Name	Data Type	Access
<code>accessibleIcon</code>	<code>AccessibleIcon</code>	Read-only
<code>accessibleIndexInParent</code>	<code>int</code>	Read-only
<code>accessibleName</code>	<code>String</code>	Read-write bound
<code>accessibleParent</code>	<code>Accessible</code>	Read-write
<code>accessibleRelationSet</code>	<code>AccessibleRelationSet</code>	Read-only
<code>accessibleRole</code>	<code>AccessibleRole</code>	Read-only
<code>accessibleSelection</code>	<code>AccessibleSelection</code>	Read-only
<code>accessibleStateSet</code>	<code>AccessibleStateSet</code>	Read-only
<code>accessibleTable</code>	<code>AccessibleTable</code>	Read-only
<code>accessibleText</code>	<code>AccessibleText</code>	Read-only
<code>accessibleValue</code>	<code>AccessibleValue</code>	Read-only
<code>locale</code>	<code>Locale</code>	Read-only

As Table 22-1 shows, there are several other classes found in the `javax.accessibility` package. However, typically, you don't need to worry about them, provided that you create your components and screens to be accessible.

Creating Accessible Components

This section presents some hints to help you create applications that will be accessible when used with assistive technologies. This is not meant to be an exhaustive list, but it does provide an overview of some helpful techniques.

- As a first task, try to use your program without a mouse. Do your menus support accelerators and mnemonics? Do your buttons have mnemonics associated with them? Do your text fields have labels associated with them via the `setLabelFor()` method, and does each label have a mnemonic?
- Make sure your components have a short string associated with them. If a component, such as an image-only button, doesn't have a string, call the `setAccessibleName()` method of the `AccessibleContext`. Remember to localize this name if your program is targeting an internationalized audience.
- Work with tooltip text wherever possible. If it is not appropriate to have tooltip text with a component, be sure to call `setAccessibleDescription()`.
- Are your custom components accessible? If you've subclassed `JComponent`, that class doesn't implement the `Accessible` interface. But, if you've subclassed `JPanel`, it does. However, even though `JPanel` implements the interface, your component might not be providing the necessary accessibility information. Consider having your custom `AccessibleContext` extend `JComponent.AccessibleJComponent` when appropriate.

- Components that are inside containers that aren't accessible are themselves not accessible. Be sure to use `JPanel` as your container, rather than the `AWT Container` class, to ensure your screens are accessible.

Note To see how well you've done creating accessible programs, you can try using the Java Accessibility Utilities, available from the JFC Assistive Technologies home page at <http://java.sun.com/products/jfc/accessibility/>. These downloadable utilities are designed to let you see exposed accessibility properties in different forms. However, I personally couldn't get them to work. The `jaccess.jar` and `jaccess-examples.jar` files needed weren't available, nor were the imported classes for the code that was provided.

Working with the Java Access Bridge

If you happen to be working on a Microsoft Windows platform, you can try out the Java Access Bridge, available from <http://java.sun.com/products/accessbridge/>. This utility is easy to use.

Caution To get the Java Access Bridge, do not follow the link from the main Accessibility page. The link available there in early 2005 pointed to the 1.0.4 beta version of the product. You should download at least version 1.2, available directly from <http://java.sun.com/products/accessbridge/>.

After downloading `accessbridge-1.2.zip`, unpack it and run the `Install` program, found in the installer subdirectory. After the program checks Java virtual machines (JVMs) for compatibility, it prompts you to select in which of the compatible JVMs you want the bridge installed. As Figure 22-1 shows, if you happen to have a few JVMs on your system, this may be in several places. Just pick the ones you are most likely to use. The program might also prompt you to remove some of the older versions on your machine. The directories that begin with `c:\program files\java` are the different versions of Java Plug-in for the browser.




Figure 22-1. *Installing the Java Access Bridge*

After clicking the Install (or Install in All) button, you'll see a success window, as shown in Figure 22-2 (assuming everything succeeded). Installation is quick.




Figure 22-2. *Java Access Bridge successfully installed*

Once you've installed the bridge, you can run programs like Java Monkey and Java Ferret (yes, those are their real names). Once running, these programs attach themselves to any Java programs that run through the same JVM. For instance, you can try running the tooltip sample program presented in Chapter 4 with Java Monkey, repeated here in Listing 22-1.

Listing 22-1. *Tooltip Sample*

```
import javax.swing.*;
import java.awt.*;

public class TooltipSample {

    public static void main(String args[]) {
        Runnable runner = new Runnable() {
            public void run() {
                JFrame frame = new JFrame("Tooltip Sample");
                frame.setDefaultCloseOperation(JFrame.EXIT_ON_CLOSE);

                JPanel panel = new JPanel();
                panel.setToolTipText("<Html>Tooltip<br>Message");
                frame.add(panel, BorderLayout.CENTER);

                JButton button = new JButton("Hello, World") {
                    public JToolTip createToolTip() {
                        JToolTip tip = super.createToolTip();
                        tip.setBackground(Color.YELLOW);
                        tip.setForeground(Color.RED);
                        return tip;
                    }
                    public boolean contains(int x, int y) {
                        if (x < 100) {
                            setToolTipText("Got Green Eggs?");
                        } else {
                            setToolTipText("Got Ham?");
                        }
                    }
                }
            }
        };
        frame.add(button, BorderLayout.SOUTH);
        frame.setVisible(true);
    }
}
```

```

        return super.contains(x, y);
    }
};
button.setToolTipText("Hello, World");
frame.add(button, BorderLayout.NORTH);

frame.setSize(300, 150);
frame.setVisible(true);
}
};
EventQueue.invokeLater(runner);
}
}

```

You'll see the screen shown in Figure 22-3. If you don't immediately see the component tree, select the Refresh Tree option under the File menu in the Java Monkey window.




Figure 22-3. Main Java Monkey screen

Select the Accessibility API Panel option under the Panels menu to see the information available through the AccessibleContext, such as the name, description, and role. Figure 22-4 shows an example. Be sure to scroll down to see all the available information.




Figure 22-4. Secondary Java Monkey screen

The other program that comes with the Java Access Bridge is Java Ferret. This is more of a tracking program, where you can enable the tracking of different events, such as mouse, focus, and menu selection. If you've enabled mouse tracking, you'll see the program updated. Figure 22-5 shows an example of the Java Ferret information displayed when you move the mouse over the JButton in the sample tooltip program (Listing 22-1).




Figure 22-5. *Java Ferret interface*

Note Does anyone else find it ironic that the Java Monkey and Java Ferret programs are not themselves very accessible? Where are the mnemonics and menu accelerators?

Summary

This chapter explored how the Swing APIs help make your programs more accessible, both for the normal user and the physically challenged. By following the suggestions in this chapter, your programs should be well on their way to meeting federal and international guidelines. With the help of the Java Monkey and Ferret programs, you can discover if sufficient attributes are exposed to users needing the accessibility features.

And this wraps up your tour of Swing. Be sure to visit The Swing Connection maintained by Sun at <http://www.theswingconnection.com/> to follow the latest happenings.



UI Manager Properties

Throughout this book are tables that list the property names and data types for all the `UIResource` elements of specific Swing components. Although these tables show all the information about a specific component, it is handy to have the information about property names for all of the components in one place.

With that in mind, this appendix provides a complete, alphabetical list of properties used by the predefined look and feel classes—Motif, Metal/Ocean, Windows, GTK, and Synth—provided with the Swing release for the Java 2 Platform Standard Edition, version 5.0 (J2SE 5.0). The table indicates with an *X* which of the five look and feel classes uses a particular property. For properties defined within the base Basic look and feel, these are assumed to be used by all the look and feel types, since all of the system-defined look and feel classes extend from `BasicLookAndFeel`. It is possible that a subclass masks the use of a property defined for the Basic look and feel, and in fact doesn't physically use one flagged as such in the table. Also, since the GTK look and feel is a subclass of Synth, a similar situation arises with GTK, too.

To change the default setting for any of these properties, you need to notify the `UIManager` by storing a new setting in the lookup table of the `UIManager`. For instance, to change the default text for the Yes button in a `JOptionPane`, you need to replace the `OptionPane.yesButtonText` property with the new setting (*Si*, in this example):

```
UIManager.put("OptionPane.yesButtonText", "Si");
```

Then any component created after the setting change will get the new value: *Si*. If you want a displayed component to get the new setting, you must call its `updateUI()` method after changing the setting.

When you change the current look and feel, any custom settings you install may be lost. If the class of the property value setting implements the `UIResource` interface (an empty marker interface such as `Serializable`), the setting will be replaced by the default setting of the look and feel. For example, the following setting would be saved when the look and feel changes:

```
UIManager.put("OptionPane.background", Color.RED);
```

Conversely, the following setting would not be saved when the look and feel changes:

```
UIManager.put("OptionPane.background", new ColorUIResource(Color.RED));
```

If the property value setting does not implement the `UIResource` interface, the property setting is retained when the look and feel changes.

Note The specific set of available properties changes with each JFC/Project Swing release. The listing here reflects the current settings for J2SE 5.0. Some properties did not exist in earlier versions, and others may get replaced in later versions. The changes tend to be minor, but they do exist.

UIResource Elements for the Predefined Look and Feel Classes

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
AbstractButton.clickText	String	X	X	X	X	X
AbstractDocument.additionText	String	X	X	X	X	X
AbstractDocument.deletionText	String	X	X	X	X	X
AbstractDocument.redoText	String	X	X	X	X	X
AbstractDocument.styleChangeText	String	X	X	X	X	X
AbstractDocument.undoText	String	X	X	X	X	X
AbstractUndoableEdit.redoText	String	X	X	X	X	X
AbstractUndoableEdit.undoText	String	X	X	X	X	X
activeCaption	Color	X	X	X	X	X
activeCaptionBorder	Color	X	X	X	X	X
activeCaptionText	Color	X	X	X	X	X
Application.useSystemFontSettings	Boolean		X	X		
ArrowButton.size	Integer				X	X
ArrowButtonUI	String				X	X
AuditoryCues.allAuditoryCues	String[]	X	X	X	X	X
AuditoryCues.cueList	String[]	X	X	X	X	X
AuditoryCues.defaultCueList	String[]		X			
AuditoryCues.noAuditoryCues	String[]	X	X	X	X	X
AuditoryCues.playList	String[]	X	X	X	X	X
black	Color				X	
Button.actionMap	ActionMap	X	X	X	X	X
Button.background	Color	X	X	X	X	X
Button.border	Border	X	X	X	X	X
Button.contentAreaFilled	Boolean				X	X
Button.darkShadow	Color	X	X	X	X	X
Button.dashedRectGapHeight	Integer			X		
Button.dashedRectGapWidth	Integer			X		

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
Button.dashedRectGapX	Integer			X		
Button.dashedRectGapY	Integer			X		
Button.defaultButtonFollowsFocus	Boolean	X	X	X	X	X
Button.disabledForeground	Color			X		
Button.disabledGrayRange	Integer[]		X			
Button.disabledShadow	Color			X		
Button.disabledText	Color		X			
Button.disabledToolBarBorderBackground	Color		X			
Button.focus	Color		X	X		
Button.focusInputMap	InputMap	X	X	X	X	X
Button.font	Font	X	X	X	X	X
Button.foreground	Color	X	X	X	X	X
Button.gradient	List		X			
Button.highlight	Color	X	X	X	X	X
Button.icon	Icon				X	X
Button.iconTextGap	Integer				X	X
Button.light	Color	X	X	X	X	X
Button.margin	Insets	X	X	X	X	X
Button.rollover	Boolean	X	X	X	X	X
Button.rolloverIconType	String		X			
Button.select	Color	X	X			
Button.shadow	Color	X	X	X	X	X
Button.showMnemonics	Boolean			X		
Button.textIconGap	Integer	X	X	X	X	X
Button.textShiftOffset	Integer	X	X	X	X	X
Button.toolbarBorderBackground	Color		X			
ButtonUI	String	X	X	X	X	X
caretColor	Color				X	
CheckBox.background	Color	X	X	X	X	X
CheckBox.border	Border	X	X	X	X	X
CheckBox.darkShadow	Color			X		

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
CheckBox.disabledText	Color		X			
CheckBox.focus	Color	X	X	X		
CheckBox.focusInputMap	InputMap	X	X	X	X	X
CheckBox.font	Font	X	X	X	X	X
CheckBox.foreground	Color	X	X	X	X	X
CheckBox.gradient	List		X			
CheckBox.highlight	Color			X		
CheckBox.icon	Icon	X	X	X	X	X
CheckBox.interiorBackground	Color			X		
CheckBox.light	Color			X		
CheckBox.margin	Insets	X	X	X	X	X
CheckBox.rollover	Boolean		X			
Checkbox.select ^a	Color		X			
CheckBox.shadow	Color			X		
CheckBox.textIconGap	Integer	X	X	X	X	X
CheckBox.textShiftOffset	Integer	X	X	X	X	X
CheckBoxMenuItem.acceleratorFont	Font	X	X	X	X	X
CheckBoxMenuItem.accelerator➡ Foreground	Color	X	X	X	X	X
CheckBoxMenuItem.accelerator➡ SelectionForeground	Color	X	X	X	X	X
CheckBoxMenuItem.actionMap	ActionMap	X	X	X	X	X
CheckBoxMenuItem.arrowIcon	Icon	X	X	X	X	X
CheckBoxMenuItem.background	Color	X	X	X	X	X
CheckBoxMenuItem.border	Border	X	X	X	X	X
CheckBoxMenuItem.borderPainted	Boolean	X	X	X	X	X
CheckBoxMenuItem.checkIcon	Icon	X	X	X	X	X
CheckBoxMenuItem.commandSound	String	X	X	X	X	X
CheckBoxMenuItem.disabled➡ Foreground	Color	X	X	X	X	X
CheckBoxMenuItem.font	Font	X	X	X	X	X
CheckBoxMenuItem.foreground	Color	X	X	X	X	X
CheckBoxMenuItem.gradient	List		X			

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
CheckBoxMenuItem.margin	Insets	X	X	X	X	X
CheckBoxMenuItem.opaque	Boolean	X	X	X	X	X
CheckBoxMenuItem.selection ➡ Background	Color	X	X	X	X	X
CheckBoxMenuItem.selection ➡ Foreground	Color	X	X	X	X	X
CheckBoxMenuItemUI	String	X	X	X	X	X
CheckBoxUI	String	X	X	X	X	X
ColorChooser.background	Color	X	X	X	X	X
ColorChooser.cancelText	String	X	X	X	X	X
ColorChooser.font	Font	X	X	X	X	X
ColorChooser.foreground	Color	X	X	X	X	X
ColorChooser.hsbBlueText	String	X	X	X	X	X
ColorChooser.hsbBrightnessText	String	X	X	X	X	X
ColorChooser.hsbDisplayed ➡ MnemonicIndex	Integer	X	X	X	X	X
ColorChooser.hsbGreenText	String	X	X	X	X	X
ColorChooser.hsbHueText	String	X	X	X	X	X
ColorChooser.hsbMnemonic	Integer	X	X	X	X	X
ColorChooser.hsbNameText	String	X	X	X	X	X
ColorChooser.hsbRedText	String	X	X	X	X	X
ColorChooser.hsbSaturationText	String	X	X	X	X	X
ColorChooser.okText	String	X	X	X	X	X
ColorChooser.panels	AbstractColor ➡ ChooserPanel[]				X	X
ColorChooser.previewText	String	X	X	X	X	X
ColorChooser.resetMnemonic	Integer	X	X	X	X	X
ColorChooser.resetText	String	X	X	X	X	X
ColorChooser.rgbBlueDisplayed ➡ MnemonicIndex	Integer	X	X	X	X	X
ColorChooser.rgbBlueMnemonic	Integer	X	X	X	X	X
ColorChooser.rgbBlueText	String	X	X	X	X	X
ColorChooser.rgbDisplayed ➡ MnemonicIndex	Integer	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
ColorChooser.rgbGreenDisplayed ➡ MnemonicIndex	Integer	X	X	X	X	X
ColorChooser.rgbGreenMnemonic	Integer	X	X	X	X	X
ColorChooser.rgbGreenText	String	X	X	X	X	X
ColorChooser.rgbMnemonic	Integer	X	X	X	X	X
ColorChooser.rgbNameText	String	X	X	X	X	X
ColorChooser.rgbRedDisplayed ➡ MnemonicIndex	Integer	X	X	X	X	X
ColorChooser.rgbRedMnemonic	Integer	X	X	X	X	X
ColorChooser.rgbRedText	String	X	X	X	X	X
ColorChooser.sampleText	String	X	X	X	X	X
ColorChooser.showPreviewPanelText	Boolean	X	X	X	X	X
ColorChooser.swatchesDefault ➡ RecentColor	Color	X	X	X	X	X
ColorChooser.swatchesDisplayed ➡ MnemonicIndex	Integer	X	X	X	X	X
ColorChooser.swatchesMnemonic	Integer	X	X	X	X	X
ColorChooser.swatchesNameText	String	X	X	X	X	X
ColorChooser.swatchesRecent ➡ SwatchSize	Dimension	X	X	X	X	X
ColorChooser.swatchesRecentText	String	X	X	X	X	X
ColorChooser.swatchesSwatchSize	Dimension	X	X	X	X	X
ColorChooserUI	String	X	X	X	X	X
ComboBox.actionMap	ActionMap	X	X	X	X	X
ComboBox.ancestorInputMap	InputMap	X	X	X	X	X
ComboBox.background	Color	X	X	X	X	X
ComboBox.border	Border	X	X	X	X	X
ComboBox.buttonBackground	Color	X	X	X	X	X
ComboBox.buttonDarkShadow	Color	X	X	X	X	X
ComboBox.buttonHighlight	Color	X	X	X	X	X
ComboBox.buttonShadow	Color	X	X	X	X	X
ComboBox.control	Color	X				
ComboBox.controlForeground	Color	X				
ComboBox.disabledBackground	Color	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
ComboBox.disabledForeground	Color	X	X	X	X	X
ComboBox.font	Font	X	X	X	X	X
ComboBox.foreground	Color	X	X	X	X	X
ComboBox.rendererUseListColors	Boolean				X	X
ComboBox.selectionBackground	Color	X	X	X	X	X
ComboBox.selectionForeground	Color	X	X	X	X	X
ComboBox.showPopupOnNavigation	Boolean	X	X	X	X	X
ComboBox.timeFactor	Long	X	X	X	X	X
ComboBox.togglePopupText	String	X	X	X	X	X
ComboBoxUI	String	X	X	X	X	X
ComponentUI	String	X	X	X	X	X
control	Color	X	X	X	X	X
controlDkShadow	Color	X	X	X	X	X
controlHighlight	Color	X	X	X	X	X
controlLightShadow	Color	X				
controlLtHighlight	Color	X	X	X	X	X
controlShadow	Color	X	X	X	X	X
controlText	Color	X	X	X	X	X
dark	Color				X	
desktop	Color	X	X	X	X	X
Desktop.ancestorInputMap	InputMap	X	X	X	X	X
Desktop.background	Color	X	X	X	X	X
Desktop.windowBindings	Object[] ^b	X	X	X	X	X
DesktopIcon.background	Color		X			
DesktopIcon.border	Border	X	X	X	X	X
DesktopIcon.font	Font		X			
DesktopIcon.foreground	Color		X			
DesktopIcon.icon	Icon	X				
DesktopIcon.width	Integer		X	X		
DesktopIcon.windowBindings	Object[] ^c	X				
DesktopIconUI	String	X	X	X	X	X
DesktopPane.actionMap	ActionMap	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
DesktopPaneUI	String	X	X	X	X	X
DirectoryPaneUI	String	X	X	X	X	X
EditorPane.actionMap	ActionMap	X	X	X	X	X
EditorPane.background	Color	X	X	X	X	X
EditorPane.border	Border	X	X	X	X	X
EditorPane.caretAspectRatio	Number				X	
EditorPane.caretBlinkRate	Integer	X	X	X	X	X
EditorPane.caretForeground	Color	X	X	X	X	X
EditorPane.focusInputMap	InputMap	X	X	X	X	X
EditorPane.font	Font	X	X	X	X	X
EditorPane.foreground	Color	X	X	X	X	X
EditorPane.inactiveForeground	Color	X	X	X	X	X
EditorPane.keyBindings	KeyBinding[]	X	X	X	X	X
EditorPane.margin	Insets	X	X	X	X	X
EditorPane.selectionBackground	Color	X	X	X	X	X
EditorPane.selectionForeground	Color	X	X	X	X	X
EditorPaneUI	String	X	X	X	X	X
FileChooser.acceptAllFileFilterText	String	X	X	X	X	X
FileChooser.ancestorInputMap	InputMap	X	X	X	X	X
FileChooser.cancelButtonMnemonic	Integer	X	X	X	X	X
FileChooser.cancelButtonText	String	X	X	X	X	X
FileChooser.cancelButtonToolTipText	String	X	X	X	X	X
FileChooser.deleteFileButtonMnemonic	Integer				X	
FileChooser.deleteFileButtonText	String				X	
FileChooser.deleteFileButtonToolTipText	String				X	
FileChooser.detailsViewButtonAccessibleName	String		X	X		
FileChooser.detailsViewButtonToolTipText	String		X	X		
FileChooser.detailsViewIcon	Icon	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
FileChooser.directoryDescription ➡ Text	String	X	X	X	X	X
FileChooser.directoryOpenButton ➡ Mnemonic	Integer	X	X	X	X	X
FileChooser.directoryOpenButton ➡ Text	String	X	X	X	X	X
FileChooser.directoryOpenButton ➡ ToolTipText	String	X	X	X	X	X
FileChooser.enterFileNameLabel ➡ Mnemonic	Integer	X				
FileChooser.enterFileNameLabel ➡ Text	String	X				
FileChooser.fileDescriptionText	String	X	X	X	X	X
FileChooser.fileNameLabelMnemonic	Integer		X	X		
FileChooser.fileNameLabelText	String		X	X		
FileChooser.filesLabelMnemonic	Integer	X				
FileChooser.filesLabelText	String	X			X	
FileChooser.filesOfTypeLabel ➡ Mnemonic	Integer		X	X		
FileChooser.filesOfTypeLabelText	String		X	X		
FileChooser.filterLabelMnemonic	Integer	X			X	
FileChooser.filterLabelText	String	X			X	
FileChooser.foldersLabelMnemonic	String	X				
FileChooser.foldersLabelText	String	X			X	
FileChooser.helpButtonMnemonic	Integer	X	X	X	X	X
FileChooser.helpButtonText	String	X	X	X	X	X
FileChooser.helpButtonToolTipText	String	X	X	X	X	X
FileChooser.homeFolder ➡ AccessibleName	String		X	X		
FileChooser.homeFolderIcon	Icon	X	X	X	X	X
FileChooser.homeFolderToolTipText	String		X	X		
FileChooser.listFont	Font			X		
FileChooser.listViewBackground	Color			X		
FileChooser.listViewBorder	Border			X		
FileChooser.listViewButton ➡ AccessibleName	String		X	X		

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
FileChooser.listViewButton➡ ToolTipText	String		X	X		
FileChooser.listViewIcon	Icon	X	X	X	X	X
FileChooser.listViewWindowsStyle	Boolean			X		
FileChooser.lookInLabelMnemonic	Integer		X	X		
FileChooser.lookInLabelText	String		X	X		
FileChooser.newFolderAccessible➡ Name	String		X	X		
FileChooser.newFolderButton➡ Mnemonic	Integer				X	
FileChooser.newFolderButtonText	String				X	
FileChooser.newFolderButtonTool➡ TipText				X		
FileChooser.newFolderDialogText	String				X	
FileChooser.newFolderError➡ Separator	String	X	X	X	X	X
FileChooser.newFolderErrorText	String	X	X	X	X	X
FileChooser.newFolderIcon	Icon	X	X	X	X	X
FileChooser.newFolderToolTipText	String		X	X		
FileChooser.openButtonMnemonic	Integer	X	X	X	X	X
FileChooser.openButtonText	String	X	X	X	X	X
FileChooser.openButtonToolTipText	String	X	X	X	X	X
FileChooser.openDialogTitleText	String	X	X	X	X	X
FileChooser.other.newFolder	String	X	X	X	X	X
FileChooser.other.newFolder. subsequent	String	X	X	X	X	X
FileChooser.pathLabelMnemonic	Integer	X			X	
FileChooser.pathLabelText	String	X			X	
FileChooser.readOnly	Boolean	X	X	X	X	X
FileChooser.renameFileButton➡ Mnemonic	Integer				X	
FileChooser.renameFileButtonText	String				X	
FileChooser.renameFileButton➡ ToolTipText	String				X	
FileChooser.renameFileDialogText	String				X	

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
FileChooser.renameFileErrorText	String				X	
FileChooser.renameFileErrorTitle	String				X	
FileChooser.saveButtonMnemonic	Integer	X	X	X	X	X
FileChooser.saveButtonText	String	X	X	X	X	X
FileChooser.saveButtonToolTipText	String	X	X	X	X	X
FileChooser.saveDialogTitleText	String	X	X	X	X	X
FileChooser.saveInLabelText	String		X	X		
FileChooser.updateButtonMnemonic	Integer	X	X	X	X	X
FileChooser.updateButtonText	String	X	X	X	X	X
FileChooser.updateButtonToolTipText	String	X	X	X	X	X
FileChooser.upFolderAccessibleName	String		X	X		
FileChooser.upFolderIcon	Icon	X	X	X	X	X
FileChooser.upFolderToolTipText	String		X	X		
FileChooser.usesSingleFilePane	Boolean	X	X	X	X	X
FileChooser.useSystemExtensionHiding	Boolean	X	X	X	X	X
FileChooser.win32.newFolder	String	X	X	X	X	X
FileChooser.win32.newFolder.subsequent	String	X	X	X	X	X
FileChooserUI	String	X	X	X	X	X
FileView.computerIcon	Icon	X	X	X	X	X
FileView.directoryIcon	Icon	X	X	X	X	X
FileView.fileIcon	Icon	X	X	X	X	X
FileView.floppyDriveIcon	Icon	X	X	X	X	X
FileView.hardDriveIcon	Icon	X	X	X	X	X
FormattedTextField.actionMap	ActionMap	X	X	X	X	X
FormattedTextField.background	Color	X	X	X	X	X
FormattedTextField.border	Border	X	X	X	X	X
FormattedTextField.caretAspectRatio	Number				X	
FormattedTextField.caretBlinkRate	Integer	X	X	X	X	X
FormattedTextField.caretForeground	Color	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
FormattedTextField.focusInputMap	InputMap	X	X	X	X	X
FormattedTextField.font	Font	X	X	X	X	X
FormattedTextField.foreground	Color	X	X	X	X	X
FormattedTextField.inactive ➡ Background	Color	X	X	X	X	X
FormattedTextField.inactive ➡ Foreground	Color	X	X	X	X	X
FormattedTextField.keyBindings	KeyBinding[]	X	X	X	X	X
FormattedTextField.margin	Insets	X	X	X	X	X
FormattedTextField.selection ➡ Background	Color	X	X	X	X	X
FormattedTextField.selection ➡ Foreground	Color	X	X	X	X	X
FormattedTextFieldUI	String	X	X	X	X	X
FormView.browseFileButtonText	String	X	X	X	X	X
FormView.resetButtonText	String	X	X	X	X	X
FormView.submitButtonText	String	X	X	X	X	X
GTKColorChooserPanel.displayed ➡ MnemonicIndex	Integer				X	
GTKColorChooserPanel.mnemonic	Integer				X	
GTKColorChooserPanel.nameText	String				X	
inactiveCaption	Color	X	X	X	X	X
inactiveCaptionBorder	Color	X	X	X	X	X
inactiveCaptionText	Color	X	X	X	X	X
info	Color	X	X	X	X	X
infoText	Color	X	X	X	X	X
InternalFrame.actionMap	ActionMap	X	X	X	X	X
InternalFrame.activeBorderColor	Color			X		
InternalFrame.activeTitle ➡ Background	Color	X	X	X	X	X
InternalFrame.activeTitle ➡ Foreground	Color	X	X	X	X	X
InternalFrame.activeTitleGradient	List		X	X		
InternalFrame.border	Border	X	X	X	X	X
InternalFrame.borderColor	Color	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
InternalFrame.borderDarkShadow	Color	X	X	X	X	X
InternalFrame.borderHighlight	Color	X	X	X	X	X
InternalFrame.borderLight	Color	X	X	X	X	X
InternalFrame.borderShadow	Color	X	X	X	X	X
InternalFrame.borderWidth	Integer			X		
InternalFrame.closeButtonToolTip	String	X	X	X	X	X
InternalFrame.closeIcon	Icon	X	X	X	X	X
InternalFrame.closeSound	String	X	X	X	X	X
InternalFrame.icon	Icon	X	X	X	X	X
InternalFrame.iconButtonToolTip	String	X	X	X	X	X
InternalFrame.iconifyIcon	Icon	X	X	X	X	X
InternalFrame.inactiveBorderColor	Color			X		
InternalFrame.inactiveTitle ➡ Background	Color	X	X	X	X	X
InternalFrame.inactiveTitle ➡ Foreground	Color	X	X	X	X	X
InternalFrame.inactiveTitle ➡ Gradient	List		X	X		
InternalFrame.layoutTitlePane ➡ AtOrigin	Boolean	X	X	X	X	X
InternalFrame.maxButtonToolTip	String	X	X	X	X	X
InternalFrame.maximizeIcon	Icon	X	X	X	X	X
InternalFrame.maximizeSound	String	X	X	X	X	X
InternalFrame.menuIcon	Icon		X			
InternalFrame.minimizeIcon	Icon	X	X	X	X	X
InternalFrame.minimizeIcon ➡ Background	Color			X		
InternalFrame.minimizeSound	String	X	X	X	X	X
InternalFrame.optionDialogBorder	Border		X			
InternalFrame.paletteBorder	Border		X			
InternalFrame.paletteCloseIcon	Icon		X			
InternalFrame.paletteTitleHeight	Integer		X			
InternalFrame.resizeIconHighlight	Color			X		
InternalFrame.resizeIconShadow	Color			X		

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
InternalFrame.restoreButton➡ ToolTip	String	X	X	X	X	X
InternalFrame.restoreDownSound	String	X	X	X	X	X
InternalFrame.restoreUpSound	String	X	X	X	X	X
InternalFrame.titleButtonHeight	Integer			X		
InternalFrame.titleButtonWidth	Integer			X		
InternalFrame.titleFont	Font	X	X	X	X	X
InternalFrame.titlePaneHeight	Integer			X		
InternalFrame.useTaskBar	Boolean				X	X
InternalFrame.windowBindings	Object[] ^d	X	X	X	X	X
InternalFrameTitlePane.close➡ ButtonAccessibleName	String	X	X	X	X	X
InternalFrameTitlePane.close➡ ButtonText	String	X	X	X	X	X
InternalFrameTitlePane.closeIcon	Icon				X	X
InternalFrameTitlePane. iconifyButtonAccessibleName	String	X	X	X	X	X
InternalFrameTitlePane. iconifyIcon	Icon				X	X
InternalFrameTitlePane. maximizeButtonAccessibleName	String	X	X	X	X	X
InternalFrameTitlePane. maximizeButtonText	String	X	X	X	X	X
InternalFrameTitlePane. maximizeIcon	Icon				X	X
InternalFrameTitlePane. minimizeButtonText	String	X	X	X	X	X
InternalFrameTitlePane. minimizeIcon	Icon				X	X
InternalFrameTitlePane. moveButtonText	String	X	X	X	X	X
InternalFrameTitlePane. restoreButtonText	String	X	X	X	X	X
InternalFrameTitlePane. sizeButtonText	String	X	X	X	X	X
InternalFrameTitlePane. titlePaneLayout	LayoutManager				X	X
InternalFrameTitlePaneUI	String			X	X	


UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
InternalFrameUI	String	X	X	X	X	X
IsindexView.prompt	String	X	X	X	X	X
Label.actionMap	ActionMap	X	X	X	X	X
Label.background	Color	X	X	X	X	X
Label.border	Border	X	X	X	X	X
Label.disabledForeground	Color	X	X	X	X	X
Label.disabledShadow	Color	X	X	X	X	X
Label.font	Font	X	X	X	X	X
Label.foreground	Color	X	X	X	X	X
LabelUI	String	X	X	X	X	X
light	Color				X	
List.actionMap	ActionMap	X	X	X	X	X
List.background	Color	X	X	X	X	X
List.border	Border	X	X	X	X	X
List.cellHeight	Integer				X	X
List.cellRenderer	ListCellRenderer ➡	X	X	X	X	X
List.focusCellHighlightBorder	Border	X	X	X	X	X
List.focusInputMap	InputMap	X	X	X	X	X
List.focusInputMap.RightToLeft	InputMap	X	X	X	X	X
List.font	Font	X	X	X	X	X
List.foreground	Color	X	X	X	X	X
List.lockToPositionOnScroll	Boolean	X	X	X	X	X
List.rendererUseListColors	Boolean				X	X
List.rendererUseUIBorder	Boolean				X	X
List.selectionBackground	Color	X	X	X	X	X
List.selectionForeground	Color	X	X	X	X	X
List.timeFactor	Long	X	X	X	X	X
ListUI	String	X	X	X	X	X
menu	Color	X	X	X	X	X
Menu.acceleratorDelimiter	String				X	X
Menu.acceleratorFont	Font	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
Menu.acceleratorForeground	Color	X	X	X	X	X
Menu.acceleratorSelection➡ Foreground	Color	X	X	X	X	X
Menu.actionMap	ActionMap	X	X	X	X	X
Menu.arrowIcon	Icon	X	X	X	X	X
Menu.background	Color	X	X	X	X	X
Menu.border	Border	X	X	X	X	X
Menu.borderPainted	Boolean	X	X	X	X	X
Menu.checkIcon	Icon	X	X	X	X	X
Menu.crossMenuMnemonic	Boolean	X	X	X	X	X
Menu.delay	Integer				X	X
Menu.disabledForeground	Color	X	X	X	X	X
Menu.font	Font	X	X	X	X	X
Menu.foreground	Color	X	X	X	X	X
Menu.margin	Insets	X	X	X	X	X
Menu.menuPopupOffsetX	Integer	X	X	X	X	X
Menu.menuPopupOffsetY	Integer	X	X	X	X	X
Menu.opaque	Boolean	X	X	X	X	X
Menu.selectionBackground	Color	X	X	X	X	X
Menu.selectionForeground	Color	X	X	X	X	X
Menu.shortcutKeys	int[]	X	X	X	X	X
Menu.submenuPopupOffsetX	Integer	X	X	X	X	X
Menu.submenuPopupOffsetY	Integer	X	X	X	X	X
Menu.textIconGap	Integer				X	X
Menu.useMenuBarBackground➡ ForTopLevel	Boolean	X	X	X	X	X
MenuBar.actionMap	ActionMap	X	X	X	X	X
MenuBar.background	Color	X	X	X	X	X
MenuBar.border	Border	X	X	X	X	X
MenuBar.borderColor	Color		X			
MenuBar.darkShadow	Color	X				
MenuBar.font	Font	X	X	X	X	X
MenuBar.foreground	Color	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
MenuBar.gradient	List		X			
MenuBar.highlight	Color	X	X	X	X	X
MenuBar.shadow	Color	X	X	X	X	X
MenuBar.windowBindings	Object[] ^e	X	X	X	X	X
MenuBarUI	String	X	X	X	X	X
MenuItem.acceleratorDelimiter	String	X	X	X	X	X
MenuItem.acceleratorFont	Font	X	X	X	X	X
MenuItem.acceleratorForeground	Color	X	X	X	X	X
MenuItem.acceleratorSelection  Foreground	Color	X	X	X	X	X
MenuItem.actionMap	ActionMap	X	X	X	X	X
MenuItem.arrowIcon	Icon	X	X	X	X	X
MenuItem.background	Color	X	X	X	X	X
MenuItem.border	Border	X	X	X	X	X
MenuItem.borderPainted	Boolean	X	X	X	X	X
MenuItem.checkIcon	Icon	X	X	X	X	X
MenuItem.commandSound	String	X	X	X	X	X
MenuItem.disabledForeground	Color	X	X	X	X	X
MenuItem.font	Font	X	X	X	X	X
MenuItem.foreground	Color	X	X	X	X	X
MenuItem.margin	Insets	X	X	X	X	X
MenuItem.opaque	Boolean	X	X	X	X	X
MenuItem.selectionBackground	Color	X	X	X	X	X
MenuItem.selectionForeground	Color	X	X	X	X	X
MenuItem.textIconGap	Integer				X	X
MenuItemUI	String	X	X	X	X	X
menuPressedItemB	Color			X		
menuPressedItemF	Color			X		
menuText	Color	X	X	X	X	X
MenuUI	String	X	X	X	X	X
MetalTitlePane.closeMnemonic	Integer		X			
MetalTitlePane.closeTitle	String		X			

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
MetalTitlePane.iconifyMnemonic	Integer		X			
MetalTitlePane.iconifyTitle	String		X			
MetalTitlePane.maximizeMnemonic	Integer		X			
MetalTitlePane.maximizeTitle	String		X			
MetalTitlePane.restoreMnemonic	Integer		X			
MetalTitlePane.restoreTitle	String		X			
mid	Color				X	
OptionPane.actionMap	ActionMap	X	X	X	X	X
OptionPane.background	Color	X	X	X	X	X
OptionPane.border	Border	X	X	X	X	X
OptionPane.buttonAreaBorder	Border	X	X	X	X	X
OptionPane.buttonClickThreshold	Integer	X	X	X	X	X
OptionPane.buttonFont	Font	X	X	X	X	X
OptionPane.buttonOrientation	Integer	X	X	X	X	X
OptionPane.buttonPadding	Integer	X	X	X	X	X
OptionPane.cancelButtonMnemonic	String	X	X	X	X	X
OptionPane.cancelButtonText	String	X	X	X	X	X
OptionPane.cancelIcon	Icon	X	X	X	X	X
OptionPane.error➡ Dialog.border.background	Color		X			
OptionPane.error➡ Dialog.titlePane.background	Color		X			
OptionPane.error➡ Dialog.titlePane.foreground	Color		X			
OptionPane.error➡ Dialog.titlePane.shadow	Color		X			
OptionPane.errorIcon	Icon	X	X	X	X	X
OptionPane.errorSound	String	X	X	X	X	X
OptionPane.font	Font	X	X	X	X	X
OptionPane.foreground	Color	X	X	X	X	X
OptionPane.informationIcon	Icon	X	X	X	X	X
OptionPane.informationSound	String	X	X	X	X	X
OptionPane.inputDialogTitle	String	X	X	X	X	X
OptionPane.isYesLast	Boolean	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
OptionPane.messageAnchor	Integer	X	X	X	X	X
OptionPane.messageAreaBorder	Border	X	X	X	X	X
OptionPane.messageDialogTitle	String	X	X	X	X	X
OptionPane.messageFont	Font	X	X	X	X	X
OptionPane.messageForeground	Color	X	X	X	X	X
OptionPane.minimumSize	Dimension	X	X	X	X	X
OptionPane.noButtonMnemonic	String	X	X	X	X	X
OptionPane.noButtonText	String	X	X	X	X	X
OptionPane.noIcon	Icon	X	X	X	X	X
OptionPane.okButtonMnemonic	String	X	X	X	X	X
OptionPane.okButtonText	String	X	X	X	X	X
OptionPane.okIcon	Icon	X	X	X	X	X
OptionPane.questionDialog. border.background	Color		X			
OptionPane.questionDialog. titlePane.background	Color		X			
OptionPane.questionDialog. titlePane.foreground	Color		X			
OptionPane.questionDialog. titlePane.shadow	Color		X			
OptionPane.questionIcon	Icon	X	X	X	X	X
OptionPane.questionSound	String	X	X	X	X	X
OptionPane.sameSizeButtons	Boolean	X	X	X	X	X
OptionPane.separatorPadding	Integer				X	X
OptionPane.setButtonMargin	Boolean	X	X	X	X	X
OptionPane.titleText	String	X	X	X	X	X
OptionPane.warningDialog. border.background	Color		X			
OptionPane.warningDialog. titlePane.background	Color		X			
OptionPane.warningDialog. titlePane.foreground	Color		X			
OptionPane.warningDialog. titlePane.shadow	Color		X			
OptionPane.warningIcon	Icon	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
OptionPane.warningSound	String	X	X	X	X	X
OptionPane.windowBindings	Object[] ^f	X	X	X	X	X
OptionPane.yesButtonMnemonic	String	X	X	X	X	X
OptionPane.yesButtonText	String	X	X	X	X	X
OptionPane.yesIcon	Icon	X	X	X	X	X
OptionPaneUI	String	X	X	X	X	X
Panel.background	Color	X	X	X	X	X
Panel.border	Border	X	X	X	X	X
Panel.font	Font	X	X	X	X	X
Panel.foreground	Color	X	X	X	X	X
PanelUI	String	X	X	X	X	X
PasswordField.actionMap	ActionMap	X	X	X	X	X
PasswordField.background	Color	X	X	X	X	X
PasswordField.border	Border	X	X	X	X	X
PasswordField.caretAspectRatio	Number				X	
PasswordField.caretBlinkRate	Integer	X	X	X	X	X
PasswordField.caretForeground	Color	X	X	X	X	X
PasswordField.disabledBackground	Color			X		
PasswordField.focusInputMap	InputMap	X	X	X	X	X
PasswordField.font	Font	X	X	X	X	X
PasswordField.foreground	Color	X	X	X	X	X
PasswordField.inactiveBackground	Color	X	X	X	X	X
PasswordField.inactiveForeground	Color	X	X	X	X	X
PasswordField.keyBindings	KeyBinding[]	X	X	X	X	X
PasswordField.margin	Insets	X	X	X	X	X
PasswordField.selectionBackground	Color	X	X	X	X	X
PasswordField.selectionForeground	Color	X	X	X	X	X
PasswordFieldUI	String	X	X	X	X	X
PopupMenu.actionMap	ActionMap	X	X	X	X	X
PopupMenu.background	Color	X	X	X	X	X
PopupMenu.border	Border	X	X	X	X	X
PopupMenu.consumeEventOnClose	Boolean	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
PopupMenu.font	Font	X	X	X	X	X
PopupMenu.foreground	Color	X	X	X	X	X
PopupMenu.popupSound	String	X	X	X	X	X
PopupMenu.selectedWindow➡ InputMapBindings	Object[] ^g	X	X	X	X	X
PopupMenu.selectedWindow➡ InputMapBindings.RightToLeft	Object[] ^h	X	X	X	X	X
PopupMenuSeparatorUI	String	X	X	X	X	X
PopupMenuUI	String	X	X	X	X	X
ProgressBar.background	Color	X	X	X	X	X
ProgressBar.border	Border	X	X	X	X	X
ProgressBar.cellLength	Integer	X	X	X	X	X
ProgressBar.cellSpacing	Integer	X	X	X	X	X
ProgressBar.cycleTime	Integer	X	X	X	X	X
ProgressBar.font	Font	X	X	X	X	X
ProgressBar.foreground	Color	X	X	X	X	X
ProgressBar.highlight	Color			X		
ProgressBar.horizontalSize	Dimension	X	X	X	X	X
ProgressBar.repaintInterval	Integer	X	X	X	X	X
ProgressBar.selectionBackground	Color	X	X	X	X	X
ProgressBar.selectionForeground	Color	X	X	X	X	X
ProgressBar.shadow	Color			X		
ProgressBar.verticalSize	Dimension	X	X	X	X	X
ProgressBarUI	String	X	X	X	X	X
ProgressMonitor.progressText	String	X	X	X	X	X
RadioButton.background	Color	X	X	X	X	X
RadioButton.border	Border	X	X	X	X	X
RadioButton.darkShadow	Color	X	X	X	X	X
RadioButton.disabledText	Color		X			
RadioButton.focus	Color	X	X	X		
RadioButton.focusInputMap	InputMap	X	X	X	X	X
RadioButton.font	Font	X	X	X	X	X
RadioButton.foreground	Color	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
RadioButton.gradient	List		X			
RadioButton.highlight	Color	X	X	X	X	X
RadioButton.icon	Icon	X	X	X	X	X
RadioButton.interiorBackground	Color			X		
RadioButton.light	Color	X	X	X	X	X
RadioButton.margin	Insets	X	X	X	X	X
RadioButton.rollover	Boolean		X			
RadioButton.select	Color		X			
RadioButton.shadow	Color	X	X	X	X	X
RadioButton.textIconGap	Integer	X	X	X	X	X
RadioButton.textShiftOffset	Integer	X	X	X	X	X
RadioButtonMenuItem. acceleratorFont	Font	X	X	X	X	X
RadioButtonMenuItem. acceleratorForeground	Color	X	X	X	X	X
RadioButtonMenuItem. acceleratorSelectionForeground	Color	X	X	X	X	X
RadioButtonMenuItem.actionMap	ActionMap	X	X	X	X	X
RadioButtonMenuItem.arrowIcon	Icon	X	X	X	X	X
RadioButtonMenuItem.background	Color	X	X	X	X	X
RadioButtonMenuItem.border	Border	X	X	X	X	X
RadioButtonMenuItem.borderPainted	Boolean	X	X	X	X	X
RadioButtonMenuItem.checkIcon	Icon	X	X	X	X	X
RadioButtonMenuItem.commandSound	String	X	X	X	X	X
RadioButtonMenuItem. disabledForeground	Color	X	X	X	X	X
RadioButtonMenuItem.font	Font	X	X	X	X	X
RadioButtonMenuItem.foreground	Color	X	X	X	X	X
RadioButtonMenuItem.gradient	List		X			
RadioButtonMenuItem.margin	Insets	X	X	X	X	X
RadioButtonMenuItem.opaque	Boolean	X	X	X	X	X
RadioButtonMenuItem. selectionBackground	Color	X	X	X	X	X
RadioButtonMenuItem. selectionForeground	Color	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
RadioButtonMenuItemUI	String	X	X	X	X	X
RadioButtonUI	String	X	X	X	X	X
RootPane.actionMap	ActionMap	X	X	X	X	X
RootPane.ancestorInputMap	InputMap	X	X	X	X	X
RootPane.colorChooserDialogBorder	Border		X			
RootPane.defaultButton ➡ WindowKeyBindings	Object[] ⁱ	X	X	X	X	X
RootPane.errorDialogBorder	Border		X			
RootPane.fileChooserDialogBorder	Border		X			
RootPane.frameBorder	Border		X			
RootPane.informationDialogBorder	Border		X			
RootPane.plainDialogBorder	Border		X			
RootPane.questionDialogBorder	Border		X			
RootPane.warningDialogBorder	Border		X			
RootPaneUI	String	X	X	X	X	X
scrollbar	Color	X	X	X	X	X
ScrollBar.actionMap	ActionMap	X	X	X	X	X
ScrollBar.allowsAbsolute ➡ Positioning	Boolean	X	X	X	X	X
ScrollBar.ancestorInputMap	InputMap	X	X	X	X	X
ScrollBar.ancestorInputMap. RightToLeft	InputMap	X	X	X	X	X
ScrollBar.background	Color	X	X	X	X	X
ScrollBar.border	Color	X	X	X	X	X
ScrollBar.darkShadow	Color		X			
ScrollBar.focusInputMap	InputMap	X	X	X	X	X
ScrollBar.focusInputMap. RightToLeft	InputMap	X	X	X	X	X
ScrollBar.foreground	Color	X	X	X	X	X
ScrollBar.gradient	List		X			
ScrollBar.highlight	Color		X			

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
ScrollBar.maximumThumbSize	Dimension	X	X	X	X	X
ScrollBar.minimumThumbSize	Dimension	X	X	X	X	X
ScrollBar.shadow	Color		X			
ScrollBar.squareButtons	Boolean	X	X	X	X	X
ScrollBar.thumb	Color	X	X	X	X	X
ScrollBar.thumbDarkShadow	Color	X	X	X	X	X
ScrollBar.thumbHeight	Integer				X	X
ScrollBar.thumbHighlight	Color	X	X	X	X	X
ScrollBar.thumbShadow	Color	X	X	X	X	X
ScrollBar.track	Color	X	X	X	X	X
ScrollBar.trackForeground	Color			X		
ScrollBar.trackHighlight	Color	X	X	X	X	X
ScrollBar.trackHighlight ➡ Foreground	Color			X		
ScrollBar.width	Integer	X	X	X	X	X
ScrollBarUI	String	X	X	X	X	X
ScrollPane.actionMap	ActionMap	X	X	X	X	X
ScrollPane.ancestorInputMap	InputMap	X	X	X	X	X
ScrollPane.ancestorInputMap. RightToLeft	InputMap	X	X	X	X	X
ScrollPane.background	Color	X	X	X	X	X
ScrollPane.border	Border	X	X	X	X	X
ScrollPane.font	Font	X	X	X	X	X
ScrollPane.foreground	Color	X	X	X	X	X
ScrollPane.viewportBorder	Border	X	X	X	X	X
ScrollPane.viewportBorderInsets	Insets				X	X
ScrollPaneUI	String	X	X	X	X	X
Separator.background	Color	X	X	X	X	X
Separator.foreground	Color	X	X	X	X	X
Separator.highlight ^j	Color	X	X	X	X	X
Separator.insets	Insets				X	
Separator.shadow ^k	Color	X	X	X	X	X
Separator.thickness	Integer				X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
SeparatorUI	String	X	X	X	X	X
Slider.actionMap	ActionMap	X	X	X	X	X
Slider.altTrackColor	Color		X			
Slider.background	Color	X	X	X	X	X
Slider.border	Border	X	X	X	X	X
Slider.darkShadow	Color		X			
Slider.focus	Color	X	X	X	X	X
Slider.focusGradient	List		X			
Slider.focusInputMap	InputMap	X	X	X	X	X
Slider.focusInputMap.RightToLeft	InputMap	X	X	X	X	X
Slider.focusInsets	Insets	X	X	X	X	X
Slider.foreground	Color	X	X	X	X	X
Slider.gradient	List		X			
Slider.highlight	Color	X	X	X	X	X
Slider.horizontalSize	Dimension	X	X	X	X	X
Slider.horizontalThumbIcon	Icon		X			
Slider.majorTickLength	Integer		X			
Slider.minimumHorizontalSize	Dimension	X	X	X	X	X
Slider.minimumVerticalSize	Dimension	X	X	X	X	X
Slider.paintThumbArrowShape	Boolean	X	X	X	X	X
Slider.paintValue	Boolean				X	X
Slider.shadow	Color	X	X	X	X	X
Slider.thumb	Color		X			
Slider.thumbHeight	Integer				X	X
Slider.thumbWidth	Integer				X	X
Slider.tickColor	Color	X	X	X	X	X
Slider.trackBorder	Border				X	X
Slider.trackWidth	Integer		X			
Slider.verticalSize	Dimension	X	X	X	X	X
Slider.verticalThumbIcon	Icon		X			
SliderUI	String	X	X	X	X	X
Spinner.actionMap	ActionMap	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
Spinner.ancestorInputMap	InputMap	X	X	X	X	X
Spinner.arrowButtonBorder	Border	X	X	X	X	X
Spinner.arrowButtonInsets	Insets	X	X	X	X	X
Spinner.arrowButtonSize	Dimension	X	X	X	X	X
Spinner.background	Color	X	X	X	X	X
Spinner.border	Border	X	X	X	X	X
Spinner.editorBorderPainted	Boolean	X	X	X	X	X
Spinner.font	Font	X	X	X	X	X
Spinner.foreground	Color	X	X	X	X	X
SpinnerUI	String	X	X	X	X	X
SplitPane.actionMap	ActionMap	X	X	X	X	X
SplitPane.activeThumb	Color	X				
SplitPane.ancestorInputMap	InputMap	X	X	X	X	X
SplitPane.background	Color	X	X	X	X	X
SplitPane.border	Border	X	X	X	X	X
SplitPane.centerOneTouchButtons	Boolean	X	X	X	X	X
SplitPane.darkShadow	Color	X	X	X	X	X
SplitPane.dividerFocusColor	Color		X			
SplitPane.dividerSize	Integer	X	X	X	X	X
SplitPane.highlight	Color	X	X	X	X	X
SplitPane.leftButtonText	String	X	X	X	X	X
SplitPane.oneTouchButtonOffset	Integer	X	X	X	X	X
SplitPane.oneTouchButtonSize	Integer	X	X	X	X	X
SplitPane.oneTouchButtonsOpaque	Boolean		X			
SplitPane.oneTouchExpandable	Boolean				X	X
SplitPane.oneTouchOffset	Integer				X	
SplitPane.rightButtonText	String	X	X	X	X	X
SplitPane.shadow	Color	X	X	X	X	X
SplitPane.size	Integer				X	X
SplitPane.supportsOneTouchButtons	Boolean	X	X	X	X	X
SplitPaneDivider.border	Border	X	X	X	X	X
SplitPaneDivider.draggingColor	Color	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
SplitPaneDivider.oneTouchButton ➡ Size	Integer				X	X
SplitPaneUI	String	X	X	X	X	X
StandardDialogUI	String	X	X	X	X	X
swing.boldMetal	Boolean		X			
swing.plaf.metal.controlFont	Font		X			
swing.plaf.metal.smallFont	Font		X			
swing.plaf.metal.systemFont	Font		X			
swing.plaf.metal.userFont	Font		X			
TabbedPane.actionMap	ActionMap	X	X	X	X	X
TabbedPane.ancestorInputMap	InputMap	X	X	X	X	X
TabbedPane.background	Color	X	X	X	X	X
TabbedPane.borderHighlightColor	Color		X			
TabbedPane.contentAreaColor	Color	X	X	X	X	X
TabbedPane.contentBorderInsets	Insets	X	X	X	X	X
TabbedPane.contentOpaque	Boolean	X	X	X	X	X
TabbedPane.darkShadow	Color	X	X	X	X	X
TabbedPane.focus	Color	X	X	X	X	X
TabbedPane.focusInputMap	InputMap	X	X	X	X	X
TabbedPane.font	Font	X	X	X	X	X
TabbedPane.foreground	Color	X	X	X	X	X
TabbedPane.highlight	Color	X	X	X	X	X
TabbedPane.light	Color	X	X	X	X	X
TabbedPane.opaque	Boolean	X	X	X	X	X
TabbedPane.selected	Color	X	X	X	X	X
TabbedPane.selectedForeground	Color	X	X	X	X	X
TabbedPane.selectedTabPadInsets	Insets	X	X	X	X	X
TabbedPane.selectHighlight	Color		X			
TabbedPane.selectionFollowsFocus	Boolean	X	X	X	X	X
TabbedPane.shadow	Color	X	X	X	X	X
TabbedPane.tabAreaBackground	Color	X	X	X	X	X
TabbedPane.tabAreaInsets	Insets	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
TabbedPane.tabInsets	Insets	X	X	X	X	X
TabbedPane.tabRunOverlay	Integer	X	X	X	X	X
TabbedPane.tabsOpaque	Boolean	X	X	X	X	X
TabbedPane.tabsOverlapBorder	Boolean	X	X	X	X	X
TabbedPane.textIconGap	Integer	X	X	X	X	X
TabbedPane.unselectedBackground	Color		X			
TabbedPane.unselectedTab ➡ Background	Color	X				
TabbedPane.unselectedTab ➡ Foreground	Color	X				
TabbedPane.unselectedTabHighlight	Color	X				
TabbedPane.unselectedTabShadow	Color	X				
TabbedPaneUI	String	X	X	X	X	X
Table.actionMap	ActionMap	X	X	X	X	X
Table.ancestorInputMap	InputMap	X	X	X	X	X
Table.ancestorInputMap. RightToLeft	InputMap	X	X	X	X	X
Table.background	Color	X	X	X	X	X
Table.darkShadow	Color			X		
Table.focusCellBackground	Color	X	X	X	X	X
Table.focusCellForeground	Color	X	X	X	X	X
Table.focusCellHighlightBorder	Border	X	X	X	X	X
Table.font	Font	X	X	X	X	X
Table.foreground	Color	X	X	X	X	X
Table.gridColor	Color	X	X	X	X	X
Table.highlight	Color			X		
Table.light	Color			X		
Table.rendererUseTableColors	Boolean				X	X
Table.rendererUseUIBorder	Boolean				X	X
Table.rowHeight	Integer				X	X
Table.scrollPaneBorder	Border	X	X	X	X	X
Table.selectionBackground	Color	X	X	X	X	X
Table.selectionForeground	Color	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
Table.shadow	Color			X		
TableHeader.background	Color	X	X	X	X	X
TableHeader.cellBorder	Border	X	X	X	X	X
TableHeader.font	Font	X	X	X	X	X
TableHeader.foreground	Color	X	X	X	X	X
TableHeaderUI	String	X	X	X	X	X
TableUI	String	X	X	X	X	X
text	Color	X	X	X	X	X
TextArea.actionMap	ActionMap	X	X	X	X	X
TextArea.background	Color	X	X	X	X	X
TextArea.border	Border	X	X	X	X	X
TextArea.caretAspectRatio	Number				X	
TextArea.caretBlinkRate	Integer	X	X	X	X	X
TextArea.caretForeground	Color	X	X	X	X	X
TextArea.focusInputMap	InputMap	X	X	X	X	X
TextArea.font	Font	X	X	X	X	X
TextArea.foreground	Color	X	X	X	X	X
TextArea.inactiveForeground	Color	X	X	X	X	X
TextArea.keyBindings	KeyBinding[]	X	X	X	X	X
TextArea.margin	Insets	X	X	X	X	X
TextArea.selectionBackground	Color	X	X	X	X	X
TextArea.selectionForeground	Color	X	X	X	X	X
TextAreaUI	String	X	X	X	X	X
TextField.actionMap	ActionMap	X	X	X	X	X
TextField.background	Color	X	X	X	X	X
TextField.border	Border	X	X	X	X	X
TextField.caretAspectRatio	Number				X	X
TextField.caretBlinkRate	Integer	X	X	X	X	X
TextField.caretForeground	Color	X	X	X	X	X
TextField.darkShadow	Color	X	X	X	X	X
TextField.disabledBackground	Color	X	X	X	X	X
TextField.focusInputMap	InputMap	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
TextField.font	Font	X	X	X	X	X
TextField.foreground	Color	X	X	X	X	X
TextField.highlight	Color	X	X	X	X	X
TextField.inactiveBackground	Color	X	X	X	X	X
TextField.inactiveForeground	Color	X	X	X	X	X
TextField.keyBindings	KeyBinding[]	X	X	X	X	X
TextField.light	Color	X	X	X	X	X
TextField.margin	Insets	X	X	X	X	X
TextField.selectionBackground	Color	X	X	X	X	X
TextField.selectionForeground	Color	X	X	X	X	X
TextField.shadow	Color	X	X	X	X	X
TextFieldUI	String	X	X	X	X	X
textHighlight	Color	X	X	X	X	X
textHighlightText	Color	X	X	X	X	X
textInactiveText	Color	X	X	X	X	X
TextPane.actionMap	ActionMap	X	X	X	X	X
TextPane.background	Color	X	X	X	X	X
TextPane.border	Border	X	X	X	X	X
TextPane.caretAspectRatio	Number				X	
TextPane.caretBlinkRate	Integer	X	X	X	X	X
TextPane.caretForeground	Color	X	X	X	X	X
TextPane.focusInputMap	InputMap	X	X	X	X	X
TextPane.font	Font	X	X	X	X	X
TextPane.foreground	Color	X	X	X	X	X
TextPane.inactiveForeground	Color	X	X	X	X	X
TextPane.keyBindings	KeyBinding[]	X	X	X	X	X
TextPane.margin	Insets	X	X	X	X	X
TextPane.selectionBackground	Color	X	X	X	X	X
TextPane.selectionForeground	Color	X	X	X	X	X
TextPaneUI	String	X	X	X	X	X
textText	Color	X	X	X	X	X
TitledBorder.border	Border	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
TitledBorder.font	Font	X	X	X	X	X
TitledBorder.titleColor	Color	X	X	X	X	X
ToggleButton.background	Color	X	X	X	X	X
ToggleButton.border	Border	X	X	X	X	X
ToggleButton.darkShadow	Color	X	X	X	X	X
ToggleButton.disabledText	Color		X			
ToggleButton.focus	Color		X	X		
ToggleButton.focusInputMap	InputMap	X	X	X	X	X
ToggleButton.font	Font	X	X	X	X	X
ToggleButton.foreground	Color	X	X	X	X	X
ToggleButton.gradient	List		X			
ToggleButton.highlight	Color	X	X	X	X	X
ToggleButton.light	Color	X	X	X	X	X
ToggleButton.margin	Insets	X	X	X	X	X
ToggleButton.select	Color	X	X			
ToggleButton.shadow	Color	X	X	X	X	X
ToggleButton.textIconGap	Integer	X	X	X	X	X
ToggleButton.textShiftOffset	Integer	X	X	X	X	X
ToggleButtonUI	String	X	X	X	X	X
ToolBar.actionMap	ActionMap	X	X	X	X	X
ToolBar.ancestorInputMap	InputMap	X	X	X	X	X
ToolBar.background	Color	X	X	X	X	X
ToolBar.border	Border	X	X	X	X	X
ToolBar.borderColor	Color		X			
ToolBar.darkShadow	Color	X	X	X	X	X
ToolBar.dockingBackground	Color	X	X	X	X	X
ToolBar.dockingForeground	Color	X	X	X	X	X
ToolBar.floatingBackground	Color	X	X	X	X	X
ToolBar.floatingForeground	Color	X	X	X	X	X
ToolBar.font	Font	X	X	X	X	X
ToolBar.foreground	Color	X	X	X	X	X
ToolBar.handleIcon	Icon				X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
ToolBar.highlight	Color	X	X	X	X	X
ToolBar.isRollover	Boolean	X	X	X	X	X
ToolBar.light	Color	X	X	X	X	X
ToolBar.nonrolloverBorder	Border	X	X	X	X	X
ToolBar.rolloverBorder	Border	X	X	X	X	X
ToolBar.separatorSize	Dimension	X	X	X	X	X
ToolBar.shadow	Color	X	X	X	X	X
ToolBarSeparatorUI	String	X	X	X	X	X
ToolBarUI	String	X	X	X	X	X
ToolTip.background	Color	X	X	X	X	X
ToolTip.backgroundInactive	Color	X	X	X	X	X
ToolTip.border	Border	X	X	X	X	X
ToolTip.borderInactive	Color	X	X	X	X	X
ToolTip.font	Font	X	X	X	X	X
ToolTip.foreground	Color	X	X	X	X	X
ToolTip.foregroundInactive	Color	X	X	X	X	X
ToolTip.hideAccelerator	Boolean		X			
ToolTipUI	String	X	X	X	X	X
Tree.actionMap	ActionMap	X	X	X	X	X
Tree.ancestorInputMap	InputMap	X	X	X	X	X
Tree.background	Color	X	X	X	X	X
Tree.changeSelectionWithFocus	Boolean	X	X	X	X	X
Tree.closedIcon	Icon	X	X	X	X	X
Tree.collapsedIcon	Icon	X	X	X	X	X
Tree.drawDashedFocusIndicator	Boolean			X		
Tree.drawHorizontalLines	Boolean				X	X
Tree.drawsFocusBorderAroundIcon	Boolean	X	X	X	X	X
Tree.drawVerticalLines	Boolean				X	X
Tree.editorBorder	Border	X	X	X	X	X
Tree.editorBorderSelectionColor	Color	X				
Tree.expandedIcon	Icon	X	X	X	X	X
Tree.expanderSize	Integer				X	

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
Tree.focusInputMap	InputMap	X	X	X	X	X
Tree.focusInputMap.RightToLeft	InputMap	X	X	X	X	X
Tree.font	Font	X	X	X	X	X
Tree.foreground	Color	X	X	X	X	X
Tree.hash	Color	X	X	X	X	X
Tree.iconBackground	Color	X				
Tree.iconForeground	Color	X				
Tree.iconHighlight	Color	X				
Tree.iconShadow	Color	X				
Tree.leafIcon	Icon	X	X	X	X	X
Tree.leftChildIndent	Integer	X	X	X	X	X
Tree.line	Color		X			
Tree.lineTypeDashed	Boolean	X	X	X	X	X
Tree.openIcon	Icon	X	X	X	X	X
Tree.padding	Integer				X	X
Tree.paintLines	Boolean	X	X	X	X	X
Tree.rendererUseTreeColors	Boolean				X	X
Tree.rightChildIndent	Integer	X	X	X	X	X
Tree.rowHeight	Integer	X	X	X	X	X
Tree.scrollsHorizontally AndVertically ➡	Boolean	X	X	X	X	X
Tree.scrollsOnExpand	Boolean	X	X	X	X	X
Tree.selectionBackground	Color	X	X	X	X	X
Tree.selectionBorderColor	Color	X	X	X	X	X
Tree.selectionForeground	Color	X	X	X	X	X
Tree.showsRootHandles	Boolean	X	X	X	X	X
Tree.textBackground	Color	X	X	X	X	X
Tree.textForeground	Color	X	X	X	X	X
Tree.timeFactor	Integer	X	X	X	X	X
TreeUI	String	X	X	X	X	X
Viewport.background	Color	X	X	X	X	X
Viewport.font	Font	X	X	X	X	X

UIResource Elements for the Predefined Look and Feel Classes (Continued)

Property String	Object Type	CDE/Motif	Metal	Windows	GTK	Synth
Viewport.foreground	Color	X	X	X	X	X
ViewportUI	String	X	X	X	X	X
white	Color				X	
win.ansiVar.font.height	Integer		X	X		
win.frame.captionFont.height	Integer		X	X		
win.menu.font.height	Integer		X	X		
win.tooltip.font.height	Integer		X	X		
window	Color	X	X	X	X	X
windowBorder	Color	X	X	X	X	X
windowText	Color	X	X	X	X	X

- a. Lowercase “b” is correct.
- b. Flattened ComponentInputMap pieces. Describes the InputMap, with every even number item being a String giving the KeyStroke as specified in KeyStroke.getKeyStroke(String) (or a KeyStroke), and every odd number item the Object used to determine the associated Action in an ActionMap.
- c. Flattened ComponentInputMap pieces. Describes the InputMap, with every even number item being a String giving the KeyStroke as specified in KeyStroke.getKeyStroke(String) (or a KeyStroke), and every odd number item the Object used to determine the associated Action in an ActionMap.
- d. Flattened ComponentInputMap pieces. Describes the InputMap, with every even number item being a String giving the KeyStroke as specified in KeyStroke.getKeyStroke(String) (or a KeyStroke), and every odd number item the Object used to determine the associated Action in an ActionMap.
- e. Flattened ComponentInputMap pieces. Describes the InputMap, with every even number item being a String giving the KeyStroke as specified in KeyStroke.getKeyStroke(String) (or a KeyStroke), and every odd number item the Object used to determine the associated Action in an ActionMap.
- f. Flattened ComponentInputMap pieces. Describes the InputMap, with every even number item being a String giving the KeyStroke as specified in KeyStroke.getKeyStroke(String) (or a KeyStroke), and every odd number item the Object used to determine the associated Action in an ActionMap.
- g. Flattened ComponentInputMap pieces. Describes the InputMap, with every even number item being a String giving the KeyStroke as specified in KeyStroke.getKeyStroke(String) (or a KeyStroke), and every odd number item the Object used to determine the associated Action in an ActionMap.
- h. Flattened ComponentInputMap pieces. Describes the InputMap, with every even number item being a String giving the KeyStroke as specified in KeyStroke.getKeyStroke(String) (or a KeyStroke), and every odd number item the Object used to determine the associated Action in an ActionMap.
- i. Flattened ComponentInputMap pieces. Describes the InputMap, with every even number item being a String giving the KeyStroke as specified in KeyStroke.getKeyStroke(String) (or a KeyStroke), and every odd number item the Object used to determine the associated Action in an ActionMap.
- j. Deprecated, do not use. Property still set and available though.
- k. Deprecated, do not use. Property still set and available though.

INDEX

A

- AbstractAction class, 170
 - default implementation of Action interface, 38
 - lookup property keys, 41
 - properties, 41
 - Swing-specific event handling, 37
 - TextAction class as extension of, 535
 - using actions, 38–41
- AbstractBorder class
 - creating, 216
 - extending to create borders, 232
 - implements Border interface, 212
 - javax.swing.border package, 216
 - methods, 217
- AbstractButton class
 - as parent class, 64
 - ButtonModel interface, 99
 - components grouped into ButtonGroup class, 115
 - DefaultButtonModel interface, 99
 - handling events, 102
 - icons, 102
 - internal positioning, 102
 - mnemonics, 101
 - parent class to JButton class, 67
 - properties, 98
- AbstractCellEditor class, 623, 676
 - creating CheckBoxNodeEditor class 653–658
 - managing CellEditorListener objects, 653
- AbstractColorChooserPanel class, 301
 - getDefaultChooserPanels() method, 320
 - implementing methods, 313
 - installChooserPanel() method, 312
 - represented by tabs in upper part of JColorChooser, 310
 - subclassing, 311
- AbstractDocument class, 521
 - attaching DocumentFilter to, 538
 - introduction, 540
 - PlainDocument class as specific implementation of, 541
 - properties, 540
 - setDocumentFilter() method, 542
- AbstractDocument.Content class
 - implementations, 596
- AbstractFormatter class
 - as mask for formatted text, 566
- AbstractFormatterFactory class, 566
 - as mask for formatted text, 566
- AbstractLayoutCache class
 - implements RowMapper interface, 670
- AbstractListModel class, 451
 - extended by DefaultComboBoxModel class, 460
 - introduction, 452
 - subclassing, 462
- AbstractSpinnerModel class
 - AbstractSpinnerModel class
 - implements, 514
 - introduction, 513
 - SpinnerListModel class implements, 513
 - SpinnerNumberModel class
 - implements, 513
- AbstractTableModel class
 - data storage, 676
 - enabling default table cell renderers, 694–695
 - introduction, 691, 692
 - specifying fixed JTable columns, 692–694
- AbstractUndoableEdit class, 783, 788
 - subclassing, 798
 - UIResource Elements, 791
- Abstract Window Toolkit (AWT), 1
 - accelerator property
 - JMenu class, 171
 - JMenuItem class, 164
 - acceleratorForeground property
 - MetalLookAndFeel class, 772
 - accelerators, 46

- acceleratorSelectedForeground property
 - MetalLookAndFeel class, 772
- accept() method
 - filechooser class, 331
- acceptAllFileFilter property
 - JFileChooser class, 327
- acceptAllFileFilterUsed property
 - JFileChooser class, 327
- accessibility, 805
 - classes, 805, 806
 - Accessible interface, 806
 - AccessibleContext class, 806
 - creating accessible components, 807
 - Java Access Bridge, 808–810
- accessibility classes
 - javax.accessibility package, 805
- Accessible interface, 806
 - implementation of, 807
- accessibleAction property
 - AccessibleContext class, 806
- accessibleChildrenCount property
 - AccessibleContext class, 806
- accessibleComponent property
 - AccessibleContext class, 806
- AccessibleContext class
 - extending JComponent.
 - AccessibleJComponent, 807
 - introduction, 806
 - setAccessibleDescription() method, 807
- accessibleContext property
 - Box class, 379
 - JButton class, 105
 - JCheckBox class, 127
 - JCheckBoxMenuItem component, 185
 - JColorChooser class, 307
 - JComboBox class, 492
 - JComponent class, 79
 - JDesktopPane component, 263
 - JDialog class, 250
 - JEditorPane class, 575
 - JFileChooser class, 327
 - JFrame class, 243
 - JInternalFrame class, 254
 - JLabel class, 89
 - JLayeredPane class, 242
 - JList class, 464
 - JMenu class, 171
 - JMenuBar class, 159
 - JMenuItem class, 164
 - JOptionPane class, 281
 - JPasswordField class, 564
 - JPopupMenu class, 179
 - JProgressBar component, 440
 - JRadioButton class, 136
 - JRadioButtonMenuItem component, 191
 - JRootPane class, 237
 - JScrollBar component, 426
 - JScrollPane class, 407
 - JSeparator class, 175
 - JSlider component, 431
 - JSpinner class, 510
 - JSplitPane class, 385
 - JTabbedPane class, 399
 - JTable class, 681
 - JTableHeader class, 716
 - JTextArea class, 571
 - JTextComponent class, 523
 - JTextField class, 529
 - JToggleButton class, 120
 - JToolBar class, 203
 - JToolTip class, 85
 - JTree class, 628
 - JViewport class, 412
 - JWindow class, 248
 - ProgressMonitor class, 296
- accessibleDescription property
 - AccessibleContext class, 806
- accessibleEditableText property
 - AccessibleContext class, 806
- accessibleIcon property
 - AccessibleContext class, 807
- accessibleIndexInParent property
 - AccessibleContext class, 807
- AccessibleJLabel class
 - JLabel class, 806
- accessibleName property
 - AccessibleContext class, 807
 - AccessibleJLabel class, 806
- accessibleParent property
 - AccessibleContext class, 807
- accessibleRelationSet property
 - AccessibleContext class, 807
- accessibleRole property
 - AccessibleContext class, 807
- accessibleSelection property
 - AccessibleContext class, 807
- accessibleStateSet property
 - AccessibleContext class, 807

- accessibleTable property
 - AccessibleContext class, 807
- accessibleText property
 - AccessibleContext class, 807
- accessibleValue property
 - AccessibleContext class, 807
- accessory property
 - JFileChooser class, 327
- Action interface
 - as extension of the ActionListener interface, 37, 170
 - definition, 37
 - Swing-specific event handling, 37
- Action objects
 - adding to JMenuBar class, 589
 - Swing text components come with, 585
- action property
 - AbstractButton class, 98
 - JComboBox class, 492
 - TextField class, 529
- actionCommand property
 - AbstractButton class, 98
 - DefaultButtonModel interface, 100
 - JButton class, 107
 - JComboBox class, 492
 - TextField class, 529, 557
- ActionEvent event
 - JButton class, 107
- ActionFocusMover class
 - programmatically moving focus, 49
- ActionListener interface
 - AbstractButton class, 102
 - Action interface is extension of, 37, 170
 - adding to JFileChooser class, 324, 325
 - creating, 19
 - creating to handle input focus, 48
 - customizing for JColorChooser class, 305–307
 - focusNextComponent() method, 48
 - handling JCheckBox selection events, 130
 - handling JCheckBoxMenuItem selection events with ItemListener, 186
 - handling JRadioButton selection events, 139, 140
 - handling JRadioButtonMenuItem selection events, 190, 192
 - handling JToggleButton selection events, 121
 - listening to JComboBox events, 493–496
 - listening to JMenuItem events, 166
 - listening to TextField events, 556
- actionListeners property
 - AbstractButton class, 98
 - JComboBox class, 492
 - TextField class, 529
 - Timer class, 36
- ActionMap class
 - InputMap class, 37
 - Keymap interface, 554
 - sharing instances to share actions, 44
- actionMap property
 - JComponent class, 41, 79
- actionPerformed() method, 21
- actions property
 - JFormattedTextField class, 567
 - JTextComponent class, 523, 535
 - TextField class, 529
- ActiveValue class, 755
 - constructing JLabel components, 757
- activeWindow property
 - KeyboardFocusManager class, 55
- add() method
 - ButtonGroup class, 117
 - Container class, 157, 381, 397
 - DefaultListModel class, 453
 - DefaultMutableTreeNode interface, 662
 - JMenu class, 169
 - JMenuBar class, 158
 - JPopupMenu class, 177
 - JToolBar class, 203
- addActionForKeyStroke() method
 - Keymap interface, 45
- addActionListener() method
 - JButton class, 20
- addAuxiliaryLookAndFeel() method
 - UIManager class, 776
- addCellEditorListener() method
 - CellEditor interface, 654
- addChoosableFileFilter() method
 - JFileChooser class, 330
- addChooserPanel() method
 - JColorChooser class, 314
- addComponent() method
 - Seven-Button GridBagLayout example, 352
- addCustomEntriesToTable() method
 - MetalLookAndFeel class, 774
- addEdit() method
 - CompoundEdit class, 791
 - UndoManager class, 792

- addElement() method
 - DefaultListModel class, 453
- addLayoutComponent() method
 - LayoutManager interface, 345
 - LayoutManager2 interface, 345
- addListSelectionListener() method
 - JList class, 476
- addSelectedInterval() method
 - JList class, 479
- addSeparator() method
 - JMenu class, 169, 175
 - JPopupMenu class, 177, 178, 182
 - JToolBar class, 208
- addTab() method
 - JTabbedPane class, 398
- addUndoableListener() method
 - UndoableEditSupport class, 794
- AdjustmentListener interface
 - handling JScrollBar events, 423
- adjustmentListeners property
 - JScrollBar component, 426
- alignment property
 - TabStop class, 604
- alignmentX property
 - JComponent class, 78
- alignmentY property
 - JComponent class, 78
- allFrames property
 - JDesktopPane component, 263
- allowsChildren property
 - DefaultMutableTreeNode interface, 663
- AncestorListener event handler
 - JComponent class, 81
- anchorSelectionIndex property
 - DefaultListSelectionModel class, 475, 683
 - JList class, 464
- anchorSelectionPath property
 - JTree class, 628, 630
- approveButtonMnemonic property
 - JFileChooser class, 327
- approveButtonText property
 - JFileChooser class, 327
- approveButtonToolTipText property
 - JFileChooser class, 327
- armed property
 - DefaultButtonModel interface, 100
 - JMenuItem class, 164
- ArrayList class
 - converting data structure to ListModel, 453
- asynchronousLoadPriority property
 - AbstractDocument class, 540
- AttributeContext interface, 595
- attributeCount property
 - SimpleAttributeSet class, 598
- attributeNames property
 - SimpleAttributeSet class, 598
- attributes property
 - HTMLDocument.Iterator class, 609
- AttributeSet interface, 585
 - changing and checking status with StyleConstants class, 603
 - constants, 598, 599
 - introduction, 597
 - setting JTextPane text attributes, 580
 - SimpleAttributeSet class
 - implementation, 597
 - specifying with Style interface, 606
 - styles, 595
- autoCreateColumnsFromModel property
 - JTable class, 681, 708
- autoResizeMode property
 - JTable class, 681
- autoscrolls property
 - JComponent class, 79
- auxiliaryLookAndFeels property
 - UIManager class, 748
- AWT (Abstract Window Toolkit), 1
- AWT 1.1 event model
 - handling JScrollBar events, 423
- AWT components
 - AWT containers compared to Swing containers, 235
 - distinction between equivalent Swing components, 3
 - layout managers, 343
 - mapping to Swing components, 3
 - replacements, 3
 - resizing, 388
 - Swing menu components, 156
 - to Swing Window mapping, 4
- AWTEvent class
 - getID() method, 257
- AWTEventMulticaster class
 - managing listener lists, 29, 31, 32
- AWTKeyStroke class
 - KeyStroke class as subclass of, 42

B

- background property
 - Component class, 682
 - DefaultTreeCellRenderer class, 635
 - JComponent class, 78
- backgroundNonSelectionColor property
 - DefaultTreeCellRenderer class, 635
- backgroundSelectionColor property
 - DefaultTreeCellRenderer class, 635
- backgroundSet property
 - JComponent class, 78
- BadLocationException class, 599
- BasicColorChooserUI class, 309
- BasicComboBoxEditor class
 - javax.swing.plaf.basic package, 499
- BasicDirectoryModel class
 - ListModel implementation, 452
- BasicLookAndFeel class, 741
 - initClassDefaults() method, 771
 - look and feel classes extend from, 813
- BasicMenuUI class, 199
- BasicSplitPaneDivider subclass, 389
- BasicSplitPaneUI subclass
 - createDefaultDivider() method, 389
- BasicTextAreaUI interface, 60
- beginUpdate() method
 - UndoableEditSupport class, 794
- BevelBorder class, 220
 - methods, 221
- bidiRootElement property
 - AbstractDocument class, 540
- black property
 - MetalLookAndFeel class, 772
- blinkRate property
 - Caret interface, 548
- blockIncrement property
 - JScrollBar component, 421, 426
- Border interface
 - javax.swing.border package, 212
 - methods, 212
- border property
 - JComponent class, 78, 441
 - JViewport class, 412
 - TitledBorder class, 229
- BorderFactory class
 - javax.swing package, 215
- BorderLayout class
 - introduction, 347, 348, 349
 - using LayoutManager2 interface, 345
- BorderLayout manager, 204
 - default layout manager for JApplet class, 252
- borderOpaque property
 - CompoundBorder class, 227
 - LineBorder class, 220
 - TitledBorder class, 229
- borderPainted property
 - AbstractButton class, 98
 - JMenuBar class, 159
 - JPopupMenu class, 179
 - JProgressBar component, 440, 441
 - JToolBar class, 203
- borderPaintedFlat property
 - JCheckBox class, 127, 128
- borders, 211
 - basics, 211
 - AbstractBorder class, 216
 - Border interface, 212
 - BorderFactory class, 215
 - creating, 232, 234
 - predefined borders, 218
 - BevelBorder class, 220
 - CompoundBorder class, 226
 - EmptyBorder class, 218
 - EtchedBorder class, 223
 - LineBorder class, 219
 - MatteBorder class, 224
 - SoftBevelBorder class, 222
 - TitledBorder class, 227
- borderSelectionColor property
 - DefaultTreeCellRenderer class, 635
- bottomComponent property
 - JSplitPane class, 385, 386
- bounded range components
 - available components, 419
 - BoundedRangeModel interface, 419
 - DefaultBoundedRangeModel class, 420
 - JProgressBar class, 439–447
 - JScrollBar class, 421–428
 - JSlider class, 428–438
- BoundedRangeModel interface
 - definition, 420
 - getModel() method, 426
 - JTextField class, 447, 449
 - properties, 419
- bounds property
 - JComponent class, 77

Box class
 BoxLayout class as default layout manager
 of container, 357
 creating, 378
 creating areas that grow, 380–381
 creating rigid areas, 382–383
 introduction, 377
 properties, 379

Box.Filler class. *See* Filler class

BoxLayout class
 as default layout manager of Box class, 377
 creating, 358
 filling box with JLabel, JTextField, and
 JButton, 378
 growing components, 380
 introduction, 357, 358
 laying out components, 359
 with different alignments, 362
 with same alignments, 359–361
 laying out larger components, 363, 364
 layout manager for JMenuBar class, 381

breadthFirstEnumeration() method
 DefaultMutableTreeNode class, 665

ButtonGroup class
 grouping JRadioButton components in,
 136–139
 grouping objects into, 98
 introduction, 116–118
 logical grouping of AbstractButton
 components, 115
 placing JCheckBoxMenuItem component
 in, 184
 placing JRadioButtonMenuItem
 components within, 189

ButtonModel interface, 98
 AbstractButton class, 99
 DefaultButtonModel class implements, 115

C

Calendar class
 constants, 514

calendarField property
 SpinnerDateModel class, 515

cancelCellEditing() method
 CellEditor interface, 654

canceled property
 ProgressMonitor class, 296

canImport() method
 TransferHandler class, 734

CannotRedoException class, 784, 790

CannotUndoException class, 784, 790

CardLayout class
 compared to JTabbedPane class, 394
 introduction, 357
 using LayoutManager2 interface, 345

caret category of properties
 JTextComponent class, 524

Caret interface, 522
 introduction, 547–550
 properties, 548

caret property
 JTextComponent class, 523

caretColor property
 JTextComponent class, 523

CaretEvent class
 introduction, 550–552

CaretListener interface
 associating with JTextComponent, 550
 introduction, 550–552

caretListeners property
 JTextComponent class, 523

caretPosition property
 JTextComponent class, 523

caretUpdate() method
 CaretListener interface, 551

cell editor, 718
 creating complex version, 722–724
 creating simple version, 718–722

CellEditor interface, 644
 and CellEditorListener interface
 methods, 650
 creating the CheckBoxNodeEditor class, 653
 editing tree nodes, 644
 methods, 654–655
 getCellEditorValue() method, 654
 isCellEditable() method, 648

cellEditor property
 JTable class, 681
 JTree class, 628
 TableColumn class, 713

CellEditorListener interface
 definition, 650
 list of objects managed by
 AbstractCellEditor class, 653

cellEditorValue property
 DefaultCellEditor class, 647

cellRenderer property
 JList class, 464, 469
 JTree class, 628
 TableColumn class, 713

- cellSelectionEnabled property
 - JTable class, 681, 682
- changedUpdate() method
 - DocumentListener interface, 558
- ChangeListener, 420
 - AbstractButton class, 102
 - adding to JSlider component, 284
 - attaching to Style interface, 606
 - handling JCheckBox selection events
 - 131, 133
 - handling JProgressBar events, 445, 446
 - handling JRadioButton selection events,
 - 142, 145
 - handling JScrollBar events, 424, 425
 - handling JSlider events, 430
 - handling JToggleButton selection events, 121
 - listening to JMenu events, 173
 - listening to JMenuItem events, 165
- ChangeListener interface
 - listening for JSpinner class events,
 - 511–512
- changeListener property
 - JSpinner class, 510
- changeListeners property
 - AbstractButton class, 98
 - JProgressBar component, 440
 - JSlider component, 431
 - JTabbedPane class, 399
 - JViewport class, 412
- changeUpdate() method
 - DocumentListener interface, 546
- characterAttributes property
 - JTextPane class, 580
- CharacterConstants class
 - keys for attributes, 598
- check box node editor
 - creating CheckBoxNode class, 650–651
 - creating CheckBoxNodeEditor class,
 - 653–658
 - creating CheckBoxNodeRenderer class,
 - 651–653
 - creating test program, 658–659
 - introduction, 650
- CheckBoxUI class
 - user interface delegate, 126
- checkIcon property
 - JCheckBoxMenuItem component, 188
- childCount property
 - DefaultMutableTreeNode interface, 663
- children() method
 - TreeNode class, 664
- choosableFileFilters property
 - JFileChooser class, 327
- chooserPanels property
 - JColorChooser class, 307, 320
- choosers
 - JColorChooser class
 - creating, 301
 - customizing look and feel, 320–322
 - introduction, 300–301
 - properties, 307–320
 - using, 302–307
 - JFileChooser class
 - creating, 323
 - customizing look and feel, 336–341
 - introduction, 322
 - properties, 326–327
 - using, 323–326
 - working with file filters, 328–336
- className property
 - UIManager.LookAndFeelInfo class, 749
- clearSelection() method
 - JList class, 479
- clickCountToStart property
 - DefaultCellEditor class, 647
- clipboard access operations
 - JTextComponent class, 526
 - operations with JTextField class,
 - 534–537
- closable property
 - JInternalFrame class, 254
- closed property
 - JInternalFrame class, 254, 255
- closedIcon property
 - DefaultTreeCellRenderer class, 635
- coalesce property
 - Timer class, 36
- color category of properties
 - JTextComponent class, 524
- Color class
 - decode() method, 499
 - displaying list of colors from, 311
 - dragging-and-dropping, 730
- color property
 - JColorChooser class, 307, 308

- ColorChooserComponentFactory class
 - 301, 308
 - getPreviewPanel() method, 320
 - panels provided to JColorChooser class, 310
 - using, 320
- ColorChooserUI class, 320
 - bug in implementation class, 309
- ColorConstants class
 - keys for attributes, 598
- colorModel property
 - JComponent class, 78
- ColorSelectionModel interface
 - changing color chooser, 313
 - color changes, 313
 - data model for JColorChooser, 303
 - DefaultColorSelectionModel class
 - implements, 301
- column property
 - TableModelEvent class, 700
- columnCount property
 - DefaultTableColumnModel class, 709
 - DefaultTableModel class, 697
 - JTable class, 681
- columnHeader property
 - JScrollPane class, 407
- columnHeaderView property
 - JScrollPane class, 407, 409
- columnIdentifiers property
 - DefaultTableModel class, 698
- columnMargin property
 - DefaultTableColumnModel class, 709
- columnModel property
 - JTable class, 681
 - JTableHeader class, 716
- columnModelListeners property
 - DefaultTableColumnModel class, 709
- columns property
 - DefaultTableColumnModel class, 709
 - JTextArea class, 571
 - JTextField class, 529
- columnSelectionAllowed property
 - DefaultTableColumnModel class, 709
 - JTable class, 681, 682
- ComboBoxEditor interface
 - editing JComboBox class elements, 499
 - entering choices for JComboBox class, 491
- ComboBoxModel interface, 64, 451
 - extended by MutableComboBoxModel interface, 460
 - introduction, 460
 - storing labels and colors arrays, 314
- ComboBoxUI example, 765–766
- Command design pattern
 - Concrete Command, 799
 - participants, 788
- commitEdit() method
 - JFormattedTextField component, 612
- component anchoring
 - GridBagConstraints class, 354
- Component class
 - background property, 682
 - compared to JComponent class, 67
 - foreground property, 682
 - methods
 - getComponentOrientation() method, 345
 - getListeners() method, 29
 - getName() method, 397
 - setFocusable() method, 49
 - setFocusTraversalKeys() method, 55
 - shortcut API methods, 55
- component property
 - DefaultCellEditor class, 647
 - JMenu class, 171
 - JMenuBar class, 159
 - JMenuItem class, 164
 - JPopupMenu class, 179
 - JToolTip class, 85
- component resizing
 - GridBagConstraints class, 354
- componentCount property
 - JComponent class, 78
- ComponentListener interface
 - supported by JFrame class, 245
- componentOrientation property
 - JComponent class, 78
 - JScrollPane class, 407
 - JTextComponent class, 523
- componentPopupMenu property
 - JComponent class, 79
- components property
 - JComponent class, 78
- ComponentUI class
 - UI delegates a subclass of, 741
- CompoundBorder class, 226
 - configuring properties, 227
 - creating, 226

- CompoundEdit class, 783
 - inProgress property, 791
 - methods, 791
- Concrete Command
 - Command design pattern, 799
- configureEnclosingScrollPane() method
 - JTable class, 680
- Constraints class, 371
- Container class
 - add() method, 157, 381, 397
 - compared to JComponent class, 67
 - setLayout() method, 344
 - transferFocusDownCycle() method, 55
- ContainerListener interface
 - supported by JFrame class, 245
- ContainerOrderFocusTraversalPolicy class, 53
- contains() method
 - DefaultListModel class, 460
 - JToolTip class, 85
- contentAreaFilled property
 - AbstractButton class, 98
- contentPane property
 - JDialog class, 250
 - JFrame class, 243
 - JInternalFrame class, 254
 - JRootPane class, 237
 - JWindow class, 248
- CONTENTS_CHANGED type constant
 - ListDataEvent class, 455
- contentType property
 - JEditorPane class, 575
- CONTIGUOUS_TREE_SELECTION mode
 - TreeSelectionModel interface, 669
- continuousLayout property
 - JSplitPane class, 384, 385, 391
- control property
 - MetalLookAndFeel class, 772
- controlButtonsAreShown property
 - JFileChooser class, 327
- controlDarkShadow property
 - MetalLookAndFeel class, 772
- controlDisabled property
 - MetalLookAndFeel class, 772
- controlHighlight property
 - MetalLookAndFeel class, 772
- controlInfo property
 - MetalLookAndFeel class, 772
- controlShadow property
 - MetalLookAndFeel class, 772
- controlTextColor property
 - MetalLookAndFeel class, 772
- controlTextFont property
 - MetalLookAndFeel class, 772
- conversion operations
 - JTextComponent class, 526
- convertValueToText() method
 - JTree class, 642
- copy() method
 - JTextComponent class, 534
- copyAction class constant
 - DefaultEditorKit class, 592
- copyInto() method
 - DefaultListModel class, 460
- createBevelBorder() method
 - BevelBorder class, 221
- createBlackLineBorder() method
 - LineBorder class, 219
- CreateColorSamplePopup program
 - modified version, 318–320
- createCompoundBorder() method
 - CompoundBorder class, 226
- createDefaultColumnsFromModel() method
 - JTable class, 708
- createDefaultDivider() method
 - BasicSplitPaneUI subclass, 389
- createDialog() method
 - JColorChooser class, 305
 - JOptionPane class, 272, 276, 292
- createDisabledImage() method
 - GrayFilter class, 97
- createEtchedBorder() method
 - EtchedBorder class, 224
- createGlue() method
 - Box class, 380, 382
- createGrayLineBorder() method
 - LineBorder class, 220
- createHorizontalBox() method
 - Box class, 378
- createInternalFrame() method
 - JOptionPane class, 272, 276
- createLineBorder() method
 - LineBorder class, 220
- createLoweredBevelBorder() method
 - BevelBorder class, 221
- createMatteBorder() method
 - MatteBorder class, 226

- createRadioButtonGrouping() method
 - JRadioButton class, 139
 - RadioButtonUtils class, 137, 140, 141
 - createRaisedBevelBorder() method
 - BevelBorder class, 222
 - createRigidArea() method
 - Box class, 382
 - createRootPane() method
 - JApplet class, 252
 - JDialog class, 250, 252
 - JFrame class, 246
 - JWindow class, 248
 - createStandardLabels() method
 - Hashtable class, 435
 - createTitledBorder() method
 - TitledBorder class, 229
 - createToolTip() method
 - JToolTip class, 84
 - createTransferable() method
 - TransferHandler class, 734, 735
 - createValue() method
 - LazyValue interface, 755
 - createVerticalBox() method
 - Box class, 378
 - crossPlatformLookAndFeelClassName
 - property
 - UIManager class, 748
 - current() method
 - ElementIterator class, 611
 - currentDirectory property
 - JFileChooser class, 327
 - currentManager() method
 - JComponent class, 70
 - currentTheme property
 - MetalLookAndFeel class, 774
 - cursor property
 - JComponent class, 79
 - cursorSet property
 - JComponent class, 79
 - cut() method
 - JTextComponent class, 534
 - cutAction class constant
 - DefaultEditorKit class, 592
 - cutAction() method
 - DefaultEditorKit class, 535
- D**
- data model category of properties
 - JTextComponent class, 524
 - data model modification methods
 - DefaultComboBoxModel class, 461
 - dataVector property
 - DefaultTableModel class, 698
 - Date object
 - providing to JFormattedTextField
 - constructor, 612
 - date property
 - SpinnerDateModel class, 515
 - DateEditor class
 - introduction, 519
 - properties, 519
 - DateFormat class, 612
 - DateFormatter class, 566
 - debugGraphicsOption property
 - JComponent class, 78
 - DecimalFormat class
 - associated with NumberEditor class, 520
 - decode() method
 - Color class, 499
 - Decorator pattern
 - sorting JTable elements, 700
 - DefaultBoundedRangeModel class
 - getListeners() method, 421
 - implementing BoundedRangeModel
 - interface, 420
 - defaultButton property
 - JButton class, 105
 - JRootPane class, 237
 - DefaultButtonModel class, 98
 - AbstractButton class, 99
 - properties, 100
 - ToggleButtonModel class customizes
 - behavior of, 115
 - defaultCapable property
 - JButton class, 105
 - DefaultCaret class, 547
 - DefaultCellEditor class, 644, 676, 719
 - as cell editor with JTable, 624
 - combining with DefaultTreeCellEditor
 - class, 648
 - creating, 645, 646
 - editing table cells, 718
 - editing tree nodes, 645
 - implementation of TreeCellEditor
 - class, 623
 - properties, 647
 - DefaultCellRenderer class, 676

- defaultClosedIcon property
 - DefaultTreeCellRenderer class, 635
- defaultCloseOperation property
 - JDialog class, 250
 - JFrame class, 243, 246
 - JInternalFrame class, 254, 255
- DefaultColorSelectionModel class
 - javax.swing.colorchooser package, 301
- DefaultComboBoxModel class
 - implements ComboBoxModel interface, 451
 - introduction, 460–463
- DefaultDesktopManager class, 252
 - implementation of DesktopManager interface, 266
- DefaultEditor class
 - properties, 518
- DefaultEditorKit class
 - class constants, 591
 - copyAction class constant, 592
 - cutAction class constant, 592
 - cutAction() method, 535
 - pasteAction class constant, 592
 - readOnlyAction class constant, 592
 - writableAction class constant, 592
- DefaultFocusManager class, 47
- DefaultFocusTraversalPolicy
 - FocusTraversalPolicy class, 53
- DefaultFormatterFactory class
 - javax.swing.text package, 620, 621
- DefaultHighlighter class, 547
- DefaultHighlighter.HighlightPainter class, 547
- DefaultKeyboardFocusManager class, 37, 55
- defaultLeafIcon property
 - DefaultTreeCellRenderer class, 635
- DefaultListCellRenderer class, 468
 - and ListCellRenderer interface, 468, 470
- DefaultListModel class
 - data model implementation of JList, 451
 - introduction, 453
 - methods, 459
- DefaultListSelectionModel class
 - properties, 475, 683
- defaultLookAndFeelDecorated property
 - JDialog class, 250
 - JFrame class, 244
- DefaultMenuLayout class
 - javax.swing.plaf.basic package, 381
- DefaultMetalTheme class
 - introduction, 774
- DefaultMutableTreeNode class, 624
 - building hierarchies, 661, 662
 - creating, 661
 - DynamicUtilTreeNode as subclass of, 666
 - properties, 663
 - traversing trees, 664
 - userObject property, 640, 666
 - working with tree nodes, 661–664
- DefaultMutableTreeNode interface
 - querying node relationships, 664
- defaultOpenIcon property
 - DefaultTreeCellRenderer class, 635
- defaultRootElement property
 - AbstractDocument class, 540
 - DefaultStyledDocument class, 596
- defaults property
 - LookAndFeel class, 742
 - UIManager class, 748
- DefaultSingleSelectionModel class, 395
 - default implementation of
 - SingleSelectionModel interface, 162
- DefaultStyledDocument class, 521, 574, 595
 - creating, 596
 - implementation of StyledDocument interface, 596
 - properties, 596
- DefaultTableCellRenderer class, 686, 687
- DefaultTableColumnModel class
 - implementation of TableColumnModel interface, 676
 - properties, 708
 - used when TableColumnModel interface is not specified, 678
- DefaultTableModel class
 - creating, 696, 697
 - creating sparse table model, 698, 699
 - encapsulates TableModel interface, 676
 - filling, 697
 - introduction, 696
 - listening to JTable events with
 - TableModelListener, 699
 - properties, 697
- DefaultTreeCellEditor class, 644
 - combining with DefaultCellEditor class, 648
 - implementation of TreeCellEditor class, 623
 - introduction, 647
 - using for a JTextField editor with JTree, 645

- DefaultTreeCellRenderer class
 - configuring, 651
 - creating custom renderer, 637–641
 - implementation of TreeCellRenderer interface, 623
 - introduction, 635
 - properties, 635, 636
- DefaultTreeModel class
 - introduction, 667, 668
 - storing TreeModel for JTree, 624
 - working with tree nodes, 659
- DefaultTreeSelectionModel class
 - implementation of TreeSelectionModel, 624
 - introduction, 670
- delay property
 - JMenu class, 171
 - Timer class, 36
- delegation-based event handling, 17
 - event delegation model, 17, 18
 - event listeners as observers, 19
 - creating listener instance, 20
 - defining the listener, 19
 - registering listener with component, 20
 - sequence diagram, 18
- depth property
 - DefaultMutableTreeNode interface, 663
- depthFirstEnumeration() method
 - DefaultMutableTreeNode class, 665
- description property
 - ImageIcon class, 96
 - LookAndFeel class, 742
- desktopColor property
 - MetalLookAndFeel class, 773
- desktopIcon property
 - JInternalFrame class, 254
- DesktopManager interface, 262, 265
 - management of frames within desktop, 252
- desktopManager property
 - JDesktopPane component, 263
- desktopPane property
 - JInternalFrame class, 254
- dialogInit() method
 - JDialog class, 252
- dialogTitle property
 - JFileChooser class, 327
- dialogType property
 - JFileChooser class, 327
- DiamondAbstractButtonStateIcon icon
 - using with component that is not AbstractButton type, 189
- Dictionary class, 435
 - java.util package, 641
- die() method
 - UndoableEdit interface, 790
- directorySelectionEnabled property
 - JFileChooser class, 327, 331
- disabledIcon property
 - AbstractButton class, 98, 102
 - JLabel class, 89
- disabledSelectedIcon property
 - AbstractButton class, 98, 102
- disabledTextColor property
 - JTextComponent class, 523
- discardAllEdits() method
 - UndoManager class, 793
- DISCONTIGUOUS_TREE_SELECTION mode
 - TreeSelectionModel interface, 669
- dismissDelay property
 - ToolTipManager class, 87
- displayable property
 - JComponent class, 79
- displayedMnemonic property
 - JLabel class, 89, 91
- displayedMnemonicIndex property
 - AbstractButton class, 98, 101
 - JLabel class, 89, 91
- dividerLocation property
 - JSplitPane class, 385, 387, 388
- dividerSize property
 - JSplitPane class, 385
- Document interface, 788
 - AbstractDocument class provides basic implementation, 540
 - binding commands to, 788
 - displaying contents with EditorKit class, 607
 - extended by StyledDocument interface, 595
 - filtering document models, 542–546
 - implementations, 521
 - AbstractDocument class, 60
 - insertString() method, 583
 - introduction, 537–540
 - PlainDocument implementation, 526, 570
 - specifying Document data model for
 - JPasswordField class, 564
- document property
 - JFormattedTextField class, 567
 - JTextComponent class, 523
 - JTextField class, 529, 530
 - JTextPane class, 580

- DocumentEvent interface
 - introduction, 546
- DocumentEvent.ElementChange class, 547
- DocumentEvent.EventType class
 - constants, 546
- DocumentFilter class
 - attaching to AbstractDocument, 538
 - customizing, 542–545
 - filtering document models, 542
 - methods, 542
- documentFilter property
 - AbstractDocument class, 540
- DocumentListener interface
 - attaching to data model, 538
 - introduction, 546
 - listening to JTextField events, 558, 559
- documentListeners property
 - AbstractDocument class, 540
- documentProperties property
 - AbstractDocument class, 540
- dot property
 - Caret interface, 548
- doubleBuffered property
 - JComponent class, 70, 78
- doubleBufferingEnabled property
 - RepaintManager class, 71
- doubleBufferMaximumSize property
 - RepaintManager class, 71
- downFocusCycle() method
 - KeyboardFocusManager class, 55
- drag-and-drop support, 729
 - built-in drag-and-drop support, 729–731
 - support for images, 733
 - TransferHandler class, 731–733
- dragEnabled property
 - JColorChooser class, 307
 - JFileChooser class, 327
 - JList class, 464
 - JTable class, 681
 - JTextComponent class, 523
 - JTree class, 628
- draggable image
 - implementing, 736–740
- draggedColumn property
 - JTableHeader class, 716
- draggedDistance property
 - JTableHeader class, 716
- dragMode property
 - JDesktopPane component, 263

- dropTarget property
 - JComponent class, 79
- dump-model action, 591
- DynamicUtilTreeNode class
 - inner class of JTree, 624, 666

E

- echoChar property
 - JPasswordField class, 564
- echoCharIsSet() method
 - JPasswordField class, 564
- edit property
 - UndoableEditEvent class, 794
- editable property
 - JComboBox class, 492
 - JTextComponent class, 523
 - JTree class, 628, 643
- editing property
 - JTable class, 681
 - JTree class, 628
- editingCanceled() method
 - CellEditorListener interface, 650
- editingColumn property
 - JTable class, 681
- editingPath property
 - JTree class, 628
- editingRow property
 - JTable class, 681
- editingStopped() method
 - CellEditorListener interface, 650
- editor property
 - JComboBox class, 492
 - JSpinner class, 510
- editorComponent property
 - JTable class, 681
- EditorContainer class
 - placing custom editors within, 623
- EditorKit class
 - capabilities of TextAction objects, 607
- editorKit property
 - JEditorPane class, 575
 - JTextPane class, 580
- editValid property
 - JFormattedTextField class, 567
- Element interface
 - and Document interface, 538
- elementAt() method
 - DefaultListModel class, 459
- ElementChange class, 547

- ElementIterator class
 - introduction, 611
- elements() method
 - DefaultListModel class, 460
- empty property
 - DefaultListModel class, 453
 - SimpleAttributeSet class, 598
- EmptyBorder class
 - methods, 218
- EmptySelectionModel class, 669
 - inner class of JTree, 624
- enabled property
 - AbstractAction class, 41
 - AbstractButton class, 98
 - DefaultButtonModel interface, 100
 - JComboBox class, 492
 - JComponent class, 79
 - JMenuItem class, 164
 - JScrollBar component, 426
 - ToolTipManager class, 87
- end property
 - SpinnerDateModel class, 515
- end() method
 - CompoundEdit class, 791
 - StateEdit class, 801
 - UndoManager class, 793
- endOffset property
 - HTMLDocument.Iterator class, 609
- endPosition property
 - AbstractDocument class, 540
- endUpdate() method
 - UndoableEditSupport class, 794
- ensureCapacity() method
 - DefaultListModel class, 460
- ensureIndexIsVisible() method
 - JList class, 468
- Enumeration class
 - using instead of Iterator class, 666
- equals() methods
 - problems with DefaultComboBoxModel class, 462
- EtchedBorder class, 223
 - constructors and methods, 223
- event delegation model, 17, 18
- event handling, 17
 - delegation-based event handling, 17
 - event delegation model, 17, 18
 - Swing components, 10, 11

- EventListenerList class, 29
 - managing listener lists, 32, 33, 34
- EventQueue class
 - invokeAndWait() method, 21, 34
 - invokeLater() method, 21, 22, 34, 746
 - isDispatchThread() method, 21
- events category of properties
 - JTextComponent class, 524
- EventType class, 576
 - constants, 546
- expandsSelectedPath property
 - JTree class, 628, 630
- ExpandVetoException class, 673
- exportAsDrag() method
 - TransferHandler class, 732
- extent property
 - BoundedRangeModel interface, 419
 - JSlider component, 431
- extentSize property
 - JViewport class, 412

■ F

- File class
 - dragging-and-dropping, 730
 - java.io package, 333
- filechooser class
 - accept() method, 331
- FileFilter class
 - compared to java.io.FileFilter interface, 323
 - creating subclasses, 331
 - javax.swing.filechooser package, 322
 - working with JFileChooser class, 328–330
- FileFilter interface
 - java.io package, 331
- fileFilter property
 - JFileChooser class, 327
- fileHidingEnabled property
 - JFileChooser class, 327
- FilenameFilter class
 - compared to FileFilter class, 328
- fileSelectionEnabled property
 - JFileChooser class, 327, 331
- fileSelectionMode property
 - JFileChooser class, 327, 331
- FileSystemView class, 323
 - custom views as subclasses, 333
 - javax.swing.filechooser package, 322
 - selectable buttons, 324
 - using with JFileChooser class, 333, 334

- fileSystemView property
 - JFileChooser class, 327
- FileView class
 - using with JFileChooser class, 334–336
- fileView property
 - JFileChooser class, 327, 334
- Filler class
 - inner class of Box class, 377
 - working with, 380
- final keyword, 23
- findColorLabel() method
 - SystemColorChooserPanel class, 314
- findColorPosition() method
 - SystemColorChooserPanel class, 313
- fireContentsChanged() method
 - AbstractListModel class, 452
- fireEditingStopped() method
 - AbstractCellEditor class, 654
- fireIntervalAdded() method
 - AbstractListModel class, 452
- fireIntervalRemoved() method
 - AbstractListModel class, 452
- first() method
 - ElementIterator class, 611
- firstChild property
 - DefaultMutableTreeNode interface, 663
- firstIndex property
 - ListSelectionEvent class, 476
- firstLeaf property
 - DefaultMutableTreeNode interface, 663
- firstRow property
 - TableModelEvent class, 700
- firstVisibleIndex property
 - JList class, 464, 468
- fixedCellHeight property
 - JList class, 464, 466
- fixedCellWidth property
 - JList class, 464, 466
- fixedRowHeight property
 - JTree class, 628, 629
- floatable property
 - JToolBar class, 203
- FlowLayout class
 - compared to BoxLayout class, 357
 - introduction, 345, 346, 347
- focus cycle, 50
 - restricting focus cycle example, 51, 52
- focusable property
 - JComponent class, 78
- focusAccelerator property
 - JTextComponent class, 523
- focusColor property
 - MetalLookAndFeel class, 773
- focusCycleRoot property, 50
 - JComponent class, 78
 - JInternalFrame class, 254
- focusCycleRootAncestor property
 - JInternalFrame class, 254
- focusCycleRootAncestor property
 - JComponent class, 78
- focusedWindow property
 - KeyboardFocusManager class, 55
- FocusListener
 - supported by JFrame class, 245
- FocusListener interface
 - focus management, 47
- focusLostBehavior property
 - JFormattedTextField class, 567
 - JFormattedTextField component, 612
- FocusManager class, 47
- focusNextComponent() method
 - ActionListener interface, 48
 - KeyboardFocusManager class, 55
- focusOwner property
 - JComponent class, 78
 - JInternalFrame class, 254
 - KeyboardFocusManager class, 55
- focusPainted property
 - AbstractButton class, 98
- focusPreviousComponent() method
 - KeyboardFocusManager class, 55
- focusTraversablePolicySet property
 - JComponent class, 78
- focusTraversalKeysEnabled property
 - JComponent class, 78
- FocusTraversalPolicy class, 37
 - focus management, 47
 - methods for controlling traversal order, 52
 - predefined traversal policies, 53
 - reversing focus traversal, 53, 55
- focusTraversalPolicy property
 - JComponent class, 78
- focusTraversalPolicyProvider property
 - JComponent class, 50, 78
- font property
 - DefaultTreeCellRenderer class, 635
 - JComponent class, 78
 - JTextArea class, 571
 - TextField class, 529

- FontConstants class
 - keys for attributes, 598
- fontSet property
 - JComponent class, 78
- foreground property
 - Component class, 682
 - JComponent class, 78
- foregroundSet property
 - JComponent class, 78
- Format class
 - java.text package, 566
- format property
 - DateEditor class, 519
 - NumberEditor class, 520
- formatter property
 - JFormattedTextField class, 567
- formatterFactory property
 - JFormattedTextField class, 567
- frameIcon property
 - JInternalFrame class, 254
- frameInit() method
 - JFrame class, 246, 247
- French version
 - JOptionPane class, 290
- fromIndex property
 - TableColumnModelEvent class, 709

G

- GapContent class
 - AbstractDocument.Content
 - implementation, 596
- get() method
 - DefaultListModel class, 459
 - UIManager class, 758, 763
- getAcceptAllFileFilter() method
 - JFileChooser class, 330
- getActionListeners() method
 - JButton class, 29
- getActionMap() method
 - JComponent class, 593
- getActions() method
 - JTextComponent class, 586
- getBorder() method
 - UIManager class, 747
- getBorderInsets() method
 - AbstractBorder class, 217
 - Border interface, 214
 - MotifButtonUI class, 217
- getCellEditorValue() method
 - CellEditor interface, 654
- getChange() method
 - DocumentEvent interface, 547
- getChildCount() method
 - MutableTreeNode interface, 660
- getClientProperty() method
 - JComponent class, 759
- getColor() method
 - UIManager class, 747
- getColumnClass() method
 - TableModel interface, 687, 695
- getComponent() method
 - MenuElement interface, 195
- getComponentAfter() method
 - FocusTraversalPolicy class, 52
- getComponentBefore() method
 - FocusTraversalPolicy class, 52
- getComponentOrientation() method
 - Component class, 345
- getComponentPopupMenu() method
 - JComponent class, 178
- getConstraint() method
 - SpringLayout class, 372
- getContentType() method
 - predefined editor kits, 576
- getDefaultChooserPanels() method
 - AbstractColorChooserPanel class, 320
- getDefaultComponent() method
 - FocusTraversalPolicy class, 52
- getDimension() method
 - UIManager class, 747
- getEditorComponent() method
 - ComboBoxEditor class, 499
- getElementAt() method
 - DefaultListModel class, 459
- getElements() method
 - ButtonGroup class, 118
- getFileSystemView() method
 - FileSystemView class, 333
- getFirstComponent() method
 - FocusTraversalPolicy class, 52
- getFont() method
 - UIManager class, 747
- getHeaderRenderer() method
 - TableColumn class, 713
- getIcon() method
 - UIManager class, 747
- getID() method
 - AWTEvent class, 257

- getlheritsPopupMenu() method
 - JComponent class, 178
- getInitialComponent() method
 - FocusTraversalPolicy class, 52
- getInputMap() method
 - JComponent class, 43
- getInputValue() method
 - JOptionPane class, 272
- getInsets() method
 - UIManager class, 747
- getInstalledLookAndFeels() method
 - UIManager class, 743, 776
 - UIManager.LookAndFeelInfo class, 742
- getInt() method
 - UIManager class, 747
- getInteriorRectangle() method
 - AbstractBorder class, 217
- getInternalFrame() method
 - InternalFrameEvent class, 257
- getItem() method
 - ComboBoxEditor class, 499
- getKeymap() method
 - JTextComponent class, 586
- getKeyStroke() method
 - KeyStroke class, 43
- getKeyStrokeForEvent() method
 - KeyStroke class, 43
- getKeyText() method
 - KeyEvent class, 29
- getLastComponent() method
 - FocusTraversalPolicy class, 52
- getListCellRendererComponent() method
 - ListCellRenderer interface, 469
- getListDataListeners() method
 - AbstractListModel class, 452
- getListeners() method
 - Component class, 29
 - DefaultBoundedRangeModel class, 421
- getMaxCharactersPerLineCount() method
 - JOptionPane class, 281
- getModel() method
 - BoundedRangeModel interface, 426, 431
- getName() method
 - Component class, 397
- getNextMatch() method
 - JList class, 481
- getNextNode() method
 - DefaultMutableTreeNode class, 664
- getNextVisualPositionFrom() method
 - NavigationFilter class, 552
- getObject() method
 - UIManager class, 747
- getPaintTicks() method
 - JSlider component, 435
- getPath() method
 - TreePath class, 673
- getPopupLocation() method
 - JComponent class, 178
- getPreviewPanel() method
 - ColorChooserComponentFactory class, 320
- getPreviousNode() method
 - DefaultMutableTreeNode class, 664
- getProgress() method
 - ProgressMonitor class, 293
- getProperty() method
 - AbstractDocument class, 540
- getPropertyName() method
 - JInternalFrame class, 255
- getRoot() method
 - TreeModel class, 666
- getSelectedElements() method
 - JRadioButton class, 141
- getSelectedIndex() method
 - JComboBox class, 495, 497
- getSelectedItem() method
 - JComboBox class, 495
- getSelection() method
 - OptionPaneUtils class, 273, 274
- getSharedOwnerFrame() method
 - SwingUtilities class, 277
- getSourceActions() method
 - TransferHandler class, 734
- getString() method
 - UIManager class, 747
- getSubElements() method
 - MenuElement interface, 195
- getSupportsWindowDecorations() method
 - JRootPane class, 238
- getTableCellRendererComponent() method
 - TableCellRenderer interface, 686, 687
- getTreeCellEditorComponent() method
 - TreeCellEditor interface, 648, 656
- getUI() method
 - UIManager class, 747
- getUIClassID() method
 - JToolBar class, 763

- getValue() method
 - JOptionPane class, 272
 - SpinnerDateModel class, 515
- glassPane property
 - JDialog class, 250
 - JFrame class, 243
 - JInternalFrame class, 254
 - JRootPane class, 237
 - JWindow class, 248
- glue, creating, 380–381
- Graphics class
 - translate() method, 214
- graphics property
 - JComponent class, 78
- graphicsConfiguration property
 - JComponent class, 78
- GrayFilter class, 97
 - createDisabledImage() method, 97
- grid positioning
 - GridBagConstraints class, 355, 356
- GridBagConstraints class
 - and GridBagConstraints class, 351
 - component anchoring, 354
 - component resizing, 354
 - grid positioning, 355–356
 - introduction, 353
 - padding, 356
 - weight, 357
- GridBagLayout class
 - associating GridBagConstraints object to component, 345
 - compared to BoxLayout class, 357
 - components should have
 - GridBagConstraints associated, 353
 - introduction, 350–352
 - rows and columns, 353
 - using LayoutManager2 interface, 345
- gridColor property
 - JTable class, 681–682
- GridLayout class
 - compared to BoxLayout class, 357
 - compared to GridBagConstraints class, 350
 - introduction, 349–350
- group property
 - DefaultButtonModel interface, 100
- growing components, creating, 380–381

■ H

- Hashtable class, 41
 - createStandardLabels() method, 435
 - creating JTree from, 625
 - UIDefaults class as subclass, 749
- headerRenderer property
 - TableColumn class, 713
- headerValue property
 - TableColumn class, 713
- height property
 - JComponent class, 77
- helpMenu property
 - JMenuBar class, 159
- hide() method
 - Popup class, 200
- HierarchyBoundsListener
 - supported by JFrame class, 246
- HierarchyListener
 - supported by JFrame class, 246
- highestLayer() method
 - JLayeredPane class, 240
- Highlight class, 547
- highlightedTextColor property
 - MetalLookAndFeel class, 773
- highlighter category of properties
 - JTextComponent class, 524
- Highlighter interface, 522
 - introduction, 547–550
- highlighter property
 - JTextComponent class, 523
- Highlighter.Highlight class, 547
- HighlightPainter class, 547
- horizontalAlignment property
 - AbstractButton class, 98, 102
 - JLabel class, 89
 - JTextField class, 529, 530
- horizontalScrollBar property
 - JScrollPane class, 407
- horizontalScrollBarPolicy property
 - JScrollPane class, 407
- horizontalTextPosition property
 - AbstractButton class, 98, 102
 - JLabel class, 89
- horizontalVisibility property
 - JTextField class, 529, 530
- HTML documents
 - iterating through, 608–612
 - loading as StyledDocument into
 - JEditorPane, 607

- HTML.Tag class
 - constants, 608, 609
 - searching for tag types in document, 611
- HTMLDocument interface, 522
- HTMLDocument.Iterator class
 - next() method, 609
 - properties, 609
 - using, 608, 610, 611
- HTMLToolkit class, 585
- HTMLToolkit.Parser class
 - javax.swing.text.html package, 607
- HTMLToolkit.ParserCallback class, 607
- HTMLToolkit.ParserDelegator class, 607
- HyperlinkEvent class, 574
- HyperlinkEvent.EventType class, 576
- HyperlinkListener interface, 574
 - handling JEditorPane events example, 577–578
 - hyperlinkUpdate() method, 576
- hyperlinkListeners property
 - JEditorPane class, 575
- hyperlinkUpdate() method
 - HyperlinkListener interface, 576
-
- I/O operations
 - JTextComponent class, 526
- icon argument
 - JOptionPane class, 270
- Icon interface, 92
 - creating, 93, 94
 - displaying images within components, 67
 - javax.swing package, 734
 - paintIcon() method, 93
 - using, 94
- icon property
 - AbstractButton class, 98
 - ImageSelection class, 734
 - JInternalFrame class, 254, 255
 - JLabel class, 89
 - JOptionPane class, 281
- iconHeight property
 - ImageIcon class, 96
- iconifiable property
 - JInternalFrame class, 254
- iconImage property
 - JFrame class, 243
- icons
 - JMenuItem and subclasses inherit support, 156
- iconTextGap property
 - JLabel class, 89
- iconWidth property
 - ImageIcon class, 96
- ID property
 - LookAndFeel class, 742
- identifier property
 - TableColumn class, 713
- ignoreRepaint property
 - JComponent class, 78
- IllegalArgumentException class
 - and GridLayout class, 350
 - can be caused by
 - MutableTreeNode.insert(), 661
 - changing border of JViewport class, 412
 - creating JProgressBar components, 440
 - creating JScrollbar components, 423
 - creating JSlider components, 429
 - creating JTabbedPane class, 396
 - moving JSplitPane divider, 387
 - setting delay property of JMenu class, 172
 - setting orientation of JSplitPane class, 386
 - setting policies for JScrollPane class, 405
- image property
 - ImageIcon class, 96
- ImageIcon class, 94
 - creating, 95, 805–806
 - predefined images, 67
 - properties, 96
 - using, 95
- imageLoadStatus property
 - ImageIcon class, 96
- imageObserver property
 - ImageIcon class, 96
- images, drag-and-drop support, 733
- ImageSelection class
 - creating, 734
 - icon property, 734
- importData() method
 - TransferHandler class, 734–735
- inactiveControlTextColor property
 - MetalLookAndFeel class, 773
- inactiveSystemTextColor property
 - MetalLookAndFeel class, 773
- indeterminate property
 - JProgressBar component, 440
- index0 property
 - ListDataEvent class, 454

- index1 property
 - ListDataEvent class, 454
- indexOf() method
 - DefaultListModel class, 460
- INFORMATION_MESSAGE pop-up
 - JOptionPane class, 277
- inheritsPopupMenu property
 - JComponent class, 79
- initClassDefaults() method
 - BasicLookAndFeel class, 771
- initialDelay property
 - Timer class, 36
 - ToolTipManager class, 87
- initialSelectionValue property
 - JOptionPane class, 281
- initialValue argument
 - JOptionPane class, 271
- initialValue property
 - JOptionPane class, 281
- inProgress property
 - CompoundEdit class, 791
- inputAttributes property
 - JTextPane class, 581
- inputContext property
 - JComponent class, 79
- InputEvent class, 23
- InputMap class
 - ActionMap class, 37
 - getting for component based on focus
 - activation condition, 43
 - Keymap interface, 544
- inputMap property
 - JComponent class, 41, 79
- InputMethodListener
 - supported by JFrame class, 246
- inputMethodRequests property
 - JComponent class, 79
 - JTextComponent class, 523
- inputValue property
 - JOptionPane class, 281, 284
- InputVerifier interface, 37
 - component-level verification during focus
 - traversal, 56
 - listening to JTextField events, 558
 - setVerifyInputWhenFocusTarget()
 - method, 57
- inputVerifier property
 - JComponent class, 78
- insert() method
 - MutableTreeNode interface, 660, 662
- insertElementAt() method
 - DefaultListModel class, 453
- insertNodeInto() method
 - DefaultTreeModel class, 668
- insertSeparator() method
 - JMenu class, 175
- insertString() method
 - Document interface, 583
 - DocumentFilter class, 542
- insertUpdate() method
 - DocumentListener interface, 546
- insets property
 - JComponent class, 78
 - JViewport class, 412
- insideBorder property
 - CompoundBorder class, 227
- installChooserPanel() method
 - AbstractColorChooserPanel class, 312, 313
- installedLookAndFeels property
 - UIManager class, 748
- intercellSpacing property
 - JTable class, 681, 682
- InternalFrameAdapter class, 253
 - InternalFrameListener methods, 256
- InternalFrameEvent class, 253
 - constants for event subtypes, 257
- InternalFrameFocusTraversalPolicy
 - FocusTraversalPolicy class, 53
- InternalFrameIconifyListener class, 264
- InternalFrameListener interface, 253
 - definition, 256
 - methods, 256
- internalFrameListeners property
 - JInternalFrame class, 254
- InternationalFormatter class
 - java.swing.text package, 612
- INTERVAL_ADDED type constant
 - ListDataEvent class, 455
- INTERVAL_REMOVED type constant
 - ListDataEvent class, 455
- inverted property
 - JSlider component, 431
- invokeAndWait() method
 - EventQueue class, 21, 34
 - SwingUtilities class, 23

- invokeLater() method
 - EventQueue class, 21, 22, 34, 746
 - SwingUtilities class, 23
- invoker property
 - JPopupMenu class, 179
- invokesStopCellEditing property
 - JTree class, 628
- IOException class
 - thrown by read/write methods of
 - JTextComponent class, 530
- isBorderOpaque() method
 - AbstractBorder class, 217
 - Border interface, 214
- isCellEditable() method
 - CellEditor interface, 648, 655
- isDispatchThread() method
 - EventQueue class, 21
- isEventDispatchThread() method
 - SwingUtilities class, 21
- isFilled property
 - JSlider component, 438
- isInProgress() method
 - UndoManager class, 792
- isLeftMouseButton() method
 - SwingUtilities class, 24
- isMiddleMouseButton() method
 - SwingUtilities class, 24
- isNodeAncestor() method
 - DefaultMutableTreeNode interface, 664
- isNodeChild() method
 - DefaultMutableTreeNode interface, 664
- isNodeDescendant() method
 - DefaultMutableTreeNode interface, 664
- isNodeRelated() method
 - DefaultMutableTreeNode interface, 664
- isNodeSibling() method
 - DefaultMutableTreeNode interface, 664
- isRightMouseButton() method
 - SwingUtilities class, 24
- isSelectedIndex() method
 - DefaultListSelectionModel class, 475
- isTraversable() method
 - FileSystemView class, 334
- itemCount property
 - JComboBox class, 492
 - JMenu class, 171
- ItemListener interface
 - handling JCheckBox selection events, 130
 - handling JCheckBoxMenuItem selection events, 187

- handling JRadioButton selection events, 142
- handling JRadioButtonMenuItem selection events, 192
- handling JToggleButton selection events, 121–124
- listening to JComboBox events, 493–496
- itemListeners property
 - AbstractButton class, 98
 - JComboBox class, 492
- Iterator class
 - using instead of Enumeration class, 666

J

- Japanese-language buttons
 - JOptionPane class, 291
- JApplet class
 - BorderLayout class as default layout manager for, 347
 - extending, 252
 - introduction, 252
- JAR files, 1
- Java Access Bridge
 - working with, 808–810
- Java archive, 1
- Java Ferret, introduction, 810
- java.awt package
 - Color class, 730
 - FocusTraversalPolicy class, 47
 - KeyboardFocusManager, 47
- java.awt.datatransfer package
 - drag-and-drop capabilities, 729
 - Transferable interface, 733
- java.awt.event package
 - KeyEvent class, 163
- java.beans package
 - PropertyChangeListener, 420
- java.io package
 - File class, 333, 730
 - FileFilter interface, 331
- java.swing package
 - TransferHandler class, 731
- java.swing.text package
 - InternationalFormatter class, 612
- java.text package
 - DecimalFormat class, 520
 - Format class, 566
 - MessageFormat class, 727
 - NumberFormat class, 615

- java.util package
 - Dictionary class, 641
 - Hashtable class, 41
 - Map interface, 41
 - Timer class, 36
 - Undo Framework, 783
- javax.accessibility package
 - accessibility classes, 805
- javax.swing package, 2
 - BorderFactory class, 215
 - DefaultFocusManager class, 47
 - filechooser class, 331
 - FocusManager class, 47
 - Icon class, 734
- javax.swing.border package
 - AbstractBorder class, 216
 - Border interface, 212
- javax.swing.colorchooser package
 - support classes for JColorChooser class, 301
- javax.swing.event package, 32
 - EventListenerList class, 29, 33
 - event-related classes, 624
 - support for Undo Framework, 783
- javax.swing.filechooser package
 - support classes for JFileChooser, 322
- javax.swing.plaf package, 2
 - classes that implement UIResource interface, 753–754
- javax.swing.plaf.basic package
 - BasicComboBoxEditor class, 499
 - DefaultMenuLayout class, 381
- javax.swing.plaf.metal package
 - MetalLookAndFeel class, 748, 772
- javax.swing.table package
 - support classes for JTable class, 675
- javax.swing.text package
 - DefaultFormatterFactory class, 620, 621
- javax.swing.text.html package
 - HTMLToolkit.Parser class, 607
- javax.swing.tree package
 - tree specific classes, 624
- javax.swing.undo package, 11
 - Undo Framework, 783
- JButton class, 67, 104, 722
 - ActionEvent event, 107
 - addActionListener() method, 20
 - changing look and feel at runtime through, 744–746
 - configuring a default button, 105
 - creating, 104
 - customizing look and feel, 108
 - UIResource-related properties, 109
 - generating ActionEvent objects, 19
 - getActionListeners() method, 29
 - handling events, 106, 107
 - placing icon onto, 271
 - properties, 105
 - using on JOptionPane, 285
- JCheckBox class
 - appearance with DefaultCellEditor as TreeCellEditor, 646
 - compared to JCheckBoxMenuItem component, 185
 - creating, 126–127
 - creating CheckBoxNodeEditor class, 653–658
 - customizing look and feel, 133
 - UIResource-related properties, 134
 - editing table cells, 718
 - handling selection events, 130–133
 - introduction, 125
 - properties, 127–130
- JCheckBoxMenuItem component, 8
 - compared to JRadioButtonMenuItem component, 190
 - creating, 184
 - customizing look and feel, 187
 - UIResource-related properties, 187, 189
 - handling selection events, 186
 - with ActionListener, 186
 - with ItemListener, 187
 - introduction, 184
 - properties, 185
- JColorChooser class, 9, 722
 - built-in drag-and-drop support, 730
 - changing color chooser panels, 310–320
 - changing preview panel, 308–309
 - creating, 301
 - creating and showing in pop-up window, 303–307
 - dragging-and-dropping colors across, 730
 - introduction, 300–301
 - listening for color selection changes, 303
 - properties, 307
 - providing OK/cancel event listeners, 305
 - using, 302

- JComboBox class, 64, 314, 719
 - changing look and feel at runtime
 - through, 744–746
 - creating components, 491
 - customizing look and feel, 503–506
 - data model provided by
 - DefaultComboBoxModel class, 460
 - demonstrating use of, 462–463
 - editing elements, 497–503
 - editing table cells, 718
 - introduction, 490, 491
 - properties, 491, 492
 - rendering elements, 493
 - selecting elements, 493–497
 - sharing data model with JList, 506, 508
 - uses implementation of ComboBoxModel interface, 460
 - using with DefaultCellEditor as
 - TreeCellEditor, 647
- JComboBoxMenuItem class
 - using with MenuElement interface, 195
- JComponent class
 - adding to JColorChooser, 308
 - compared to AWT Component and
 - Container classes, 67
 - customizing display characteristics tooltip objects, 84
 - descendent classes, 67
 - handling events, 80
 - listening to inherited events, 82, 84
 - with AncestorListener, 81
 - with PropertyChangeListener, 80
 - with VetoableChangeListener, 81
 - implements Accessible interface, 807
 - introduction, 67
 - methods
 - currentManager() method, 70
 - getActionMap() method, 593
 - getClientProperty() method, 759
 - getInputMap() method, 43
 - putClientProperty() method, 759
 - setComponentPopupMenu()
 - method, 178
 - setMinimumSize() method, 388
 - setToolTipText() method, 84, 87
 - painting JComponent objects, 69
 - properties, 41, 74–77
 - border property, 441
 - client properties, 73
 - component-set-oriented properties, 78
 - event support properties, 79
 - focus-oriented properties, 78
 - focusTraversalPolicyProvider
 - property, 50
 - internationalization support
 - properties, 79
 - layout-oriented properties, 78
 - opaque property, 525
 - other properties, 79
 - painting properties, 70, 78
 - painting support properties, 78
 - position-oriented properties, 77
 - state support properties, 79
 - Swing menu elements are subclasses
 - of, 156
 - UIResource properties, 72
- JDesktopIcon class
 - changing, 261
 - inner class of JInternalFrame, 252
- JDesktopPane component, 8
 - adding internal frames to, 262
 - and JInternalFrame class, 253
 - as a specialized JLayeredPane, 252
 - complete desktop example, 263–265
 - creating, 262
 - customizing look and feel, 263
 - introduction, 262
 - properties, 262
- JDialog class
 - BorderLayout class as default layout
 - manager for, 347
 - creating, 248–249
 - extending, 252
 - handling events, 250–252
 - introduction, 248
 - placing JOptionPane class within, 271–272
 - properties, 250
 - setUndecorated() method, 237
- JEditorPane class, 5
 - as subclass of JTextComponent class, 521
 - built-in drag-and-drop support, 730
 - creating, 575
 - customizing look and feel, 579
 - UIResource-related properties, 579
 - handling events, 576–579
 - HTMLDocument interface, 522
 - JTextPane as subclass of, 521
 - introduction, 574

- loading HTML documents as
 - StyledDocument, 607
- properties, 575–576
- JFileChooser class, 452
 - adding ActionListener, 324–325
 - creating, 323
 - customizing look and feel, 336
 - dragging-and-dropping File object, 730
 - introduction, 322
 - properties, 326
 - showing in pop-up window, 326
 - using, 323–324
 - working with file filters, 328
 - adding accessory panels, 331
 - choosing directories instead of files, 331
 - using FileSystemView class, 333
 - using FileView class, 334–336
- JFormattedTextField class, 7
 - and DefaultFormatterFactory class, 621
 - and JSpinner class, 509
 - built-in drag-and-drop support, 730
 - creating, 566–567
 - customizing look and feel, 569
 - UIResource-related properties, 569–570
 - date and time formats, 612–614
 - example, 567–569
 - finding actions, 591
 - formats, 612
 - input masks, 618–620
 - introduction, 566
 - properties, 567
 - notify-field-accept action, 587
 - number formats, 615–617
 - setMask() method, 618
 - setText() method, 615
 - setValue() method, 615
 - using formatted input options and
 - validation available, 585
 - working with editors based on, 518
- JFormattedTextField.
 - AbstractFormatterFactory class
 - manages use of formatter objects, 617
- JFrame class
 - adding components, 245
 - BorderLayout class as default layout
 - manager for, 347
 - close operation constants, 244
 - compared to JInternalFrame class, 253
 - creating, 243
 - defaultLookAndFeelDecorated
 - property, 244
 - extending, 246
 - handling events, 245
 - introduction, 242
 - properties, 243
 - setting window decoration style, 244
 - setUndecorated() method, 237
- JInternalFrame class, 8
 - and JDesktopPane, 266
 - BorderLayout class as default layout
 - manager for, 347
 - changing JDesktopIcon, 261
 - creating, 253
 - customizing look and feel, 257
 - UIResource-related properties, 259–261
 - handling events, 256–257
 - introduction, 253
 - palette with other frames, 261
 - placing JOptionPane class within, 271
 - properties, 254–255
 - property constants, 255–256
 - without AWT counterpart, 235
- JIT compilers, 1
- JLabel class, 67
 - AccessibleJLabel class, 806
 - creating, 89
 - customizing look and feel, 92
 - UIResource value settings, 92
 - DefaultListCellRenderer class as subclass
 - of, 468
 - dragging text from, 732
 - event handling, 91
 - implementation of within
 - TableCellRenderer interface, 676
 - introduction, 88
 - properties, 89
 - setDisplayMnemonic() method, 527
 - setLabelFor() method, 528
- JLayeredPane class
 - adding components in layers, 240–241
 - as component of JRootPane class, 235
 - component layers and positions, 241
 - creating, 240
 - introduction, 239–240
 - properties, 242

- JList class
 - adding element level tooltips, 488–490
 - creating components, 463–464
 - creating dual list box, 481–488
 - customizing look and feel, 480
 - UIResource-related properties, 480–481
 - data model implementation, 451
 - displaying multiple columns, 479–480
 - introduction, 463
 - properties, 464–465
 - rendering elements, 468–470
 - creating complex ListCellRenderer, 471–473
 - scrolling components, 466–468
 - scrolling support, 406
 - selecting elements, 473–479
 - sharing data model with JComboBox 506, 508
- JMenu class
 - adding menu items to, 169
 - addSeparator() method, 175
 - creating, 168–169
 - customizing look and feel, 173
 - UIResource-related properties, 173–175
 - insertSeparator() method, 175
 - introduction, 168
 - listening to events
 - with ChangeListener, 173
 - with MenuListener, 173
 - properties, 171
 - setting menu components, 172
 - using Action objects, 170, 171
- JMenuBar class
 - adding Action objects, 589
 - adding glue component to, 381
 - adding to or removing menus from menu bars, 157–158
 - and JApplet class, 252
 - changing layout manager, 161
 - contained in JLayeredPane class, 236
 - creating, 157
 - customizing look and feel, 159
 - UIResource-related properties, 160
 - introduction, 157
 - properties, 158–159
 - setHelpMenu() method, 381
- jMenuBar property
 - JDialog class, 250
 - JFrame class, 243
 - JInternalFrame class, 254
 - JRootPane class, 237
- JMenuItem class
 - creating, 162–163
 - customizing look and feel, 167
 - UIResource-related properties, 167–168
 - handling events, 164–167
 - introduction, 162
 - properties, 163
 - setText() method, 589
- JOptionPane class, 9
 - adding components to button area, 285
 - adding components to message area, 284
 - automatically creating in pop-up window, 274–275
 - arguments for factory methods, 276
 - confirm pop-ups, 278
 - input pop-ups, 278–279
 - message pop-ups, 277
 - option pop-ups, 280
 - createDialog() method, 292
 - creating, 268–269
 - creating JDialog class, 249
 - creating pop-up dialogs hosted by
 - JInternalFrame class, 254
 - customizing look and feel, 287–291
 - displaying, 271–274
 - displaying multiline messages, 281–282
 - initialValue argument, 271
 - introduction, 267–268
 - listening for property changes, 286
 - message argument, 269–270
 - message property, 283
 - messageType argument, 270
 - options argument, 271
 - optionType argument, 270
 - properties, 280–281
 - showInternalMessageDialog() method, 277
 - showMessageDialog() method, 277
- JPanel class, 67
 - AbstractColorChooserPanel as JPanel subclass, 312
 - creating, 110
 - customizing look and feel, 112
 - UIResource-related properties, 112
 - FlowLayout class as default layout manager for, 345
 - implementing Accessible interface, 807

- mixing lightweight and heavyweight components, 179
 - placing JRadioButton objects within, 227
 - setting previewPanel property to empty JPanel, 308
 - using, 110–112
- JPasswordField class, 5
- built-in drag-and-drop support, 730
 - creating, 563–564
 - customizing look and feel, 565
 - UIResource-related properties, 565
 - finding actions, 591
 - introduction, 563
 - notify-field-accept action, 587
 - properties, 564
 - subclass of JTextField class, 521
- JPopupMenu class
- adding menu item to JMenu, 170
 - adding menu items to, 177
 - creating, 176
 - customizing look and feel, 180
 - UIResource-related properties, 181
 - displaying, 178
 - example, 182–184
 - introduction, 176
 - JMenu contained within, 168
 - properties, 179
 - Separator class, 182
 - watching for pop-up menu visibility, 180
- JProgressBar component, 6
- creating, 439–440
 - customizing look and feel, 446
 - UIResource-related properties, 446
 - handling events, 445–446
 - introduction, 439
 - labeling, 441
 - painting borders, 441
 - process of step through, 442–445
 - properties, 440
 - using an indeterminate progress bar, 442
- JRadioButton class
- compared to JRadioButtonMenuItem component, 189
 - creating, 135–136
 - customizing look and feel, 147
 - UIResource-related properties, 148
 - grouping in a ButtonGroup, 136–139
 - handling selection events, 139–145
 - introduction, 134
 - listing text actions, 586
 - placing within JPanel, 227
 - properties, 136
- JRadioButtonMenuItem component, 8
- configuring properties, 191
 - creating, 190
 - customizing look and feel, 191
 - UIResource-related properties, 191–192
 - example, 192–194
 - handling selection events, 190
 - introduction, 184, 189
- JRootPane class
- and JDialog class, 248
 - creating, 236
 - creating JLayeredPane class, 240
 - customizing look and feel, 238–239
 - introduction, 235
 - layering effect, 180
 - properties, 236–238
 - RootLayout inner class, 343
 - windowDecorationStyle property, 244
- JScrollBar component
- BoundedRangeModel interface
 - properties, 419
 - compared to JSlider component, 6
 - creating, 422
 - customizing look and feel, 427
 - UIResource-related properties, 427–428
 - handling scrolling events, 423
 - introduction, 421
 - listening to scrolling events
 - with AdjustmentListener, 423
 - with ChangeListener, 424–425
 - methods, 426
 - properties, 14, 426
- JScrollPane class
- creating, 404–405
 - creating columns that don't scroll, 692
 - creating viewport view, 406
 - customizing look and feel, 410
 - UIResource-related properties, 410
 - introduction, 403
 - JScrollBar component used within, 421
 - JTextComponent text components can be placed within, 523
 - JViewport class used with, 371
 - manually positioning JTable view, 679
 - placing JList component within, 466
 - placing JTableHeader objects within, 715

- placing JTextArea within, 570
 - placing JTree within, 627
 - placing tree within, 623
 - policies, 405
 - properties, 407
 - resetting viewport position, 410
 - Scrollable interface, 406
 - use of ScrollPaneLayout class, 370
 - using with JTable class, 678
 - working with headers and corners, 409
 - working with ScrollPaneLayout manager, 408
- JScrollPane.ScrollBar. *See* Scrollable interface
- JSeparator class, 8
- creating, 175
 - customizing look and feel, 176
 - UIResource-related properties, 176
 - does not implement MenuElement interface, 195
 - introduction, 175
 - properties, 175
 - setOrientation() method, 182, 208
- JSlider class, 6
- adding to JOptionPane, 284
 - client properties, 438
 - creating, 428–429
 - customizing look and feel, 435–438
 - displaying tick marks within, 432
 - handling events, 430
 - introduction, 428
 - labeling positions, 434
 - methods, 431
 - properties, 431
 - snapping thumb into position, 434
 - UIResource-related properties, 437
- JSpinner class, 6
- creating, 510
 - custom models, 517
 - customizing look and feel, 512
 - UIResource properties, 512–513
 - editors, 518
 - DateEditor class, 519
 - DefaultEditor class, 518
 - ListEditor class, 519
 - NumberEditor class, 520
 - introduction, 509
 - listening for events with ChangeListener interface, 511–512
 - properties, 510–511
 - SpinnerModel interface as data model, 513
- JSplitPane class, 10
- changing components, 386
 - creating, 384
 - customizing look and feel, 393
 - UIResource-related properties, 393
 - introduction, 383
 - listening for property changes, 390–392
 - moving divider, 387
 - one-touch expandable divider, 388
 - properties, 385
 - resizing, 389
 - resizing components, 388
 - setting orientation, 386
- JTabbedPane class, 10
- adding and removing tabs, 397–398
 - addTab() method, 398
 - creating, 395–396
 - customizing look and feel, 401
 - UIResource-related properties, 402–403
 - displaying multiple chooser panels in JColorChooser, 301
 - introduction, 394
 - listening for changing tab selection, 399–401
 - properties, 398–399
 - used instead of CardLayout class, 357
- JTable class, 7, 677
- autoCreateColumnsFromModel property, 708
 - auto-resize modes, 683–685
 - createDefaultColumnsFromModel() method, 708
 - creating, 677–678
 - customizing look and feel, 689
 - UIResource-related properties, 689–690
 - display settings, 682
 - editing table cells, 718
 - example, 675
 - handling events, 689
 - listening to events with TableColumnModelListener, 709–712
 - listing properties within with UIDefaults class, 749
 - manually positioning view, 679
 - preinstalled renderers, 695
 - print() method, 724, 727
 - properties, 680, 682

- removing column headers, 680
- rendering table cells, 686–689
- scrolling components, 678–679
- scrolling support, 406
- selection modes, 682, 683
- sorting elements, 700–707
- support classes, 675
- `JTableHeader` class, 676
 - creating, 716
 - customizing look and feel, 717
 - introduction, 715
 - properties, 716
 - using tooltips in headers, 716, 717
- `JTextArea` class
 - adding to window, 476
 - as subclass of `JTextComponent` class, 521
 - as view part of MVC, 59
 - built-in drag-and-drop support, 730
 - creating, 570
 - customizing look and feel, 572
 - `UIResource`-related properties, 573–574
 - handling events, 572
 - introduction, 570
 - model and UI delegate, 60
 - properties, 571, 572
 - supporting undoable operations, 784
- `JTextComponent` class
 - associating `CaretListener` interface with, 550
 - associating `NavigationFilter` class with, 552
 - drawing in the background of component, 525–526
 - `getActions()` method, 586
 - `getKeymap()` method, 586
 - introduction, 523
 - `modelToView()` method, 549
 - operations, 526
 - operations with `JTextField` class, 530–537
 - properties, 523
 - `read()` method, 607
 - `registerKeyboardAction()` method, 554
 - scrolling support, 406
 - `setKeymap()` method, 586
 - subclasses, 521
 - `write()` method, 607
- `JTextComponent.KeyBinding` class, 556
- `JTextField` class, 499
 - as editor for `JTree`, 645
 - as subclass of `JTextComponent` class, 521
 - `BoundedRangeModel` interface, 447, 449
 - built-in drag-and-drop support, 730
 - creating, 527
 - customizing look and feel, 562–563
 - dragging text from `JLabel` class to `JTextField` class, 733
 - editing `JComboBox` class elements, 498
 - editing table cells, 718
 - handling events, 556–562
 - introduction, 526
 - `JPasswordField` as subclass of, 521, 565
 - `JTextComponent` operations, 530
 - accessing the clipboard, 534–537
 - loading and saving content, 530–534
 - notify-field-accept action, 587
 - properties, 529
 - using `JLabel` mnemonics, 527–529
- `JTextPane` class, 5
 - as subclass of `JEditorPane` component, 521
 - built-in drag-and-drop support, 730
 - creating, 580
 - creating stylized text for display, 585
 - customizing look and feel, 581
 - `DefaultStyledDocument` class as data model, 596
 - Hello, Java example, 600–601
 - introduction, 580
 - loading with content, 582–583
 - populating `StyledDocument` for, 599
 - properties, 580–581
- `JToggleButton` class, 6
 - creating, 119–120
 - customizing look and feel, 124
 - `UIResource` elements, 125
 - handling selection events, 121–124
 - introduction, 119
 - properties, 120
 - `ToggleButtonModel` class as inner class of, 115
- `JToggleButtonMenuItem` example, 195–199
- `JToolBar` class, 8, 784
 - adding components to, 202
 - creating, 202
 - customizing look and feel, 205
 - `getUIClassID()` method, 763

- handling events, 205
- introduction, 202
- properties, 203
- Separator class, 208
- usage example, 206–208
- JToolTip class, 7
 - creating, 84
 - creating customized objects, 84
 - customizing look and feel, 86
 - displaying positional tooltip text, 85
 - properties, 85
- JTree class, 7
 - convertValueToText() method, 642
 - creating a proper JComboBox editor for, 648
 - creating, 624–627
 - creating custom renderer, 637–641
 - customizing look and feel, 630–634
 - DefaultTreeCellEditor class, 647
 - DefaultTreeModel class, 667
 - DynamicUtilTreeNode inner class, 624, 666
 - editable property, 643
 - EmptySelectionModel inner class, 624, 669
 - introducing trees, 623–624
 - properties, 628–630
 - scrolling support, 406
 - scrolling trees, 627–628
 - should use DefaultTreeCellEditor for JTextField editor, 645
 - working with tree tooltips, 641–643
- JViewport class
 - contained within JScrollPane, 403
 - creating, 412
 - customizing look and feel, 417
 - introduction, 412
 - keyboard movement control, 414–417
 - properties, 412
 - scroll modes, 414
 - use of ViewportLayout class, 371
 - usually used with JScrollPane class, 371
- JWindow class
 - BorderLayout class as default layout manager for, 347
 - creating, 247
 - extending, 248
 - fitting JPopupMenu menu items, 179
 - handling events, 248
 - introduction, 247
 - properties, 248
- K**
- KeyBinding class, 556
- KeyboardFocusManager class, 37, 48
 - activeWindow property, 55
 - focus management, 47
 - focusedWindow property, 55
 - focusOwner property, 55
 - input focus behavior of Swing components, 55
 - methods, 55
- KeyEvent class
 - getKeyText() method, 29
 - java.awt.event package, 163
- KeyListener class
 - listening to JTextField events, 557
 - sending keystrokes to ActionListener, 30
 - supported by JFrame class, 246
 - using, 586
- Keymap interface, 37
 - addActionForKeyStroke() method, 45
 - implementation as a wrapper to InputMap/ActionMap combination, 586
 - introduction, 554–556
 - maps KeyStroke to TextAction, 586
- keymap property
 - JTextComponent class, 523, 554
- keys property
 - AbstractAction class, 41
- KeySelectionManager interface, 195, 493
 - keystroke manager for JComboBox class, 491
 - listening to JComboBox keyboard events, 494
- keySelectionManager property
 - JComboBox class, 492, 494
- KeyStroke class
 - creating, 42
 - getKeyStroke() method, 43
 - getKeyStrokeForEvent() method, 43
 - keystroke registration conditions, 42
 - registering, 43, 44, 45
 - registering to JTextComponent class, 554
 - Swing-specific event handling, 37
 - using, 586
- KeyTextComponent class
 - registering ActionListener, 31

L

- label property
 - AbstractButton class, 99
 - JPopupMenu class, 179
- labelFor property
 - JLabel class, 90, 91
- labelTable property
 - JSlider component, 431
- largeModel property
 - JTree class, 628, 630
- lastChild property
 - DefaultMutableTreeNode interface, 663
- lastDividerLocation property
 - JSplitPane class, 385, 389, 390, 392
- lastIndex property
 - ListSelectionEvent class, 476
- lastIndexOf() method
 - DefaultListModel class, 460
- lastLeaf property
 - DefaultMutableTreeNode interface, 663
- lastPathComponent property
 - TreePath class, 671
- lastRow property
 - TableModelEvent class, 700
- lastSelectedPathComponent property
 - JTree class, 628, 630
- lastVisibleIndex property
 - JList class, 465, 468
- layer property
 - JInternalFrame class, 254
- LayeredHighlighter class, 547
- LayeredHighlighter.LayerPainter class, 547
- layeredPane property
 - JDialog class, 250
 - JFrame class, 243
 - JInternalFrame class, 254
 - JRootPane class, 237
 - JWindow class, 248
- LayerPainter class, 547
- layout management
 - changing manager for JMenuBar class, 161
 - changing manager for JTabbedPane class, 399
 - Swing components, 10, 11
- layout managers
 - See also* AWT layout managers and Swing layout managers
 - BorderLayout class, 347–349
 - BoxLayout class, 357–364
 - CardLayout class, 357
 - FlowLayout class, 345–347
 - GridBagConstraints class, 353–357
 - GridBagLayout class, 350–353
 - GridLayout class, 349–350
 - introduction, 343
 - LayoutManager interface, 344–345
 - OverlayLayout class, 365–370
 - responsibilities, 343–344
 - ScrollPaneLayout class, 370
 - SizeRequirements class, 370
 - SpringLayout class, 371–375
 - ViewportLayout class, 371
- layout property
 - AbstractButton class, 98
 - Box class, 379
 - JComponent class, 78
 - JDialog class, 250
 - JFrame class, 243
 - JInternalFrame class, 255
 - JLayeredPane class, 240
 - JScrollPane class, 407
 - JToolBar class, 203
 - JWindow class, 248
- LayoutFocusTraversalPolicy class
 - focus management, 47
 - FocusTraversalPolicy class, 53
- LayoutManager interface
 - introduction, 344
 - methods, 344
- LayoutManager2 interface
 - methods, 345
- layoutOrientation property
 - JList class, 465
- lazy, definition, 755
- LazyValue interface, 755
 - creating, 755
 - createValue() method, 755
- leadAnchorNotificationEnabled property
 - DefaultListSelectionModel class, 475, 683
- leader property
 - TabStop class, 604
- leadSelectionIndex property
 - DefaultListSelectionModel class, 475, 683
 - JList class, 465
- leadSelectionPath property
 - DefaultTreeSelectionModel class, 670
 - JTree class, 628, 630

- leadSelectionRow property
 - DefaultTreeSelectionModel class, 670
 - JTree class, 629–630
- leaf nodes
 - creating editor for, 648–649
- leaf property
 - DefaultMutableTreeNode interface, 663
- leafCount property
 - DefaultMutableTreeNode interface, 663
- leafIcon property
 - DefaultTreeCellRenderer class, 635
- leftComponent property
 - JSplitPane class, 385–386
- length property
 - AbstractDocument class, 540
- level property
 - DefaultMutableTreeNode interface, 663
- lightweight property
 - JComponent class, 79
- lightWeightPopupEnabled property
 - JComboBox class, 492
 - JPopupMenu class, 179
 - ToolTipManager class, 87
- LineBorder class
 - configuring properties, 220
 - creating, 219
- lineColor property
 - LineBorder class, 220
- lineCount property
 - JTextArea class, 571
- lineWrap property
 - JTextArea class, 571
- list model controls, 451
 - See also* individual controls
- list property
 - SpinnerListModel class, 516
- ListCellRenderer interface, 719
 - and DefaultListCellRenderer class, 468, 470
 - cell renderer for JComboBox class, 491
 - creating complex version, 471–473
 - drawing elements of JList class, 463
 - getListCellRendererComponent()
 - method, 469
 - making lazy, 755
- listData property
 - JList class, 465
- ListDataEvent class
 - properties, 454
- ListDataListener class, 451
 - list managed by DefaultListModel class, 453
 - list management provided by
 - AbstractListModel, 452
 - listening for ListModel events, 454–460
 - listening to JComboBox events, 497
 - managed by ListModel interface, 452
 - using, 455
- ListEditor class
 - introduction, 519
- ListModel interface
 - converting ArrayList data structure, 453
 - data model for JList class, 463
 - defines data model for JComboBox class, 491
 - extended by
 - ComboBoxModel interface, 460
 - introduction, 451
 - management of ListDataListener, 452
 - partially implemented by
 - AbstractListModel, 452
- ListSelectionEvent class
 - properties, 476
- ListSelectionListener interface
 - listening to JList events, 476–478
 - registering with ListSelectionModel class, 683
- listSelectionListeners property
 - DefaultListSelectionModel class, 475, 683
 - JList class, 465
- ListSelectionModel interface, 676
 - allowing users to select columns and rows
 - from table, 708
 - attaching ListSelectionListener, 476
 - constants for different selection
 - modes, 683
 - controls selection process for JList, 473
 - creating columns that do not scroll, 692
 - default implementation is
 - DefaultListSelectionModel class, 475
 - handling JTable events, 689
 - model for selecting elements of JList class, 463
 - modes, 474
 - multiple-selection mode, 678
 - registering ListSelectionListener, 683
 - settings control selection within table, 676
- load() method
 - SynthLookAndFeel class, 780

- locale property
 - AccessibleContext class, 807
 - JComponent class, 79
- localization
 - NumberFormat class, 615
- locationOnScreen property
 - JComponent class, 77
- locationToIndex() method
 - JList class, 478
- logicalStyle property
 - JTextPane class, 581
- look and feel architecture, 741
 - creating new look and feel, 767–772
 - LookAndFeel class, 741–766
 - metal themes, 772
 - SynthLookAndFeel class, 777–781
 - using auxiliary look and feel, 776
- look and feel image files, 768–770
- LookAndFeel class
 - as root class for specific look and feel, 741
 - changing current look and feel, 743–747
 - customizing current look and feel, 747
 - creating new UI delegate, 763–766
 - UIDefaults class, 749–752
 - UIDefaults.ActiveValue,
 - UIDefaults.LazyValue, and
 - UIDefaults.ProxyLazyValue classes,755–759
 - UIManager class, 747–749
 - UIManager.LookAndFeelInfo class, 749
 - UIResource interface, 753–755
 - using client properties, 759–763
 - introduction, 741–742
 - listing installed classes, 742
 - makeIcon() method, 755
- lookAndFeel property
 - UIManager class, 748
- lookAndFeelDefaults property
 - UIManager class, 748
- lowestLayer() method
 - JLayeredPane class, 240
- M**
- MacLookAndFeel implementation
 - LookAndFeel.supportedLookAndFeel, 742
- magicCaretPosition property
 - Caret interface, 548
- majorTickSpacing property
 - JSlider component, 431
- makeIcon() method
 - LookAndFeel class, 755
- Map interface, 41
- margin property
 - AbstractButton class, 98
 - JMenuBar class, 159
 - JPopupMenu class, 179
 - JTextComponent class, 523, 524
 - JToolBar class, 203
- mark property
 - Caret interface, 548
- MaskFormatter class, 566
 - overwriteMode property, 620
 - placeholderCharacter property, 620
 - validCharacters property, 620
- MatteBorder class, 224
 - color implementation, 225
 - constructors and methods, 225
 - Icon implementation, 225
- maxCharactersPerLineCount property
 - JOptionPane class, 281, 282, 292
- maximizable property
 - InternalFrame class, 255
- maximum property
 - BoundedRangeModel interface, 419
 - InternalFrame class, 255
 - JProgressBar component, 440
 - JScrollBar component, 426
 - JSlider component, 431
 - ProgressMonitor class, 296
 - SpinnerNumberModel class, 517
- maximumDividerLocation property
 - JSplitPane class, 385
- maximumRowCount property
 - JComboBox class, 492
- maximumSize property
 - JComponent class, 78
 - JScrollBar component, 426
- maximumSizeSet property
 - JComponent class, 78
- maxSelectionIndex property
 - DefaultListSelectionModel class, 475, 683
- maxSelectionRow property
 - DefaultTreeSelectionModel class, 670
 - JTree class, 629, 630
- maxWidth property
 - TableColumn class, 713
- menu components
 - example, 152
 - hierarchy, 156

- menuBackground property
 - MetalLookAndFeel class, 773
- menuComponentCount property
 - JMenu class, 171
- menuComponents property
 - JMenu class, 171
- menuCount property
 - JMenuBar class, 159
- menuDisabledForeground property
 - MetalLookAndFeel class, 773
- MenuDragMouseEvent class
 - definition, 167
- MenuDragMouseListener interface
 - listening to JMenuItem events, 167
- menuDragMouseListeners property
 - JMenuItem class, 164
- MenuElement interface, 157
 - creating custom components, 195
- menuForeground property
 - MetalLookAndFeel class, 773
- MenuKeyListener interface
 - listening to JMenuItem events, 166
- menuKeyListeners property
 - JMenuItem class, 164
 - JPopupMenu class, 179
- MenuListener interface
 - listening to JMenu events, 173
- menuListeners property
 - JMenu class, 172
- menus, adding to or removing from menu bars, 157, 158
- menuSelectedBackground property
 - MetalLookAndFeel class, 773
- menuSelectedForeground property
 - MetalLookAndFeel class, 773
- menuSelectionChanged() method
 - MenuElement interface, 195
- MenuSelectionManager class, 167, 195
- menuTextFont property
 - MetalLookAndFeel class, 773
- message property
 - JOptionPane class, 269, 270, 281, 283
- MessageFormat class
 - java.text package, 727
- messageType property
 - JOptionPane class, 270, 281
- Metal themes, creating, 774
- MetalLookAndFeel class
 - addCustomEntriesToTable() method, 774
 - currentTheme property, 774
 - javax.swing.plaf.metal package, 748, 772
 - properties, 772
- MetalLookAndFeel implementation
 - LookAndFeel.supportedLookAndFeel, 742
- Metalworks system demo
 - examples for customizing themes, 775
- millisToDecideToPopup property
 - ProgressMonitor class, 292, 296
- millisToPopup property
 - ProgressMonitor class, 292, 296
- minimum property
 - BoundedRangeModel interface, 419
 - JProgressBar component, 440
 - JScrollBar component, 426
 - JSlider component, 431
 - ProgressMonitor class, 296
 - SpinnerNumberModel class, 517
- minimumDividerLocation property
 - JSplitPane class, 385
- minimumSize property
 - JComponent class, 78
 - JScrollBar component, 426
- minimumSizeSet property
 - JComponent class, 78
- minorTickSpacing property
 - JSlider component, 431
- minSelectionIndex property
 - DefaultListSelectionModel class, 475, 683
 - JList class, 465
- minSelectionRow property
 - DefaultTreeSelectionModel class, 670
 - JTree class, 629, 630
- minWidth property
 - TableColumn class, 713
- mnemonic property
 - AbstractButton class, 98
 - DefaultButtonModel interface, 100
- mnemonics, 46
- model property
 - AbstractButton class, 99
 - DateEditor class, 519
 - JComboBox class, 492
 - JList class, 465
 - JMenu class, 172

- JProgressBar component, 440
- JScrollBar component, 426
- JSlider component, 431
- JSpinner class, 510
- JTabbedPane class, 399
- JTable class, 681
- JTree class, 629
- ListEditor class, 520
- NumberEditor class, 520
- modelIndex property
 - TableColumn class, 713
- modelToView() method
 - JTextComponent class, 549
- ModifyModelSample program
 - using DefaultListModel class modifying methods, 455–459
- mostRecentFocusOwner property
 - JInternalFrame class, 255
- MotifButtonUI class
 - getBorderInsets() method, 217
- MotifLookAndFeel implementation
 - LookAndFeel.supportedLookAndFeel, 742
- mouseClicked() method
 - MouseListener interface, 23
- mouseDragged() method
 - MouseMotionListener interface, 23
- mouseEntered() method
 - MouseListener interface, 23
- MouseEnterFocusMover class
 - programmatically moving focus, 49
- mouseExited() method
 - MouseListener interface, 23
- MouseListener interface
 - methods, 23
- MouseListener interface
 - creating to handle input focus, 48
 - requestFocusInWindow() method, 48
 - supported by JFrame class, 246
- MouseMotionListener interface
 - methods, 23
 - supported by JFrame class, 246
- mouseMoved() method
 - MouseMotionListener interface, 23
- mousePosition property
 - JComponent class, 79
- mousePressed() method
 - MouseListener interface, 23
- mouseReleased() method
 - MouseListener interface, 23
- moveDot() method
 - Caret interface, 549
 - NavigationFilter class, 552
- moveToBack() method
 - JLayeredPane class, 241
- moveToFront() method
 - JLayeredPane class, 241
- multiClickThreshold property
 - AbstractButton class, 99
- multiline messages
 - displaying in JOptionPane, 281, 282
- MULTIPLE_INTERVAL_SELECTION mode
 - ListSelectionModel interface, 474
- multiSelectionEnabled property
 - JFileChooser class, 327
- multithreaded Swing event handling, 21, 23
 - managing listener lists, 29
 - AWTEventMulticaster class, 29–32
 - EventListenerList, 32–34
 - selectable button example, 22
 - Timer class, 34–36
 - using PropertyChangeListeners as Observers, 26–28
 - using SwingUtilities class for mouse button identification, 23–26
- MutableAttributeSet interface, 585, 595
 - adding name to with Style interface, 606
 - introduction, 597
 - modifying with StyleConstants class, 602–603
 - setting JTextPane text attributes, 580
- MutableComboBoxModel interface, 64, 451
 - implementing DefaultComboBoxModel class, 461
 - introduction, 460
- MutableTreeNode interface, 659
 - insert() method, 662
 - nodes of JTree are implementations of, 624
 - working with tree nodes, 660
- MVC architecture, 11, 59
 - BoundedRangeModel interface, 419
 - flow described
 - communication, 59
 - UI delegates for Swing components, 60
 - handling JScrollBar events, 423
 - predefined data models, 63–64
 - sharing data models, 61–63

N

- name property
 - JComponent class, 79
 - LookAndFeel class, 742
 - MetalLookAndFeel class, 773
 - UIManager.LookAndFeelInfo class, 749
- NamedStyle class, 595, 606
- nativeLookAndFeel property
 - LookAndFeel class, 742
- NavigationFilter class, 522
 - introduction, 552
 - restricting caret movement example
 - 552, 554
- navigationFilter property
 - JTextComponent class, 523
- next() method
 - ElementIterator class, 611
 - HTMLDocument.Iterator class, 609
- nextLeaf property
 - DefaultMutableTreeNode interface, 663
- nextNode property
 - DefaultMutableTreeNode interface, 663
- nextSibling property
 - DefaultMutableTreeNode interface, 663
- nextValue property
 - JSpinner class, 510
 - SpinnerDateModel class, 515
 - SpinnerListModel class, 516
 - SpinnerNumberModel class, 517
- nodeChanged() method
 - DefaultTreeModel class, 668
- nodesChanged() method
 - DefaultTreeModel class, 668
- nodeStructureChanged() method
 - DefaultTreeModel class, 668
- nodesWereInserted() method
 - DefaultTreeModel class, 668
- nodesWereRemoved() method
 - DefaultTreeModel class, 668
- non-AWT upgraded components, 5
- normalBounds property
 - JInternalFrame class, 255
- note property
 - ProgressMonitor class, 296
- notify-field-accept action
 - extra action for JTextField,
 - JFormattedTextField, and
 - JPasswordField, 587

- Number object
 - providing to JFormattedTextField
 - constructor, 612
- number property
 - SpinnerNumberModel class, 517
- NumberEditor class
 - introduction, 520
 - properties, 520
- NumberFormat class, 612
 - java.text package, 615
- NumberFormatter class, 566

O

- Observer design pattern
 - delegation-based event handling, 17, 18
 - event listeners as observers, 19
- OceanTheme class
 - introduction, 774
- oneTouchExpandable property
 - JSplitPane class, 386, 388
- opaque property
 - JComponent class, 70, 78
 - JDesktopPane component, 263
 - JTextComponent class, 525
- openIcon property
 - DefaultTreeCellRenderer class, 635
- optimizedDrawingEnabled property
 - JComponent class, 70, 78
 - JLayeredPane class, 242
 - JRootPane class, 237
 - JViewport class, 412
- OptionPaneUtils class
 - creating narrow JOptionPane, 281, 282
 - getSelection() method, 273, 274
- options property
 - JOptionPane class, 271, 281
- optionType property
 - JOptionPane class, 270, 281
- orientation property
 - JProgressBar component, 440
 - JScrollBar component, 426
 - JSeparator class, 175
 - JSlider component, 431
 - JSplitPane class, 386
 - JToolBar class, 203
- outsideBorder property
 - CompoundBorder class, 227
- OvalPanel class, 391

- OverlayLayout class
 - introduction, 365–370
- overwriteMode property
 - MaskFormatter class, 620
- P**
- padding
 - GridBagConstraints class, 356
- page property
 - JEditorPane class, 575
- paint() method
 - JComponent class, 69
- paintBorder() method
 - AbstractBorder class, 217, 232
 - Border interface, 212
 - JComponent class, 69, 70
- paintChildren() method
 - JComponent class, 69, 70
- paintComponent() method
 - JComponent class, 69, 70
 - JPanel class, 111
- paintIcon() method
 - Icon interface, 93
- paintImmediately() method
 - JComponent class, 70, 78
- paintingTile property
 - JComponent class, 78
- paintLabels property
 - JSlider component, 431
- paintTicks property
 - JSlider component, 431
- paintTrack property
 - JSlider component, 431
- Panel class
 - displaying the menu choices, 179
- paragraphAttributes property
 - JTextPane class, 581
- ParagraphConstants class
 - keys for attributes, 598
 - TabSet attribute, 603
- parent property
 - DefaultMutableTreeNode interface, 663
 - JComponent class, 77
- parentPath property
 - TreePath class, 671
- password property
 - JPasswordField class, 564
- paste() method
 - JTextComponent class, 534
- pasteAction class constant
 - DefaultEditorKit class, 592
- path property
 - DefaultMutableTreeNode interface, 663
 - TreePath class, 671
- pathByAddingChild() method
 - TreePath class, 671
- pathCount property
 - TreePath class, 671
- percentComplete property
 - JProgressBar component, 441
- placeholderCharacter property
 - MaskFormatter class, 620
- plaf, 2
- PlainDocument class, 60, 521
 - implementation of Document interface, 526
 - as data model for JTextArea, 570
 - introduction, 541, 542
- PlainView view
 - BasicTextAreaUI interface, 60
- Popup class
 - creating, 200
- pop-up menu usage example, 182–184
- pop-up usage example, 200–202
- pop-up window
 - showing JFileChooser in, 326
- PopupFactory class
 - creating Popup objects, 200
- popupMenu property
 - JMenu class, 172
- PopupMenuEvent event
 - PopupMenuListener class, 180
- PopupMenuListener class
 - watching for pop-up menu visibility, 180
- popupMenuListeners property
 - JComboBox class, 492
 - JPopupMenu class, 179
- popupMenuVisible property
 - JMenu class, 172
- pop-ups, 267
 - JOptionPane class
 - automatically creating in pop-up window, 274–280
 - creating, 268–271
 - customizing look and feel, 287–291
 - displaying, 271–274
 - introduction, 267–268
 - properties, 280–287

- ProgressMonitor class
 - creating, 292
 - customizing look and feel, 297
 - introduction, 291–292
 - properties, 296–297
 - using, 293–296
- ProgressMonitorInputStream class
 - creating, 297
 - introduction, 297
 - properties, 299
 - using, 298–299
- popupSize property
 - JPopupMenu class, 179
- popupVisible property
 - JComboBox class, 492
- position constants
 - JOptionPane class, 274
- position property
 - TabStop class, 604
- positioning operations
 - JTextComponent class, 526
- postEdit() method
 - UndoableEditSupport class, 794
- preferredScrollableViewportSize property
 - JList class, 465, 466
 - JTable class, 681
 - JTextArea class, 571
 - JTextComponent class, 523
 - JTree class, 629
- preferredSize property
 - DefaultTreeCellRenderer class, 635
 - JComponent class, 78
 - JEditorPane class, 575
 - JTextArea class, 571
 - JTextField class, 529
- preferredSizeSet property
 - JComponent class, 78
- preferredWidth property
 - TableColumn class, 713
- preOrderEnumeration() method
 - DefaultMutableTreeNode class, 665
- pressed property
 - DefaultButtonModel interface, 100
- pressedIcon property
 - AbstractButton class, 99
- previewPanel property
 - JColorChooser class, 307, 308
- previous() method
 - ElementIterator class, 611
- previousLeaf property
 - DefaultMutableTreeNode interface, 663
- previousNode property
 - DefaultMutableTreeNode interface, 663
- previousSibling property
 - DefaultMutableTreeNode interface, 663
- previousValue property
 - JSpinner class, 510
 - SpinnerDateModel class, 515
 - SpinnerListModel class, 516
 - SpinnerNumberModel class, 517
- primary1 property
 - MetalLookAndFeel class, 773
- primary2 property
 - MetalLookAndFeel class, 773
- primary3 property
 - MetalLookAndFeel class, 773
- primaryControl property
 - MetalLookAndFeel class, 773
- primaryControlDarkShadow property
 - MetalLookAndFeel class, 773
- primaryControlHighlight property
 - MetalLookAndFeel class, 773
- primaryControlInfo property
 - MetalLookAndFeel class, 773
- primaryControlShadow property
 - MetalLookAndFeel class, 773
- print() method
 - JTable class, 724, 727
- PrinterException class, 727
- printing tables, 724
- processKeyEvent() method
 - MenuElement interface, 195
- processMouseEvent() method
 - MenuElement interface, 195
- progress property
 - ProgressMonitor class, 296
- ProgressMonitor class
 - creating, 292
 - introduction, 291–292
 - properties, 296–297
 - using, 293–296
- progressMonitor property
 - ProgressMonitorInputStream class, 300
- ProgressMonitorHandler inner class, 294
- ProgressMonitorInputStream class
 - creating, 297
 - introduction, 297
 - properties, 299
 - using, 298–299

- PropertiesList example
 - demonstrating tooltips, 488, 490
 - PropertyChangeListener, 420
 - AbstractButton class, 102
 - as accessory component for JFileChooser class, 331, 333
 - JOptionPane, 287
 - listening for JSplitPane property changes, 390
 - supported by JFrame class, 246
 - PropertyChangeListener interface
 - event handler for JComponent class, 80
 - using as Observers, 26, 27, 28
 - propertyChangeListeners property
 - AbstractAction class, 41
 - TableColumn class, 713
 - UIManager class, 748
 - PropertyChangeSupport class, 26
 - prototypeCellValue property
 - JList class, 465, 466
 - prototypeDisplayValue property
 - JComboBox class, 492
 - ProxyLazyValue class, 755
 - associating with Tree.openIcon setting, 756, 757
 - deferring object creation, 755, 756
 - put() method
 - UIManager class, 747, 758
 - putClientProperty() method
 - JComponent class, 759
 - putConstraint() method
 - SpringLayout class, 372, 373
 - putDefaults() method
 - UIDefaults class, 749
 - putProperty() method
 - AbstractDocument class, 540
- Q**
- QUESTION_MESSAGE pop-up
 - JOptionPane class, 278
- R**
- RadioButtonUtils class
 - complete definition, 145
 - createRadioButtonGrouping() method, 137, 140
 - listing text actions, 587
 - read() method
 - JTextComponent class, 530
 - readOnlyAction class constant
 - DefaultEditorKit class, 592
 - redo() method
 - CompoundEdit class, 792
 - UndoableEdit interface, 790
 - UndoManager class, 784
 - registeredKeyStrokes property
 - JComponent class, 79
 - registerKeyboardAction() method
 - JTextComponent class, 554
 - reload() method
 - DefaultTreeModel class, 668
 - remove() method
 - DocumentFilter class, 542
 - JMenuBar class, 158
 - JPopupMenu class, 178
 - removeCellEditorListener() method
 - CellEditor interface, 654
 - removeChooserPanel() method
 - JColorChooser class, 320
 - removeElement() method
 - DefaultListModel class, 454
 - removeListenerListener() method
 - JList class, 476
 - removeNodeFromParent() method
 - DefaultTreeModel class, 668
 - removeSelectedInterval() method
 - JList class, 479
 - removeUpdate() method
 - DocumentListener interface, 546
 - renderer property
 - JComboBox class, 492
 - renderers, preinstalled
 - JTable class, 695
 - reorderingAllowed property
 - JTableHeader class, 716
 - repaint() method
 - JComponent class, 69
 - RepaintManager class
 - customizing painting behavior, 69
 - introduction, 70, 71
 - properties, 71
 - repeats property
 - Timer class, 36
 - replace() method
 - DocumentFilter class, 542
 - requestFocusEnabled property
 - JComponent class, 78

- requestFocusInWindow() method
 - MouseListener interface, 48
- resetToPreferredSizes() method
 - JSplitPane class, 387
- reshowDelay property
 - ToolTipManager class, 87
- resizable property
 - JInternalFrame class, 255
 - TableColumn class, 713
- resizeWeight property
 - JSplitPane class, 386, 389
- resizingAllowed property
 - JTableHeader class, 716
- resizingColumn property
 - JTableHeader class, 716
- resolveParent property
 - SimpleAttributeSet class, 598
- restart() method
 - Timer class, 35
- restoreState method
 - StateEditable interface, 800
- restoreState() method
 - StateEditable interface, 801
- restricting focus cycle example, 51
- revalidate() method
 - JComponent class, 70, 79
- reversing focus traversal, 53–55
- rightComponent property
 - JSplitPane class, 386
- rigid component, creating, 382, 383
- rollover property
 - DefaultButtonModel interface, 100
 - JToolBar class, 203, 205
- rolloverEnabled property
 - AbstractButton class, 99, 102
- rolloverIcon property
 - AbstractButton class, 99, 102
- rolloverSelectedIcon property
 - AbstractButton class, 99, 102
- root pane containers
 - introduction, 235
 - JApplet class, 252
 - JDialog class, 248–252
 - JFrame class, 242–247
 - JLayeredPane class, 239–242
 - JRootPane class, 235–239
 - JWindow class, 247–248
 - RootPaneContainer interface, 239
 - working with a desktop, 252
 - JDesktopPane class, 262–266
 - JInternalFrame class, 253–262
- root property
 - DefaultMutableTreeNode interface, 663
- rootElements property
 - AbstractDocument class, 540
- RootLayout class
 - layout manager for JRootPane class, 235–236
- RootLayout inner class, 343
- rootPane property
 - JComponent class, 78
 - JDialog class, 250
 - JFrame class, 243
 - JInternalFrame class, 255
 - JWindow class, 248
- RootPaneContainer interface
 - adding components to JFrame class, 245
 - getting root pane, 236
 - implemented by JApplet class, 252
 - implemented by JDialog class, 248
 - implemented by JInternalFrame class, 253
 - introduction, 239
- rootVisible property
 - JTree class, 629, 630
- roundedCorners property
 - LineBorder class, 220
- rowCount property
 - DefaultTableModel class, 697
 - JTable class, 681
 - JTree class, 629
- rowHeader property
 - JScrollPane class, 407
- rowHeaderView property
 - JScrollPane class, 407, 409
- rowHeight property
 - JTable class, 681
 - JTree class, 629
- RowMapper class
 - implementation of TreePath class, 624
- RowMapper interface
 - AbstractLayoutCache class
 - implements, 670
- rowMapper property
 - DefaultTreeSelectionModel class, 670
- rowMargin property
 - JTable class, 681
- rows property
 - JTextArea class, 571

- rowSelectionAllowed property
 - JTable class, 681, 682
- Runnable objects
 - creating with EventQueue class, 21
- running property
 - Timer class, 36
- S**
- Scrollable interface, 404, 466
 - definition, 406
 - implemented by JTable class, 678
 - implemented by JTextComponent class, 523
 - implementation properties, 524
 - implemented by JTree, 623, 627
- scrollableTracksViewportHeight property
 - JEditorPane class, 575
 - JList class, 465
 - JTable class, 681
 - JTextComponent class, 523
 - JTree class, 629
- scrollableTracksViewportWidth property
 - JEditorPane class, 575
 - JList class, 465
 - JTable class, 681
 - JTextArea class, 571
 - JTextComponent class, 523
 - JTree class, 629
- Scrollbar component
 - compared to JScrollBar and JSlider components, 6
- scrolling support
 - Swing components, 406
- scrollMode property
 - JViewport class, 412, 414
- scrollOffset property
 - JTextField class, 529, 530
- ScrollPaneLayout class
 - introduction, 370
- ScrollPaneLayout manager class
 - locations, 408
- scrollPathToVisible() method
 - JTree class, 627
- scrollRowToVisible() method
 - JTree class, 627
- scrollsOnExpand property
 - JTree class, 629, 630
- secondary1 property
 - MetalLookAndFeel class, 773
- secondary2 property
 - MetalLookAndFeel class, 773
- secondary3 property
 - MetalLookAndFeel class, 773
- selectAll() method
 - ComboBoxEditor class, 499
- selected property
 - AbstractButton class, 99
 - DefaultButtonModel interface, 100
 - JInternalFrame class, 255
 - JMenu class, 172
 - JMenuBar class, 159
 - JPopupMenu class, 179
- selectedColor property
 - ColorSelectionModel interface, 303
- selectedColumn property
 - JTable class, 681–682
- selectedColumnCount property
 - DefaultTableColumnModel class, 709
 - JTable class, 681–682
- selectedColumns property
 - DefaultTableColumnModel class, 709
 - JTable class, 681–682
- selectedComponent property
 - JTabbedPane class, 399
- selectedFile property
 - JFileChooser class, 327
- selectedFiles property
 - JFileChooser class, 327
- selectedFrame property
 - JDesktopPane component, 263
- selectedIcon property
 - AbstractButton class, 99
- selectedIndex property
 - JComboBox class, 492
 - JList class, 465
 - JTabbedPane class, 399
- selectedIndices property
 - JList class, 465
- selectedItem property
 - DefaultComboBoxModel class, 461
 - extended by ComboBoxModel interface, 460
 - JComboBox class, 492
- selectedObjects property
 - AbstractButton class, 99
 - DefaultButtonModel interface, 100
 - JCheckBoxMenuItem component, 185
 - JComboBox class, 492

- selectedRow property
 - JTable class, 681–682
- selectedRowCount property
 - JTable class, 681–682
- selectedRows property
 - JTable class, 681–682
- selectedText property
 - JTextComponent class, 524
- selectedTextColor property
 - JTextComponent class, 524
- selectedValue property
 - JList class, 465
- selectedValues property
 - JList class, 465
- selection operations
 - JTextComponent class, 526
- selectionBackground property
 - JList class, 465
 - JTable class, 681, 682
 - TextField class, 547
- selectionColor property
 - JTextComponent class, 524
- selectionCount property
 - DefaultTreeSelectionModel class, 670
 - JTree class, 629
- selectionEmpty property
 - DefaultListSelectionModel class, 475, 683
 - DefaultTreeSelectionModel class, 670
 - JList class, 465
 - JTree class, 629
- selectionEnd property
 - JTextComponent class, 524
- selectionForeground property
 - JList class, 465
 - JTable class, 681, 682
- selectionForKey() method
 - KeySelectionManager interface, 494
- selectionMode property
 - DefaultListSelectionModel class, 475
 - DefaultTreeSelectionModel class, 670
 - JList class, 465, 475
 - JTable class, 681–682
- selectionModel property
 - DefaultListSelectionModel class, 683
 - DefaultTableColumnModel class, 709
 - JColorChooser class, 307
 - JList class, 465
 - JMenuBar class, 159
 - JPopupMenu class, 179
 - JTable class, 682, 683
 - JTree class, 629
- selectionPath property
 - DefaultTreeSelectionModel class, 670
 - JTree class, 629
- selectionPaths property
 - DefaultTreeSelectionModel class, 670
 - JTree class, 629, 630
- selectionRow property
 - JTree class, 629
- selectionRows property
 - DefaultTreeSelectionModel class, 670
 - JTree class, 629, 630
- selectionStart property
 - JTextComponent class, 524
- selectionValues property
 - JOptionPane class, 281
- selectionVisible property
 - Caret interface, 548
- Separator class, 182
 - JToolBar class, 208
- separatorBackground property
 - MetalLookAndFeel class, 773
- separatorForeground property
 - MetalLookAndFeel class, 773
- set() method
 - DefaultListModel class, 453
- setAcceptAllFileFilterUsed() method
 - JFileChooser class, 331
- setAccessibleDescription() method
 - AccessibleContext class, 807
- setAccessibleName() method
 - AccessibleContext class, 807
- setAction() method
 - JComboBox class, 494
 - JPopupMenu class, 177
- setAlignment() method
 - StyleConstants class, 602
- setBackgroundAt() method
 - JTabbedPane class, 398
- setBorder() method
 - JViewport class, 412
- setBorderPainted method
 - hiding border, 219
- setBorderPainted() method
 - JProgressBar component, 441
- setBottomComponent() method
 - JSplitPane class, 386

- setColor() method
 - JColorChooser class, 313
- setComponentAt() method
 - JTabbedPane class, 398
- setComponentPopupMenu() method
 - JComponent class, 178
- setConstraints() method
 - SpringLayout.Constraints class, 371
- setCorner() method
 - JScrollPane class, 409
- setCurrentManager() method
 - RepaintManager class, 70
- setDefaultCloseOperation() method
 - JFrame class, 246
- setDescription() method
 - ImageIcon class, 806
- setDisabledIconAt() method
 - JTabbedPane class, 398
- setDisplayedMnemonic() method
 - JLabel class, 527
- setDisplayedMnemonicIndexAt() method
 - JTabbedPane class, 398
- setDividerLocation() method
 - JSplitPane class, 387
- setDocumentFilter() method
 - AbstractDocument class, 542
- setDot() method
 - NavigationFilter class, 552
- setDragEnabled() method
 - components with built-in drag-and-drop support, 729
- setEditor() method
 - JSpinner class, 518
- setElementAt() method
 - DefaultListModel class, 453
- setEnabled property
 - AbstractButton class, 102
- setEnabled() method
 - disables selection of component, 232
- setEnabledAt() method
 - JTabbedPane class, 398
- setExtent method
 - JScrollBar component, 426
 - JSlider component, 431
- setFileFilter() method
 - JFileChooser class, 330
- setFocusable() method
 - Component class, 49
- setFocusTraversalKeys() method
 - Component class, 55
- setForegroundAt() method
 - JTabbedPane class, 398
- setHelpMenu() method
 - JMenuBar class, 381
- setIconAt() method
 - JTabbedPane class, 398
- setInheritsPopupMenu() method
 - JComponent class, 178
- setIndeterminate() method
 - JProgressBar component, 442
- setInverted() method
 - JSlider component, 436
- setItem() method
 - ComboBoxEditor class, 499
- setJMenuBar() method
 - adding JMenuBar to a window, 157
- setKeymap() method
 - JTextComponent class, 586
- setLabelFor() method
 - JLabel class, 528, 807
- setLabelTable() method
 - JSlider component, 435
- setLayer() method
 - JLayeredPane class, 240
- setLayout() method
 - Container class, 344
 - JToolBar class, 204
- setLayoutOrientation() method
 - JList class, 479
- setLookAndFeel() method
 - UIManager class, 743
- setMajorTickSpacing() method
 - JSlider component, 432
- setMask() method
 - JFormattedTextField component, 618
- setMaximum method
 - JScrollBar component, 426
 - JSlider component, 431
- setMinimum method
 - JScrollBar component, 426
 - JSlider component, 431
- setMinimumSize() method
 - JComponent class, 388
- setMinorTickSpacing() method
 - JSlider component, 432
- setMnemonic() method
 - AbstractButton class, 101

- setMnemonicAt() method
 - JTabbedPane class, 398
- setModel() method
 - JTree class, 625
- setOrientation() method
 - JSeparator class, 182, 208
- setPaintLabels() method
 - JSlider component, 435
- setPaintTicks() method
 - JSlider component, 432
- setPaintTrack() method
 - JSlider component, 436
- setParent() method
 - MutableTreeNode interface, 660
- setPopupLocation() method
 - JComponent class, 178
- setPosition() method
 - JLayeredPane class, 241
- setPreviewPanel() method
 - JColorChooser class, 309, 320
- setProgress() method
 - ProgressMonitor class, 293
- setRowHeight() method
 - JTable class, 682
- setSelected() method
 - ButtonGroup class, 118
- setSelectedIcon() method
 - JCheckBox class, 127, 128
- setSelectedIndex() method
 - JRadioButton class, 136
- setSelectedIndex() method
 - JComboBox class, 493
- setSelectedInterval() method
 - JList class, 479
- setSelectedItem() method
 - JComboBox class, 493
- setSelectedValue() method
 - JList class, 479
- setSnapToTicks() method
 - JSlider component, 434
- setStringPainted() method
 - JProgressBar component, 441
- setText() method
 - JFormattedTextField component, 615
 - JMenuItem class, 589
- setTitleAt() method
 - JTabbedPane class, 398
- setToolTipText() method
 - JComponent class, 84, 87
- setToolTipTextAt() method
 - JTabbedPane class, 398
- setTopComponent() method
 - JSplitPane class, 386
- setTransferHandler() method
 - passing in replacement object to be transferred, 731
- setUndecorated() method
 - JDialog class, 237
 - JFrame class, 237
- setValue() method
 - JFormattedTextField component, 615
 - JOptionPane class, 286
 - JScrollBar component, 426
 - JSlider component, 431
- setValueAt() method
 - JTable class, 678
- setVerifyInputWhenFocusTarget() method
 - InputVerifier interface, 57
- setView() method
 - JViewport class, 412
- setVisibleRowCount() method
 - JList class, 467
- sharedInstance() method
 - ToolTipManager class, 86
- shouldSelectCell() method
 - CellEditor interface, 655
- show() method
 - Popup class, 200
- showDialog() method
 - JColorChooser class, 304, 305, 314
 - JFileChooser class, 327
- showGrid property
 - JTable class, 682
- showHorizontalLines property
 - JTable class, 682
- showing property
 - JComponent class, 79
- showInputDialog() method
 - JOptionPane class, 276, 278
- showInternalInputDialog() method
 - JOptionPane class, 278
- showInternalMessageDialog() method
 - JOptionPane class, 277
- showInternalOptionDialog() method
 - JOptionPane class, 280
- showInternalXXXDialog() methods
 - JOptionPane class, 274
- showMessageDialog() method
 - JOptionPane class, 277
- showOptionDialog() method
 - JOptionPane class, 280

- showsRootHandles property
 - JTree class, 629, 630
- showVerticalLines property
 - JTable class, 682
- showXXXDialog() methods
 - JOptionPane class, 274, 275
- siblingCount property
 - DefaultMutableTreeNode interface, 663
- simple numeric text field verification
 - example, 56–57
- SimpleAttributeSet class, 585
 - creating, 598
 - implementation of MutableAttributeSet
 - interface, 595
 - introduction, 597
 - properties, 598
 - using, 598–601
- SINGLE_INTERVAL_SELECTION mode
 - ListSelectionModel interface, 474
- SINGLE_SELECTION mode
 - ListSelectionModel interface, 474
- SINGLE_TREE_SELECTION mode
 - TreeSelectionModel interface, 669
- SingleSelectionModel interface
 - introduction, 161
- size property
 - DefaultComboBoxModel class, 461
 - DefaultListModel class, 453
 - JComponent class, 77
- SizeRequirements class, 370
- SmallAttributeSet class, 595
- snapToTicks property
 - JSlider component, 431, 434
- SoftBevelBorder class, 222
 - constructors, 223
- SortingFocusTraversalPolicy
 - FocusTraversalPolicy class, 53
- spinner property
 - DefaultEditor class, 518
- SpinnerDateModel class
 - getValue() method, 515
 - introduction, 514–515
 - properties, 515
- SpinnerListModel class
 - introduction, 515–516
 - properties, 516
 - subclassing, 517–518
 - working with ListEditor class, 519
- SpinnerModel interface
 - data model for JSpinner, 513
 - properties, 515
- SpinnerNumberModel class
 - introduction, 516–517
 - properties, 517
- SpringLayout class
 - Constraints inner class, 371
 - introduction, 371–375
- SpringLayout.Constraints class, 371
 - setConstraints() method, 371
- StackOverflowError, 214
- start property
 - SpinnerDateModel class, 515
- start() method
 - Timer class, 35
- startOffset property
 - HTMLDocument.Iterator class, 609
- startPosition property
 - AbstractDocument class, 540
- state of text properties
 - JTextComponent class implementation
 - properties, 525
- state property
 - JCheckBoxMenuItem component, 185
- StateEdit class, 783
 - as UndoableEdit implementation, 800–801
 - end() method, 801
 - example with StateEditable, 801–804
- StateEditable interface
 - example with StateEdit class, 801–804
 - implementation of updated document, 800
 - methods, 800
 - restoreState() method, 801
- stepSize property
 - SpinnerNumberModel class, 517
- stop() method
 - Timer class, 35
- stopCellEditing() method
 - CellEditor interface, 654
- storeState method
 - StateEditable interface, 800
- StreamDescriptionProperty constant
 - Document interface, 531
- string property
 - JProgressBar component, 441
- StringContent class
 - AbstractDocument.Content
 - implementation, 596

- stringPainted property
 - JProgressBar component, 441
- strut, creating, 382–383
- Style interface, 595
 - introduction, 606
 - setting JTextPane text attributes, 580
- StyleConstants class, 595
 - constants, 601–602
 - introduction, 601
 - methods, 602–603
 - sharing between multiple documents, 596
- StyleContext class
 - introduction, 606
- StyleContext.NamedStyle class, 606
- StyleContext.SmallAttributeSet class, 595
- StyledDocument interface, 521
 - Document interface extension of, 595
 - extending Document interface, 595
 - implemented by DefaultStyledDocument class, 596
 - loading JTextPane class with content, 582–583
 - manages Style objects, 595
 - using with JTextField class, 530
- styledDocument property
 - JTextPane class, 581
- StyledDocument.NamedStyle class, 595
- StyledEditorKit class
 - finding actions, 591
- styleNames property
 - DefaultStyledDocument class, 596
- subElements property
 - JMenu class, 172
 - JMenuBar class, 159
 - JMenuItem class, 164
 - JPopupMenu class, 179
- subTextFont property
 - MetalLookAndFeel class, 773
- supportedLookAndFeel property
 - LookAndFeel class, 742
- surrendersFocusOnKeystroke property
 - JTable class, 682
- Swing
 - advanced containers, 377
 - Box class, 377–383
 - JScrollPane class, 403–412
 - JSplitPane class, 383–394
 - JTabbedPane class, 394–403
 - JViewport class, 412–417
 - client properties, 759–763
 - introduction, 1
 - layout management, 10, 11
 - menus, 151
 - JCheckBoxMenuItem class, 184–189
 - JMenu class, 168–175
 - JMenuBar class, 157–161
 - JMenuItem class, 162–168
 - JPopupMenu class, 176–184
 - JRadioButtonMenuItem class, 189–195
 - JSeparator class, 175–176
 - menu class hierarchy, 156
 - MenuElement interface, 195–199
 - SingleSelectionModel interface, 161–162
 - working with, 152–156
 - pop-ups, 200–202
 - toolbars, 151
 - JToolBar class, 202–208
- Swing components, 2
 - See also* text components
 - AbstractButton class, 98–103
 - AWT component replacements, 3
 - chapter mapping, 12
 - containers compared to AWT
 - containers, 235
 - delegates, 763–765
 - distinction between equivalent AWT components, 3
 - event handling, 10–11
 - GrayFilter class, 97
 - Icon interface, 92–94
 - ImageIcon class, 94–97
 - JButton class, 104–110
 - JComponent class, 67
 - component pieces, 69–73
 - events, 80–84
 - properties, 74–79
 - JLabel class, 88–92
 - JPanel class, 110–112
 - JToolTip class, 84–88
 - layout managers, 343
 - non-AWT upgraded components, 5
 - predefined models, 64
 - resizing, 388
 - scrolling support, 406
 - SwingSet demonstration, 11
 - undo framework, 11

- Swing focus management, 46, 47
 - examining focus cycles, 50–52
 - FocusTraversalPolicy class, 52, 53, 55
 - KeyboardFocusManager class, 55
 - moving the focus, 48–50
 - verifying input during focus traversal, 56–57
 - swing.auxiliarylaf property
 - registering auxiliary look and feel classes, 776
 - swing.properties file, 746
 - SwingPropertyChangeSupport class, 29
 - SwingSet demonstration, 11
 - Swing-specific event handling, 37
 - AbstractAction class, 38–41
 - Action interface, 37–38
 - KeyStroke class, 41–45
 - mnemonics and accelerators, 46
 - SwingUtilities class
 - getSharedOwnerFrame() method, 277
 - isEventDispatchThread() method, 21
 - mouse button identification, 23, 24, 26
 - updateComponentTreeUI() method, 743
 - wrapper methods, 23
 - synchronous painting
 - JComponent class, 70
 - SynthLookAndFeel class, 777
 - configuring, 777, 779
 - default properties, 780
 - working with Synth images, 780–781
 - SystemColor class
 - displaying list of colors from, 311
 - SystemColorChooserPanel class, 312, 313
 - changing color chooser, 313
 - complete source, 314–318
 - systemLookAndFeelClassName property
 - UIManager class, 748
 - systemTextFont property
 - MetalLookAndFeel class, 773
- T**
- tabCount property
 - JTabbedPane class, 399
 - tabLayoutPolicy property
 - JTabbedPane class, 399
 - table property
 - JTableHeader class, 716
 - TableCellEditor class, 676, 719, 723
 - defining, 722
 - editing table cells, 718
 - TableCellRenderer interface, 676
 - display of cells within table, 676
 - getTableCellRendererComponent()
 - method, 686, 687
 - TableColumn class, 676
 - creating, 712
 - introduction, 712
 - properties, 713
 - removing column headers, 680
 - using icons in column headers, 713–715
 - TableColumnModel interface, 676
 - definition, 708
 - handling JTable events, 689
 - introduction, 708
 - listening for TableColumnModelEvent
 - objects, 709
 - removing TableColumn, 712
 - specifying when creating JTable class, 678
 - storing column selection model, 683
 - TableColumnModelEvent class
 - properties, 709
 - TableColumnModelListener
 - attaching to TableColumnModel
 - object, 710
 - listening to JTable events, 709–712
 - tableHeader property
 - JTable class, 682
 - TableModel interface, 676
 - AbstractTableModel class, 691–696
 - default implementation, 695
 - DefaultTableModel class, 696–700
 - getColumnClass() method, 687, 695
 - handling JTable events, 689
 - implemented by AbstractTableModel
 - class, 691
 - introduction, 690
 - leaving TableColumn in, 712
 - ordering stored columns of data, 676
 - sorting JTable elements, 700–707
 - using column order of, 678
 - TableModelEvent class
 - properties, 699
 - TableModelListener interface
 - list managed by AbstractTableModel
 - class, 691
 - listening to JTable events, 699

- tables, 675
 - editing table cells
 - creating complex cell editor, 722–724
 - creating simple cell editor, 718–722
 - editing table cells, 718–724
 - introducing, 675–676
 - JTable class, 677–690
 - JTableHeader class, 715–718
 - printing tables, 724–727
 - TableColumnModel interface
 - DefaultTableColumnModel class, 708–709
 - listening to JTable events with
 - TableColumnModelListener, 709–712
 - TableColumn class, 712–715
 - TableColumnModel interface, 707–708, 712
 - TableModel interface, 690
 - AbstractTableModel class, 691–696
 - DefaultTableModel class, 696–700
 - sorting JTable elements, 700–707
- tabPlacement property
 - JTabbedPane class, 399
- tabRunCount property
 - JTabbedPane class, 399
- TabSet attribute
 - ParagraphConstants class, 603
- TabSet class
 - introduction, 603
- tabSize property
 - JTextArea class, 571
- TabStop class
 - alignment settings, 604
 - creating, 603
 - introduction, 603
 - properties, 604
 - using, 605–606
- tag property
 - HTMLDocument.Iterator class, 609
- tearOff property
 - JMenu class, 172
- text capabilities, 585
 - creating styled text, 595–607
 - editor kits, 607–612
 - JFormattedTextField component, 612–621
 - using actions, 585–594
- text components
 - finding actions, 591–594
 - JFormattedTextField class, 566–570
 - JPasswordField class, 563–566
 - JTextArea class, 570–580
 - JTextComponent class, 523–526
 - JTextField class, 526–563
 - JTextPane class, 580–583
 - listing actions, 586–589
 - overview, 521–522
 - using actions, 585–586, 589–591
- text justification
 - TitledBorder class, 230
- text property
 - AbstractButton class, 99
 - JEditorPane class, 575
 - JLabel class, 89
 - JTextComponent class, 524
- TextAction class, 522, 585
 - as extension of AbstractAction class, 535
 - listing text actions, 587
 - provides concrete Action implementations, 585
 - Swing-specific event handling, 37
 - using, 586
- TextField class
 - selectionBackground property, 547
- textField property
 - DefaultEditor class, 518
- textHighlightColor property
 - MetalLookAndFeel class, 773
- textNonSelectionColor property
 - DefaultTreeCellRenderer class, 635
- textSelectionColor property
 - DefaultTreeCellRenderer class, 635
- TextUI interface, 60
- TextUtilities class, 537
- thickness property
 - LineBorder class, 220
- Timer class
 - creating objects, 34
 - notifying an ActionListener after a predefined number of milliseconds, 34, 35
 - properties, 35–36
 - using objects, 35
- tipText property
 - JToolTip class, 85
- title justification
 - TitledBorder class, 230
- title positioning
 - TitledBorder class, 231

- title property
 - JInternalFrame class, 255
 - TitledBorder class, 229
- titleColor property
 - TitledBorder class, 229
- TitledBorder class, 227
 - configuring properties, 229
 - creating, 228
 - customizing look and feel, 232
- titleFont property
 - TitledBorder class, 229
- titleJustification property
 - TitledBorder class, 229
- titlePosition property
 - TitledBorder class, 229
- toArray() method
 - DefaultListModel class, 460
- toggle buttons, 115
 - ButtonGroup class, 116–118
 - JCheckBox class, 125–134
 - JRadioButton class, 134–149
 - JToggleButton class, 119–125
 - ToggleButtonModel class, 115–116
- ToggleButtonModel class
 - button model for JRadioButtonMenuItem components, 189
 - data model for JCheckBoxMenuItem class, 184
 - defining JToggleButton structure, 119
 - introduction, 115–116
- ToggleButtonUI class
 - defining JToggleButton structure, 119
- toggleClickCount property
 - JTree class, 629, 630
- toIndex property
 - TableColumnModelEvent class, 709
- toolkit property
 - JComponent class, 79
- ToolTipManager class
 - adding element level tooltips, 488
 - disabling, 87
 - properties, 87
 - registering component with, 641
 - sharedInstance() method, 86
 - unregistering table, 689
- tooltips
 - PropertiesList example, 488, 490
- toolTipText property
 - JComponent class, 79
- ToolTipTreeCellRenderer class, 642
- topComponent property
 - JSplitPane class, 386
- topLevelAncestor property
 - JComponent class, 78
- topLevelMenu property
 - JMenu class, 172
- totalColumnWidth property
 - DefaultTableColumnModel class, 709
- Transferable interface
 - creating transferable image object, 734
 - java.awt.datatransfer package, 733
 - methods, 733
- transferFocus() method
 - Component class, 55
- transferFocusBackward() method
 - Component class, 55
- transferFocusDownCycle() method
 - Container class, 55
- transferFocusUpCycle() method
 - Component class, 55
- TransferHandler class
 - canImport() method, 734
 - createTransferable() method, 735
 - creating a transferable image object, 734
 - importData() method, 735
 - introduction, 731
- transferHandler property
 - JComponent class, 79
- translate() method
 - Graphics class, 214
- tree nodes
 - creating proper ComboBox editor for a tree, 648
 - DefaultMutableTreeNode class, 661–664
 - editing, 643
 - with CellEditor interface, 644
 - with DefaultCellEditor class, 645
 - with DefaultTreeCellEditor class, 647
 - with TreeCellEditor interface, 644
 - MutableTreeNode interface, 660
 - traversing trees, 664
 - TreeNode interface, 659
- tree tooltips
 - working with, 641–643
- TreeCellEditor interface, 644
 - creating CheckBoxNodeEditor class, 653–658
 - editing table cells, 718

- editing tree nodes, 623, 644
 - getTreeCellEditorComponent() method, 648, 656
 - TreeCellRenderer interface
 - creating custom renderer, 637–641
 - DefaultTreeCellRenderer class, 635
 - implementations, 623
 - introduction, 634
 - TreeExpansionEvent class, 672
 - TreePath getPath() method, 673
 - TreeExpansionListener interface, 672
 - treeExpansionListeners property
 - JTree class, 629
 - treelock property
 - JComponent class, 79
 - TreeModel interface
 - DefaultTreeModel class implements, 667
 - introduction, 667
 - getRoot() method, 666
 - storing within DefaultTreeModel class, 624
 - working with tree nodes, 659
 - TreeModelEvent class
 - notifying registered listeners, 668
 - TreeModelListener interface
 - DefaultTreeModel class manages, 667
 - reporting changes to model, 668
 - TreeNode interface
 - nodes of JTree are implementations of, 624
 - traversing trees, 664
 - working with tree nodes, 659
 - TreePath class, 624
 - introduction, 671–672
 - trees
 - additional expansion events, 672–673
 - editing tree nodes, 643–659
 - introduction, 623–624
 - JTree class, 624–634
 - TreeCellRenderer interface, 634–643
 - TreeModel interface, 667
 - TreeSelectionModel interface, 668–672
 - working with tree nodes, 659–667
 - TreeSelectionEvent class, 671
 - TreeSelectionListener interface, 671
 - treeSelectionListeners property
 - JTree class, 629
 - TreeSelectionModel interface
 - DefaultTreeSelectionModel class, 670
 - introduction, 668–670
 - tree selection management, 624
 - TreeWillExpandListener interface, 673
 - treeWillExpandListeners property
 - JTree class, 629
 - trimToSize() method
 - DefaultListModel class, 460
 - type property
 - ListDataEvent class, 454
 - TableModelEvent class, 700
- ## U
- UI delegates
 - adding, 771–772
 - creating, 763–766
 - UI property
 - AbstractButton class, 99
 - JColorChooser class, 307
 - JComboBox class, 492
 - JDesktopPane component, 263
 - JFileChooser class, 327
 - JInternalFrame class, 255
 - JLabel class, 90
 - JList class, 465
 - JMenuBar class, 159
 - JMenuItem class, 164
 - JOptionPane class, 281
 - JPopupMenu class, 179
 - JProgressBar component, 441
 - JRootPane class, 237
 - JScrollBar component, 426
 - JScrollPane class, 407
 - JSeparator class, 175
 - JSlider component, 431
 - JSpinner class, 510
 - JSplitPane class, 386
 - JTabbedPane class, 399
 - JTable class, 682
 - JTableHeader class, 716
 - JTextComponent class, 524
 - JToolBar class, 203
 - JToolTip class, 85
 - JTree class, 629
 - JViewport class, 412
 - UIClassID property
 - JButton class, 105
 - JCheckBox class, 127
 - JCheckBoxMenuItem component, 185
 - JColorChooser class, 307
 - JComboBox class, 492
 - JDesktopPane component, 263

- JEditorPane class, 575
- JFileChooser class, 327
- JFormattedTextField class, 567
- JInternalFrame class, 255
- JLabel class, 90
- JList class, 465
- JMenu class, 172
- JMenuBar class, 159
- JMenuItem class, 164
- JOptionPane class, 281
- JPasswordField class, 564
- JPopupMenu class, 179
- JProgressBar component, 441
- JRadioButton class, 136
- JRadioButtonMenuItem component, 191
- JRootPane class, 237
- JScrollBar component, 426
- JScrollPane class, 407
- JSeparator class, 175
- JSlider component, 431
- JSpinner class, 510
- JSplitPane class, 386
- JTabbedPane class, 399
- JTable class, 682
- JTableHeader class, 716
- JTextArea class, 571
- TextField class, 529
- JTextPane class, 581
- JToggleButton class, 120
- JToolBar class, 203
- JToolTip class, 85
- JTree class, 629
- JViewport class, 412
- uiClassID property
 - JComponent class, 79
- UIDefaults class
 - inner classes, 755
 - introduction, 71, 749
 - listing properties within JTable, 749–752
- UIDefaults.ActiveValue class, 755
 - look and feel properties stored as, 741
- UIDefaults.LazyValue class, 755
 - look and feel properties stored as, 741
- UIDefaults.ProxyLazyValue class, 755
- UIManager class
 - addAuxiliaryLookAndFeel() method, 776
 - checking component settings in
 - UIDefaults lookup table, 72
 - currently installed look and feel classes
 - provided by, 741
 - get() method, 758, 763
 - getInstalledLookAndFeel() method
 - 743, 776
 - getter methods, 747
 - introduction, 747
 - properties, 748, 813–846
 - put() method, 758
 - setLookAndFeel() method, 743
- UIManager.LookAndFeelInfo class, 741
 - getInstalledLookAndFeel() method, 742
 - introduction, 749
- UIResource interface, 741
 - classes that implement, 753–754
 - introduction, 753
- UIResource properties, fetching, 72
- Undo Framework, 783
 - Command design pattern, 788, 789
 - components, 789
 - AbstractUndoableEdit class, 791
 - CompoundEdit class, 791
 - defining custom undoable class, 795–800
 - UndoableEdit interface, 789–790
 - UndoableEditEvent class, 794
 - UndoableEditListener interface, 794
 - UndoableEditSupport class, 794
 - UndoManager class, 792, 793
 - using an outside object to manage Undo
 - states, 800
 - example, 801–804
 - StateEdit class, 801
 - StateEditable interface, 800
 - using with Swing text components, 784–788
 - working with, 783, 784
- undo() method
 - CompoundEdit class, 792
 - UndoableEdit interface, 790
 - UndoManager class, 784
- undoable program example, 795–800
- UndoableDrawingPanel class, 797
- UndoableEdit command
 - posting to UndoableEditListener
 - objects, 801
 - UndoManager class, 788, 799
- UndoableEdit interface, 788
 - creating, 797
 - definition, 789
 - flow between states, 790
 - StateEdit class implementation, 800
- UndoableEditEvent class
 - edit property, 794

- UndoableEditEvent event
 - UndoableEditListener interface, 794
 - UndoableEditSupport class, 794
 - UndoManager class, 793
- undoableEditHappened() method
 - listener objects, 794
- UndoableEditListener interface, 794
 - attaching to document of component, 784
 - managing objects with
 - UndoableEditSupport class, 794
 - UndoableEditEvent event, 794
 - UndoableEditSupport class, 794
 - UndoManager class, 784
- undoableEditListeners property
 - AbstractDocument class, 540
- UndoableEditSupport class, 801
 - addUndoableListener() method, 794
 - beginUpdate() method, 794
 - endUpdate() method, 794
 - managing UndoableEditListener objects, 794
 - postEdit() method, 794
 - UndoableEditListener listener, 794
- UndoManager class, 783
 - extending to expose UndoableEdit list, 794
 - managing undo and redo capabilities for
 - Swing text components, 784
 - methods, 792
 - UndoableEdit command, 788
- UndoManagerHelper class, 785
 - definition, 785, 787
 - using the Undo Framework with the Swing text components, 787
- uninstallChooserPanel() method
 - AbstractColorChooserPanel class, 313
- unitIncrement property
 - JScrollBar component, 422, 426
- updateChooser() method
 - AbstractColorChooserPanel class, 313
- updateComponentTreeUI() method
 - SwingUtilities class, 743
- updateUI() method
 - changing look and feel setting of
 - component, 813
- upFocusCycle() method
 - KeyboardFocusManager class, 55

- userObject property
 - DefaultMutableTreeNode class, 640, 666
 - DefaultMutableTreeNode interface, 663
- userObjectPath property
 - DefaultMutableTreeNode interface, 663
- userTextColor property
 - MetalLookAndFeel class, 773
- userTextFont property
 - MetalLookAndFeel class, 774

V

- validateRoot property
 - JTextField class, 529
- valid property
 - HTMLDocument.Iterator class, 609
 - JComponent class, 79
- validateRoot property
 - JComponent class, 79
 - JRootPane class, 237
 - JScrollPane class, 407
 - JSplitPane class, 386
- validCharacters property
 - MaskFormatter class, 620
- value property
 - BoundedRangeModel interface, 419
 - JFormattedTextField class, 567
 - JOptionPane class, 281, 285
 - JProgressBar component, 441
 - JScrollBar component, 426
 - JSlider component, 431
 - JSpinner class, 510
 - SpinnerDateModel class, 515
 - SpinnerListModel class, 516
 - SpinnerNumberModel class, 517
- valueForPathChanged() method
 - TreeModel interface, 667
- valueIsAdjusting property
 - BoundedRangeModel interface, 420, 424
 - DefaultListSelectionModel class, 475, 683
 - JList class, 465
 - JScrollBar component, 426
 - JSlider component, 431
 - ListSelectionEvent class, 476
- Vector class
 - creating JTree from, 625–627

- verifyInputWhenFocusTarget property
 - JComponent class, 78
- verticalAlignment property
 - AbstractButton class, 99, 102
 - JLabel class, 90
- verticalScrollBar property
 - JScrollPane class, 407
- verticalScrollBarPolicy property
 - JScrollPane class, 407
- verticalTextPosition property
 - AbstractButton class, 99, 102
 - JLabel class, 90
- VetoableChangeListener event handler
 - JComponent class, 81
- View class
 - displaying Document contents with
 - EditorKit class, 607
- view property
 - JViewport class, 412
- ViewFactory class
 - displaying Document contents with
 - EditorKit class, 607
- viewport property
 - JScrollPane class, 407
- viewportBorder property
 - JScrollPane class, 407
- viewportBorderBounds property
 - JScrollPane class, 407
- ViewportLayout class, 371, 412
- viewportView property
 - JScrollPane class, 406, 407
- viewPosition property
 - JViewport class, 412, 414
- viewRect property
 - JViewport class, 412, 413
- viewSize property
 - JViewport class, 412, 413
- visible property
 - Caret interface, 548
 - JComponent class, 79
 - JPopupMenu class, 179
- visibleAmount property
 - JScrollBar component, 426
- visibleRect property
 - JComponent class, 77
- visibleRowCount property
 - JList class, 465
 - JTree class, 629, 630

W

- wantsInput property
 - JOptionPane class, 281, 285
- warningString property
 - InternalFrame class, 255
- weight
 - GridBagConstraints class, 357
- wheelScrollingEnabled property
 - JScrollPane class, 407
- white property
 - MetalLookAndFeel class, 774
- width property
 - JComponent class, 77
 - TableColumn class, 713
- WindowAdapter class
 - WindowListener methods, 256
- windowBackground property
 - MetalLookAndFeel class, 774
- WindowConstants interface
 - close operation constants, 244
 - implemented by JDialog class, 248
 - working with JFrame class to manage
 - closing operations, 242
- windowDecorationStyle property
 - JRootPane class, 237, 244
 - class constants, 237
- windowInit() method
 - JWindow class, 248
- WindowListener interface
 - supported by JFrame class, 246
 - WindowAdapter class, 256
- WindowsClassicLookAndFeel
 - implementation
 - LookAndFeel.supportedLookAndFeel, 747
- WindowsLookAndFeel implementation
 - LookAndFeel.supportedLookAndFeel, 742
 - using on non-Windows machine, 767–768
- windowTextFont property
 - MetalLookAndFeel class, 774
- windowTitleBackground property
 - MetalLookAndFeel class, 774
- windowTitleForeground property
 - MetalLookAndFeel class, 774
- windowTitleInactiveBackground property
 - MetalLookAndFeel class, 774
- windowTitleInactiveForeground property
 - MetalLookAndFeel class, 774
- WORA (write-once, run anywhere), 1

WrappedPlainView view

 BasicTextAreaUI interface, 60

wrapStyleWord property

 JTextArea class, 571

writableAction class constant

 DefaultEditorKit class, 592

write() method

 JTextComponent class, 531

X

x property

 JComponent class, 77

Y

y property

 JComponent class, 77